

The following changes to the tender documents are effective immediately and will form part of the contract documents:

1. Replace section 08 36 19 – Multi-Leaf Vertical Lift Doors with section 08 36 20 – Overhead Doors. (refer to ATTA006.PDF)
2. Question: On print E1 for the Coast Guard Station, under the cable legend they show an article 3 for cable and conduit. Following this schematic and the legend I am unable to find article three on the schematic. Please clarify as to what equipment this article pertains to.

Answer: Cable shown in between 100 amp 2 pole circuit breaker (Panel A – Circuits 40,42) to fused disconnect switch for Vakta Vessel Receptacle to be Type 3 in lieu of Type 7 as shown on the Single Line Diagram. (refer to ATTA007.PDF)