

Part 1 General

1.1 RELATED REQUIREMENTS

- .1 Section 01 51 00 – Temporary utilities
- .2 Section 01 52 00 – Construction facilities
- .3 Section 01 74 11 – Cleaning
- .4 Section 01 74 21 – Construction/Demolition waste management and disposal

1.2 INSTALLATION AND REMOVAL

- .1 Provide temporary controls in order to execute Work expeditiously.
- .2 Remove from site all such work after use.

1.3 FENCE CONSTRUCTION

- .1 The around construction site, erect temporary site enclosure using new 1.8 m high galvanized wire fence attached to fence posts spaced at 2.4 m on centre. Provide one lockable truck gate. Maintain fence in good repair. The meshes must be anti-climb type so that the fence cannot be climbed by a person. Steel posts must be anchored to the ground.

1.4 GUARD RAILS AND BARRICADES

- .1 Provide secure, rigid guard rails and barricades around deep excavations or others.
- .2 Provide as required by governing authorities.

1.5 ACCESS TO SITE

- .1 Provide and maintain access roads, sidewalk crossings, ramps and construction runways as may be required for access to Work.

1.6 PUBLIC TRAFFIC FLOW

- .1 Provide and maintain competent signal flag operators, traffic signals, barricades and flares, lights, or lanterns as required to perform Work and protect public.

1.7 FIRE ROUTES

- .1 Maintain access to property including overhead clearances for use by emergency response vehicles.

1.8 PROTECTION FOR OFF-SITE AND PUBLIC PROPERTY

- .1 Protect surrounding private and public property from damage during performance of Work.
- .2 Prior to commencement to the work, carry out a joint inspection with the Departmental Representative and the contractor in order to identify and document any damage to public and private properties.

- .3 Be responsible for damage incurred.

1.9 WASTE MANAGEMENT AND DISPOSAL

- .1 Separate waste materials for reuse and recycling in accordance with Section 01 74 21-
Construction/Demolition Waste Management and Disposal.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

- .1 Not Used.

END OF SECTION