

- Filter stone (various caliber): 20 000 m.t.
- Armour stone: 8 à 12 m.t: 4 000 m.t.
6 à 10 m.t: 1 500 m.t.
3 à 5 m.t: 4 000 m.t.
2 à 4 m.t: 10 000 m.t.

- .2 Sign an occupancy lease with the Departmental Representative for the stone produced and stored in quarry during that period in order to be paid as stone produced.
- .3 The contractor may also store a part of the stone produced during this period within the limits of the site to be paid for as produced and delivered stone.

1.4 SITE INSPECTION

- .1 Before submitting bid, Contractor shall be responsible to visit site and get all necessary information regarding nature and scope of the contract, as well as all the conditions that may affect the execution of the contract.
- .2 By bidding for present contract, Contractor confirms their knowledge of the nature and location of the contract, general and local conditions, especially weather or climatic conditions, wave action, tide levels, storm surge, ices, specific physical conditions at the contract site and any other situation that may affect the execution of the contract and the value of the work.

1.5 CONTRACTOR USE OF PREMISES

- .1 The areas accessible to Contractor are indicated on the plan. These areas include: A space along the shore where contractor has the possibility of constructing a temporary work platform. If Contractor wishes to use other parcels of land, he must reach an agreement with the owners concerned and pay for it. A copy of the agreement shall be sent to the Departmental Representative.
- .2 The use of the site is restricted to the areas needed for the execution of the contract and access routes.
- .3 The use of the premises should follow the guidelines of the Departmental Representative. The Contractor shall be responsible for the safety of operations with regard to users of adjacent facilities (camping and other shop) and residences. See section 01 56 00 - *Temporary access and protection works* for guidelines.
- .4 The wharf is in decayed condition. Especially those cells 6-7-8 and the dolphin that have collapsed.
- .5 Coordinate the use of surrounding sites following the guidelines of the Departmental Representative.

1.6 OCCUPANCY BY THE DEPARTMENTAL REPRESENTATIVE

- .1 Departmental Representative will occupy premises during entire construction period for the follow-up.
- .2 Co-operate with the Departmental Representative in scheduling operations to minimize potential sources of conflict and to facilitate the Departmental Representative usage.

1.7 REQUIREMENTS CNESST

- .1 The contractor shall submit the documentary evidence itself and its subcontractors have complied with the requirements of the Commission on Standards, Equality, Health and Safety of the Quebec Labour.
- .2 Under the provisions of the Act respecting occupational health and safety in the province of Quebec (RSQ, chapter S-2.1) and only for the purpose of the said Act, it is up to the contractor to take the one hand from the beginning of work, the role and duties of prime contractor as stated in the said Act, in addition to its obligations as a result of an employer assigned to it under that Act status and, secondly, its obligations with regard to health and safety.

1.8 EXISTING UTILITY SERVICES

- .1 Notify Department Representative and utility companies of intended interruption of services and obtain required permission.
- .2 No service shall be provides to contractor for the performance of the work. He must be autonomous in electrical, water, etc.
- .3 Protect, relocate or maintain existing active services. When inactive services are encountered, cap off in manner approved by authorities having jurisdiction.
- .4 Record locations of maintained, re-routed and abandoned service lines.
- .5 Construct fences and barriers in accordance with Section 01 56 00 - Temporary Barriers and Enclosures.

1.9 SITE STAKING

- .1 Fully stake out the site and ensure its complete implementation depending on the indicated location, lines and levels.
- .2 Before work begins, the Contractor shall verify all measurements on the site and notify the Departmental Representative of any errors or mismatches.

1.10 REQUIRED DOCUMENTS

- .1 Maintain at job site, one copy each document as follows:
 - .1 Contract Drawings.
 - .2 Specifications.
 - .3 Addenda.
 - .4 Reviewed Shop Drawings.
 - .5 List of Outstanding Shop Drawings.
 - .6 Change Orders.
 - .7 Other Modifications to Contract.
 - .8 Field Test Reports.
 - .9 Copy of Approved Work Schedule.
 - .10 Health and Safety Plan and Other Safety Related Documents.

- .11 Other documents as specified.

1.11 BENCHMARKS

- .1 The benchmark to be used for construction work is indicated on the plan.
- .2 All the elevations indicated on plan are referred to chart datum (marine).
- .3 The benchmark is the 87KSA23. It is located from the church of Mont-Louis, driving, 8 km west toward Mont-St-Pierre, take the street Chamoine-Richard. The benchmark is located north-east of the private road, on private land, south-east of the house no 10.

Part 2 Products

2.1 NOT USED

- .1 Not used.

Part 3 Execution

3.1 NOT USED

- .1 Not used.

END OF SECTION