

MCTS CENTRE	WIRING OF EQUIPMENT	Section 26 90 00
PORT AUX BASQUES, NL	SUPPLIED BY OTHERS	Page 1
R.082780.004		2017-06-28

PART 1 - GENERAL

1.1 GENERAL

- .1 This section describes the extent of services to be provided for wiring of equipment supplied by others.
- .2 Within the context of this section, Others means:
 - .1 Other divisions of this specification.
 - .2 The Owner, as defined in the Contract.
 - .3 Other contractors supplying and installing equipment to the contract.

1.2 EXTENT OF SERVICES PROVIDED

- .1 The work of this contract is to include all power and control wiring of equipment which is provided by Division 26.
- .2 All power and control wiring above 50 V for equipment supplied by Division 25 will be the responsibility of this contractor. Coordinate with Integrated Automation contractor for exact requirements.
- .3 All control wiring 50 V and less for equipment supplied by Division 25 will be the responsibility of Division 25. Conduit and wire associated with this is the responsibility of Division 25 unless otherwise indicated.
- .4 All power and control wiring associated with equipment supplied by Division 01 will be the responsibility of this contractor. Coordinate with general contractor for exact requirements.
- .5 Final connection of all wiring to equipment provided by others (except control wiring below 50 V associated with Division 25 equipment) will be by division 26. Coordinate with the provider for connection instructions.

- 1.3 RESPONSIBILITY OF DIVISION 26 .1 It is the responsibility of the Division 26 subcontractor to verify final requirements for wiring of all equipment noted. Verification of wiring requirements to include:
- .1 Confirmation of electrical characteristics.
 - .2 Location of connection point.
 - .3 Method of connection (i.e. direct or plug-in etc.)
- .2 Obtain and become familiar with shop drawings for all relevant equipment.
- .3 No claim for extra will be entertained for wiring equipment which has been indicated, or changes to installed wiring where installation proceeded prior to verification of electrical requirements.

PART 2 - PRODUCTS

- 2.1 NOT USED .1 Not Used.

PART 3 - EXECUTION

- 3.1 NOT USED .1 Not Used.