

MCTS CENTRE	DISCONNECT SWITCHES -	Section 26 28 23
PORT AUX BASQUES, NL	FUSED AND NON-FUSED	Page 1
R.082780.004		2017-06-28

PART 1 - GENERAL

- | | | |
|--|----|--|
| <u>1.1 REFERENCES</u> | .1 | Canada Green Building Council (CaGBC)
.1 LEED Canada-NC-2009, LEED (Leadership in Energy and Environmental Design): Green Building Rating System Reference Package For New Construction and Major Renovations. |
| <u>1.2 ACTION AND INFORMATIONAL SUBMITTALS</u> | .1 | Submit in accordance with Section 01 33 00 - Submittal Procedures. |
| | .2 | Product Data:
.1 Submit manufacturer's instructions, printed product literature and data sheets for disconnect switches - fused and non-fused and include product characteristics, performance criteria, physical size, finish and limitations. |
| | .3 | Sustainable Design Submittals:
.1 LEED Canada submittals: in accordance with Section 01 35 21 - LEED Requirements.
.2 Construction Waste Management:
.1 Submit project Waste Management Plan highlighting recycling and salvage requirements.
.2 Submit calculations on end-of-project recycling rates, salvage rates, and landfill rates demonstrating that 75% of construction wastes were recycled or salvaged. |
| | .3 | Recycled Content:
.1 Submit listing of recycled content products used, including details of required percentages or recycled content materials and products, showing their costs and percentages of post-consumer content, and total cost of materials for project. |

- | | | |
|--|----|---|
| 1.3 DELIVERY,
STORAGE AND
HANDLING | .1 | Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements and with manufacturer's written instructions. |
| | .2 | Develop Construction Waste Management Plan related to Work of this Section and in accordance with Section 01 35 21 - LEED Requirements. |
| | .3 | Packaging Waste Management: remove for reuse or return of pallets, crates, padding, banding, and packaging materials as specified in Construction Waste Management Plan in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal and Section 01 35 21 - LEED Requirements. |

PART 2 - PRODUCTS

- | | | |
|----------------------------|----|--|
| 2.1 DISCONNECT
SWITCHES | .1 | Fusible, and Non-fusible, Horsepower rated disconnect switch in CSA enclosure as indicated, to CAN/CSA-C22.2 No.4 size as indicated. |
| | .2 | Provision for padlocking in [on-off] [off] switch position by 3 locks. |
| | .3 | Mechanically interlocked door to prevent opening when handle in ON position. |
| | .4 | Fuses: size as indicated, in accordance with Section 26 28 13.01 - Fuses - Low Voltage. |
| | .5 | Fuseholders: suitable without adaptors, for type and size of fuse indicated. |
| | .6 | Quick-make, quick-break action. |
| | .7 | ON-OFF switch position indication on switch enclosure cover. |
-

- 2.2 EQUIPMENT IDENTIFICATION
- .1 Provide equipment identification in accordance with Section 26 05 00 - Common Work Results for Electrical.
 - .2 Indicate name of load controlled on size 4 nameplate.

PART 3 - EXECUTION

- 3.1 INSTALLATION
- .1 Install disconnect switches complete with fuses if applicable.

- 3.2 CLEANING
- .1 Progress Cleaning: clean in accordance with Section 01 74 11 - Cleaning.
 - .2 Waste Management: separate waste materials for reuse and recycling in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal and Section 01 35 21 - LEED Requirements.
 - .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.