

PART 1 - GENERAL

- | | | |
|--|----|---|
| <u>1.1 INSTALLATION
AND REMOVAL</u> | .1 | Provide temporary controls in order to execute work expeditiously. |
| | .2 | Remove from site all such work after use. |
| <u>1.2 HOARDING</u> | .1 | Erect temporary site enclosure using new 1.2 m high snow fence wired to rolled steel "T" bar fence posts spaced at 2.4 m centres. Provide one lockable truck gate. Maintain fence in good repair. |
| <u>1.3 GUARD RAILS AND
BARRICADES</u> | .1 | Provide secure, rigid guard rails and barricades around open excavations. |
| | .2 | Provide as required by governing authorities. |
| <u>1.4 ACCESS TO SITE</u> | .1 | Provide and maintain access to adjacent facilities. |
| <u>1.5 PUBLIC TRAFFIC
FLOW</u> | .1 | Provide and maintain competent signal flag operators, traffic signals, barricades and flares, lights, or lanterns as required to perform work and protect the public. |
| <u>1.6 FIRE ROUTES</u> | .1 | Maintain access to property including overhead clearances for use by emergency response vehicles. |
| <u>1.7 PROTECTION FOR
OFF-SITE AND PUBLIC
PROPERTY</u> | .1 | Protect surrounding private and public property from damage during performance of work. |
| | .2 | Be responsible for damage incurred. |
-

MCTS CENTRE
PORT AUX BASQUES, NL
R.082780.004

TEMPORARY BARRIERS AND
ENCLOSURES

Section 01 56 00
Page 2
2017-06-28

1.8 MEASUREMENT FOR .1
PAYMENT

No separate measurements for payment shall be made for items under this section. Include costs for Temporary Barriers & Enclosures in the Lump Sum portion of the work on the Bid and Acceptance Form.

PART 2 - PRODUCTS

2.1 NOT USED .1 Not Used.

PART 3 - EXECUTION

3.1 NOT USED .1 Not Used.