

TOPOGRAPHIC SURVEY CONDUCTED JANUARY-FEBRUARY, 2017.
CONTROL POINTS :

MONUMENT	NORTHING	EASTING
82G2337	5272004.439	254170.507
82G2344	5273775.057	254658.120

ALL SOUNDINGS & ELEVATIONS IN METRES.
ALL AZIMUTHS ARE GRID REFERENCED TO LONGITUDE 58°-30' WEST, THE CENTRAL MERIDIAN OF MTM ZONE 3.
ALL COORDINATES METRIC, 3° TRANSVERSE MERCATOR PROJECTION (NAD83).




NOTES :

- CONTRACTOR IS RESPONSIBLE TO OBTAIN ALL NECESSARY PERMITS AND CLEARANCES AT ZERO COST TO THE OWNER PRIOR TO START OF CONSTRUCTION.
- LOCATION SHOWN FOR ALL UNDERGROUND UTILITIES ARE APPROXIMATE. OWNER AND CONSULTANT ASSUMES NO RESPONSIBILITY FOR ACCURACY OR COMPLETENESS OF INFORMATION AS SHOWN. CONTRACTOR SHALL CONDUCT OWN PRE-CONSTRUCTION ASSESSMENT TO IDENTIFY AND LOCATE ALL UNDERGROUND UTILITIES WHICH MIGHT IMPACT PROPOSED WORK UNDER THIS CONTRACT. CONTRACTOR SHALL TAKE ALL REQUIRED PRECAUTIONS WHILE EXCAVATING NOT TO DAMAGE EXISTING UTILITIES. CONTRACTOR RESPONSIBLE TO MAKE REPAIRS AT OWN COSTS TO SATISFACTION OF UTILITY.
- FOR TEST PITS LOG INFORMATION, REFER TO REPORT COMPLETED BY FRACTION CONSULTANTS INC. DATED DECEMBER, 2016, CONTAINED IN APPENDIX 'G' OF THE SPECIFICATIONS. NOTIFY DEPARTMENTAL REPRESENTATIVE IF SUBSURFACE CONDITIONS VARY SIGNIFICANTLY DURING CONSTRUCTION FROM THOSE NOTED WITHIN THE REPORT AND AWAIT INSTRUCTIONS.
- UNLESS OTHERWISE NOTED, ALL EXISTING LANDSCAPED AREAS DISTURBED DURING CONSTRUCTION SHALL BE REINSTATED TO PRE-CONSTRUCTION OR BETTER QUALITY WITH 150mm TOPSOIL AND HYDROSEEDING. REFER TO LANDSCAPE PLAN A13 FOR LANDSCAPING TYPES AND LIMITS. COORDINATE WITH DEPARTMENTAL REPRESENTATIVE.
- CONTRACTOR SHALL BE RESPONSIBLE AS PART OF THE CONTRACT SCOPE OF WORK, TO VERIFY/DETERMINE THE ACTUAL SIZE OF THE EXISTING AND WATERMAIN SERVICE. THIS SHALL BE INCLUDED IN THE UNIT PRICE FOR INSTALLATION OF MAIN LINE PIPING.

revision	description	date
E	ISSUED FOR TENDER	JULY 11 2017
D	ISSUED FOR TENDER	JUN 28 2017
C	ISSUED FOR 99% REVIEW	JUN 08 2017
B	ISSUED FOR CLIENT REVIEW	APR 21 2017
A	ISSUED FOR 66% REVIEW	MAR 24 2017

project: MCTS CENTRE
designed: [Signature] conq
date: July 12, 2017
drawn: [Signature] dessin
date: July 12, 2017
approved: [Signature] approuv
date: July 12, 2017
Tender: [Signature] Submission
Project Manager: [Signature] Adm. des projets TPSC
project number: R.082780.004
drawing no.: C2



NOTES CONT.

- PRIOR TO START OF CONSTRUCTION, CONTRACTOR SHALL DEVELOP AND SUBMIT FOR OWNER AND CONSULTANT APPROVAL, A VEHICULAR AND PEDESTRIAN MOVEMENT PLAN FOR THE WORK SITE. ANY AMENDMENTS TO THE APPROVED PLAN SHALL REQUIRE DEPARTMENTAL REPRESENTATIVE PRIOR APPROVAL.
- UNLESS OTHERWISE NOTED, ALL INFRASTRUCTURE TO BE REMOVED, INCLUDING LAND CLEARING DEBRIS, IS THE RESPONSIBILITY OF THE CONTRACTOR TO DISPOSE OF OFF SITE.
- CONTRACTOR SHALL BE RESPONSIBLE FOR ENSURING THAT EMERGENCY VEHICLES HAVE UNIMPEDED EMERGENCY ACCESS AT ALL TIME.
- CONTRACTOR SHALL COORDINATE AND PAY ALL COSTS FOR TEMPORARY BRACING OF UTILITY POLES, WATERMANS, SEWERS, DUCT BANKS, ETC.
- CONTRACTOR TO PROVIDE A SAFETY PLAN PRIOR TO THE COMMENCEMENT OF WORK.
- SURVEY PROVIDED BY ROBIN C. DAVIS SURVEYS, DATED JANUARY 20, 2017.
- EXISTING WATERMAIN SHOWN IS APPROXIMATE ONLY. CONTRACTOR TO DETERMINE LOCATION, SIZE, TYPE AND DEPTH OF COVER AND ADVISE DEPARTMENTAL REPRESENTATIVE PRIOR TO CONSTRUCTION.
- CONTRACTOR RESPONSIBLE TO DISPOSE OFF SITE ALL EXCAVATED SATURATED ROOT MAT AND DECAYED ORGANIC MATERIAL. STOCKPILE ANY AVAILABLE TOPSOIL AND REUSE DURING LANDSCAPING. COORDINATE WITH DEPARTMENTAL REPRESENTATIVE.

LEGEND :

- xx.xx EXISTING SURFACE ELEVATIONS
- EXISTING CONTOURS
- ⊕ EXISTING BOREHOLE
- ⊙ EXISTING TESTPIT
- EXISTING POLES
- EXISTING HYDRANT
- - - EXISTING DITCH
- - - EXISTING WATERLINE
- LEED PROJECT BOUNDARY
- LIMIT OF WORK