





NOTE :


- EXCAVATE TO UNDERLYING TILL LAYER BY REMOVING ORGANICS AS REQUIRED. PROOF ROLL AND REPLACE WITH MATERIAL AS SPECIFIED TO BRING THE SITE TO SUBGRADE. OBTAIN DEPARTMENTAL REPRESENTATIVE APPROVAL OF SUBGRADE BEFORE PLACING TYPE '3' FILL. APPROXIMATELY 3,050 cu.m. TO BE REMOVED. TO BE CONFIRMED ON SITE.
- REFER TO STRUCTURAL DRAWINGS FOR DEPTH OF BUILDING CONCRETE FOUNDATION WALL AND FOOTINGS.




SECTION **4**
C6




SECTION **3**
C6



SECTION **2**
C6



SECTION **1**
C6



E	ISSUED FOR TENDER	JULY 11 2017
D	ISSUED FOR TENDER	JUN 28 2017
C	ISSUED FOR 99% REVIEW	JUN 08 2017
B	ISSUED FOR CLIENT REVIEW	APR 21 2017
A	ISSUED FOR 66% REVIEW	MAR 24 2017
revisions		date

project MCTS CENTRE
 PORT AUX BASQUES

drawing SITE SECTIONS

designed *tw* July 12, 2017
 drawn *shu* July 12, 2017
 approved *bc vb* July 12, 2017
 date
 Tender *J.P. Macgillivray July 17 2017*
 WSCC Project Manager / Administrateur de projets TPSCC

project number **R.082780.004**
 drawing no. **C6**