



## RETURN BIDS TO:

## RETOURNER LES SOUMISSIONS À:

Bid Receiving Public Works and Government  
Services Canada/Réception des soumissions Travaux  
publics et Services gouvernementaux Canada  
800 Burrard Street, Room 219  
800, rue Burrard, pièce 219  
Vancouver  
British Columbia  
V6Z 0B9  
Bid Fax: (604) 775-9381

## SOLICITATION AMENDMENT MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise  
indicated, all other terms and conditions of the Solicitation  
remain the same.

Ce document est par la présente révisé; sauf indication contraire,  
les modalités de l'invitation demeurent les mêmes.

### Comments - Commentaires

Vendor/Firm Name and Address  
Raison sociale et adresse du  
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution  
Public Works and Government Services Canada - Pacific  
Region  
800 Burrard Street, Room 219  
800, rue Burrard, pièce 219  
Vancouver  
British C  
V6Z 0B9

<b>Title - Sujet</b> Cableway Deconstruction & Site Rehab	
<b>Solicitation No. - N° de l'invitation</b> K4E21-170161/A	<b>Amendment No. - N° modif.</b> 002
<b>Client Reference No. - N° de référence du client</b>	<b>Date</b> 2017-08-09
<b>GETS Reference No. - N° de référence de SEAG</b> PW-\$PWY-020-8112	
<b>File No. - N° de dossier</b> PWY-7-40083 (020)	<b>CCC No./N° CCC - FMS No./N° VME</b>
<b>Solicitation Closes - L'invitation prend fin</b> <b>at - à 02:00 PM</b> <b>on - le 2017-08-14</b>	<b>Time Zone</b> <b>Fuseau horaire</b> Pacific Daylight Saving Time PDT
<b>F.O.B. - F.A.B.</b> <b>Plant-Usine:</b> <input type="checkbox"/> <b>Destination:</b> <input checked="" type="checkbox"/> <b>Other-Autre:</b> <input type="checkbox"/>	
<b>Address Enquiries to: - Adresser toutes questions à:</b> Ly, Ronny(PWY)	<b>Buyer Id - Id de l'acheteur</b> pwy020
<b>Telephone No. - N° de téléphone</b> (604) 318-5750 ( )	<b>FAX No. - N° de FAX</b> (604) 775-6633
<b>Destination - of Goods, Services, and Construction:</b> <b>Destination - des biens, services et construction:</b> EC - Cableway Deconstruction and Site Rehabilitation – Birchbank, BC	

Instructions: See Herein

Instructions: Voir aux présentes

<b>Delivery Required - Livraison exigée</b>	<b>Delivery Offered - Livraison proposée</b>
<b>Vendor/Firm Name and Address</b> <b>Raison sociale et adresse du fournisseur/de l'entrepreneur</b>	
<b>Telephone No. - N° de téléphone</b> <b>Facsimile No. - N° de télécopieur</b>	
<b>Name and title of person authorized to sign on behalf of Vendor/Firm</b> <b>(type or print)</b> <b>Nom et titre de la personne autorisée à signer au nom du fournisseur/</b> <b>de l'entrepreneur (taper ou écrire en caractères d'imprimerie)</b>	
<b>Signature</b>	<b>Date</b>

Solicitation No. - N° de l'invitation

K4E21-170161/A

Client Ref. No. - N° de réf. du client

Amd. No. - N° de la modif.

002

File No. - N° du dossier

Buyer ID - Id de l'acheteur

pwpy020

CCC No./N° CCC - FMS No./N° VME

---

Please find Addendum 001 herein.

THE FOLLOWING ADDENDUM SUPERCEDES INFORMATION CONTAINED IN DRAWINGS AND SPECIFICATIONS ISSUED FOR THE PROJECT TO THE EXTENT REFERENCED. THIS ADDENDUM FORMS PART OF THE TENDER DOCUMENTS AND IS SUBJECT TO ALL OF THE CONDITIONS SET OUT IN THE CONTRACT CONDITIONS.

### Tender Questions

Q. There is a section that the foundations are to be removed to 300 and then others that read that all must be removed. Please clarify

A. The foundations are to be removed as per the drawings. Some foundations are to be completely removed, while others are to be removed to 300mm. These vary from foundation to foundation and are intentionally variable.

Q. #011155.1.24.4 request a professional surveyor; is that really needed for this demolition?

A. It does not need to be done by a professional surveyor, as long as they describe with measurements and details what exactly has been removed or "left" in place and where it is located. The production of drawings will still be required.

Q. #028311, this work would require a WCB nop and work procedure approval. If the contractor work procedures meet with WCB approval then that would meet with your approval or???

A. The lead paint should be dealt with in accordance with the specifications and the environmental assessment provided in Appendix A.

Q. Tender reads that we drop the cables into the water and drag out. Will that be allowed, has all approvals been secured or is there any permits required?

A. The dragging out of the cables through the water will be allowed, as long as it is done within the prescribed window (refer to Appendix A in Specifications). All necessary permits for working in and around streams will be handled by third party.

### Drawings

#### **1.1 ON PAGE S5 TO THE METHEDOLOGY SECTION, ADD THE FOLLOWING:**

All steel reinforcement and anchoring rods should be cut off at the elevation of the remaining concrete face and should not be sticking out. All metals should be removed and disposed of appropriately.

**END OF ADDENDUM 001**

**ALL OTHER TERMS AND CONDITIONS REMAIN UNCHANGED**