



RETURN BIDS TO:

RETOURNER LES SOUMISSIONS À:

Bid Receiving Public Works & Government Services
Canada/Réception des soumissions Travaux publics et
Services gouvernementaux Canada

1713 Bedford Row

Halifax, N.S./Halifax, (N.E.)

B3J 1T3

Halifax

Bid Fax: (902) 496-5016

SOLICITATION AMENDMENT MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise
indicated, all other terms and conditions of the Solicitation
remain the same.

Ce document est par la présente révisé; sauf indication contraire,
les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address

Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution

Atlantic Region Acquisitions/Région de l'Atlantique
Acquisitions

1713 Bedford Row

Halifax, N.S./Halifax, (N.E.)

B3J 3C9

Halifax

Nova Scot

Title - Sujet Machais Lighthouse Preservation	
Solicitation No. - N° de l'invitation EB144-180469/A	Amendment No. - N° modif. 004
Client Reference No. - N° de référence du client EB144-18-0469	Date 2017-08-16
GETS Reference No. - N° de référence de SEAG PW-\$PWA-124-5625	
File No. - N° de dossier PWA-7-78037 (124)	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2017-08-22	Time Zone Fuseau horaire Atlantic Daylight Saving Time ADT
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Matheson (PWA), Valerie	Buyer Id - Id de l'acheteur pwa124
Telephone No. - N° de téléphone (902) 496-5100 ()	FAX No. - N° de FAX (902) 496-5016
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction:	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

Amendment 004 is generated to respond to questions raised after the release of the Solicitation.

- 1 Is the main light waterproof?
 - a. The lantern light is not watertight and must be protected from weather.
- 2 Does the main light have to be exposed to view at all times? (*i.e. can it be covered by translucent tarping?*)
 - a. Translucent tarping may be used to protect the light during the project. Departmental representative will approve tarping plan and materials prior to installation. Any tarping installed must be able to withstand high winds encountered on site.
- 3 The drawings do not reflect the level of “gouged” out cracks on the exterior, is it safe to assume those are the only cracks that need to be filled?
 - a. The approximate lineal distance of routed cracks is 476m. No further routing of cracks is required.

Is it your intent to use Detail 5 on S400 for filling all those “gouged” out cracks?

 - b. Yes.
- 4 Are there any residues or chemicals left over on the exterior concrete from the removals of Phase 1 (*i.e. products used to remove lead*), or anything applied to the outside that would have been absorbed by the concrete structure and will inhibit the adhesion of the new coating?
 - a. The coating/paint was not found to contain lead and was removed using a hilti chipping tool with concrete cup grinder (*i.e. no chemicals were used*).
- 5 Is there heat inside the lighthouse? If so – what type?
 - a. No.
- 6 Will you be sending out a list of the people who attended the site visits?
 - a. No.
- 7 Will the 2 week project meetings be on-site? If yes – do you cover the costs for project management to attend? (*i.e. fly us out every 2 week?*)
 - a. Progress meetings will be held on site. It is the contractor’s responsibility to attend the site meetings, as required.
- 8 Will there be an on-site full time inspector from PWGSC to address day to day questions/decisions that arise?
 - a. No, Requests for Instruction (RFI) should be addressed to PSPC Project Manager for clarification should any questions arise.

- 9 Will you pay for material stored on the Coast Guard property on Grand Manan, should we intend to use those grounds as storage?
- a. Fisheries & Oceans Canada property on Southwest Head, Grand Manan Island, NB, may be used for storing materials. The contractor must advise departmental representative in writing prior to use of the site. Securing any property for the purpose of material storage is the financial responsibility of the contractor.
- 10 We are interested in bidding this project, but have missed the site meeting. Will it be possible to get a copy of what may have been discussed onsite? Also, will it be possible to extend the closing date?
- a. All questions have been addressed via the posted amendments to this Solicitation. The Solicitation has been extended by one week and is scheduled to close on August 22, 2017.
- 11 Could a ballpark timeline on posting of this tender be provided?
- a. Tender posted on buy and sell will close on August 22, 2017.
- 12 Will DFO supply temporary power and lighting for the duration of the project?
- a. Power for the island is supplied via a solar panel array and two (2) generators (16.5 kw, 17 kw). Contractor may use this power supply but is responsible to make own assessment to determine if additional generators are required.
- 13 Can you indicate if temporary power and lighting is part of the scope of the project or is it the contractor's responsibility?
- a. Power for the island is supplied via a solar panel array and two (2) generators (16.5 kw, 17 kw). Contractor may use this power supply but is responsible to make own assessment to determine if additional generators are required. As per Specification 01 14 00 Work Restrictions, contractor must *"Coordinate all work activities and temporary enclosures to allow for the continuous operation and 360 degree sightlines of the existing lantern light."*
- 14 Does the plywood have to be removed to access the existing concrete floor for lead abatement.
- a. No

All other terms and conditions remain the same.