



**RETURN BIDS TO:**

**RETOURNER LES SOUMISSIONS À:**

**Bid Receiving - PWGSC / Réception des soumissions  
- TPSGC**

**11 Laurier St./11 rue Laurier  
Place du Portage, Phase III  
Core 0B2 / Noyau 0B2  
Gatineau, Québec K1A 0S5**

**SOLICITATION AMENDMENT  
MODIFICATION DE L'INVITATION**

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

**Comments - Commentaires**

**Vendor/Firm Name and Address  
Raison sociale et adresse du  
fournisseur/de l'entrepreneur**

**Issuing Office - Bureau de distribution**

Construction Services Division/Division des services de  
construction  
11 Laurier St./11 Rue Laurier  
3C2, Place du Portage  
Phase III  
Gatineau, Québec K1A 0S5

<b>Title - Sujet</b> O-276 Roof/Siding & O-276 Roof	
<b>Solicitation No. - N° de l'invitation</b> EP076-180006/A	<b>Amendment No. - N° modif.</b> 004
<b>Client Reference No. - N° de référence du client</b> 20180006	<b>Date</b> 2017-08-18
<b>GETS Reference No. - N° de référence de SEAG</b> PW-\$\$\$FG-364-73117	
<b>File No. - N° de dossier</b> fg364.EP076-180006	<b>CCC No./N° CCC - FMS No./N° VME</b>
<b>Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2017-08-24</b>	<b>Time Zone Fuseau horaire</b> Eastern Daylight Saving Time EDT
<b>F.O.B. - F.A.B.</b>	
<b>Plant-Usine:</b> <input type="checkbox"/> <b>Destination:</b> <input type="checkbox"/> <b>Other-Autre:</b> <input type="checkbox"/>	
<b>Address Enquiries to: - Adresser toutes questions à:</b> Doyle, Ashton	<b>Buyer Id - Id de l'acheteur</b> fg364
<b>Telephone No. - N° de téléphone</b> (873) 469-4679 ( )	<b>FAX No. - N° de FAX</b> ( ) -
<b>Destination - of Goods, Services, and Construction: Destination - des biens, services et construction:</b>	

**Instructions: See Herein**

**Instructions: Voir aux présentes**

<b>Delivery Required - Livraison exigée</b>	<b>Delivery Offered - Livraison proposée</b>
<b>Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur</b>	
<b>Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur</b>	
<b>Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)</b>	
<b>Signature</b>	<b>Date</b>

Solicitation No. - N° de l'invitation  
EP076-180006/A

Amd. No. - N° de la modif.  
004

Buyer ID - Id de l'acheteur  
FG364

Client Ref. No. - N° de réf. du client  
20180006 FG364

File No. - N° du dossier  
EP076-180006/A

Project No. - N° du projet  
R.081980.001

This Amendment number 004 is raised to:

1. Publish industry questions and responses; and
  2. Issue addendum 004.
- 

1. The following question is hereby responded to (note that questions 1 - 19 were responded to in previous amendments):

Question #20

The details 17 through 21 on A303 are listed as scale 1:10, but they appear to be at the scale 1:5. Can you have your technical team correct these by addenda?

Answer #20

Refer to addendum no. 004.

Question #21

Detail 3 A-201 there are numerous piece of equipment in the way (furniture, mechanical ducts, gym area etc...)? Will the furniture be moved while the works get done?

Answer #21

Yes; furniture and gym equipment will be moved

Question #22

What is the extend of the foaming application at both ends of building at the precast panels (from which grid line)?

Answer #22

See Drawings 1/A102 & 2/A102 for extent of panel replacement and foaming applications

Question #23

Is there parking space available on site?

Answer #23

Bid as per specifications, Section 01 52 00 point 1.7.1

Question #24

Detail 5 A-102 can we install scaffolding at the mezzanine 3 level in order to have access to do the foam and drywall application . Are there any load restrictions at the mezzanine floor?

Answer #24

Solicitation No. - N° de l'invitation  
EP076-180006/A

Amd. No. - N° de la modif.  
004

Buyer ID - Id de l'acheteur  
FG364

Client Ref. No. - N° de réf. du client  
20180006 FG364

File No. - N° du dossier  
EP076-180006/A

Project No. - N° du projet  
R.081980.001

Not for normal loads associated with gypsum board and foaming installations

Question #25

Could you please clarify the tapered insulation requirements on building T-58. Does this roof system require full tapered insulation?

Answer #25

Install tapered insulation as indicated on Drawing 1/A101 Roof Plan

Question #26

Can the roofing subcontractors carry their own bid bonds & performance bonds for this project?

Answer #26

Bid as per solicitation documents. Refer to SC02 Insurance Terms of the Invitation to Tender.

Question #27

Division 09 91 99 Section 2.06.1 Exterior painting – galvanized metal – does this mean we have to paint or repaint all galvanized steel walkways, stairs, structural steel, platforms and mechanical and electrical equipment specified under this contract?

Answer #27

Do not paint existing galvanized metal.

Question #28

Detail 14 on A105 does not tell us if we should remove the stairs and how to proceed with the roofing replacement at the end of the stairs. Similar to detail 15 on A105.

Answer #28

Detail 14/A105; Do not remove the stairs; see drawings 19/A302 & 20/A302  
Detail 15/A105 - Remove the stairs

Question #29

Detail 10 on A105 does not tell us if we should remove the stairs, or platform supports to proceed with the roofing replacement.

Answer #29

Do not remove the stairs or platform

Question #30

Will we have temporary access to inside the Hangar T-58 with lifting equipment if needed?  
What will be the restrictions applied?

Solicitation No. - N° de l'invitation  
EP076-180006/A

Amd. No. - N° de la modif.  
004

Buyer ID - Id de l'acheteur  
FG364

Client Ref. No. - N° de réf. du client  
20180006 FG364

File No. - N° du dossier  
EP076-180006/A

Project No. - N° du projet  
R.081980.001

**Answer #30**

Yes; Use only electric powered lifting equipment.

**Question #31**

Note 18 on Sheet A203 indicates to remove and reinstall the garbage compacter however, the site plan indicates that it is to remain functional during the project. Please clarify if it is to be disconnected or not.

**Answer #31**

Compactor must remain functional. Remove and re-install when Metal panels are installed in this location.

**Question #32**

Note 19 on Sheet A202 and A203 indicates to remove and replace the existing exterior metal door (at grid C on elevation 1/A203) however the details shown on 3 and 4/A305 indicate this is a new door and frame. Will there be new hardware for this door? Please clarify.

**Answer #32**

Refer to Addendum 001.

**All other terms and conditions remain unchanged**

Solicitation No. - N° de l'invitation  
EP076-180006/A

Amd. No. - N° de la modif.  
004

Buyer ID - Id de l'acheteur  
FG364

Client Ref. No. - N° de réf. du client  
20180006 FG364

File No. - N° du dossier  
EP076-180006/A

Project No. - N° du projet  
R.081980.001

### **Addendum No. 004**

**Project Number: R.081980.001**

**The following changes in the bid documents are effective immediately. This addendum will form part of the contract documents.**

### **DRAWINGS**

1. A 303
  1. Details 17/A303; 18/A303; 19/A303; 19A/A303 & 21/A303: Revise the scale of these details from Scale 1:10 to Scale 1:5