

MCTS CENTRE PORT AUX BASQUES, NL

Addendum 2

The following shall be included in the scope of the Work of this project.

PART A – REQUEST FOR CLARIFICATIONS

Q Section 09 80 00 – Acoustical Treatment indicates an “Acoustic Wall Panel System” (2.1.1) that is described as being “Demountable acoustic units” (2.3.1), but locations are not identified in the drawings. Where and to what extent is this needed?

A. See item #3 below – Part B Specifications

Q. Could you provide the measurements on the Stormwater Treatment Unit (oil/water separator) for the Port aux Basques MCTS Facilities, Drawing C9 has no dimensions for this particular item.

A. "Stormwater treatment unit detail provided on drawing C9 is a generic representation of a Stormwater treatment unit. Contractor shall provide a Stormwater treatment unit that is sized to meet the general and performance requirements outlined in Section 33 06 01 - Oil/Sediment Interceptor of the specifications."

Q. Mechanical Acceptable Alternative Materials:

General Note (Acceptable Alternative Materials) - All alternate products must satisfy requirements for capacity, quality and performance as specified on the design drawings and specifications. Products must be CSA and/or cULC certified (ie. if any of the manufacturers products referenced below, and in the attachments, are not approved for use in Canada, shop drawing submittals will be rejected). Acceptance of these products for alternate submission does not guarantee approval during shop drawing review as the products must meet the design requirements for final approval. Any extra costs, delays, or problems associated with the use and installation of this equipment will be the responsibility of the Contractor.

A. The products listed below are accepted for alternative submission, but must satisfy all requirements of the design and restrictions as listed in the General Note above:

<u>Section</u>	<u>Equipment</u>	<u>Alternate Product</u>
23 33 15	Dampers	Alumavent / Ventex
23 33 16	Fire Dampers	Alumavent / Ventex
23 34 04	Inline Fans	ACME Eng. & Mfg. Co

23 34 00	General Purpose Fans	ACME Eng. & Mfg. Co
23 37 13	Supply Diffusers/Grilles, and Return & Exhaust Grilles	Airvector
23 37 20	Gravity Roof Vent and Louvres	Ventex
23 55 01	Duct Heaters	Thermolec (these were specified on the drawings (Reheat Coil Schedule))
23 72 01	Heat Recovery Ventilators	Aldes
23 10 02	Haz. Gas Detection System	Honeywell 301-C Controller & E3 Point CO & NO2 Sensors
23 81 24	Multiple Split AC System (VRF)	Trane

Q. 2.1.2 Linoleum sheet is specified as 3.2 mm, in most buildings now I see the 2.5 mm specified and used and it more readily available. Just wanted to be sure that 3.2 was the one required.

A. See item #2 below – Part B Specifications

Q. Section 10 99 90 – Manufactured Specialities includes: Roll-up- Map” (2.4), but none are identified in the drawings. Where and to what extent is this needed?

A. One roll-up mat required for Corridor 112, adjacent to door 113.
Size: 1.5m x 3.0m

PART B – SPECIFICATIONS

1. Section 00 01 11 – List of Contents

1. Delete Section 00 01 11 – List of Contents, revise the following Section page numbers listed below,
01 35 29.06 – Health and Safety Requirements, delete 17 and replace with 10

2. Section 09 65 16 – Resilient Sheet Flooring

1. Delete Clause 2.1.2.2 and replace with new Clause to read as follows;
.2 Thickness: 2.5 mm.

Solicitation No. - N° de l'invitation

EA003-180854/A

Client Ref. No. - N° de réf. du client

R.082780.004

Amd. No. - N° de la modif.

002

File No. - N° du dossier

PWD-7-40083

Buyer ID - Id de l'acheteur

pwd005

CCC No./N° CCC - FMS No./N° VME

3. Section 09 80 00 – Acoustic Treatment

1. Delete Section 09 80 00 – Acoustic Treatment from the contract documents in its entirety and remove this reference from the List of Contents – Section 00 01 11

END OF ADDENDUM