



## RETURN BIDS TO:

## RETOURNER LES SOUMISSIONS À:

Bid Receiving Public Works and Government  
Services Canada/Réception des soumissions Travaux  
publics et Services gouvernementaux Canada  
800 Burrard Street, Room 219  
800, rue Burrard, pièce 219  
Vancouver  
British Columbia  
V6Z 0B9  
Bid Fax: (604) 775-9381

## SOLICITATION AMENDMENT MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise  
indicated, all other terms and conditions of the Solicitation  
remain the same.

Ce document est par la présente révisé; sauf indication contraire,  
les modalités de l'invitation demeurent les mêmes.

### Comments - Commentaires

Vendor/Firm Name and Address  
Raison sociale et adresse du  
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution  
Public Works and Government Services Canada - Pacific  
Region  
800 Burrard Street, Room 219  
800, rue Burrard, pièce 219  
Vancouver  
British C  
V6Z 0B9

<b>Title - Sujet</b> Fire Alarm System Replacement	
<b>Solicitation No. - N° de l'invitation</b> EZ899-180659/A	<b>Amendment No. - N° modif.</b> 002
<b>Client Reference No. - N° de référence du client</b>	<b>Date</b> 2017-08-22
<b>GETS Reference No. - N° de référence de SEAG</b> PW-\$PWY-028-8134	
<b>File No. - N° de dossier</b> PWY-7-40115 (028)	<b>CCC No./N° CCC - FMS No./N° VME</b>
<b>Solicitation Closes - L'invitation prend fin</b> <b>at - à 02:00 PM</b> <b>on - le 2017-08-30</b>	<b>Time Zone</b> <b>Fuseau horaire</b> Pacific Daylight Saving Time PDT
<b>F.O.B. - F.A.B.</b> <b>Plant-Usine:</b> <input type="checkbox"/> <b>Destination:</b> <input checked="" type="checkbox"/> <b>Other-Autre:</b> <input type="checkbox"/>	
<b>Address Enquiries to: - Adresser toutes questions à:</b> Lam (PWY), Tian	<b>Buyer Id - Id de l'acheteur</b> pwy028
<b>Telephone No. - N° de téléphone</b> (604) 363-7968 ( )	<b>FAX No. - N° de FAX</b> (604) 775-6633
<b>Destination - of Goods, Services, and Construction:</b> <b>Destination - des biens, services et construction:</b> CSC - William Head Institution - Victoria, BC	

Instructions: See Herein

Instructions: Voir aux présentes

<b>Delivery Required - Livraison exigée</b>	<b>Delivery Offered - Livraison proposée</b>
<b>Vendor/Firm Name and Address</b> <b>Raison sociale et adresse du fournisseur/de l'entrepreneur</b>	
<b>Telephone No. - N° de téléphone</b> <b>Facsimile No. - N° de télécopieur</b>	
<b>Name and title of person authorized to sign on behalf of Vendor/Firm</b> <b>(type or print)</b> <b>Nom et titre de la personne autorisée à signer au nom du fournisseur/</b> <b>de l'entrepreneur (taper ou écrire en caractères d'imprimerie)</b>	
<b>Signature</b>	<b>Date</b>

Solicitation No. - N° de l'invitation  
EZ899-180659/A

Amd. No. - N° de la modif.  
002

Buyer ID - Id de l'acheteur  
pwy028

Client Ref. No. - N° de réf. du client

File No. - N° du dossier CCC No./N°

CCC - FMS No./N° VME

---

The Solicitation Amendment 002 is raised to issue Addendum 001.

Please find Addendum 001 herein.

All other terms and conditions remain unchanged.

The following changes in the tender documents are effective immediately. This addendum will form part of the contract documents.

---

## DRAWINGS

### .1 Drawing FP-001- Legend and drawing list

1. Add general project note 5 as follows “5. All new pipe and equipment is to be painted red. All touch ups are to be made to match existing paint colours. All exposed piping, to be painted, shall be factory sandblasted and prime coated after fabrication with two coats of red primer. “

## QUESTIONS & ANSWERS

1. **Q:** The specs and plans call for tamper and flow switches to be added to the piping, however I noticed that there are already a number of new tamper switches installed to valves and not electrically connected. There is also conduit and wire installed in the vicinity of some of these valves and switches. Are these switches to be completed under this contract? **A:** These switches are indicated on the drawing FP-102 as drawing note 41 . Each of these tamper switches have been installed and are to be provided with wiring to be installed back to the fire alarm panel in this room.
2. **Q:** Stantec Hazardous Building Materials Assessment does not say if lead paint is leachable or non-leachable. Please confirm as it affects disposal requirements/costs? **A:** No lead-containing material will be going to the landfill on this project. There are no affects to be considered.
3. **Q:** Existing piping is painted. Is new pipe to be painted to match? Or is not in contract. **A:** Refer to the additional note added to FP-001 above for answer.

## SPECIFICATIONS

### .1 N/A

1.

**END OF ADDENDUM No. 1**

---