



NOTES:

- SEE DETAIL DRAWING E-26.
- SEE BOILER ROOM MCC DETAIL ON DRAWING E-29.
- EXISTING 100 FRACTIONAL H.P. SUMP PUMP LOCATED UNDER ROOM 032. PROVIDE NEW MANUAL MOTOR STARTER & CIRCUITRY.
- DIV. 16 CONTRACTOR IS RESPONSIBLE FOR CUTTING & PATCHING OF EXISTING ASPHALT FOR CARD READERS.
- MODIFIED DOOR OPERATOR BY DIV. 1 CONTRACTOR. CONDUIT & WIRE BY DIV. 16.
- DEVICE BOX & CIRCUIT FOR HAND DRYER. HAND DRYERS BY DIV. 1.
- ALL UNIT HEATERS SUPPLIED AND INSTALLED BY DIV. 15 CONTRACTOR. ALL MANUAL MOTOR STARTERS AND LINE VOLTAGE TRANSFORMERS SUPPLIED AND INSTALLED BY DIV. 16 CONTRACTOR.
- DIV. 16 TO SUPPLY AND INSTALL A 2-SPEED COMBINATION STARTER FOR EX. 7. CO-ORDINATE WITH DIV. 15 CONTRACTOR.

BASEMENT FLOOR PLAN

SCALE: 1/8" = 1'-0"

FIT-UP REQUIREMENTS DELETION OF RECEPTACLES DELETION OF MODIFIED WALL AND ASSOCIATED CARD READERS ADDITIONS OF UNIT HEATERS	
revisions	date

A	A detail no. no. du détail	A
C	B location drawing no. sur dessin no.	B C

project  
G.O.C.B.  
BEDFORD ROW  
HALIFAX, N.S.

FIT-UP REQUIREMENTS

drawing  
BASEMENT FLOOR PLAN  
POWER

ELECTRICAL

designed	G.C. HICKS	conçu
date		
drawn	W.SZUBIELSKI	dessiné
date		
reviewed	<i>[Signature]</i>	examiné
date	Apr 14/91	
approved		approuvé
date		
Tender	<i>[Signature]</i>	Soumission
PWC Project Manager	Administrateur de projets TPC	
project number	800769	no. du projet
drawing no.	E-11	no. du dessin