

Part 1 General

1.1 Summary

- .1 Section Includes.
 - .1 Methods and procedures for start-up, verification and commissioning, for building Energy Monitoring and Control System (EMCS) and includes:
 - .1 Start-up testing and verification of systems.
 - .2 Check out demonstration or proper operation of components.
 - .3 On-site operational tests.

1.2 Definitions

- .1 For additional acronyms and definitions refer to Section 25 05 01 - EMCS: General Requirements.
- .2 AEL: ratio between total test periods less any system downtime accumulated within that period and test period.
- .3 Downtime: results whenever EMCS is unable to fulfill required functions due to malfunction of equipment defined under responsibility of EMCS contractor. Downtime is measured by duration, in time, between time that Contractor is notified of failure and time system is restored to proper operating condition. Downtime not to include following:
 - .1 Outage of main power supply in excess of back-up power sources, provided that:
 - .1 Automatic initiation of back-up was accomplished.
 - .2 Automatic shut-down and re-start of components was as specified.
 - .2 Failure of communications link, provided that:
 - .1 Controller automatically and correctly operated in stand-alone mode.
 - .2 Failure was not due to failure of any specified EMCS equipment.
 - .3 Functional failure resulting from individual sensor inputs or output devices, provided that:
 - .1 System recorded said fault.
 - .2 Equipment defaulted to fail-safe mode.
 - .3 AEL of total of all input sensors and output devices is at least 99 % during test period.

1.3 Design Requirements

- .1 Confirm with Departmental Representative that Design Criteria and Design Intents are still applicable.
- .2 Commissioning personnel to be fully aware of and qualified to interpret Design Criteria and Design Intents.

1.4 Action And Informational Submittals

- .1 Submittals in accordance with Section 01330 - Submittal Procedures.

- .2 Final Report: submit report to Departmental Representative.
 - .1 Include measurements, final settings and certified test results.
 - .2 Bear signature of commissioning technician and supervisor
 - .3 Report format to be approved by Departmental Representative before commissioning is started.
 - .4 Revise "as-built" documentation, commissioning reports to reflect changes, adjustments and modifications to EMCS as set during commissioning and submit to Departmental Representative in accordance with Section 01 78 00 - Closeout Submittals.
 - .5 Recommend additional changes and/or modifications deemed advisable in order to improve performance, environmental conditions or energy consumption.

1.5 Closeout Submittals

- .1 Provide documentation, O M Manuals, and training of O M personnel for review of Departmental Representative before interim acceptance in accordance with Section 01 78 00 - Closeout Submittals.

1.6 Commissioning

- .1 Do commissioning in accordance with Section 01 91 13 - General Commissioning (Cx) Requirements.
- .2 Carry out commissioning under direction of Departmental Representative and in presence of Departmental Representative.
- .3 Inform, and obtain approval from, Departmental Representative in writing at least 14 days prior to commissioning or each test. Indicate:
 - .1 Location and part of system to be tested or commissioned.
 - .2 Testing/commissioning procedures, anticipated results.
 - .3 Names of testing/commissioning personnel.
- .4 Correct deficiencies, re-test in presence of Departmental Representative until satisfactory performance is obtained.
- .5 Acceptance of tests will not relieve Contractor from responsibility for ensuring that complete systems meet every requirement of Contract.
- .6 Load system with project software.
- .7 Perform tests as required.

1.7 Completion Of Commissioning

- .1 Commissioning to be considered as satisfactorily completed when objectives of commissioning have been achieved and reviewed by Departmental Representative and PWGSC Commissioning Manager.

1.8 Issuance Of Final Certificate Of Completion

- .1 Final Certificate of Completion will not be issued until receipt of written approval indicating successful completion of specified commissioning activities including receipt of commissioning documentation.

Part 2 Products

2.1 Equipment

- .1 Provide sufficient instrumentation to verify and commission the installed system. Provide two-way radios.
- .2 Instrumentation accuracy tolerances: higher order of magnitude than equipment or system being tested.
- .3 Independent testing laboratory to certify test equipment as accurate to within approved tolerances no more than 2 months prior to tests.
- .4 Locations to be approved, readily accessible and readable.
- .5 Application: to conform to normal industry standards.

Part 3 Execution

3.1 Procedures

- .1 Test each system independently and then in unison with other related systems.
- .2 Commission each system using procedures prescribed by the Departmental Representative.
- .3 Commission integrated systems using procedures prescribed by Departmental Representative.
- .4 Debug system software.
- .5 Optimize operation and performance of systems by fine-tuning PID values and modifying CDLs as required.
- .6 Test full scale emergency evacuation and life safety procedures including operation and integrity of smoke management systems under normal and emergency power conditions as applicable.

3.2 Field Quality Control

- .1 Pre-Installation Testing.
 - .1 General: consists of field tests of equipment just prior to installation.
 - .2 Testing may be on site or at Contractor's premises as approved by Departmental Representative.
 - .3 Configure major components to be tested in same architecture as designed system. Include BECC equipment and 2 sets of Building Controller's including MCU's, LCU's, and TCU's.
 - .4 Equip each Building Controller with sensor and controlled device of each type (AI, AO, DI, DO).
 - .5 Additional instruments to include:
 - .1 DP transmitters.
 - .2 VAV supply duct SP transmitters.
 - .3 DP switches used for dirty filter indication and fan status.

- .6 In addition to test equipment, provide inclined manometer, digital micro-manometer, milli-amp meter, source of air pressure infinitely adjustable between 0 and 500 Pa, to hold steady at any setting and with direct output to milli-amp meter at source.
- .7 After setting, test zero and span in 10% increments through entire range while both increasing and decreasing pressure.
- .8 Departmental Representative to mark instruments tracking within % in both directions as "approved for installation".
- .9 Transmitters above 0.5% error will be rejected.
- .10 DP switches to open and close within 2% of setpoint.
- .2 Completion Testing.
 - .1 General: test after installation of each part of system and after completion of mechanical and electrical hook-ups, to verify correct installation and functioning.
 - .2 Include following activities:
 - .1 Test and calibrate field hardware including stand-alone capability of each controller.
 - .2 Verify each A-to-D convertor.
 - .3 Test and calibrate each AI using calibrated digital instruments.
 - .4 Test each DI to ensure proper settings and switching contacts.
 - .5 Test each DO to ensure proper operation and lag time.
 - .6 Test each AO to ensure proper operation of controlled devices. Verify tight closure and signals.
 - .7 Test operating software.
 - .8 Test application software and provide samples of logs and commands.
 - .9 Verify each CDL including energy optimization programs.
 - .10 Debug software.
 - .11 Blow out flow measuring and static pressure stations with high pressure air at 700 kPa.
 - .12 Provide point verification list in table format including point identifier, point identifier expansion, point type and address, low and high limits and engineering units. Include space on commissioning technician and Departmental Representative. This document will be used in final startup testing.
 - .3 Final Start-up Testing: Upon satisfactory completion of tests, perform point-by-point test of entire system under direction of Departmental Representative and provide:
 - .1 2 technical personnel capable of re-calibrating field hardware and modifying software.
 - .2 Detailed daily schedule showing items to be tested and personnel available.
 - .3 Departmental Representative's acceptance signature to be on executive and applications programs.
 - .4 Commissioning to commence during final startup testing.

- .5 O M personnel to assist in commissioning procedures as part of training.
- .6 Commissioning to be supervised by qualified supervisory personnel and Departmental Representative.
- .7 Commission systems considered as life safety systems before affected parts of the facility are occupied.
- .8 Operate systems as long as necessary to commission entire project.
- .9 Monitor progress and keep detailed records of activities and results.
- .4 Final Operational Testing: to demonstrate that EMCS functions in accordance with contract requirements.
 - .1 Prior to beginning of 30 day test demonstrate that operating parameters (setpoints, alarm limits, operating control software, sequences of operation, trends, graphics and CDL's) have been implemented to ensure proper operation and operator notification in event of off-normal operation.
 - .1 Repetitive alarm conditions to be resolved to minimize reporting of nuisance conditions.
 - .2 Test to last at least 30 consecutive 24 hour days.
 - .3 Tests to include:
 - .1 Demonstration of correct operation of monitored and controlled points.
 - .2 Operation and capabilities of sequences, reports, special control algorithms, diagnostics, software.
 - .4 System will be accepted when:
 - .1 EMCS equipment operates to meet overall performance requirements. Downtime as defined in this Section must not exceed allowable time calculated for this site.
 - .2 Requirements of Contract have been met.
 - .5 In event of failure to attain specified AEL during test period, extend test period on day-to-day basis until specified AEL is attained for test period.
 - .6 Correct defects when they occur and before resuming tests.
- .5 Departmental Representative to verify reported results.

3.3 Adjusting

- .1 Final adjusting: upon completion of commissioning as reviewed by Departmental Representative, set and lock devices in final position and permanently mark settings.

3.4 Demonstration

- .1 Demonstrate to Departmental Representative operation of systems including sequence of operations in regular and emergency modes, under normal and emergency conditions, start-up, shut-down interlocks and lock-outs in accordance with Section 01 79 00 - Demonstration and Training.

END OF SECTION

Part 1 General

1.1 Summary

- .1 Section Includes:
 - .1 General requirements for building Energy Monitoring and Control System (EMCS) that are common to NMS EMCS Sections.

1.2 References

- .1 American National Standards Institute (ANSI)/The Instrumentation, Systems and Automation Society (ISA).
 - .1 ANSI/ISA 5.5, Graphic Symbols for Process Displays.
- .2 American National Standards Institute (ANSI)/ Institute of Electrical and Electronics Engineers (IEEE).
 - .1 ANSI/IEEE 260.1, American National Standard Letter Symbols Units of Measurement (SI Units, Customary Inch-Pound Units, and Certain Other Units).
- .3 American Society of Heating, Refrigerating and Air-Conditioning Engineers, Inc. (ASHRAE).
 - .1 ASHRAE STD 135, BACNET - Data Communication Protocol for Building Automation and Control Network.
- .4 Canadian Standards Association (CSA International).
 - .1 CAN/CSA-Z234.1, Canadian Metric Practice Guide.
- .5 Consumer Electronics Association (CEA).
 - .1 CEA-709.1, Control Network Protocol Specification.
- .6 Department of Justice Canada (Jus).
 - .1 Canadian Environmental Assessment Act (CEAA), 1995, c. 37.
 - .2 Canadian Environmental Protection Act (CEPA), 1999, c. 33.
- .7 Electrical and Electronic Manufacturers Association (EEMAC).
 - .1 EEMAC 2Y-1, Light Gray Colour for Indoor Switch Gear.
- .8 Health Canada/Workplace Hazardous Materials Information System (WHMIS).
 - .1 Material Safety Data Sheets (MSDS).
- .9 Transport Canada (TC).
 - .1 Transportation of Dangerous Goods Act (TDGA), 1992, c. 34.

1.3 Acronyms And Abbreviations

- .1 Acronyms used in EMCS:
 - .1 AEL - Average Effectiveness Level.
 - .2 AI - Analog Input.

- .3 AIT - Agreement on International Trade.
- .4 AO - Analog Output.
- .5 BACnet - Building Automation and Control Network.
- .6 BC(s) - Building Controller(s).
- .7 BECC - Building Environmental Control Center.
- .8 CAD - Computer Aided Design.
- .9 CDL - Control Description Logic.
- .10 CDS - Control Design Schematic.
- .11 COSV - Change of State or Value.
- .12 CPU - Central Processing Unit.
- .13 DI - Digital Input.
- .14 DO - Digital Output.
- .15 DP - Differential Pressure.
- .16 ECU - Equipment Control Unit.
- .17 EMCS - Energy Monitoring and Control System.
- .18 HVAC - Heating, Ventilation, Air Conditioning.
- .19 IDE - Interface Device Equipment.
- .20 I/O - Input/Output.
- .21 ISA - Industry Standard Architecture.
- .22 LAN - Local Area Network.
- .23 LCU - Local Control Unit.
- .24 MCU - Master Control Unit.
- .25 NAFTA - North American Free Trade Agreement.
- .26 NC - Normally Closed.
- .27 NO - Normally Open.
- .28 OS - Operating System.
- .29 O M - Operation and Maintenance.
- .30 OWS - Operator Work Station.
- .31 PC - Personal Computer.
- .32 PCI - Peripheral Control Interface.
- .33 PCMCIA - Personal Computer Micro-Card Interface Adapter.
- .34 PID - Proportional, Integral and Derivative.
- .35 RAM - Random Access Memory.
- .36 SP - Static Pressure.
- .37 ROM - Read Only Memory.
- .38 TCU - Terminal Control Unit.
- .39 USB - Universal Serial Bus.
- .40 UPS - Uninterruptible Power Supply.
- .41 VAV - Variable Air Volume.

1.4 Definitions

- .1 Point: may be logical or physical.
 - .1 Logical points: values calculated by system such as setpoints, totals, counts, derived corrections and may include, but not limited to result of and statements in CDL's.
 - .2 Physical points: inputs or outputs which have hardware wired to controllers which are measuring physical properties, or providing status conditions of contacts or relays which provide interaction with related equipment (stop, start) and valve or damper actuators.
- .2 Point Name: composed of two parts, point identifier and point expansion.
 - .1 Point identifier: comprised of three descriptors, "area" descriptor, "system" descriptor and "point" descriptor, for which database to provide 25 character field for each point identifier. "System" is system that point is located on.
 - .1 Area descriptor: building or part of building where point is located.
 - .2 System descriptor: system that point is located on.
 - .3 Point descriptor: physical or logical point description. For point identifier "area", "system" and "point" will be short forms or acronyms. Database must provide 25 character field for each point identifier.
 - .2 Point expansion: comprised of three fields, one for each descriptor. Expanded form of short form or acronym used in "area", "system" and "point" descriptors is placed into appropriate point expansion field. Database must provide 32 character field for each point expansion.
 - .3 Bilingual systems to include additional point identifier expansion fields of equal capacity for each point name for second language.
 - .1 System to support use of numbers and readable characters including blanks, periods or underscores to enhance user readability for each of the above strings.
- .3 Point Object Type: points fall into following object types:
 - .1 AI (analog input).
 - .2 AO (analog output).
 - .3 DI (digital input).
 - .4 DO (digital output).
 - .5 Pulse inputs.
- .4 Symbols and engineering unit abbreviations utilized in displays: to ANSI/ISA S5.5.
 - .1 Printouts: to ANSI/IEEE 260.1.
 - .2 Refer also to Section 25 05 54- EMCS: Identification.

1.5 System Description

- .1 Refer to control schematics for system architecture.
- .2 Work covered by sections referred to above consists of fully operational EMCS, including, but not limited to, following:
 - .1 Building Controllers.
 - .2 Control devices as listed in I/O point summary tables.

- .3 OWS(s).
- .4 Data communications equipment necessary to effect EMCS data transmission system.
- .5 Field control devices.
- .6 Software/Hardware complete with full documentation.
- .7 Complete operating and maintenance manuals.
- .8 Training of personnel.
- .9 Acceptance tests, technical support during commissioning, full documentation.
- .10 Wiring interface co-ordination of equipment supplied by others.
- .11 Miscellaneous work as specified in these sections and as indicated.
- .3 Design Requirements:
 - .1 Design and provide conduit and wiring linking elements of system.
 - .2 Supply sufficient programmable controllers of types to meet project requirements. Quantity and points contents as reviewed by Departmental Representative prior to installation.
 - .3 Location of controllers as reviewed by Departmental Representative prior to installation.
 - .4 Provide utility power to EMCS and emergency power to EMCS as indicated.
 - .5 Metric references: in accordance with CAN/CSA Z234.1.
- .4 Language Operating Requirements:
 - .1 Provide English operator selectable access codes.
 - .2 Use non-linguistic symbols for displays on graphic terminals wherever possible. Other information to be in English.
 - .3 Operating system executive: provide primary hardware-to-software interface with associated documentation to be in English.
 - .4 System manager software: include in English system definition point database, additions, deletions or modifications, control loop statements, use of high level programming languages, report generator utility and other OS utilities used for maintaining optimal operating efficiency.
 - .5 Include, in English:
 - .1 Input and output commands and messages from operator-initiated functions, field related changes, alarms as defined in CDL's or assigned limits (i.e. commands relating to day-to-day operating functions and not related to system modifications, additions, or logic re-definitions).
 - .2 Graphic "display" functions, point commands to turn systems on or off, manually override automatic control of specified hardware points.
 - .3 Reporting function such as trend log, trend graphics, alarm report logs, energy report logs, maintenance generated logs.
- .5 Contractor to update existing graphics as per new system configuration. Implement a warm-up routine with night temperature setback. Coordinate graphic requirements with Departmental Representative.

1.6 Action And Informational Submittals

- .1 Make submittals in accordance with 25 05 02 - EMCS: Shop Drawings, Product Data and Review Process.
- .2 Submit for review:
 - .1 Equipment list, systems manufacturers, at time of bid.
 - .2 List existing field control devices to be re-used included in bid, along with unit price.
- .3 Quality Control:
 - .1 Provide equipment and material from manufacturer's regular production, CSA certified, manufactured to standard quoted plus additional specified requirements.
 - .2 Where CSA certified equipment is not available submit such equipment to inspection authorities for special inspection and approval before delivery to site.
 - .3 Submit proof of compliance to specified standards with shop drawings and product data in accordance with Section 25 05 02 - EMCS: Shop Drawings, Product Data and Review Process. Label or listing of specified organization is acceptable evidence.
 - .4 In lieu of such evidence, submit certificate from testing organization, approved by Departmental Representative, certifying that item was tested in accordance with their test methods and that item conforms to their standard/code.
 - .5 For materials whose compliance with organizational standards/codes/specifications is not regulated by organization using its own listing or label as proof of compliance, furnish certificate stating that material complies with applicable referenced standard or specification.
 - .6 Permits and fees: in accordance with general conditions of contract.
 - .7 Submit certificate of acceptance from authority having jurisdiction to Departmental Representative.
 - .8 Existing devices intended for re-use: submit test report.

1.7 Quality Assurance

- .1 For existing buildings, facilities, or campus, match existing controls equipment and provide equipment from same manufacturer and vendor. Installer shall have experience and shall have performed work in the building, facility or campus with in the past 2 yrs.
- .2 Have local office within 50 km of project staffed by trained personnel capable of providing instruction, routine maintenance and emergency service on systems,
- .3 Provide record of successful previous installations submitting tender showing experience with similar installations utilizing computer-based systems.
- .4 Have access to local supplies of essential parts and provide 7 year guarantee of availability of spare parts after obsolescence.
- .5 Ensure qualified supervisory personnel continuously direct and monitor Work and attend site meetings.

1.8 Delivery, Storage And Handling

- .1 Material Delivery Schedule: provide Departmental Representative with schedule within 2 weeks after award of Contract.

1.9 Existing- Control Components

- .1 Utilize existing control wiring and piping where possible.
- .2 Re-use field control devices that are usable in their original configuration provided that they conform to applicable codes, standards specifications.
 - .1 Do not modify original design of existing devices without written permission from Departmental Representative.
 - .2 Provide for new, properly designed device where re-usability of components is uncertain.
- .3 Inspect and test existing devices intended for re-use within 30 days of award of contract, and prior to installation of new devices.
 - .1 Furnish test report within 40 days of award of contract listing each component to be re-used and indicating whether it is in good order or requires repair by Departmental Representative.
 - .2 Failure to produce test report will constitute acceptance of existing devices by contractor.
- .4 Non-functioning items:
 - .1 Provide with report specification sheets or written functional requirements to support findings.
 - .2 Departmental Representative will repair or replace existing items judged defective yet deemed necessary for EMCS.
- .5 Submit written request for permission to disconnect controls and to obtain equipment downtime before proceeding with Work.
- .6 Assume responsibility for controls to be incorporated into EMCS after written receipt of approval from Departmental Representative.
 - .1 Be responsible for items repaired or replaced by Departmental Representative.
 - .2 Be responsible for repair costs due to negligence or abuse of equipment.
 - .3 Responsibility for existing devices terminates upon final acceptance of EMCS.
- .7 Remove existing controls not re-used or not required. Place in approved storage for disposition as directed.

Part 2 Products

2.1 Equipment

- .1 Complete list of equipment and materials to be used on project and forming part of bid documents by adding manufacturer's name, model number and details of materials, and submit for approval.

2.2 Adaptors

- .1 Provide adaptors between metric and imperial components.

Part 3 Execution

3.1 Manufacturer's Recommendations

- .1 Installation: to manufacturer's recommendations.

3.2 Examination

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for installation in accordance with manufacturer's written instructions.
 - .1 Visually inspect substrate.
 - .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.
 - .3 Proceed with installation only after unacceptable conditions have been remedied.

3.3 Painting

- .1 Painting: in accordance with Section 09 91 23 - Interior Painting, supplemented as follows:
 - .1 Clean and touch up marred or scratched surfaces of factory finished equipment to match original finish.
 - .2 Restore to new condition, finished surfaces too extensively damaged to be primed and touched up to make good.
 - .3 Clean and prime exposed hangers, racks, fastenings, and other support components.
 - .4 Paint unfinished equipment installed indoors.

3.4 Cleaning

- .1 Progress Cleaning: clean in accordance with Section 01 74 11 – Cleaning.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 - Cleaning.
- .3 Waste Management: separate waste materials for reuse and recycling.
 - .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.
 - .2

END OF SECTION

Part 1 General

1.1 Summary

- .1 Section Includes.
 - .1 Methods and procedures for shop drawings submittals, preliminary and detailed review process including review meetings, for building Energy Monitoring and Control System (EMCS).

1.2 Definitions

- .1 Acronyms and definitions: refer to Section 25 05 01 - EMCS: General Requirements.

1.3 Design Requirements

- .1 Preliminary Design Review: to contain following contractor and systems information.
 - .1 Location of local office.
 - .2 Description and location of installing and servicing technical staff.
 - .3 Location and qualifications of programming design and programming support staff.
 - .4 List of spare parts.
 - .5 Location of spare parts stock.
 - .6 Names of sub-contractors and site-specific key personnel.
 - .7 Sketch of site-specific system architecture.
 - .8 Specification sheets for each item including memory provided, programming language, speed, type of data transmission.
 - .9 Descriptive brochures.
 - .10 Sample CDL and graphics (systems schematics).
 - .11 Response time for each type of command and report.
 - .12 Item-by-item statement of compliance.
 - .13 Proof of demonstrated ability of system to communicate utilizing BACnet.

1.4 Action And Informational Submittals

- .1 Submittals in accordance with Section 01 33 00 - Submittal Procedures and coordinate with requirements in this Section.
- .2 Submit preliminary design document within 5 working days after tender closing and before contract award, for review by Departmental Representative.
- .3 Shop Drawings to consist of 3 hard copies and 1 soft copy of design documents, shop drawings, product data and software.
- .4 Hard copy to be completely indexed and coordinated package to assure compliance with contract requirements and arranged in same sequence as specification and cross-referenced to specification section and paragraph number.
- .5 Soft copy to be in Autocad - latest version and Microsoft Word latest version format, structured using menu format for easy loading and retrieval on OWS.

1.5 Preliminary Shop Drawing Review

- .1 Submit preliminary shop drawings within 30 working days of award of contract and include following:
 - .1 Specification sheets for each item. To include manufacturer's descriptive literature, manufacturer's installation recommendations, specifications, drawings, diagrams, performance and characteristic curves, catalogue cuts, manufacturer's name, trade name, catalogue or model number, nameplate data, size, layout, dimensions, capacity, other data to establish compliance.
 - .2 Detailed system architecture showing all points associated with each controller including signal levels, pressures where new EMCS ties into existing control equipment.
 - .3 Spare point capacity of each controller by number and type.
 - .4 Controller locations.
 - .5 Auxiliary control cabinet locations.
 - .6 Single line diagrams showing cable routings, conduit sizes, spare conduit capacity between control centre, field controllers and systems being controlled.
 - .7 Valves: complete schedule listing including following information: designation, service, manufacturer, model, point ID, design flow rate, design pressure drop, required Cv, Valve size, actual Cv, spring range, pilot range, required torque, actual torque and close off pressure (required and actual).
 - .8 Dampers: sketches showing module assembly, interconnecting hardware, operator locations, operator spring range, pilot range, required torque, actual torque.
 - .9 Flow measuring stations: complete schedule listing designation, service, point ID, manufacturer, model, size, velocity at design flow rate, manufacturer, model and range of velocity transmitter.
 - .10 Compressor schematic and sizing data.

1.6 Detailed Shop Drawing Review

- .1 Submit detailed shop drawings within 60 working days after award of contract and before start of installation and include following:
 - .1 Corrected and updated versions (hard copy only) of submissions made during preliminary review.
 - .2 Wiring diagrams.
 - .3 Piping diagrams and hook-ups.
 - .4 Interface wiring diagrams showing termination connections and signal levels.
 - .5 Shop drawings for each input/output point, sensors, transmitters, showing information associated with each particular point including:
 - .1 Sensing element type and location.
 - .2 Transmitter type and range.
 - .3 Associated field wiring schematics, schedules and terminations.
 - .4 Complete Point Name Lists.
 - .5 Setpoints, curves or graphs and alarm limits (high and low, 3 types critical, cautionary and maintenance), signal range.

- .6 Software and programming details associated with each point.
- .7 Manufacturer's recommended installation instructions and procedures.
- .8 Input and output signal levels or pressures where new system ties into existing control equipment.
- .6 Control schematics, narrative description, CDL's fully showing and describing automatic and manual procedure required to achieve proper operation of project, including under complete failure of EMCS.
- .7 Graphic system schematic displays of systems with point identifiers and textual description of system, and typical floor plans as specified.
- .8 Complete system CDL's including companion English language explanations on same sheet but with different font and italics. CDL's to contain specified energy optimization programs.
- .9 Listing and example of specified reports.
- .10 Listing of time of day schedules.
- .11 Mark up to-scale construction drawing to detail control room showing location of equipment and operator work space.
- .12 Type and size of memory with statement of spare memory capacity.
- .13 Full description of software programs provided.
- .14 Sample of "Operating Instructions Manual" to be used for training purposes.
- .15 Outline of proposed start-up and verification procedures. Refer to Section 25 01 11 - EMCS: Start-up, Verification and Commissioning.

1.7 Quality Assurance

- .1 Preliminary Design Review Meeting: Convene meeting within 45 working days of award of contract to:
 - .1 Undertake functional review of preliminary design documents, resolve inconsistencies.
 - .2 Resolve conflicts between contract document requirements and actual items (e.g.: points list inconsistencies).
 - .3 Review interface requirements of materials supplied by others.
 - .4 Review "Sequence of Operations".
- .2 Contractor's programmer to attend meeting.
- .3 Departmental Representative retains right to revise sequence or subsequent CDL prior to software finalization without cost to Departmental Representative.

Part 2 Products

2.1 Not Used

- .1 Not Used.

Part 3 Execution

3.1 Not Used

.1 Not Used.

END OF SECTION

Part 1 General

1.1 Summary

- .1 Section Includes.
 - .1 Requirements and procedures for final control diagrams and operation and maintenance (O M) manual, for building Energy Monitoring and Control System (EMCS) Work.

1.2 Definitions

- .1 BECC - Building Environmental Control Centre.
- .2 OWS - Operator Work Station.
- .3 For additional acronyms and definitions refer to Section 25 05 01 - EMCS: General Requirements.

1.3 Action And Informational Submittals

- .1 Submittals in accordance with Section 01 78 00 - Closeout Procedures, supplemented and modified by requirements of this Section.
- .2 Submit Record Documents to Departmental Representative in English.
- .3 Provide soft copies and hard copies in hard-back, 50 mm 3 ring, D-ring binders.
 - .1 Binders to be 2/3 maximum full.
 - .2 Provide index to full volume in each binder.
 - .3 Identify contents of each manual on cover and spine.
 - .4 Provide Table of Contents in each manual.
 - .5 Assemble each manual to conform to Table of Contents with tab sheets placed before instructions covering subject.

1.4 As-Builts

- .1 Provide 1 copy of detailed shop drawings generated in Section 25 05 02 - EMCS: Submittals and Review Process and include:
 - .1 Changes to contract documents as well as addenda and contract extras.
 - .2 Changes to interface wiring.
 - .3 Routing of conduit, wiring and control air lines associated with EMCS installation.
 - .4 Locations of obscure devices to be indicated on drawings.
 - .5 Listing of alarm messages.
 - .6 Panel/circuit breaker number for sources of normal/emergency power.
 - .7 Names, addresses, telephone numbers of each sub-contractor having installed equipment, local representative for each item of equipment, each system.

- .8 Test procedures and reports: provide records of start-up procedures, test procedures, checkout tests and final commissioning reports as specified in Section 25 01 11 - EMCS: Start-up, Verification and Commissioning.
- .9 Basic system design and full documentation on system configuration.
- .2 Submit for final review by Departmental Representative.
- .3 Provide before acceptance 4 Hard and 1 soft copy incorporating changes made during final review.

1.5 O&M Manuals

- .1 Custom design O M Manuals (both hard and soft copy) to contain material pertinent to this project only, and to provide full and complete coverage of subjects referred to in this Section.
- .2 Provide 2 complete sets of hard and soft copies prior to system or equipment tests
- .3 Include complete coverage in concise language, readily understood by operating personnel using common terminology of functional and operational requirements of system. Do not presume knowledge of computers, electronics or in-depth control theory.
- .4 Functional description to include:
 - .1 Functional description of theory of operation.
 - .2 Design philosophy.
 - .3 Specific functions of design philosophy and system.
 - .4 Full details of data communications, including data types and formats, data processing and disposition data link components, interfaces and operator tests or self-test of data link integrity.
 - .5 Explicit description of hardware and software functions, interfaces and requirements for components in functions and operating modes.
 - .6 Description of person-machine interactions required to supplement system description, known or established constraints on system operation, operating procedures currently implemented or planned for implementation in automatic mode.
- .5 System operation to include:
 - .1 Complete step-by-step procedures for operation of system including required actions at each OWS.
 - .2 Operation of computer peripherals, input and output formats.
 - .3 Emergency, alarm and failure recovery.
 - .4 Step-by-step instructions for start-up, back-up equipment operation, execution of systems functions and operating modes, including key strokes for each command so that operator need only refer to these pages for keystroke entries required to call up display or to input command.
- .6 Software to include:
 - .1 Documentation of theory, design, interface requirements, functions, including test and verification procedures.
 - .2 Detailed descriptions of program requirements and capabilities.

- .3 Data necessary to permit modification, relocation, reprogramming and to permit new and existing software modules to respond to changing system functional requirements without disrupting normal operation.
- .4 Software modules, fully annotated source code listings, error free object code files ready for loading via peripheral device
- .5 Complete program cross reference plus linking requirements, data exchange requirements, necessary subroutine lists, data file requirements, other information necessary for proper loading, integration, interfacing, program execution.
- .6 Software for each Controller and single section referencing Controller common parameters and functions.
- .7 Maintenance: document maintenance procedures including inspection, periodic preventive maintenance, fault diagnosis, repair or replacement of defective components, including calibration, maintenance, repair of sensors, transmitters, transducers, controller and interface firmware's, plus diagnostics and repair/replacement of system hardware.
- .8 System configuration document:
 - .1 Provisions and procedures for planning, implementing and recording hardware and software modifications required during operating lifetime of system.
 - .2 Information to ensure co-ordination of hardware and software changes, data link or message format/content changes, sensor or control changes in event that system modifications are required.
- .9 Programmer control panel documentation: provide where panels are independently interfaced with BECC, including interfacing schematics, signal identification, timing diagrams, fully commented source listing of applicable driver/handler.

Part 2 Products

2.1 Not Used

- .1 Not Used.

Part 3 Execution

3.1 Not Used

- .1 Not Used.

END OF SECTION

Part 1 General

1.1 Summary

- .1 Section Includes.
 - .1 Requirements and procedures for identification of devices, sensors, wiring tubing, conduit and equipment, for building Energy Monitoring and Control System (EMCS) Work and nameplates materials, colours and lettering sizes.

1.2 References

- .1 Canadian Standards Association (CSA International).
 - .1 CSA C22.1, The Canadian Electrical Code, Part I (19th Edition), Safety Standard for Electrical Installations.

1.3 Definitions

- .1 For acronyms and definitions refer to Section 25 05 01 - EMCS: General Requirements.

1.4 System Description

- .1 Language Operating Requirements: provide identification for control items in English.

1.5 Action And Informational Submittals

- .1 Submittals in accordance with Section 01 33 00 - Submittal Procedures supplemented and modified by requirements of this Section.
- .2 Submit to Departmental Representative for approval samples of nameplates, identification tags and list of proposed wording.

Part 2 Products

2.1 Nameplates For Panels

- .1 Identify by Plastic laminate, 3 mm thick Melamine, matt white finish, black core, square corners, lettering accurately aligned and engraved into core.
- .2 Sizes: 25 x 67 mm minimum.
- .3 Lettering: minimum 7 mm high, black.
- .4 Inscriptions: machine engraved to identify function.

2.2 Nameplates For Field Devices

- .1 Identify by plastic encased cards attached by chain.
- .2 Sizes: 50 x 100 mm minimum.
- .3 Lettering: minimum 5 mm high produced from laser printer in black\.
- .4 Data to include: point name and point address.

- .5 Companion cabinet: identify interior components using plastic enclosed cards with point name and point address.

2.3 Nameplates For Room Sensors

- .1 Identify by stick-on labels using point identifier.
- .2 Location: as directed by Departmental Representative.
- .3 Letter size: to suit, clearly legible.

2.4 Warning Signs

- .1 Equipment including motors, starters under remote automatic control: supply and install orange coloured signs warning of automatic starting under control of EMCS.
- .2 Sign to read: "Caution: This equipment is under automatic remote control of EMCS" as reviewed by Departmental Representative's.

2.5 Wiring

- .1 Supply and install numbered tape markings on wiring at panels, junction boxes, splitters, cabinets and outlet boxes.
- .2 Colour coding: to CSA C22.1. Use colour coded wiring in communications cables, matched throughout system.
- .3 Power wiring: identify circuit breaker panel/circuit breaker number inside each EMCS panel.

2.6 Conduit

- .1 Colour code EMCS conduit.
- .2 Pre-paint box covers and conduit fittings.
- .3 Coding: use fluorescent orange paint and confirm colour with Departmental Representative during "Preliminary Design Review".

Part 3 Execution

3.1 Nameplates And Labels

- .1 Ensure that manufacturer's nameplates, CSA labels and identification nameplates are visible and legible at all times.

3.2 Existing Panels

- .1 Correct existing nameplates and legends to reflect changes made during Work.

END OF SECTION

Part 1 General

1.1 References

- .1 American National Standards Institute (ANSI)
 - .1 ANSI/ASME B16.22, Wrought Copper and Copper Alloy Solder Joint Pressures Fittings.
 - .2 ANSI C2, National Electrical Safety Code.
 - .3 ANSI/NFPA 70, National Electrical Code.
- .2 CSA Group
 - .1 CSA C22.1,
 - .2 CAN/CSA-C22.3 No. 7, Underground Systems.
 - .3 CSA C22.2 No. 45.1, Electrical Rigid Metal Conduit.
 - .4 CSA C22.2 No. 56, Flexible Metal Conduit and Liquid-Tight Flexible Metal Conduit.
 - .5 CSA C22.2 No. 83, Electrical Metallic Tubing.
 - .6 CAN/CSA-C22.3 No. 1, Overhead Systems.

1.2 System Description

- .1 Electrical:
 - .1 Provide power wiring to EMCS field panels. Circuits to be for exclusive use of EMCS equipment. Panel breakers to be identified on panel legends tagged and locks applied to breaker switches.
 - .2 Hard wiring between field control devices and EMCS field panels.
 - .3 Communication wiring between EMCS field panels and OWS's including main control centre BECC.
 - .4 Modify existing starters to provide for EMCS as indicated in I/O Summaries and as indicated.
 - .5 Refer to wiring diagrams included as part of flow diagrams. Trace existing control wiring installation and provide updated wiring schematics including additions and/or deletions to control circuits for approval by engineer before commencing work.
- .2 Mechanical:
 - .1 Pipe Taps Required for EMCS equipment will be supplied and installed by EMCS Contractor.
 - .2 Wells and Control Valves Shall Be Supplied by EMCS Contractor and Installed by EMCS Contractor.
 - .3 Installation of air flow stations, dampers, and other devices requiring sheet metal trades to be mounted by Division 23. Costs to be carried by designated trade.
- .3 Structural:
 - .1 Special steelwork as required for installation of work.

1.3 Personnel Qualifications

- .1 Qualified supervisory personnel to:
 - .1 Continuously direct and monitor all work.
 - .2 Attend site meetings.

1.4 Existing Conditions

- .1 Cutting and Patching: refer to Section 01 73 00 - Execution supplemented as specified herein.
- .2 Repair all surfaces damaged during execution of work.
- .3 Turn over to Departmental Representative existing materials removed from work not identified for re-use.

Part 2 Products

2.1 Special Supports

- .1 Structural grade steel, primed and painted after construction and before installation.

2.2 Wiring

- .1 As per requirements of Division 26.
- .2 For 70V and above copper conductor with chemically cross-linked thermosetting polyethylene insulation rated RW90 and 600V. Colour code to CSA 22.1.
- .3 For wiring under 70 volts use FT6 rated wiring where wiring is not run in conduit. All other cases use FT4 wiring.
- .4 Sizes:
 - .1 120V Power supply: to match or exceed breaker, size #12 minimum.
 - .2 Wiring for safeties/interlocks for starters, motor control centres, to be stranded, #14 minimum.
 - .3 Field wiring to digital device: 20 AWG stranded twisted pair, minimum.
 - .4 Analog input and output: shielded #20 minimum stranded twisted pair. Wiring must be continuous without joints.
 - .5 More than 4 conductors: #22 minimum solid copper.
- .5 Terminations:
 - .1 Terminate wires with screw terminal type connectors suitable for wire size, and number of terminations.

2.3 Conduit

- .1 As per requirements of Division 26.
- .2 Electrical metallic tubing to CSA C22.2 No. 83. Flexible and liquid tight flexible metal conduit to CSA C22.2 No. 56. Rigid steel threaded conduit to CSA C22.2 No. 45.1.
- .3 Junction and pull boxes: welded steel.
 - .1 Surface mounting cast FS: screw-on flat covers.

- .2 Flush mounting: covers with 25 mm minimum extension all round.
- .4 Cabinets: sheet steel, for surface mounting, with hinged door, latch lock, 2 keys, complete with perforated metal mounting backboard. Panels to be keyed alike for similar functions and or entire contract as approved.
- .5 Outlet boxes: 100 mm minimum, square.
- .6 Conduit boxes, fittings:
 - .1 Bushings and connectors: with nylon insulated throats.
 - .2 With push pennies to prevent entry of foreign materials.
- .7 Fittings for rigid conduit:
 - .1 Couplings and fittings: threaded type steel.
 - .2 Double locknuts and insulated bushings: use on sheet metal boxes.
 - .3 Use factory "ells" where 90 degree bends required for 25 mm and larger conduits.
- .8 Fittings for thin wall conduit:
 - .1 Connectors and couplings: steel, set screw type.

2.4 Wiring Devices, Cover Plates

- .1 Conform to CSA.
- .2 Receptacles:
 - .1 Duplex: CSA type 5-15R.
 - .2 Single: CSA type 5-15R.
 - .3 Cover plates and blank plates: finish to match other plates in area.

2.5 Starters, Control Devices

- .1 Across-the-line magnetic starters:
 - .1 Enclosures: CSA Type 1, except where otherwise specified.
 - .2 Size, type and rating: to suit motors.
- .2 Starter diagrams:
 - .1 Provide copy of wiring and schematic diagrams - mount one copy in each starter with additional copies for operation and maintenance manual.
- .3 Auxiliary Control Devices:
 - .1 Control transformers: 60 Hz, primary voltage to suit supply, 120 V single phase secondary, VA rating to suit load plus 20% margin.
 - .2 Auxiliary contacts: one "Normally Open" and one "Normally Closed" spare auxiliary contact in addition to maintained auxiliary contacts as indicated.
 - .3 Hand-Off-Automatic switch: heavy duty type, knob lever operator.
 - .4 Double voltage relays: with barrier to separate relay contacts from operating magnet. Operating coil voltage and contact rating as indicated.
- .4 Finish for starters:

- .1 Exterior: in accordance with Section 26 05 00 - Common Work Results for Electrical.
- .2 Interior: white.

2.6 Supports For Conduit, Fastenings, Equipment

- .1 Solid masonry, tile and plastic surfaces: lead anchors or nylon shields.
 - .1 Hollow masonry walls, suspended drywall ceilings: toggle bolts.
- .2 Exposed conduits or cables:
 - .1 50 mm diameter and smaller: one-hole steel straps.
 - .2 Larger than 50 mm diameter: two-hole steel straps.
- .3 Suspended support systems:
 - .1 Individual cable or conduit runs: support with 6 mm diameter threaded rods and support clips.
 - .2 Two or more suspended cables or conduits: support channels supported by 6 mm diameter threaded rod hangers.

Part 3 Execution

3.1 Installation

- .1 Install equipment, components so that manufacturer's and CSA labels are visible and legible after commissioning is complete.

3.2 Mechanical Piping

- .1 Install piping straight, parallel and close to building structure with required grades for drainage and venting.
- .2 Ream ends of pipes before assembly.
- .3 Copper tubing not to come into contact with dissimilar metal.
- .4 Use non-corrosive lubricant or Teflon tape on male screwed threads.
- .5 Clean ends of pipes, tubing and recesses of fittings to be brazed or soldered. Assemble joints without binding.
- .6 Install di-electric couplings where dissimilar metals joined.
- .7 Sleeves:
 - .1 Installation:
 - .1 Concrete, masonry walls, and concrete floors on grade: terminate flush with finished surface.
 - .2 Other floors: terminate 25 mm above finished floor.
 - .3 Before installation, paint exposed exterior surfaces with heavy application of zinc-rich paint.
 - .2 Caulking:
 - .1 Foundation walls and below grade floors: fire retardant, waterproof non-hardening mastic.

- .2 Elsewhere: provide space for fire stopping by Section 07 84 00 – Fire Stopping. Maintain fire rating integrity.
- .3 Sleeves installed for future use: fill with lime plaster or other easily removable filler.
- .4 Ensure no contact between copper pipe or tube and sleeve.
- .8 Pressure tests:
 - .1 Pressure test all piping systems modified under this contract to 1 1/2 times maximum working pressure or 860 kPa (whichever is greater) for 4 hours without loss of pressure. Isolate equipment, components, not designed to withstand test pressure.
- .9 Introduce system pressure carefully into new piping.

3.3 Supports

- .1 Install special supports as required and as indicated.

3.4 Electrical General

- .1 Do complete installation in accordance with requirements of:
 - .1 Division 26, this specification.
 - .2 CSA 22.1 Canadian Electrical Code.
 - .3 ANSI/NFPA 70.
 - .4 ANSI C2.
- .2 Fully enclose or properly guard electrical wiring, terminal blocks, high voltage contacts and mark to prevent accidental injury.
- .3 Do underground installation to CAN/CSA-C22.3 No.7, except where otherwise specified.
- .4 Conform to manufacturer's recommendations for storage, handling and installation.
- .5 Check factory connections and joints. Tighten where necessary to ensure continuity.
- .6 Install electrical equipment between 1000 and 2000 mm above finished floor wherever possible and adjacent to related equipment.
- .7 Protect exposed live equipment such as panel, mains, outlet wiring during construction for personnel safety.
- .8 Shield and mark live parts "LIVE 120 VOLTS" or other appropriate voltage.
- .9 Install conduits, and sleeves prior to pouring of concrete.
- .10 Holes through exterior wall and roofs: flash and make weatherproof.
- .11 Make necessary arrangements for cutting of chases, drilling holes and other structural work required to install electrical conduit, cable, pull boxes, outlet boxes.
- .12 Install cables, conduits and fittings which are to be embedded or plastered over, neatly and closely to building structure to minimize furring.

3.5 Conduit System

- .1 Communication wiring shall be installed in conduit. Provide complete conduit system to link Building Controllers to BECC. Conduit sizes to suit wiring requirements and to allow for future expansion capabilities specified for systems. Maximum conduit fill not to exceed 40%. Design drawings do not show conduit layout.
- .2 Install conduits parallel or perpendicular to building lines, to conserve headroom and to minimize interference.
- .3 Do not run exposed conduits in normally occupied spaces unless otherwise indicated or unless impossible to do otherwise. Obtain approval from Departmental Representative before starting such work. Provide complete conduit system to link field panels and devices with main control centre. Conduit size to match conductors plus future expansion capabilities as specified.
- .4 Locate conduits at least 150 mm from parallel steam or hot water pipes and at least 50 mm at crossovers.
- .5 Bend conduit so that diameter is reduced by less than 1/10th original diameter.
- .6 Field thread on rigid conduit to be of sufficient length to draw conduits up tight.
- .7 Limit conduit length between pull boxes to less than 30 m.
- .8 Use conduit outlet boxes for conduit up to 32 mm diameter and pull boxes for larger sizes.
- .9 Fastenings and supports for conduits, cables, and equipment:
 - .1 Provide metal brackets, frames, hangers, clamps and related types of support structures as indicated and as required to support cable and conduit runs.
 - .2 Provide adequate support for raceways and cables, sloped vertically to equipment.
 - .3 Use supports or equipment installed by other trades for conduit, cable and raceway supports only after written approval from Departmental Representative.
- .10 Install polypropylene fish cord in empty conduits for future use.
- .11 Where conduits become blocked, remove and replace blocked sections.
- .12 Pass conduits through structural members only after receipt of Departmental Representative's written approval.
- .13 Conduits may be run in flanged portion of structural steel.
- .14 Group conduits wherever possible on suspended or surface channels.
- .15 Pull boxes:
 - .1 Install in inconspicuous but accessible locations.
 - .2 Support boxes independently of connecting conduits.
 - .3 Fill boxes with paper or foam to prevent entry of construction material.
 - .4 Provide correct size of openings. Reducing washers not permitted.
 - .5 Mark location of pull boxes on record drawings.
 - .6 Identify AC power junction boxes, by panel and circuit breaker.

- .16 Install terminal blocks or strips in cabinets.
- .17 Install bonding conductor for 120 volt and above in conduit.

3.6 Wiring

- .1 Install multiple wiring in ducts simultaneously.
- .2 Do not pull spliced wiring inside conduits or ducts.
- .3 Use CSA certified lubricants of type compatible with insulation to reduce pulling tension.
- .4 Tests: use only qualified personnel. Demonstrate that:
 - .1 Circuits are continuous, free from shorts, unspecified grounds.
 - .2 Resistance to ground of all circuits is greater than 50 Megohms.
- .5 Provide Departmental Representative with test results showing locations, circuits, results of tests.
- .6 Remove insulation carefully from ends of conductors and install to manufacturer's recommendations. Accommodate all strands in lugs. Where insulation is stripped in excess, neatly tape so that only lug remains exposed.
- .7 Wiring in main junction boxes and pull boxes to terminate on terminal blocks only, clearly and permanently identified. Junctions or splices not permitted for sensing or control signal covering wiring.
- .8 Do not allow wiring to come into direct physical contact with compression screw.
- .9 Install ALL strands of conductor in lugs of components. Strip insulation only to extent necessary for installation.

3.7 Wiring Devices, Cover Plates

- .1 Receptacles:
 - .1 Install vertically in gang type outlet box when more than one receptacle is required in one location.
- .2 Cover plates:
 - .1 Install suitable common cover plate where wiring devices are grouped.
 - .2 Use flush type cover plates only on flush type outlet boxes.

3.8 Starters, Control Devices

- .1 Install and make power and control connections as indicated.
- .2 Install correct over-current devices.
- .3 Identify each wire, terminal for external connections with permanent number marking identical to diagram.
- .4 Performance Verification:
 - .1 Operate switches and controls to verify functioning.
 - .2 Perform start and stop sequences of contactors and relays.

- .3 Check that interlock sequences, with other separate related starters, equipment and auxiliary control devices, operate as specified.

3.9 Grounding

- .1 Install complete, permanent, continuous grounding system for equipment, including conductors, connectors and accessories.
- .2 Install separate grounding conductors in conduit within building.
- .3 Install ground wire in all PVC ducts and in tunnel conduit systems.
- .4 Tests: perform ground continuity and resistance tests, using approved method appropriate to site conditions.

3.10 Tests

- .1 General:
 - .1 Perform following tests in addition to tests specified Section 25 08 20 - EMCS: Warranty and Maintenance.
 - .2 Give 14 days written notice of intention to test.
 - .3 Conduct in presence of Departmental Representative and authority having jurisdiction.
 - .4 Conceal work only after tests satisfactorily completed.
 - .5 Report results of tests to Departmental Representative in writing.
 - .6 Preliminary tests:
 - .1 Conduct as directed to verify compliance with specified requirements.
 - .2 Make needed changes, adjustments, replacements.
 - .3 Insulation resistance tests:
 - .1 Megger all circuits, feeders, equipment for 120 - 600V with 1000V instrument. Resistance to ground to be more than required by Code before energizing.
 - .2 Test insulation between conductors and ground, efficiency of grounding system to satisfaction of Departmental Representative and authority having jurisdiction.

3.11 Identification

- .1 Refer to Section 25 05 54 - EMCS: Identification.

END OF SECTION

Part 1 General

1.1 Summary

- .1 Section Includes.
 - .1 Requirements and procedures for warranty and activities during warranty period and service contracts, for building Energy Monitoring and Control System (EMCS).
- .2 References.
 - .1 Canada Labour Code (R.S. 1985, c. L-2)/Part I - Industrial Relations.
 - .2 Canadian Standards Association (CSA International).
 - .1 CSA Z204, Guidelines for Managing Indoor Air Quality in Office Buildings.

1.2 Definitions

- .1 BC(s) - Building Controller(s).
- .2 OWS - Operator Work Station.
- .3 For additional acronyms and definitions refer to Section 25 05 01 - EMCS: General Requirements.

1.3 Action And Informational Submittals

- .1 Submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Submit detailed preventative maintenance schedule for system components to Departmental Representative.
- .3 Submit detailed inspection reports to Departmental Representative.
- .4 Submit dated, maintenance task lists to Departmental Representative and include the following sensor and output point detail, as proof of system verification:
 - .1 Point name and location.
 - .2 Device type and range.
 - .3 Measured value.
 - .4 System displayed value.
 - .5 Calibration detail
 - .6 Indication if adjustment required,
 - .7 Other action taken or recommended.
- .5 Submit network analysis report showing results with detailed recommendations to correct problems found.
- .6 Records and logs: in accordance with Section 01 78 00 - Closeout Submittals.
 - .1 Maintain records and logs of each maintenance task on site.
 - .2 Organize cumulative records for each major component and for entire EMCS chronologically.

- .3 Submit records to Departmental Representative, after inspection indicating that planned and systematic maintenance have been accomplished.
- .7 Revise and submit to Departmental Representative in accordance with Section 01 78 00 - Closeout Submittals "As-built drawings" documentation and commissioning reports to reflect changes, adjustments and modifications to EMCS made during warranty period.

1.4 Maintenance Service During Warranty Period

- .1 Provide services, materials, and equipment to maintain EMCS for specified warranty period. Provide detailed preventative maintenance schedule for system components as described in Submittal article.
- .2 Emergency Service Calls:
 - .1 Initiate service calls when EMCS is not functioning correctly.
 - .2 Qualified control personnel to be available during warranty period to provide service to "CRITICAL" components whenever required at no extra cost.
 - .3 Furnish Departmental Representative with telephone number where service personnel may be reached at any time.
 - .4 Service personnel to be on site ready to service EMCS within 2 hours after receiving request for service.
 - .5 Perform Work continuously until EMCS restored to reliable operating condition.
- .3 Operation: foregoing and other servicing to provide proper sequencing of equipment and satisfactory operation of EMCS based on original design conditions and as recommended by manufacturer.
- .4 Work requests: record each service call request, when received separately on approved form and include:
 - .1 Serial number identifying component involved.
 - .2 Location, date and time call received.
 - .3 Nature of trouble.
 - .4 Names of personnel assigned.
 - .5 Instructions of work to be done.
 - .6 Amount and nature of materials used.
 - .7 Time and date work started.
 - .8 Time and date of completion.
- .5 Provide system modifications in writing.
 - .1 No system modification, including operating parameters and control settings, to be made without prior written approval of Departmental Representative.

Part 2 Products

2.1 Not Used

- .1 Not Used.

Part 3 Execution

3.1 Field Quality Control

- .1 Perform as minimum (3) three minor inspections and one major inspection (more often if required by manufacturer) per year. Provide detailed written report to Departmental Representative as described in Submittal article.
- .2 Perform inspections during regular working hours, 0800 to 1630 h, Monday through Friday, excluding statutory holidays.
- .3 Following inspections are minimum requirements and should not be interpreted to mean satisfactory performance:
 - .1 Perform calibrations using test equipment having traceable, certifiable accuracy at minimum 50% greater than accuracy of system displaying or logging value.
 - .2 Calibrate each field input/output device in accordance CSA Z204.
 - .3 Provide dated, maintenance task lists, as described in Submittal article, as proof of execution of complete system verification.
- .4 Minor inspections to include, but not limited to:
 - .1 Perform visual, operational checks to BC's, peripheral equipment, interface equipment and other panels.
 - .2 Check equipment cooling fans as required.
 - .3 Visually check for mechanical faults, air leaks and proper pressure settings on pneumatic components.
 - .4 Review system performance with Departmental Representative to discuss suggested or required changes.
- .5 Major inspections to include, but not limited to:
 - .1 Minor inspection.
 - .2 Clean OWS(s) peripheral equipment, BC(s), interface and other panels, micro-processor interior and exterior surfaces.
 - .3 Check signal, voltage and system isolation of BC(s), peripherals, interface and other panels.
 - .4 Verify calibration/accuracy of each input and output device and recalibrate or replace as required.
 - .5 Provide mechanical adjustments, and necessary maintenance on printers.
 - .6 Run system software diagnostics as required.
 - .7 Install software and firmware enhancements to ensure components are operating at most current revision for maximum capability and reliability.
 - .1 Perform network analysis and provide report as described in Submittal article.
- .6 Rectify deficiencies revealed by maintenance inspections and environmental checks.
- .7 Continue system debugging and optimization.
- .8 Testing/verification of occupancy and seasonal-sensitive systems to take place during four (4) consecutive seasons, after facility has been accepted, taken over and fully occupied.

- .1 Test weather-sensitive systems twice: first at near winter design conditions and secondly under near summer design conditions.

END OF SECTION

Part 1 General

1.1 Summary

- .1 Section Includes:
 - .1 Materials and installation for building automation controllers including:
 - .1 Master Control Unit (MCU).
 - .2 Local Control Unit (LCU).
 - .3 Equipment Control Unit (ECU).
 - .4 Terminal Control Unit (TCU).

1.2 References

- .1 American Society of Heating, Refrigeration and Air-Conditioning Engineers, Inc. (ASHRAE).
 - .1 ASHRAE 2015, HVAC Applications Handbook, SI Edition.
- .2 Canadian Standards Association (CSA International).
 - .1 C22.2 No.205, Signal Equipment.
- .3 Institute of Electrical and Electronics Engineers (IEEE).
 - .1 IEEE C37.90.1, Surge Withstand Capabilities (SWC) Tests for Relays and Relay Systems Associated with Electric Power Apparatus.
- .4 Public Works and Government Services Canada (PWGSC)/Real Property Branch/Architectural and Engineering Services.
 - .1 MD13800, Energy Management and Control Systems (EMCS) Design Manual. English: <ftp://ftp.pwgsc.gc.ca/rps/docentre/mechanical/me214-e.pdf>

1.3 Definitions

- .1 Acronyms and definitions: refer to Section 25 05 01 - EMCS: General Requirements.

1.4 Description

- .1 General: Network of controllers comprising of MCU('s), LCU('s), ECU('s) or TCU('s) to be provided as indicated in System Architecture Diagram to support building systems and associated sequence(s) of operations as detailed in these specifications.
 - .1 Provide sufficient controllers to meet intents and requirements of this section.
 - .2 Controller quantity, and point contents to be approved by Departmental Representative at time of preliminary design review.
- .2 Controllers: stand-alone intelligent Control Units.
 - .1 Incorporate programmable microprocessor, non-volatile program memory, RAM, power supplies, as required to perform specified functions.
 - .2 Incorporate communication interface ports for communication to LANs to exchange information with other Controllers.

- .3 Capable of interfacing with operator interface device.
- .4 Execute its logic and control using primary inputs and outputs connected directly to its onboard input/output field terminations or slave devices, and without need to interact with other controller. Secondary input used for reset such as outdoor air temperature may be located in other Controller(s).
 - .1 Secondary input used for reset such as outdoor air temperature may be located in other Controller(s).
- .3 Interface to include provisions for use of dial-up modem for interconnection with remote modem.
 - .1 Dial-up communications to use 56 Kbit modems and voice grade telephone lines.
 - .2 Each stand-alone panel may have its own modem or group of stand-alone panels may share modem.

1.5 Design Requirements

- .1 To include:
 - .1 Scanning of AI and DI connected inputs for detection of change of value and processing detection of alarm conditions.
 - .2 Perform On-Off digital control of connected points, including resulting required states generated through programmable logic output.
 - .3 Perform Analog control using programmable logic, (including PID) with adjustable dead bands and deviation alarms.
 - .4 Control of systems as described in sequence of operations.
 - .5 Execution of optimization routines as listed in this section.
- .2 Total spare capacity for MCUs and LCUs: at least 25 % of each point type distributed throughout the MCUs and LCUs.
- .3 Field Termination and Interface Devices:
 - .1 To: CSA C22.2 No.205.
 - .2 Electronically interface sensors and control devices to processor unit.
 - .3 Include, but not be limited to, following:
 - .1 Programmed firmware or logic circuits to meet functional and technical requirements.
 - .2 Power supplies for operation of logics devices and associated field equipment.
 - .3 Lockable wall cabinet.
 - .4 Required communications equipment and wiring (if remote units).
 - .5 Leave controlled system in "fail-safe" mode in event of loss of communication with, or failure of, processor unit.
 - .6 Input Output interface to accept as minimum AI, AO, DI, DO functions as specified.
 - .7 Wiring terminations: use conveniently located screw type or spade lug terminals.
 - .4 AI interface equipment to:

- .1 Convert analog signals to digital format with 10 bit analog-to-digital resolution.
- .2 Provide for following input signal types and ranges:
 - .1 4 - 20 mA;
 - .2 0 - 10 V DC;
 - .3 100/1000 ohm RTD input;
- .3 Meet IEEE C37.90.1 surge withstand capability.
- .4 Have common mode signal rejection greater than 60 dB to 60 Hz.
- .5 Where required, dropping resistors to be certified precision devices which complement accuracy of sensor and transmitter range specified.
- .5 AO interface equipment:
 - .1 Convert digital data from controller processor to acceptable analog output signals using 8 bit digital-to-analog resolution.
 - .2 Provide for following output signal types and ranges:
 - .1 4 - 20 mA.
 - .2 0 - 10 V DC.
 - .3 Meet IEEE C37.90.1 surge withstand capability.
- .6 DI interface equipment:
 - .1 Able to reliably detect contact change of sensed field contact and transmit condition to controller.
 - .2 Meet IEEE C37.90.1 surge withstand capability.
 - .3 Accept pulsed inputs up to 2 kHz.
- .7 DO interface equipment:
 - .1 Respond to controller processor output, switch respective outputs. Each DO hardware to be capable of switching up to 0.5 amps at 24 V AC.
 - .2 Switch up to 5 amps at 220 V AC using optional interface relay.
- .4 Controllers and associated hardware and software: operate in conditions of 0 degrees C to 44 degrees C and 20 % to 90 % non-condensing RH.
- .5 Controllers (MCU, LCU): mount in wall mounted cabinet with hinged, keyed-alike locked door.
 - .1 Provide for conduit entrance from top, bottom or sides of panel.
 - .2 ECUs and TCUs to be mounted in equipment enclosures or separate enclosures.
 - .3 Mounting details as approved by Departmental Representative for ceiling mounting.
- .6 Cabinets to provide protection from water dripping from above, while allowing sufficient airflow to prevent internal overheating.
- .7 Provide surge and low voltage protection for interconnecting wiring connections.

1.6 Action And Informational Submittals

- .1 Make submittals in accordance with Section 01 33 00 - Submittal Procedures Section 25 05 02 - EMCS: Shop Drawings, Product Data and Review Process.
 - .1 Submit product data sheets for each product item proposed for this project.

1.7 Maintenance

- .1 Provide manufacturers recommended maintenance procedures for insertion in Section 25 05 03 - EMCS: Project Record Documents.

Part 2 Products

2.1 Master Control Unit (Mcu)

- .1 General: primary function of MCU is to provide co-ordination and supervision of subordinate devices in execution of optimization routines such as demand limiting or enthalpy control.
- .2 Include high speed communication LAN Port for Peer to Peer communications with OWS(s) and other MCU level devices.
 - .1 MCU must support BACnet.
- .3 MCU local I/O capacity as follows:
 - .1 MCU I/O points as allocated in I/O Summary Table referenced in MD13800.
 - .2 LCUs may be added to support system functions.
- .4 Central Processing Unit (CPU).
 - .1 Processor to consist of minimum 16 bit microprocessor capable of supporting software to meet specified requirements.
 - .2 CPU idle time to be more than 30 % when system configured to maximum input and output with worst case program use.
 - .3 Minimum addressable memory to be at manufacturer's discretion but to support at least performance and technical specifications to include but not limited to:
 - .1 Non-volatile EEPROM to contain operating system, executive, application, sub-routine, other configurations definition software. Tape media not acceptable.
 - .2 Battery backed (72 hour minimum capacity) RAM (to reduce the need to reload operating data in event of power failure) to contain CDLs, application parameters, operating data or software that is required to be modifiable from operational standpoint such as schedules, setpoints, alarm limits, PID constants and CDL and hence modifiable on-line through operator panel or remote operator's interface. RAM to be downline loadable from OWS.
 - .4 Include uninterruptible clock accurate to plus or minus 5 secs/month, capable of deriving year/month/day/hour/minute/second, with rechargeable batteries for minimum 72 hour operation in event of power failure.

- .5 Local Operator Terminal (OT): Provide OT for each MCU unless otherwise specified in Section 25 90 01 - EMCS: Site Requirements, Applications and System Sequences of Operation.
 - .1 Mount access/display panel in MCU or in suitable enclosure beside MCU as approved by Departmental Representative.
 - .2 Support operator's terminal for local command entry, instantaneous and historical data display, programs, additions and modifications.
 - .3 Display simultaneously minimum of 16 point identifiers to allow operator to view single screen dynamic displays depicting entire mechanical systems. Point identifiers to be in English.
 - .4 Functions to include, but not be limited to, following:
 - .1 Start and stop points.
 - .2 Modify setpoints.
 - .3 Modify PID loop parameters.
 - .4 Override PID control.
 - .5 Change time/date.
 - .6 Add/modify/start/stop weekly scheduling.
 - .7 Add/modify setpoint weekly scheduling.
 - .8 Enter temporary override schedules.
 - .9 Define holiday schedules.
 - .10 View analog limits.
 - .11 Enter/modify analog warning limits.
 - .12 Enter/modify analog alarm limits.
 - .13 Enter/modify analog differentials.
 - .5 Provide access to real and calculated points in controller to which it is connected or to other controller in network. This capability not to be restricted to subset of predefined "global points" but to provide totally open exchange of data between OT and other controller in network.
 - .6 Operator access to OTs: same as OWS user password and password changes to automatically be downloaded to controllers on network.
 - .7 Provide prompting to eliminate need for user to remember command format or point names. Prompting to be consistent with user's password clearance and types of points displayed to eliminate possibility of operator error.
 - .8 Identity of real or calculated points to be consistent with network devices. Use same point identifier as at OWS's for access of points at OT to eliminate cross-reference or look-up tables.

2.2 Local Control Unit (Lcu)

- .1 Provide multiple control functions for typical built-up and package HVAC systems, hydronic systems and electrical systems.
- .2 Minimum of 16 I/O points of which minimum be 4 AOs, 4 AIs, 4 DIs, 4 DOs.
- .3 Points integral to one Building System to be resident on only one controller.
- .4 Microprocessor capable of supporting necessary software and hardware to meet specified requirements as listed in previous MCU article with following additions:

- .1 Include minimum 2 interface ports for connection of local computer terminal.
- .2 Design so that shorts, opens or grounds on input or output will not interfere with other input or output signals.
- .3 Physically separate line voltage (70V and over) circuits from DC logic circuits to permit maintenance on either circuit with minimum hazards to technician and equipment.
- .4 Include power supplies for operation of LCU and associated field equipment.
- .5 In event of loss of communications with, or failure of, MCU, LCU to continue to perform control. Controllers that use defaults or fail to open or close positions not acceptable.
- .6 Provide conveniently located screw type or spade lug terminals for field wiring.

2.3 Terminal/Equipment Control Unit (Tcu/Ecu)

- .1 Microprocessor capable of supporting necessary software and hardware to meet TCU/ECU functional specifications.
 - .1 TCU/ECU definition to be consistent with those defined in ASHRAE HVAC Applications Handbook -2015, section 45.
- .2 Controller to communicate directly with EMCS through EMCS LAN and provide access from EMCS OWS for setting occupied and unoccupied space temperature setpoints, flow setpoints, and associated alarm values, permit reading of sensor values, field control values (% open) and transmit alarm conditions to EMCS OWS.
- .3 VAV Terminal Controller.
 - .1 Microprocessor based controller with integral flow transducer, including software routines to execute PID algorithms, calculate airflow for integral flow transducer and measure temperatures as per I/O Summary required inputs. Sequence of operation to ASHRAE HVAC Applications Handbook.
 - .2 Controller to support point definition; in accordance with Section 25 05 01 - EMCS: General Requirements.
 - .3 Controller to operate independent of network in case of communication failure.
 - .4 Controller to include damper actuator and terminations for input and output sensors and devices.

2.4 Software

- .1 General.
 - .1 Include as minimum: operating system executive, communications, application programs, operator interface, and systems sequence of operation - CDL's.
 - .2 Include "firmware" or instructions which are programmed into ROM, EPROM, EEPROM or other non-volatile memory.
 - .3 Include initial programming of Controllers, for entire system.
- .2 Program and data storage.

- .1 Store executive programs and site configuration data in ROM, EEPROM or other non-volatile memory.
- .2 Maintain CDL and operating data including setpoints, operating constants, alarm limits in battery-backed RAM or EEPROM for display and modification by operator.
- .3 Programming languages.
 - .1 Program Control Description Logic software (CDL) using English like or graphical, high level, general control language.
 - .2 Structure software in modular fashion to permit simple restructuring of program modules if future software additions or modifications are required. GO TO constructs not allowed unless approved by Departmental Representative.
- .4 Operator Terminal interface.
 - .1 Operating and control functions include:
 - .1 Multi-level password access protection to allow user/manager to limit workstation control.
 - .2 Alarm management: processing and messages.
 - .3 Operator commands.
 - .4 Reports.
 - .5 Displays.
 - .6 Point identification.
- .5 Pseudo or calculated points.
 - .1 Software to provide access to value or status in controller or other networked controller in order to define and calculate pseudo point. When current pseudo point value is derived, normal alarm checks must be performed or value used to totalize.
 - .2 Inputs and outputs for process: include data from controllers to permit development of network-wide control strategies. Processes also to permit operator to use results of one process as input to number of other processes (e.g. cascading).
- .6 Control Description Logic (CDL):
 - .1 Capable of generating on-line project-specific CDLs which are software based, programmed into RAM or EEPROM and backed up to OWS. Owner must have access to these algorithms for modification or to be able to create new ones and to integrate these into CDLs on BC(s) from OWS.
 - .2 Write CDL in high level language that allows algorithms and interlocking programs to be written simply and clearly. Use parameters entered into system (e.g. setpoints) to determine operation of algorithm. Operator to be able to alter operating parameters on-line from OWS and BC(s) to tune control loops.
 - .3 Perform changes to CDL on-line.
 - .4 Control logic to have access to values or status of points available to controller including global or common values, allowing cascading or inter-locking control.

- .5 Energy optimization routines including enthalpy control, supply temperature reset, to be LCU or MCU resident functions and form part of CDL.
- .6 MCU to be able to perform following pre-tested control algorithms:
 - .1 Two position control.
 - .2 Proportional Integral and Derivative (PID) control.
- .7 Control software to provide ability to define time between successive starts for each piece of equipment to reduce cycling of motors.
- .8 Provide protection against excessive electrical-demand situations during start-up periods by automatically introducing time delays between successive start commands to heavy electrical loads.
- .9 Power Fail Restart: upon detection of power failure system to verify availability of Emergency Power as determined by emergency power transfer switches and analyze controlled equipment to determine its appropriate status under Emergency power conditions and start or stop equipment as defined by I/O Summary. Upon resumption of normal power as determined by emergency power transfer switches, MCU to analyze status of controlled equipment, compare with normal occupancy scheduling, turn equipment on or off as necessary to resume normal operation.
- .7 Event and Alarm management: use management by exception concept for Alarm Reporting. This is system wide requirement. This approach will insure that only principal alarms are reported to OWS. Events which occur as direct result of primary event to be suppressed by system and only events which fail to occur to be reported. Such event sequence to be identified in I/O Summary and sequence of operation. Examples of above are, operational temperature alarms limits which are exceeded when main air handler is stopped, or General Fire condition shuts air handlers down, only Fire alarm status shall be reported. Exception is, when air handler which is supposed to stop or start fails to do so under event condition.
- .8 Energy management programs: include specific summarizing reports, with date stamp indicating sensor details which activated and or terminated feature.
 - .1 MCU in coordination with subordinate LCU, TCU, ECU to provide for the following energy management routines:
 - .1 Time of day scheduling.
 - .2 Calendar based scheduling.
 - .3 Holiday scheduling.
 - .4 Temporary schedule overrides.
 - .5 Optimal start stop.
 - .6 Night setback control.
 - .7 Enthalpy (economizer) switchover.
 - .8 Peak demand limiting.
 - .9 Temperature compensated load rolling.
 - .10 Fan speed/flow rate control.
 - .11 Cold deck reset.
 - .12 Hot deck reset.
 - .13 Hot water reset.
 - .14 Chilled water reset.

- .15 Condenser water reset.
 - .16 Chiller sequencing.
 - .17 Night purge.
- .2 Programs to be executed automatically without need for operator intervention and be flexible enough to allow customization.
- .3 Apply programs to equipment and systems as specified or requested by the Departmental Representative.
- .9 Function/Event Totalization: features to provide predefined reports which show daily, weekly, and monthly accumulating totals and which include high rate (time stamped) and low rate (time stamped) and accumulation to date for month.
 - .1 MCUs to accumulate and store automatically run-time for binary input and output points.
 - .2 MCU to automatically sample, calculate and store consumption totals on daily, weekly or monthly basis for user-selected analog or binary pulse input-type points.
 - .3 MCU to automatically count events (number of times pump is cycled off and on) daily, weekly or monthly basis.
 - .4 Totalization routine to have sampling resolution of 1 min or less for analog inputs.
 - .5 Totalization to provide calculations and storage of accumulations up to 99,999.9 units (eg. kWh, litres, tonnes, etc.).
 - .6 Store event totalization records with minimum of 9,999,999 events before reset.
 - .7 User to be able to define warning limit and generate user-specified messages when limit reached.

2.5 Levels Of Address

- .1 Upon operator's request, EMCS to present status of any single 'point', 'system' or point group, entire 'area', or entire network on printer or OWS as selected by operator.
 - .1 Display analog values digitally to 1 place of decimals with negative sign as required.
 - .2 Update displayed analog values and status when new values received.
 - .3 Flag points in alarm by blinking, reverse video, different colour, bracketed or other means to differentiate from points not in alarm.
 - .4 Updates to be change-of-value (COV)-driven or if polled not exceeding 2 second intervals.

2.6 Point Name Support

- .1 Controllers (MCU, LCU) to support PWGSC point naming convention as defined in Section 25 05 01 - EMCS: General Requirements.

Part 3 Execution

3.1 Location

- .1 Location of Controllers to be approved by Departmental Representative.

3.2 Installation

- .1 Install Controllers in secure locking enclosures.
- .2 Provide necessary power from local 120V branch circuit panel for equipment.
- .3 Install tamper locks on breakers of circuit breaker panel.
- .4 Use uninterruptible Power Supply (UPS) and emergency power when equipment must operate in emergency and co-ordinating mode.

END OF SECTION

Part 1 General

1.1 References

- .1 American National Standards Institute (ANSI).
 - .1 ANSI C12.7, Requirements for Watthour Meter Sockets.
- .2 American Society for Testing and Materials International, (ASTM).
 - .1 ASTM B148, Standard Specification for Aluminum-Bronze Sand Castings.
- .3 National Electrical Manufacturer's Association (NEMA).
 - .1 NEMA 250, Enclosures for Electrical Equipment (1000 Volts Maximum).
- .4 Canadian Standards Association (CSA International).
 - .1 CSA-C22.1, Canadian Electrical Code, Part 1 (19th Edition), Safety Standard for Electrical Installations.

1.2 Definitions

- .1 Acronyms and Definitions: refer to Section 25 05 01 - EMCS: General Requirements.

1.3 Action And Informational Submittals

- .1 Submit shop drawings and manufacturer's installation instructions in accordance with Section 25 05 02 - EMCS: Submittals and Review Process.
- .2 Pre-Installation Tests.
 - .1 Submit samples at random from equipment shipped, as requested by Departmental Representative, for testing before installation. Replace devices not meeting specified performance and accuracy.
- .3 Manufacturer's Instructions:
 - .1 Submit manufacturer's installation instructions for specified equipment and devices.

1.4 Existing Conditions

- .1 Cutting and Patching: in accordance with Section 01 73 00 - Execution Requirements supplemented as specified herein.
- .2 Repair surfaces damaged during execution of Work.
- .3 Turn over to Departmental Representative existing materials removed from Work not identified for re-use.

Part 2 Products

2.1 General

- .1 Control devices of each category to be of same type and manufacturer.
- .2 External trim materials to be corrosion resistant.

- .3 Operating conditions: 0 - 32 degrees C with 10 - 90% RH (non-condensing) unless otherwise specified.
- .4 Terminations: use standard conduit box with slot screwdriver compression connector block unless otherwise specified.
- .5 Transmitters and sensors to be unaffected by external transmitters including walkie talkies.
- .6 Account for hysteresis, relaxation time, maximum and minimum limits in applications of sensors and controls.
- .7 Outdoor installations: use weatherproof construction in NEMA 4 enclosures.
- .8 Devices installed in user occupied space not exceed Noise Criteria (NC) of 35. Noise generated by any device must not be detectable above space ambient conditions.
- .9 Range: including temperature, humidity, pressure, as indicated in I/O summary in Section 25 90 01 - EMCS: Site Requirements, Applications and System Sequences of Operation.

2.2 Temperature Sensors

- .1 General: except for room sensors to be resistance or thermocouple type to following requirements:
 - .1 Thermocouples: limit to temperature range of 200 degrees C and over.
 - .2 RTD's: 100 or 1000 ohm at 0 degrees C (plus or minus 0.2 ohms) platinum element with strain minimizing construction, 3 integral anchored leadwires. Coefficient of resistivity: 0.00385 ohms/ohm degrees C.
 - .3 Sensing element: hermetically sealed.
 - .4 Stem and tip construction: copper or type 304 stainless steel.
 - .5 Time constant response: less than 3 seconds to temperature change of 10 degrees C.
 - .6 Immersion wells: NPS 3/4, stainless steel spring loaded construction, with heat transfer compound compatible with sensor. Insertion length 100 mm.
- .2 Room temperature sensors and display wall modules.
 - .1 Temperature sensing and display wall module.
 - .1 LCD display to show space temperature and temperature setpoint.
 - .2 Buttons for occupant selection of temperature setpoint and occupied/unoccupied mode.
 - .3 Jack connection for plugging in laptop personal computer for access to zone bus.
 - .4 Integral thermistor sensing element 10,000 ohm at 24 degrees.
 - .5 Accuracy 0.2 degrees C over range of 0 to 70 degrees C.
 - .6 Stability 0.02 degrees C drift per year.
 - .7 Separate mounting base for ease of installation.
 - .2 Room temperature sensors.
 - .1 Wall mounting, in slotted type covers having brushed aluminum finish

- .2 Element 10-50 mm long RTD with ceramic tube or equivalent protection or thermistor, 10,000 ohm, accuracy of plus or minus 0.2 degrees C.
- .3 Duct temperature sensors:
 - .1 General purpose duct type: suitable for insertion into ducts at various orientations, insertion length 460 mm.
 - .2 Averaging duct type: incorporates numerous sensors inside assembly which are averaged to provide one reading. Minimum insertion length 6000 mm. Bend probe at field installation time to 100 mm radius at point along probe without degradation of performance.
- .4 Outdoor air temperature sensors:
 - .1 Outside air type: complete with probe length 100 - 150 mm long, non-corroding shield to minimize solar and wind effects, threaded fitting for mating to 13 mm conduit, weatherproof construction in NEMA 4 enclosure.

2.3 Temperature Transmitters

- .1 Requirements:
 - .1 Input circuit: to accept 3-lead, 100 or 1000 ohm at 0 degrees C, platinum resistance detector type sensors.
 - .2 Power supply: 24 V DC into load of 575 ohms. Power supply effect less than 0.01 degrees C per volt change.
 - .3 Output signal: 4 - 20 mA into 500 ohm maximum load.
 - .4 Input and output short circuit and open circuit protection.
 - .5 Output variation: less than 0.2 % of full scale for supply voltage variation of plus or minus 10 %.
 - .6 Combined non-linearity, repeatability, hysteresis effects: not to exceed plus or minus 0.5 % of full scale output.
 - .7 Maximum current to 100 or 1000 ohm RTD sensor: not to exceed 25 mA.
 - .8 Integral zero and span adjustments.
 - .9 Temperature effects: not to exceed plus or minus 1.0 % of full scale/ 50 degrees C.
 - .10 Long term output drift: not to exceed 0.25 % of full scale/ 6 months.
 - .11 Transmitter ranges: select narrowest range to suit application from following:
 - .1 Minus 50 degrees C to plus 50 degrees C, plus or minus 0.5 degrees C.
 - .2 0 to 100 degrees C, plus or minus 0.5 degrees C.
 - .3 0 to 50 degrees C, plus or minus 0.25 degrees C.
 - .4 0 to 25 degrees C, plus or minus 0.1 degrees C.
 - .5 10 to 35 degrees C, plus or minus 0.25 degrees C.

2.4 Humidity Sensors

- .1 Room and Duct Requirements:
 - .1 Range: 5 - 90 % RH minimum.

- .2 Operating temperature range: 0 - 60 degrees C.
- .3 Absolute accuracy:
 - .1 Duct sensors: plus or minus 3%.
 - .2 Room sensors: plus or minus 2%.
- .4 Sheath: stainless steel with integral shroud for specified operation in air streams of up to 10 m/s.
- .5 Maximum sensor non-linearity: plus or minus 2% RH with defined curves.
- .6 Room sensors: wall mounted as indicated.
- .7 Duct mounted sensors: locate so that sensing element is in air flow in duct.
- .2 Outdoor Humidity Requirements:
 - .1 Range: 0 - 100 % RH minimum.
 - .2 Operating temperature range: -40 - 50 degrees C.
 - .3 Absolute accuracy: plus or minus 2%.
 - .4 Temperature coefficient: plus or minus 0.03%RH/ degrees C over 0 to 50 degrees C.
 - .5 Must be unaffected by condensation or 100% saturation.
 - .6 No routine maintenance or calibration is required.

2.5 Humidity Transmitters

- .1 Requirements:
 - .1 Input signal: from RH sensor.
 - .2 Output signal: 4 - 20 mA onto 500 ohm maximum load.
 - .3 Input and output short circuit and open circuit protection.
 - .4 Output variations: not to exceed 0.2 % of full scale output for supply voltage variations of plus or minus 10 %.
 - .5 Output linearity error: plus or minus 1.0% maximum of full scale output.
 - .6 Integral zero and span adjustment.
 - .7 Temperature effect: plus or minus 1.0 % full scale/ 6 months.
 - .8 Long term output drift: not to exceed 0.25 % of full scale output/ 6 months.

2.6 Pressure Transducers

- .1 Requirements:
 - .1 Combined sensor and transmitter measuring pressure.
 - .1 Internal materials: suitable for continuous contact with industrial standard instrument air, compressed air, water, steam, as applicable.
 - .2 Output signal: 4 - 20 mA into 500 ohm maximum load.
 - .3 Output variations: less than 0.2 % full scale for supply voltage variations of plus or minus 10 %.
 - .4 Combined non-linearity, repeatability, and hysteresis effects: not to exceed plus or minus 0.5 % of full scale output over entire range.
 - .5 Temperature effects: not to exceed plus or minus 1.5 % full scale/ 50 degrees C.

- .6 Over-pressure input protection to at least twice rated input pressure.
- .7 Output short circuit and open circuit protection.
- .8 Accuracy: plus or minus 1% of Full Scale.

2.7 Differential Pressure Transmitters

- .1 Requirements:
 - .1 General: Multi-configurable, wet-to-wet differential pressure transducer with 3 valve manifold assembly, display and NEMA 4 enclosure with hinges.
 - .2 Internal materials: suitable for continuous contact with industrial standard instrument air, compressed air, water, steam, as applicable.
 - .3 Output signal: 4 - 20 mA into 500 ohm maximum load.
 - .4 Output variations: less than 0.2 % full scale for supply voltage variations of plus or minus 10 %.
 - .5 Combined non-linearity, repeatability, and hysteresis effects: not to exceed plus or minus 0.5 % of full scale output over entire range.
 - .6 Integral zero and span adjustment.
 - .7 Temperature effects: not to exceed plus or minus 1.5 % full scale/ 50 degrees C.
 - .8 Over-pressure input protection to at least twice rated input pressure.
 - .9 Output short circuit and open circuit protection.
 - .10 Unit to have 12.5 mm N.P.T. conduit connection. Enclosure to be integral part of unit.

2.8 Static Pressure Sensors

- .1 Requirements:
 - .1 Multipoint element with self-averaging manifold.
 - .1 Maximum pressure loss: 160 Pa at 10 m/s. (Air stream manifold).
 - .2 Accuracy: plus or minus 1 % of actual duct static pressure.

2.9 Static Pressure Transmitters

- .1 Requirements:
 - .1 Output signal: 4 - 20 mA linear into 500 ohm maximum load.
 - .2 Calibrated span: not to exceed 150 % of duct static pressure at maximum flow.
 - .3 Accuracy: 0.4 % of span.
 - .4 Repeatability: within 0.5 % of output.
 - .5 Linearity: within 1.5 % of span.
 - .6 Deadband or hysteresis: 0.1% of span.
 - .7 External exposed zero and span adjustment.
 - .8 Unit to have 12.5 mm N.P.T. conduit connection. Enclosure to be integral part of unit

2.10 Velocity Pressure Sensors

- .1 Requirements:
 - .1 Multipoint static and total pressure sensing element with self-averaging manifold with integral air equalizer and straightener section.
 - .2 Maximum pressure loss: 37Pa at 1000 m/s.
 - .3 Accuracy: plus or minus 1 % of actual duct velocity.

2.11 Velocity Pressure Transmitters

- .1 Requirements:
 - .1 Output signal: 4 - 20 mA linear into 500 ohm maximum load.
 - .2 Calibrated span: not to exceed 125 % of duct velocity pressure at maximum flow.
 - .3 Accuracy: 0.4 % of span.
 - .4 Repeatability: within 0.1 % of output.
 - .5 Linearity: within 0.5 % of span.
 - .6 Deadband or hysteresis: 0.1% of span.
 - .7 External exposed zero and span adjustment.
 - .8 Unit to have 12.5 mm N.P.T. conduit connection. Enclosure to be integral part of unit.

2.12 Liquid And Steam Flow Meters

- .1 Requirements:
 - .1 Pressure rating: as specified in I/O summaries.
 - .2 Temperature rating: as specified in I/O summaries.
 - .3 Repeatability: plus or minus 0.2 %.
 - .4 Accuracy and linearity: plus or minus 1.0 %.
 - .5 Flow rangability: at least 10:1.
 - .6 Ends:
 - .1 NPS 2 and under: screwed.
 - .2 NPS 2.1/2 and over: flanged.

2.13 Pressure And Differential Pressure Switches

- .1 Requirements:
 - .1 Internal materials: suitable for continuous contact with compressed air, water, steam, etc., as applicable.
 - .2 Adjustable setpoint and differential.
 - .3 Switch: snap action type.
 - .4 Switch assembly: to operate automatically and reset automatically when conditions return to normal. Over-pressure input protection to at least twice rated input pressure.
 - .5 Accuracy: within 2% repetitive switching.

- .6 Provide switches with isolation valve and snubber, where code allows, between sensor and pressure source.
- .7 Switches on steam and high temperature hot water service: provide pigtail syphon.

2.14 Temperature Switches

- .1 Requirements:
 - .1 Operate automatically.
 - .2 Adjustable setpoint and differential.
 - .3 Accuracy: plus or minus 1 degrees C.
 - .4 Snap action rating: Switch to be DPST for hardwire and EMCS connections.
 - .5 Type as follows:
 - .1 Room: for wall mounting on standard electrical box with protective guard.
 - .2 Duct, general purpose: insertion length = 460 mm.
 - .3 Thermowell: stainless steel, with compression fitting for NPS 3/4 thermowell. Immersion length: 100 mm.
 - .4 Low temperature detection: continuous element with 6000 mm insertion length, duct mounting, to detect coldest temperature in any 30 mm length.
 - .5 Strap-on: with helical screw stainless steel clamp.

2.15 Tank Level Switches

- .1 Requirements:
 - .1 Indicate high/low water level and to alarm.
 - .2 For mounting on top of tank.
 - .3 Maximum operating temperature: 120 degrees C.
 - .4 Snap action contacts rated 15 amp at 120 V.
 - .5 Adjustable setpoint and differential.

2.16 Wind Velocity Transmitters

- .1 Requirements:
 - .1 3-cup anemometer and airfoil vane mounted on common vertical axis, designed for mast mounting.
 - .2 Anemometer:
 - .1 Range: 0-160 km/h.
 - .2 Threshold: 3.0 km/h.
 - .3 Accuracy: +/- 2%.
 - .3 Airfoil vane
 - .1 Range: 0-360 degrees with infinite resolution potentiometer with no loss of reading at transition point.
 - .2 Starting threshold: 1.1 M/s.
 - .3 Accuracy: +/- 0.5%.

- .4 Output signals: 4 to 20 Ma into 500 ohm load.
- .5 Provide two output signals: velocity, direction.
- .6 Mast: aluminum, size and height as indicated.
- .7 Provide at least 3 stainless steel guys, turnbuckles, anchor bolts.
Follow manufacturers installation guidelines.

2.17 Solenoid Control Air Valves

- .1 Capacity: to pass a minimum of 0.15 l/s air at 140 kPa differential.

2.18 Air Pressure Gauges

- .1 Diameter: 38 mm minimum.
- .2 Range: zero to two times operating pressure of measured pressure media or nearest standard range.

2.19 Electromechanical Relays

- .1 Requirements:
 - .1 Double voltage, DPDT, plug-in type with termination base.
 - .2 Coils: rated for 24V DC. Other voltage: provide transformer.
 - .3 Contacts: rated at 5 amps at 120 V AC.
 - .4 Relay to have visual status indication

2.20 Solid State Relays

- .1 General:
 - .1 Relays to be socket or rail mounted.
 - .2 Relays to have LED Indicator
 - .3 Input and output Barrier Strips to accept 14 to 28 AWG wire.
 - .4 Operating temperature range to be -20 degrees C to 70 degrees C.
 - .5 Relays to be CSA Certified.
 - .6 Input/output Isolation Voltage to be 4000 VAC at 25 degrees C for 1 second maximum duration.
 - .7 Operational frequency range, 45 to 65 HZ.
- .2 Input:
 - .1 Control voltage, 3 to 32 VDC.
 - .2 Drop out voltage, 1.2 VDC.
 - .3 Maximum input current to match AO (Analog Output) board.
- .3 Output.
 - .1 AC or DC Output Model to suit application.

2.21 Current Transducers

- .1 Requirements:

- .2 Purpose: combined sensor/transducer, to measure line current and produce proportional signal in one of following ranges:
 - .1 4-20 mA DC.
 - .2 0-1 volt DC.
 - .3 0-10 volts DC.
 - .4 0-20 volts DC.
- .3 Frequency insensitive from 10 - 80 hz.
- .4 Accuracy to 0.5% full scale.
- .5 Zero and span adjustments. Field adjustable range to suit motor applications.
- .6 Adjustable mounting bracket to allow for secure/safe mounting inside MCC.

2.22 Current Sensing Relays

- .1 Requirements:
 - .1 Suitable to detect belt loss or motor failure.
 - .2 Trip point adjustment, output status LED.
 - .3 Split core for easy mounting.
 - .4 Induced sensor power.
 - .5 Relay contacts: capable of handling 0.5 amps at 30 VAC / DC. Output to be NO solid state.
 - .6 Suitable for single or 3 phase monitoring. For 3-Phase applications: provide for discrimination between phases.
 - .7 Adjustable latch level.

2.23 Control Valves

- .1 Body: forged brass, nickel plated body, globe style.
 - .1 Flow factor (KV) as indicated on control valve schedule: CV in imperial units.
 - .2 Leakage rate ANSI class IV, 0.01% of full open valve capacity.
 - .3 Packing easily replaceable, 2 EPDM O-rings, lubricated.
 - .4 Ball: Stainless Steel.
 - .5 Stem: Stainless steel.
 - .6 Seat: PTFE.
 - .7 Characterizing Disc: replaceable, Tefzel.
 - .8 NPS 2 and under:
 - .1 Screwed National Pipe Thread (NPT) tapered female connections.
 - .2 Valves to ANSI Class 250, valves to bear ANSI mark.
 - .3 Rangeability 50:1 minimum.
 - .9 NPS 2 and larger:
 - .1 Flanged connections.
 - .2 Valves to ANSI Class 150 or 250, valves to bear ANSI mark.
 - .3 Rangeability 100:1 minimum.
- .2 Butterfly Valves NPS 2 and larger:

- .1 Body: for chilled water ANSI Class 150 cast iron lugged body installed in locations as indicated. For steam and heating water ANSI Class 150 carbon steel lugged body.
- .2 End connections to suit flanges that are ANSI Class 150.
- .3 Extended stem neck to provide adequate clearance for flanges and insulation.
- .4 Pressure limit: bubble tight sealing to 170 kilopascals.
- .5 Disc/vane: 316 stainless steel.
- .6 Seat: for service on chilled water PTFE (polytetrafluoroethylene. For service on steam and heating water PTFE.
- .7 Stem: 316 stainless steel.
- .8 Flow factor (KV) as indicated on control valve schedule: CV in imperial units.
- .9 Maximum flow requirement as indicated on control valve schedule.
- .10 Maximum pressure drop as indicated on control valve schedule: pressure drop not to exceed one half of inlet pressure.
- .11 Valves are to be provided complete with mounting plate for installation of actuators.

2.24 Pneumatic Valve Actuators

- .1 Requirements:
 - .1 Construction: steel, cast iron, aluminum.
 - .2 Diaphragm: moulded Buna-N rubber, nylon reinforced.
 - .3 Spring return to normal position.
 - .4 Spring range adjustment and position indicator.
 - .5 Provide pilot positioners on modulating control valves over 50 mm. Positioners to operate between 20 to 90 kPa unless otherwise noted or required by sequence.

2.25 Electronic / Electric Valve Actuators

- .1 Requirements:
 - .1 Construction: steel, cast iron, aluminum.
 - .2 Control signal: 0-10V DC or 4-20 mA DC.
 - .3 Positioning time: to suit application. 90 sec maximum.
 - .4 Fail to normal position as indicated.
 - .5 Scale or dial indication of actual control valve position.
 - .6 Size actuator to meet requirements and performance of control valve specifications.
 - .7 For interior and perimeter terminal heating and cooling applications floating control actuators are acceptable.
 - .8 Minimum shut-off pressure: refer to control valve schedule.

2.26 Watthour Meters And Current Transformers

- .1 Requirements:

- .1 Include three phases, test and terminal blocks for watthour meter connections and connections for monitoring of current. Provide two transformers for 600 V 3 wire systems for watthour meter use. Accuracy: plus or minus 0.25 % of full scale.
- .2 Watthour meter sockets: to ANSI C12.7.
- .3 Potential and current transformers: to ANSI/IEEE C57.13.
- .4 Potential transformers: provide two primary fuses.
- .5 Demand meters: configure to measure demand at 15 minute intervals.

2.27 Surface Water Detectors

- .1 Requirements:
 - .1 Provide alarm on presence of water on floor.
 - .2 Expendable cartridge sensor.
 - .3 Internal waterproof switch.
 - .4 One set of dry contacts 2 amps at 24 V.
 - .5 Unaffected by moisture in air.
 - .6 Self-powered.

2.28 Panels

- .1 wall mounted enamelled steel cabinets with hinged and key-locked front door.
- .2 Multiple panels as required to handle requirements with additional space to accommodate 25% additional capacity as required by Departmental Representative without adding additional cabinets.
- .3 Panels to be lockable with same key.

2.29 Wiring

- .1 In accordance with Divison 26
- .2 For wiring under 70 volts use FT6 rated wiring where wiring is not run in conduit. Other cases use FT4 wiring.
- .3 Wiring must be continuous without joints.
- .4 Sizes:
 - .1 Field wiring to digital device: 20AWG stranded twisted pair.
 - .2 Analog input and output: shielded 20 minimum stranded twisted pair.

Part 3 Execution

3.1 Installation

- .1 Install equipment, components so that manufacturer's and CSA labels are visible and legible after commissioning is complete.
- .2 Install field control devices in accordance with manufacturers recommended methods, procedures and instructions.

- .3 Temperature transmitters, humidity transmitters, current-to-pneumatic transducers, solenoid air valves, controllers, relays: install in NEMA I enclosure or as required for specific applications. Provide for electrolytic isolation in cases when dissimilar metals make contact.
- .4 Support field-mounted panels, transmitters and sensors on pipe stands or channel brackets.
- .5 Fire stopping: provide space for fire stopping in accordance with Section 07 84 00 - Firestopping. Maintain fire rating integrity.
- .6 Electrical:
 - .1 Complete installation in accordance with Section 26 05 00 - Common Work Results for Electrical.
 - .2 Modify existing starters to provide for EMCS as indicated in I/O Summaries and as indicated.
 - .3 Terminate wires with screw terminal type connectors suitable for wire size, and number of terminations.
 - .4 Install communication wiring in conduit.
 - .1 Provide complete conduit system to link Building Controllers, field panels and OWS(s).
 - .2 Conduit sizes to suit wiring requirements and to allow for future expansion capabilities specified for systems.
 - .3 Maximum conduit fill not to exceed 40%.
 - .4 Design drawings do not show conduit layout.
 - .5 Do not run exposed conduits in normally occupied spaces unless otherwise indicated or unless impossible to do otherwise. Departmental Representative to review before starting Work. Wiring in mechanical rooms, wiring in service rooms and exposed wiring must be in conduit.

3.2 Temperature And Humidity Sensors

- .1 Stabilize to ensure minimum field adjustments or calibrations.
- .2 Readily accessible and adaptable to each type of application to allow for quick easy replacement and servicing without special tools or skills.
- .3 Outdoor installation:
 - .1 Protect from solar radiation and wind effects by non-corroding shields.
 - .2 Install in NEMA 4 enclosures.
- .4 Duct installations:
 - .1 Do not mount in dead air space.
 - .2 Locate within sensor vibration and velocity limits.
 - .3 Securely mount extended surface sensor used to sense average temperature.
 - .4 Thermally isolate elements from brackets and supports to respond to air temperature only.
 - .5 Support sensor element separately from coils, filter racks.
- .5 Averaging duct type temperature sensors.

- .1 Install averaging element horizontally across the ductwork starting 300 mm from top of ductwork. Each additional horizontal run to be no more than 300 mm from one above it. Continue until complete cross sectional area of ductwork is covered. Use multiple sensors where single sensor does not meet required coverage.
- .2 Wire multiple sensors in series for low temperature protection applications.
- .3 Wire multiple sensors separately for temperature measurement.
- .4 Use software averaging algorithm to derive overall average for control purposes.
- .6 Thermowells: install for piping installations.
 - .1 Locate well in elbow where pipe diameter is less than well insertion length.
 - .2 Thermowell to restrict flow by less than 30%.
 - .3 Use thermal conducting paste inside wells.

3.3 Panels

- .1 Arrange for conduit and tubing entry from top, bottom or either side.
- .2 Wiring and tubing within panels: locate in trays or individually clipped to back of panel.
- .3 Identify wiring and conduit clearly.

3.4 Magnehelic Pressure Indicators

- .1 Install adjacent to fan system static pressure sensor and duct system velocity pressure sensor as reviewed by Departmental Representative.

3.5 Pressure And Differential Pressure Switches And Sensors

- .1 Install isolation valve and snubber on sensors between sensor and pressure source where code allows.
 - .1 Protect sensing elements on steam and high temperature hot water service with pigtail syphon between valve and sensor.

3.6 I/P Transducers

- .1 Install air pressure gauge on outlet.

3.7 Air Pressure Gauges

- .1 Install pressure gauges on pneumatic devices, I/P, pilot positioners, motor operators, switches, relays, valves, damper operators, valve actuators.
- .2 Install pressure gauge on output of auxiliary cabinet pneumatic devices.

3.8 Identification

- .1 Identify field devices in accordance with Section 25 05 54 - EMCS: Identification.

3.9 Air Flow Measuring Stations

- .1 Protect air flow measuring assembly until cleaning of ducts is completed.

3.10 Testing And Commissioning

- .1 Calibrate and test field devices for accuracy and performance in accordance with
 Section 25 01 11 - EMCS: Start-up, Verification and Commissioning.

END OF SECTION