



PRIME CONSULTANT, MECHANICAL & ELECTRICAL



ARCHITECTURAL



STAMP



GENERAL NOTES:

- CONTRACTOR MUST VERIFY ALL DIMENSIONS ON SITE BEFORE PROCEEDING WITH ANY PORTION OF THIS WORK. DO NOT SCALE DRAWING.

revisions	title	date
B	Issued for Tender	07.21.17
A	Issued for 90% Review	05.06.17

project project

District Office Infrastructure
John Cabot Building
St. John's, NL
Building ID: GOC00047

drawing dessin

PROPOSED ROOF DETAILS

designed EC/RF conçu

date MAY 2017

drawn EC dessiné

date MAY 2017

approved RF approuvé

date MAY 2017

Tender Submission
2017/07/31

Project Manager Administrateur du projet TPSCC

project number no. du projet
R.090120.001

drawing no. no. du dessin
A-2.6

INSULATED METAL PANEL TO BE REPAIRED AS PER MANUFACTURER'S RECOMMENDATIONS, WHICH SHALL OVERRIDE THIS DETAIL. CONTRACTOR TO VERIFY WALL SYSTEM, AND PROVIDE MOCK-UP OF ONE HOLE BEFORE FILLING ALL. CONTRACTOR SHALL BE RESPONSIBLE FOR FILLING ALL HOLES ASSOCIATED WITH EQUIPMENT REMOVAL.

SHEET NOTES:

- EXISTING INSULATED METAL PANEL, CONTRACTOR TO CONFIRM WALL TYPE.
- SELF ADHERED BREATHABLE AIR VAPOUR BARRIER EXTENDED 75mm IN ALL DIRECTIONS BEYOND THE DAMAGED AREA. BARRIER TO BE SEALED AT ALL SIDES WITH COMPATIBLE SEALANT
- OPEN CELL SPRAY FOAM INSULATION, SEE SPECIFICATION.
- SHEET METAL TO MATCH EXISTING WALL PANEL. TO BE SEALED AT TOP AND ALL SIDES WITH COMPATIBLE SEALANT.

PROPOSED HOLE INFILL DETAIL
SCALE 1:5 (1:10 WHEN PRINTED ON 11X17)

1
A-2.6

