



REF. NORTH

PRIME CONSULTANT, MECHANICAL & ELECTRICAL




ANTARES ENGINEERING GROUP INC.

ARCHITECTURAL

**Fougere
Menchenton**
ARCHITECTURE

STAMP



GENERAL NOTES:

1. CONTRACTOR MUST VERIFY ALL DIMENSIONS ON SITE BEFORE PROCEEDING WITH ANY PORTION OF THIS WORK. DO NOT SCALE DRAWING.

revisions	title	date
B	Issued for Tender	07.21.17
A	Issued for 90% Review	05.06.17

project project
**District Office
Infrastructure
John Cabot Building
St. John's, NL
Building ID: GOC00047**

drawing dessin
**EXISTING
FLOOR PLAN**


designed	EC/RF	conçu
date	MAY 2017	
drawn	EC	dessiné
date	MAY 2017	
approved	RF	approuvé
date	MAY 2017	
Tender	2017/07/31	Sourçation
PWGS Project Manager	Administrateur de projets TPSGC	
project number	no. du projet	
	R.090120.001	
drawing no.	no. du dessin	
	A-12.1	

LEGEND:

- EXISTING WALL **XXXX** CEILING HEIGHT
- EXISTING DOOR
- LIMITS OF CONTRACT

SHEET NOTES:

1. EXISTING DOORS TO REMAIN. DO NOT REPAINT.
2. REMOVE EXISTING MILLWORK AND DISPOSE OF OFF SITE TO A DESIGNATED AREA.
3. REMOVE EXISTING FRIDGE AND HAND OVER TO DEPARTMENTAL REPRESENTATIVE.
4. EXISTING BULKHEAD ABOVE COUNTER.
5. EXISTING BASE BOARD HEATER TO REMAIN.
6. ALL WALL SURFACES TO BE PATCHED AND PRIMED FOR REPAINTING.
7. REMOVE EXISTING CARPET AND CARPET BASE AND DISPOSE OF OFF SITE TO A DESIGNATED AREA.
8. EXISTING WINDOW TRIMS TO BE PREPARED FOR REPAINTING. CONTRACTOR TO REMOVE EXISTING WINDOW COVERINGS PRIOR TO REPAINTING WINDOW TRIMS. COORDINATE WITH OWNER TO TEMPORARILY STORE ON SITE, AND RE-INSTALL UPON COMPLETION.
9. REMOVE EXISTING PIPING, SEE MECHANICAL.
10. PROTECT FLOORING DURING WORK.



EXISTING FLOOR PLAN

SCALE 1:50 (1:100 WHEN PRINTED ON 11X17)

1

A-12.1