

PART 1 - GENERAL

- |                       |    |   |
|-----------------------|----|---|
| <u>1.1 PROTECTION</u> | .1 | Confirm demolition work does not adversely affect adjacent properties, watercourses, groundwater and wildlife, or contribute to excess air and noise pollution. |
|                       | .2 | Fires and burning of waste or materials is not permitted on site.   |
|                       | .3 | Do not bury waste or materials on site.   |
|                       | .4 | Prevent extraneous materials from contaminating air beyond application area, by providing temporary enclosures during demolition Work.                          |
|                       | .5 | Cover or wet down dry materials and waste to prevent blowing dust and debris. Control dust on all roads.  |
|                       | .6 | Protect trees, plants and foliage on site and adjacent properties where indicated.  |

- |                                    |    |   |
|------------------------------------|----|---|
| <u>1.2 REGULATORY REQUIREMENTS</u> | .1 | Perform work in compliance with applicable Federal, Provincial and Municipal Regulations. |
|------------------------------------|----|---|

PART 2 - PRODUCTS

- |                     |    |                 |
|---------------------|----|-----------------|
| <u>2.1 NOT USED</u> | .1 | Not applicable. |
|---------------------|----|-----------------|

PART 3 - EXECUTION

- |  |    |  |
|--|----|--|
| <u>3.1 TURN OVER OF EQUIPMENT AND DISPOSAL</u> | .1 | Dispose of equipment and materials as indicated in accordance with the regulations of the authority having jurisdiction. |
|  | .2 | Dispose of refrigerant in the rooftop units in accordance with the regulations of the authority having jurisdiction.     |
|  | .3 | Equipment turned over to the Owner: none.  |
-

3.2 CLEANUP .1 Upon completion of Work, remove debris, trim  
surfaces and leave work site clean.