



**RETURN BIDS TO:
RETOURNER LES SOUMISSIONS A:
Bid Receiving/Réception des
sousmissions**

**RCMP / GRC
Procurement & Contracting services
c/o Commissionaires, F Division
6101 Dewdney Avenue
Regina, SK S4P 3K7**

**Facsimile Number for Amendments:
(306) 780-3466**

**SOLICITATION AMENDMENT
MODIFICATION DE L'INVITATION**

**The referenced document is hereby
revised; unless otherwise indicated, all
other terms and conditions remain the
same.**

**Ce document est par la présente révisé;
sauf indication contraire, les modalités
de l'invitation demeurent les memes.**

Comments - Commentaries

**Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur**

Facsimile No. - No de télécopieur:

Telephone No. - no de téléphone:

Title-Sujet Damp Proof Basement Walls	
Solicitation No. - No. de l'invitation M5000-18-2161/A	Date 19 September 2017
Amendment No. - No modif. 05	
Client Reference No. - No. De Référence du Client M5000-18-2161/A	
GETS Reference No. - No. de Référence de SEAG PW-17-00792559	
Solicitation Closes -L'invitation prend fin at - à 2 :00 pm Central Standard Time on - le 21 September 2017	
F.O.B. - F.A.B. Destination	
Address Enquiries to: - Adresser toutes questions à: Teresa Hengen, Senior Contracting Officer	
Telephone No. - No de téléphone (639) 625-3449	Fax No. - N° de FAX: (306) 780-3466
Destination of Goods, Services, and Construction: Destinations des biens, services et construction: Royal Canadian Mounted Police Academy-Depot Division Medical Treatment Centre 5600 11 th Ave Regina, SK	
This document does not contain a PERSONNEL SECURITY Clearance requirements	
Delivery Required - Livraison exigée:	Delivery Offered - Livraison proposée
Name and title of person authorized to sign on behalf of Vendor/Firm Nom et titre de la personne autorisée à signer au nom du fournisseur/de l'entrepreneur	



This amendment is raised to provide additional information:

Delete:

Solicitation Closes –L'invitation prend fin

at - à 2 :00 pm Central Standard Time

on - le 20 September 2017

Insert:

Solicitation Closes –L'invitation prend fin

at - à 2 :00 pm Central Standard Time

on - le 21 September 2017

Q1: Will you be providing the depths of the foundation that requires water proofing?

A1: Based on limited drawings we can see approximately 9 foot 4 inches, this is not an actual measurement. It would be up to the awarded contractor to expose up to footing and determine actual measurement to complete project.

Q2: What do the lawn drains tie into? Storm drain? Is there a drawing?

A2 Lawn drains are shown on the sidewalk drawing. Drains on to the street through the east sidewalk.

Q3: What are the specs for the lawn weeping tile? 400 X 400 with

A3: Already answered in the addendum - 4 inch

Q4: Is there a drawing with elevation views of the walls to be damp proofed?

R4: No drawing

Q5: Can I use this product as an alternate to the cement board as Styrofoam no longer makes cement board? WallGuard – brochure attached. Or this:

<http://www.techcrete.com/downloads/Product%20Brochure.pdf>

These two companies bought out the Styrofoam line from Dow.

A5: if requested material is not available RMCP will approve alternate material with Contractor awarded contract.

Q6: Is there flashing on top of the cement board as it will stick out past the brickwork.

A6: If upon installation it extends past a flashing will be required.

Q7: Is the brick retaining wall to be reused? It may be difficult to preserve if it is cemented together.

A7: It is stated in the original statement of work that new brick is to be used - because they are glued together.

Q8: Do you have a spec of the landscape material for underneath the pea rock?

A8: a woven fabric that will block weeds and sunlight.

Q9: The area to be topped up with pea gravel, is that to the top of the curb on the south west corner? A: There is an area that looks to be about 14" down from the top of the curb.

A9: Yes