

KEY PLAN

APEGA
PERMIT TO
PRACTICE
P 3979

DO NOT SCALE DRAWINGS

Revision/	Description/Description	Date/Date
0	ISSUED FOR TENDER	2017.08.16

Client/client
PUBLIC WORKS & GOVERNMENT SERVICES CANADA

Project title/Titre du projet

EDMONTON MAXIMUM SECURITY INSTITUTION

Approved by/Approuvé par
J. MAH

Designed by/Concept par
J. MAH

Drawn by/Dessiné par
J. CHOA

PWSC Project Manager/Administrateur de Projets TPSGC
ANDREW GILLESSE

PWSC, Architectural and Engineering Resources Manager/
Ressources Architectural et de Directeur d'ingénierie, TPSGC

Client/client
PUBLIC WORKS & GOVERNMENT SERVICES CANADA

Drawing title/Titre du dessin

CONTACT & VISITATION VENTILATION PLAN


Project No./No. du projet	Sheet/Feuille	Revision no./La Révision no.
R.078013.001	M47 OF 103	0



- SHEET KEY NOTES**
- REBALANCE EXISTING SUPPLY DIFFUSER.
 - NEW SUPPLY DUCT FROM AHU-101 ABOVE IN MECHANICAL ROOM.
 - EXISTING SUPPLY DUCT FROM AHU-18 ABOVE IN MECHANICAL ROOM.
 - PROVIDE ACCESS HATCHES FOR BALANCING DAMPERS. ACCESS HATCH INSTALLED IN GYPSUM PORTION WHICH IS ABOVE THE TBAR CEILING.
 - EXTEND EXISTING DUCTWORK AND INSTALL NEW DIFFUSER.
 - CONNECT NEW DUCT TO EXISTING.

- GENERAL NOTES**
- EXISTING DRAWING INFORMATION IS NOT AS-BUILT. CONTRACTOR TO CONFIRM EXISTING CONDITIONS AND ROUTING PRIOR TO COMMENCING WORK.
 - CONSTRUCTION ACTIVITIES SHALL BE COORDINATED AND STAGED WITH THE BUILDING OPERATOR TO MINIMIZE INTERRUPTION TO OPERATIONS.
 - PATCH AND REPAIR GYPSUM CEILING AND REINSTALL TBAR.

FOR CONTINUATION SEE DWG M46



1 PLAN 1:100
M47 ADMISSION, DISCHARGE, CONTACT, VISITATION VENTILATION

