

KEY PLAN



DO NOT SCALE DRAWINGS

Revision/	Description/Description	Date/Date
0	ISSUED FOR TENDER	2017.08.16

Client/client  
**PUBLIC WORKS & GOVERNMENT SERVICES CANADA**

Project title/Titre du projet  
**EDMONTON MAXIMUM SECURITY INSTITUTION**


Approved by/Approuvé par  
J. MAH  
Designed by/Concept par  
J. MAH  
Drawn by/Dessiné par  
J. CHOA

PWSC Project Manager/Administrateur de Projets TPSGC  
ANDREW GILLESE  
PWSC, Architectural and Engineering Resources Manager/  
Ressources Architectural et de Directeur d'ingénierie, TPSGC

Client/client  
PUBLIC WORKS & GOVERNMENT SERVICES CANADA

Drawing title/Titre du dessin  
**GH BLOCK UNIT OFFICES AND MAIN FLOOR CELL BLOCK DEMOLITION PLAN**

Project No./No. du projet R.078013.001	Sheet/Feuille <b>M8</b> OF 103	Revision no./La Révision no. <b>0</b>
---	--------------------------------------	--



FOR CONTINUATION SEE DWG M9

**BLOCK 'H'**  
GROUND FLOOR

**BLOCK 'G'**  
GROUND FLOOR

**1 PLAN** 1:100  
M8 GH BLOCK UNIT OFFICES DEMOLITION

- SHEET KEY NOTES**
- REMOVE RETURN GRILLE, DUCT WORK AND CAP AS SHOWN. PATCH AND REPAIR OPENING.
  - REMOVE RETURN GRILLE, DUCT WORK AS SHOWN. DO NOT CAP. PATCH AND REPAIR OPENING. COORDINATE PATCH AND REPAIR WITH NEW DUCTWORK SCOPE.
  - DISCONNECT AND REMOVE DUCTWORK TO RETURN GRILLE AS SHOWN. RETURN GRILLE TO REMAIN.

- GENERAL NOTES**
- EXISTING DRAWING INFORMATION IS NOT AS-BUILT. CONTRACTOR TO CONFIRM EXISTING CONDITIONS AND ROUTING PRIOR TO COMMENCING WORK.
  - CONSTRUCTION ACTIVITIES SHALL BE COORDINATED AND STAGED WITH THE BUILDING OPERATOR TO MINIMIZE INTERRUPTION TO OPERATIONS.
  - PATCH AND REPAIR OPENINGS TO MAINTAIN FIRE SEAL.

