



APEGA  
PERMIT TO  
PRACTICE  
P 3979

CONTINUED ON DWG E11




DIAGRAM NTS  
MCC 4 & MCC 4A

- LEGEND**
- REPLACE LOADS BEING REPLACED. BREAKER AND STARTER TO BE REPLACED.
  - DEMOLISH LOADS BEING DEMOLISHED. DEMOLISH BREAKER AND STARTER.
  - NEW LOADS BEING ADDED. BREAKER AND STARTER TO BE INSTALLED.

- NOTES:**
1. ALL LOADS SHOWN OTHER THAN THOSE INCLUDED IN THE SCOPE OF THIS PROJECT ARE UNVERIFIED.
  2. EXISTING MCC BUCKETS TO BE SENT TO MANUFACTURE FOR TESTING. ALL BUCKETS PASSING TESTING WILL BE RETURNED TO OWNER.
  3. RE-USE EXISTING WIRE AND CONDUIT. VERIFY EXISTING WIRE SIZE AND CONDITION PRIOR TO RE-USE.
  4. NEW KEY INTERLOCK RADIAL BUS DUCT BREAKERS ARE TO MATCH EXISTING BREAKER TRIP SIZES. CONTRACTOR TO CONFIRM SIZES BEFORE REPLACEMENT.

Revision/Revision	Description/Description	Date/Date
0	ISSUED FOR TENDER	2017.08.16

**PUBLIC WORKS & GOVERNMENT SERVICES CANADA**

Project title/Titre du projet  
**EDMONTON MAXIMUM SECURITY INSTITUTION**

Approved by/Approuvé par  
JM  
Designed by/Concept par  
JS/KD  
Drawn by/Dessiné par  
RJN  
PWGSC Project Manager/Administrateur de Projets TPSGC  
ANDREW GILLESE  
PWGSC, Architectural and Engineering Resources Manager/  
Ressources Architectural et de Directeur d'ingénierie, TPSGC  
Client/client  
PUBLIC WORKS & GOVERNMENT SERVICES CANADA

Drawing title/Titre du dessin  
**SINGLE LINE DIAGRAM  
MCC #4  
(LIVING UNITS A & B)**

Project No./No. du projet <b>R.078013.001</b>	Sheet/Feuille <b>E10</b> OF 103	Revision no./ La Révision no. <b>0</b>
--	---------------------------------------	--