

KEY PLAN

APEGA  
PERMIT TO  
PRACTICE  
P 3979

DO NOT SCALE DRAWINGS

0	ISSUED FOR TENDER	2017.08.16

Revision/ Révision	Description/Description	Date/Date
-----------------------	-------------------------	-----------

Client/client

PUBLIC WORKS &  
GOVERNMENT SERVICES  
CANADA

Project title/Titre du projet

EDMONTON MAXIMUM  
SECURITY INSTITUTION

Approved by/Approuvé par  
J. MAH

Designed by/Concept par  
J. MAH

Drawn by/Dessiné par  
J. CHOA

PWGSC Project Manager/Administrateur de Projets TPSGC  
ANDREW GILLESE

PWGSC, Architectural and Engineering Resources Manager/  
Ressources Architectural et de Directeur d'Ingénierie, TPSGC

Client/client  
PUBLIC WORKS & GOVERNMENT SERVICES CANADA

Drawing title/Titre du dessin

SEGREGATION AND  
DISASSOCIATION BLOCK  
ROOF PLAN  
HEATING AND CONTROLS

Project No./No. du  
projet  
R.078013.001

Sheet/Feuille  
M37  
OF 103

Revision no./  
La Révision  
no.  
0




SHEET KEY NOTES

- 1 INSTALL NEW ELECTRIC CONTROL VALVES, CONTROL WIRING AND THERMOSTATS AS SHOWN.
- 2 INSTALL NEW ELECTRIC DUCT HEATERS FOR END CELLS. REFER TO DETAIL ON RIGHT FOR LOCATION.
- 3 RECONNECT AND REPIPE BAREFIN TO RUN IN SERIES WITH OTHER BAREFIN. REMOVE PIPE AS SHOWN.

GENERAL NOTES

- 1 EXISTING DRAWING INFORMATION IS NOT AS-BUILT. CONTRACTOR TO CONFIRM EXISTING CONDITIONS AND ROUTING PRIOR TO COMMENCING WORK.
- 2 CONSTRUCTION ACTIVITIES SHALL BE COORDINATED AND STAGED WITH THE BUILDING OPERATOR TO MINIMIZE INTERRUPTION TO OPERATIONS.
- 3 PATCH AND REPAIR OPENINGS TO MAINTAIN FIRE SEPARATION.
- 4 COORDINATE ALL REQUIRED OPENINGS IN WALLS TO PERFORM HEATING AND CONTROLS WORK. PATCH AND REPAIR WALLS. REFER TO ARCHITECTURAL PLANS FOR SPECIFIC REQUIREMENTS



1  
-  
DETAIL  
SG END CELL DUCT REHEAT LOCATION

1  
M37  
PLAN

SEGREGATION AND DISASSOCIATION BLOCK  
ROOF HEATING AND CONTROLS

1:100