

PART 1 - GENERAL

1.1 Description

- .1 This section specifies requirements for the Site Works at Loggiecroft Wharf in preparation of harbour dredging, construction and re-shaping of a containment cell, transportation of excess material to loggie's Pit and the restoration of the site upon completion of dredging.
  - .2 Site Works - Loggiecroft Wharf preparation will consist of, but not necessarily be limited to:
    - .1 Mobilization and demobilization of dredging and construction equipment.
    - .2 Installation and maintenance of erosion control measures.
    - .3 Installation and maintenance of Floating Silt curtain in the harbour.
    - .4 Installation and maintenance during dredging operations of safety PVC Snow fence and Wood Slat Snad and Snow Fence.
    - .5 Provide a buoy life ring and a rope at the containment cell.
    - .6 Contact NB Power to de-energise overhead power lines, if applicable.
    - .7 Locate under ground electrical and under water electrical cable.
    - .8 Ensure noise control and dust control measures are inplace during all construction activities.
    - .9 Construction of a outfall weir and swale from the containment cell to the harbour.
    - .10 Installation of no trespassing signs.
    - .11 Construction of the containment cell at Loggiecroft.
    - .12 Transportation of any excess material from the containment cell to Loggie's Pit.
    - .13 Installation of the filter Fabric in the bottom of the containment Cell.
    - .14 Ensure well is secured and protected from construction.
    - .15 Shape outer slope of the containment cell to ensure proper mowing of the side slope.
    - .16 Locate, Remove and re-install Floating wharf anchor blocks c/w chains.
-

September 2017

---

- 1.1 Description  
(Cont'd)
- .3 The containment cell at Loggiecroft Wharf is to be maintained under site work and includes:
- .1 Security and fencing;
  - .2 Draining of cell.
  - .3 Dust and noise control.
  - .4 Provide a buoy life ring
  - .5 Site security measures.
- .4 Site restoration is site work, and will consist of, but not necessarily be limited to, the following:
- .1 Shape containment cell to ensure proper drainage.
  - .2 Cleaning of deck and parking lot surfaces during and following dredging operations.
- 1.2 Related Work
- .1 Containment Cell Section 35 31 18
- 1.3 Protection
- .1 Protect existing objects designated to remain. In event of damage, immediately replace or make repairs to approval of and at no additional cost to Departmental Representative.
- 1.4 Measurement for Payment
- .1 Site Works - Loggiecroft Wharf: as specified including all plant, labour will constitute a fixed price item for measurement purposes.
- .2 There will not be any separate payment for the reinstatement of work that was temporarily removed for the installation of the new work. Include cost for this work in the items for payment.