



NOTES:

- SEE DRAWING S02 FOR LAYOUT. DO NOT INTERRUPT REGULAR WALL REINFORCING TO INSTALL PILASTER REINFORCING. REGULAR WALL REINFORCING MUST BE KEPT CONTINUOUS THROUGH PILASTERS (WHERE APPLICABLE.)

DETAIL - PILASTER REINFORCING
SCALE : N.T.S.

The Association of Professional Engineers and Technicians of Prince Edward Island
S. L. Myatt
No. 1257
DATE: 2017/03/17
LICENSÉE
PROFESSIONNELLE ENGENIEUR
PROVINCE DE PRINCE-ÉDOUARD

5	ISSUED FOR TENDER	09.15.2017
4	RS4 - 100% SUBMISSION	09.01.2017
3	RS4 - 99% SUBMISSION	06.30.2017
2	RS4 - 66% SUBMISSION	05.31.2017
1	RS04 - 33% SUBMISSION	04.30.2017
0	RS3 SUBMISSION	03.31.2017
revisions		date

project
**GREEN GABLES-PHASE 2
NEW VISITOR
CENTRE**
QUEENS CO., PEI

drawing
**STRUCTURAL
PILASTER DETAILS**

designed SLJM
date MAR-2017
drawn JLK
date MAR-2017
approved
date
Tender
no. du projet
R.081199.001
drawing no.
S04 OF 12