




APPROX. NORTH

FOOTING SCHEDULE

NUMBER	SIZE	REINFORCING
F1	1200 x 900 x 250	3 - 15M LONG 5 - 15M SHORT
F2	1400 x 1100 x 250	4 - 15M LONG 5 - 15M SHORT
F3	1400 x 1400 x 250	5 - 15M E.W.
F4	1600 x 1200 x 250	4 - 15M LONG 6 - 15M SHORT
F5	1800 x 1800 x 250	6 - 20M E.W.
F6	2000 x 1500 x 450	5 - 20M LONG 8 - 20M SHORT
F7	3000 x 3000 x 450	9 - 25M E.W.
F8	1000 X 100 X 250	3 - 15M E.W.




NOTES:

1. ALL UNDERGROUND SLEEVES TO BE SLEEVED THROUGH FOUNDATION WALLS. LOCALLY STEP FOOTINGS DOWN AS REQUIRED. COORDINATE PIPE/CONDUIT LOCATIONS AND ELEVATIONS WITH MECHANICAL, ELECTRICAL AND CIVIL DRAWINGS AND CONTRACTORS.
2. IF INTERIOR FOOTINGS ARE REQUIRED TO DROP DUE TO BUILDING SERVICES, PROVIDE A PILASTER AS NOTED IN DETAIL 10/S07 TO ACHIEVE ELEVATION DIFFERENCE.
3. FOR FOUNDATION CORNERS, INTERSECTIONS, WATERSTOPS, ETC. SEE DRAWING S06 FOR TYPICAL CONCRETE DETAILS.
4. REFER TO ARCHITECTURAL DRAWINGS FOR ALL DIMENSIONS.
5. ALL UNDERGROUND SERVICES TO BE SLEEVED THROUGH FOUNDATION WALLS. LOCALLY STEP FOOTING DOWN AS REQUIRED. COORDINATE PIPE/CONDUIT LOCATIONS AND ELEVATIONS WITH MECHANICAL, ELECTRICAL AND CIVIL DRAWINGS AND CONTRACTORS.

LEGEND:

- P#: DENOTES PILASTER. SEE DETAIL 1/S04 FOR SIZE AND REINFORCING.
- S.F.: DENOTES STEPPED FOOTING. SEE DETAIL 11/S07.
- F#: DENOTES FOOTING. SEE FOOTING SCHEDULE.
- EP#: DENOTES EMBEDDED PLATE. SEE DRAWING S11 FOR DETAILS.
- CJ: DENOTES CONTROL JOINT. SEE PLAN 2/S02.



5	ISSUED FOR TENDER	09.15.2017
4	RS4 - 100% SUBMISSION	09.01.2017
3	RS4 - 99% SUBMISSION	06.30.2017
2	RS4 - 66% SUBMISSION	05.31.2017
1	RS04 - 33% SUBMISSION	04.30.2017
0	RS3 SUBMISSION	03.31.2017

project GREEN GABLES-PHASE 2
NEW VISITOR
CENTRE
QUEENS CO., PEI

drawing STRUCTURAL
FOUNDATION PLAN

designed SLJM
date MAR-2017
drawn JLK
date MAR-2017
approved
date
Tender
PWGSC Project Manager / Administrateur de projets TPSGC
project number R.081199.001
drawing no. S02 OF 12