



LEGEND:

PROPOSED	EXISTING
MINOR CONTOURS	MINOR CONTOURS
MAJOR CONTOURS	MAJOR CONTOURS
WATER	WATER
SAN SEWER	SAN SEWER
ST SEWER	ST SEWER
ELEC CONDUIT	ELEC CONDUIT
TELECOMMUNICATIONS	TELECOMMUNICATIONS
SAN MH	SAN MH
ST MH	ST MH
ELEC MH	ELEC MH
EXISTING BUILDING	EXISTING BUILDING
AREA OF BUILDING EXCAVATION	AREA OF BUILDING EXCAVATION
NEW BUILDING	NEW BUILDING

- GENERAL NOTES**
- DIMENSIONS ARE IN METRIC UNITS UNLESS NOTED OTHERWISE.
 - ELEVATIONS ARE REFERENCED FROM A BENCHMARK CONTROL POINT 3534 (SMARTNET CONTROL) ELEVATION 56.661m.
 - THE DEPARTMENTAL REPRESENTATIVE AND ALL LOCAL UTILITY COMPANIES SHALL BE CONTACTED PRIOR TO THE START OF CONSTRUCTION TO COORDINATE FIELD LOCATES OF SERVICES BEFORE STARTING CONSTRUCTION.
 - FIELD SURVEY INFORMATION PROVIDED BY CBCL LIMITED.
 - GAS MAIN LOCATE IS REQUIRED BY LAW BEFORE WORK BEGINS. GAS MAIN MUST BE DAYLIGHTED WHEN EXCAVATING WITHIN 1.0m OF LOCATE.
 - ALL EXISTING INVERTS TO BE CONFIRMED PRIOR TO PIPE LAYING.
 - ALL CUT/FILL SLOPES TO BE MAX 3H : 1V AND STABILIZED WITH 150mm TOPSOIL, SEED AND STRAW MULCH UNLESS OTHERWISE INDICATED.
 - REINSTATE DISTURBED SURFACES WITH MATERIALS AND THICKNESSES TO MATCH EXISTING.
 - CIVIL CONTRACT INCLUDES WORKS UP TO 1.5m FROM BUILDING AND CONNECTION TO BUILDING PIPE.
- ABBREVIATIONS**
- | | |
|--------|--------------------------|
| FA | FINISHED ASPHALT |
| FG | FINISHED GRADE |
| FFA | FINISHED FLOOR ELEVATION |
| EX | EXISTING |
| MH | MANHOLE |
| I.D. | INSIDE DIAMETER |
| INV | INVERT |
| CB | CATCH BASIN |
| EL | BOTTOM OF SUMP ELEVATION |
| POC | POINT OF CONNECTION |
| N.I.C. | NOT IN CONTRACT |

Public Works and Government Services Canada / Travaux Publics et Services gouvernementaux Canada

root ARCHITECTURE

CBCL CBCL LIMITED
Consulting Engineers

PROFESSIONAL ENGINEER
Jody L. MacLeod
No. 572
Sept 2017
PRINCE EDWARD ISLAND

5	ISSUED FOR TENDER	09.15.2017
4	RS4 - 100% SUBMISSION	09.01.2017
3	RS4 - 99% SUBMISSION	06.30.2017
2	RS4 - 66% SUBMISSION	05.31.2017
1	RS4 - 33% SUBMISSION	04.30.2017
0	RS3 SUBMISSION	03.31.2017

revisions: date

project: **GREEN GABLES-PHASE 2 NEW VISITOR CENTRE**

QUEENS CO., PEI

drawing: **CIVIL UTILITY REMOVALS**

designed: BT
date: APR-2017
drawn: MT
date: APR-2017
approved: [Signature]
date: [Signature]
Tender: [Signature]
PWSC: Project Manager / Administrateur de projets TPSGC
project number: **R.081199.001**
drawing no.: **C16 of 20**

E-DRM/GDD-E: 551163