



PUBLIC WORKS AND GOVERNMENT SERVICES CANADA
VARIOUS MECHANICAL WORKS
700 LEIGH CAPRÉOL

■ ■ ■

SPECIFICATIONS
BUILDING SERVICES

■ ■ ■

CLIENT/Ref. : R.082049.001

TT/Ref. : 32787TT

■ ■ ■

Issued for tender
August 24th, 2017

PUBLIC WORKS AND GOVERNMENT SERVICES CANADA
VARIOUS MECHANICAL WORKS
700 LEIGH CAPRÉOL

CLIENT/Ref. : R.082049.001

TT/Ref. : 32787TT



2500, blvd. Daniel-Johnson, office. 810

Laval (Quebec) H7T 2P6

Phone : 450 687-4440

Fax: 450 687-3755

Prepared by :



Gilles Gilbert, Project
Manager

Marc Schuler, Eng.

N° OIQ : 102632 -
Mechanical

Zineddine Berkache, Eng.

N° OIQ : 137968 - Electrical

Issued for tender / August 24th, 2017

DIVISION 00	REQUIREMENTS FOR SUPPLIES AND CONTRACTS	
Section 00 01 10	Table of contents	2 pages
Section 00 01 15	Drawings list	1 page
DIVISION 01	GENERAL REQUIREMENTS	
Section 01 11 01	Summary of work	3 pages
Section 01 14 00	Work restrictions	2 pages
Section 01 31 19	Project meetings	1 page
Section 01 33 00	Submittal procedures	4 pages
Section 01 35 29.06	Health and safety requirements	4 pages
Section 01 35 43	Environmental procedures	2 pages
Section 01 41 00	Regulatory requirements	2 pages
Section 01 45 00	Quality control	2 pages
Section 01 52 00	Construction facilities	2 pages
Section 01 56 00	Temporary barriers and enclosures	1 page
Section 01 61 00	Common product requirements	4 pages
Section 01 73 00	Execution	2 pages
Section 01 74 11	Cleaning	2 pages
Section 01 77 00	Closeout procedures	2 pages
Section 01 78 00	Closeout submittals	7 pages
Section 01 79 00	Demonstration and training	2 pages
DIVISION 02	EXISTING CONDITIONS	
Section 02 41 99	Demolition for minor works	2 pages
Section 02 50 13	Management of toxic waste	3 pages
Section 02 81 01	Hazardous materials	4 pages
DIVISION 22	PLUMBING	
Section 22 05 00	Common Work Results for Plumbing	4 pages
Section 22 10 10	Plumbing Pumps	2 pages
Section 22 42 01	Plumbing Specialities and accessories	4 pages
Section 22 47 00	Drinking Fountains and Water Coolers	3 pages
DIVISION 23	HEATING, VENTILATION AND AIR CONDITIONING	
Section 23 05 00	Common work results for HVAC	3 pages
Section 23 05 05	Installation of pipework	4 pages
Section 23 05 17	Pipe welding	3 pages
Section 23 05 19.01	Thermometers and pressure gauges – piping systems	3 pages
Section 23 05 23.01	Valves – Bronze	3 pages

Section 23 05 23.02	Valves – Cast Iron	3 pages
Section 23 05 23.05	Butterfly valves	4 pages
Section 23 05 29	Hangers and supports for HVAC piping and equipment	5 pages
Section 23 05 53.01	Mechanical identification	5 pages
Section 23 05 93	Testing, adjusting and balancing for HVAC	5 pages
Section 23 07 15	Thermal insulation for piping	6 pages
Section 23 08 02	Cleaning and start-up of mechanical piping systems	3 pages
Section 23 21 13.02	Hydronic systems : Steel	3 pages
Section 23 21 14	Hydronic specialties	3 pages

DIVISION 26 **ELECTRICAL**

Section 26 05 00	Common work results for electrical	8 pages
Section 26 05 20	Wire and box connectors 0-1000 V	2 pages
Section 26 05 21	Wires and cables (0-1000V)	2 pages
Section 26 05 28	Grounding – secondary	2 pages
Section 26 05 29	Hangers and supports for electrical systems	2 pages
Section 26 05 31	Splitters, junction, pull boxes and cabinets	1 page
Section 26 05 32	Outlet boxes, conduit boxes and fittings	2 pages
Section 26 05 34	Conduits, conduit fastenings and conduit fittings	4 pages
Section 26 05 43.01	Installation of Cables in Trenches and in Ducts	2 pages
Section 26 29 10	Motor starters to 600 V	2 pages

NUMBER	TITLE
M-00	PRESENTATION PLAN – LIST OF PLANS –LEGEND
M-01	PLUMBING – BASEMENT – DEMOLITION – NEW LAYOUT
M-02	PLUMBING – 1 ST FLOOR – NEW LAYOUT
M-03	PLUMBING – 2 ND FLOOR – NEW LAYOUT
M-04	PLUMBING – 3 ND FLOOR – NEW LAYOUT
M-05	PLUMBING – 4 ND FLOOR AND ROOF – NEW LAYOUT
M-06	PLUMBING – EXCERPT – MECHANICAL ROOM – NEW LAYOUT AND DEMOLITION
E-01	ELECTRICAL – BASEMENT – DEMOLITION – NEW LAYOUT

Part 1 General

1.01 WORK BY OTHERS

- .1 Co-operate with other Contractors in carrying out their respective works and carry out instructions from the Departmental Representative.
- .2 Co-ordinate work with that of other Contractors. If any part of work under this Contract depends for its proper execution or result upon work of another Contractor, report promptly to the Departmental Representative, in writing, any defects which may interfere with proper execution of Work.

1.02 FUTURE WORK

- .1 Insure that Work avoids encroachment into areas required for future work.

1.03 WORK SEQUENCE

- .1 Construct Work in stages to accommodate the Departmental Representative's use of premises during construction.
- .2 Co-ordinate Progress Schedule and co-ordinate with the Departmental Representative Occupancy during construction.
- .3 Maintain fire access/control.

1.04 CONTRACTOR USE OF PREMISES

- .1 Unrestricted use of site until Substantial Performance.
- .2 Limit use of premises for Work, to allow:
 - .1 The Departmental Representative occupancy.
- .3 Co-ordinate use of premises under direction of Departmental Representative.
- .4 Obtain and pay for use of additional storage or work areas needed for operations under this Contract.
- .5 Remove or alter existing work to prevent injury or damage to portions of existing work which remain.
- .6 Repair or replace portions of existing work which have been altered during construction operations to match existing or adjoining work, as directed by Departmental Representative.
- .7 At completion of operations condition of existing work: equal to or better than that which existed before new work started.

1.05 OCCUPANCY BY THE DEPARTMENTAL REPRESENTATIVE

- .1 The Departmental Representative will occupy premises during entire construction period for execution of normal operations.
- .2 Co-operate with the Departmental Representative in scheduling operations to minimize conflict and to facilitate the Departmental Representative usage.

1.06 ALTERATIONS, ADDITIONS OR REPAIRS TO EXISTING BUILDING

- .1 Execute work with least possible interference or disturbance to building operations and normal use of premises. Arrange with Departmental Representative to facilitate execution of work.
- .2 Use only elevators or escalators existing in building for moving workers and material.
 - .1 Protect walls of passenger elevators, to approval of Departmental Representative prior to use.
 - .2 Accept liability for damage, safety of equipment and overloading of existing equipment.

1.07 EXISTING UTILITY SERVICES

- .1 Notify Departmental Representative and utility companies of intended interruption of services and obtain required permission.
- .2 Where Work involves breaking into or connecting to existing services, give Departmental Representative 48 hours notice for necessary interruption of mechanical or electrical service throughout course of work. Minimize duration of interruptions. Carry out work at times as directed by governing authorities with minimum disturbance to tenant operations.
- .3 Provide alternative routes for personnel and/or pedestrian and vehicular traffic.
- .4 Establish location and extent of service lines in area of work before starting Work. Notify Departmental Representative of findings.
- .5 Submit schedule to and obtain approval from Departmental Representative for any shut-down or closure of active service or facility including power and communications services. Adhere to approved schedule and provide notice to affected parties.
- .6 Provide temporary services when directed by Departmental Representative to maintain critical building and tenant systems.
- .7 Where unknown services are encountered, immediately advise Departmental Representative and confirm findings in writing.
- .8 Protect, relocate or maintain existing active services. When inactive services are encountered, cap off in manner approved by authorities having jurisdiction.
- .9 Record locations of maintained, re-routed and abandoned service lines.

1.08 REQUIRED DOCUMENTS

- .1 Maintain at job site, one copy each document as follows:
 - .1 Contract Drawings.
 - .2 Specifications.
 - .3 Addenda.
 - .4 Reviewed Shop Drawings.
 - .5 List of Outstanding Shop Drawings.
 - .6 Change Orders.
 - .7 Other Modifications to Contract.
 - .8 Field Test Reports.
 - .9 Copy of Approved Work Schedule.
 - .10 Health and Safety Plan and Other Safety Related Documents.
 - .11 Other documents as specified.

Part 2 Products

2.01 NOT USED

- .1 Not used.

Part 3 Execution

3.01 NOT USED

- .1 Not used.

END OF SECTION

1 GENERAL

1.01 RELATED REQUIREMENTS

- .1 Are applicable to this Section the general conditions of the contract, including the general clauses, the special clauses and the specifications Sections of the Division 01.

1.02 USE OF SITE AND FACILITIES

- .1 Execute work with least possible interference or disturbance to normal use of premises. Make arrangements with Departmental Representative to facilitate work as stated.
- .2 Where security is reduced by work provide temporary means to maintain security.
- .3 Departmental Representative will assign sanitary facilities for use by Contractor's personnel. Keep facilities clean.
- .4 Use only elevators, dumbwaiters, or stairs existing in building for moving workers and material.
 - .1 Protect walls of passenger elevators, to approval of Departmental Representative prior to use.
 - .2 Accept liability for damage, safety of equipment and overloading of existing equipment.
- .5 Closures: protect work temporarily until permanent enclosures are completed.

1.03 ALTERATIONS, ADDITIONS OR REPAIRS TO EXISTING BUILDING

- .1 Execute work with least possible interference or disturbance to building operations and normal use of premises. Arrange with Departmental Representative to facilitate execution of work.

1.04 SPECIAL REQUIREMENTS

- .1 The work requiring discontinuation of ventilation systems shall be made during the weekends, so Friday 18 pm to Monday 6 am. Coordinate with the Departmental's Representative.
- .2 Carry out noise generating Work Monday to Friday from 18:00 to 07:00 hours and on Saturdays and Sundays, between 8:00 to 17:00.
- .3 Ensure Contractor's personnel employed on site become familiar with and obey regulations including safety, fire, traffic and security regulations.
- .4 Keep within limits of work and avenues of ingress and egress.
- .5 Ingress and egress of Contractor vehicles at site is limited to parking and circulation's way the vehicles on the campus.
- .6 Deliver materials outside of peak traffic hours between 13:00 to 17:00 unless otherwise approved by Departmental Representative.
- .7 The demolition and reinstallation work for the new coils can be made in different but consecutive weekend. If the options recommended, the ventilation system will still need to be cleaned, sealed

from any opening un wanted and any other work deemed necessary to restore the system to operation on Monday at the time mentioned. The pipe connection to coils can be done in the next weekend.

- .8 The heating work will be done outside the winter period from November 1th to May 1th, variable depending on the outside temperature and cooling work will be done during this winter period. The contractor is responsible for coordination the delivery of equipment and works to meet these restrictive periods.

1.05 SECURITY

- .1 Where security has been reduced by Work of Contract, provide temporary means to maintain security.
- .2 Security clearances:
- .1 Personnel employed on this project will be subject to security check. Obtain clearance, as instructed, for each individual who will require to enter premises.
 - .2 Obtain requisite clearance, as instructed, for each individual required to enter premises.
 - .3 Personnel will be checked daily at start of work shift and provided with pass which must be worn at all times. Pass must be returned at end of work shift and personnel checked out.

1.06 BUILDING SMOKING ENVIRONMENT

- .1 Comply with smoking restrictions. Smoking is not permitted.

2 PRODUCTS

2.01 NOT USED

- .1 Not Used.

3 EXECUTION

3.01 NOT USED

- .1 Not Used.

END OF SECTION

1 GENERAL

1.01 RELATED REQUIREMENTS

- .1 Are applicable to this Section the general conditions of the contract, including the general clauses, the special clauses and the specifications Sections of the Division 01.

1.02 ADMINISTRATIVE

- .1 Schedule and administer project meetings throughout the progress of the work at the call of Departmental Representative.
- .2 Representative of Contractor, Subcontractor and suppliers attending meetings will be qualified and authorized to act on behalf of party each represents.

1.03 PRECONSTRUCTION MEETING

- .1 Within 15 days after award of Contract, the Departmental Representative will request a meeting of parties in contract to discuss and resolve administrative procedures and responsibilities.
- .2 Departmental Representative, Contractor, major Subcontractors, field inspectors and supervisors will be in attendance.

2 PRODUCTS

2.01 NOT USED

- .1 Not Used.

3 EXECUTION

3.01 NOT USED

- .1 Not Used.

END OF SECTION

1 GENERAL

1.01 RELATED REQUIREMENTS

- .1 Are applicable to this Section the general conditions of the contract, including the general clauses, the special clauses and the specifications Sections of the Division 01.

1.02 REFERENCES

- .1 No used.

1.03 ADMINISTRATIVE

- .1 Submit to Departmental Representative submittals listed for review. Submit promptly and in orderly sequence to not cause delay in Work. Failure to submit in ample time is not considered sufficient reason for extension of Contract Time and no claim for extension by reason of such default will be allowed.
- .2 Do not proceed with Work affected by submittal until review is complete.
- .3 Present shop drawings, product data, samples and mock-ups in SI Metric units.
- .4 Where items or information is not produced in SI Metric units converted values are acceptable.
- .5 Review submittals prior to submission to Departmental Representative. This review represents that necessary requirements have been determined and verified, or will be, and that each submittal has been checked and co-ordinated with requirements of Work and Contract Documents. Submittals not stamped, signed, dated and identified as to specific project will be returned without being examined and considered rejected.
- .6 Notify Departmental Representative, in writing at time of submission, identifying deviations from requirements of Contract Documents stating reasons for deviations.
- .7 Verify field measurements and affected adjacent Work are co-ordinated.
- .8 Contractor's responsibility for errors and omissions in submission is not relieved by Departmental Representative's review of submittals.
- .9 Contractor's responsibility for deviations in submission from requirements of Contract Documents is not relieved by Departmental Representative review.
- .10 Keep one reviewed copy of each submission on site.

1.04 SHOP DRAWINGS AND PRODUCT DATA

- .1 The term "shop drawings" means drawings, diagrams, illustrations, schedules, performance charts, brochures and other data which are to be provided by Contractor to illustrate details of a portion of Work.
- .2 Submit drawings stamped and signed by professional engineer registered or licensed in Province

- of Quebec.
- .3 Indicate materials, methods of construction and attachment or anchorage, erection diagrams, connections, explanatory notes and other information necessary for completion of Work. Where articles or equipment attach or connect to other articles or equipment, indicate that such items have been co-ordinated, regardless of Section under which adjacent items will be supplied and installed. Indicate cross references to design drawings and specifications.
 - .4 Allow 14 days for Departmental Representative's review of each submission.
 - .5 Adjustments made on shop drawings by Departmental Representative are not intended to change Contract Price. If adjustments affect value of Work, state such in writing to Departmental Representative prior to proceeding with Work.
 - .6 Make changes in shop drawings as Departmental Representative may require, consistent with Contract Documents. When resubmitting, notify Departmental Representative in writing of revisions other than those requested.
 - .7 Accompany submissions with transmittal letter, in duplicate, containing:
 - .1 Date.
 - .2 Project title and number.
 - .3 Contractor's name and address.
 - .4 Identification and quantity of each shop drawing, product data and sample.
 - .5 Other pertinent data.
 - .8 Submissions include:
 - .1 Date and revision dates.
 - .2 Project title and number.
 - .3 Name and address of:
 - .1 Subcontractor.
 - .2 Supplier.
 - .3 Manufacturer.
 - .4 Contractor's stamp, signed by Contractor's authorized representative certifying approval of submissions, verification of field measurements and compliance with Contract Documents.
 - .5 Details of appropriate portions of Work as applicable:
 - .1 Fabrication.
 - .2 Layout, showing dimensions, including identified field dimensions, and clearances.
 - .3 Setting or erection details.
 - .4 Capacities.
 - .5 Performance characteristics.
 - .6 Standards.
 - .7 Operating weight.
 - .8 Wiring diagrams.
 - .9 Single line and schematic diagrams.
 - .10 Relationship to adjacent work.
 - .9 After Departmental Representative's review, distribute copies.

- .10 Submit electronic copy of shop drawings for each requirement requested in specification Sections and as Departmental Representative may reasonably request.
- .11 Submit 6 paper copies and 1 electronic copy of product data sheets or brochures for requirements requested in specification Sections and as requested by Departmental Representative where shop drawings will not be prepared due to standardized manufacture of product.
- .12 Submit 6 paper copies and 1 electronic copy of test reports for requirements requested in specification Sections and as requested by Departmental Representative.
 - .1 Report signed by authorized official of testing laboratory that material, product or system identical to material, product or system to be provided has been tested in accord with specified requirements.
 - .2 Testing must have been within 3 years of date of contract award for project.
- .13 Submit 6 paper copies and 1 electronic copy of certificates for requirements requested in specification Sections and as requested by Departmental Representative.
 - .1 Statements printed on manufacturer's letterhead and signed by responsible officials of manufacturer of product, system or material attesting that product, system or material meets specification requirements.
 - .2 Certificates must be dated after award of project contract complete with project name.
- .14 Submit 6 paper copies and 1 electronic copy of manufacturers instructions for requirements requested in specification Sections and as requested by Departmental Representative.
 - .1 Pre-printed material describing installation of product, system or material, including special notices and Material Safety Data Sheets concerning impedances, hazards and safety precautions.
- .15 Submit 6 paper copies and 1 electronic copy of Manufacturer's Field Reports for requirements requested in specification Sections and as requested by Departmental Representative.
- .16 Documentation of the testing and verification actions taken by manufacturer's representative to confirm compliance with manufacturer's standards or instructions.
- .17 Submit 6 paper copies and 1 electronic copy of Operation and Maintenance Data for requirements requested in specification Sections and as requested by Departmental Representative.
- .18 Delete information not applicable to project.
- .19 Supplement standard information to provide details applicable to project.
- .20 If upon review by Departmental Representative, and no errors or omissions are discovered or if only minor corrections are made, copies will be returned and fabrication and installation of Work may proceed. If shop drawings are rejected, noted copy will be returned and resubmission of corrected shop drawings, through same procedure indicated above, must be performed before fabrication and installation of Work may proceed.
- .21 The review of shop drawings by Public Works and Government Services Canada (PWGSC) is for sole purpose of ascertaining conformance with general concept.
 - .1 This review shall not mean that PWGSC approves detail design inherent in shop drawings, responsibility for which shall remain with Contractor submitting same, and such review shall not relieve Contractor of responsibility for errors or omissions in shop

- drawings or of responsibility for meeting requirements of construction and Contract Documents.
- .2 Without restricting generality of foregoing, Contractor is responsible for dimensions to be confirmed and correlated at job site, for information that pertains solely to fabrication processes or to techniques of construction and installation and for co-ordination of Work of sub-trades.

1.05 PHOTOGRAPHIC DOCUMENTATION

- .1 Submit electronic and hard copy of colour digital photography in jpg format, monthly with progress statement and as directed by Departmental Representative.
- .2 Project identification: name and number of project and date of exposure indicated.
- .3 Number of viewpoints: 2 locations.
.1 Viewpoints and their location as determined by Departmental Representative.
- .4 Frequency of photographic documentation: as directed by Departmental Representative.
.1 Upon completion of: framing and services before concealment, of Work, and as directed by Departmental Representative.

1.06 CERTIFICATES AND TRANSCRIPTS

- .1 Immediately after award of Contract, submit Workers' Compensation Board status.
- .2 Submit transcription of insurance immediately after award of Contract.

2 PRODUCTS

2.01 NOT USED

- .1 Not Used.

3 EXECUTION

3.01 NOT USED

- .1 Not Used.

END OF SECTION

1 GENERAL

1.01 RELATED REQUIREMENTS

- .1 Are applicable to this Section the general conditions of the contract, including the general clauses, the special clauses and the specifications Sections of the Division 01.

1.02 REFERENCES

- .1 Canada Labour Code, Part 2, Canada Occupational Safety and Health Regulations
- .2 Health Canada/Workplace Hazardous Materials Information System (WHMIS)
 - .1 Material Safety Data Sheets (MSDS).
- .3 Province of Quebec
 - .1 An Act Respecting Occupational Health and Safety, R.S.Q..

1.03 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Make submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Submit to Departmental Representative, the CSST and the «Association paritaire en santé et sécurité du secteur de la construction» (ASP Construction) the site-specific safety program, as outlined in 1.8 at least 10 days prior to start of work. The Contractor must review his program during the course of the project if any change occurs in work methods or site conditions. The Departmental Representative may, after receiving the program or at any time during the project, ask the Contractor to update or modify the program in order to better reflect the reality of the construction site and activities. The Contractor must make the required changes before work begins.
- .3 Submit to Departmental Representative the site inspection sheet, duly completed, at the intervals indicated in 1.13.1.
- .4 Submit to Departmental Representative within 24 hours a copy of any inspection report, correction notice or recommendation issued by federal or provincial inspectors.
- .5 Submit to Departmental Representative within 24 hours an investigation report for any accident involving injury and any incident exposing a potential hazard.
- .6 Submit to Departmental Representative all safety data sheets for hazardous material to be used at the site at least three days before they are to be used.
- .7 Submit to Departmental Representative copies of all training certificates required for application of the safety program, in particular:
 - .1 General construction site safety and health courses
 - .2 First aid in the workplace and cardiopulmonary resuscitation
 - .3 Work likely to release asbestos dust;
 - .4 Work in confined spaces;

- .5 Lockout procedures;
- .6 Wearing and fitting of individual protective gear;
- .7 Forklift truck;
- .8 Positioning platform;
- .9 Any other requirement of Regulations or the safety program.
- .8 Medical examinations : Wherever legislation, regulations, directives, specification or a safety program require medical examinations, Contractor must:
 - .1 Prior to start-up, submit to Departmental Representative certificates of medical examination for all concerned supervisory staff and employees who will be on duty when the site opens.
 - .2 Thereafter, submit without delay certificates of medical examination for any newly hired concerned personnel as and when they start work at the site.
- .9 Emergency plan : The emergency plan, as defined in 1.8.3, shall be submitted to Departmental Representative at the same time as the site-specific safety program.
- .10 Notice of site opening : Notice of site opening shall be submitted to the Commission de la santé et de la sécurité du travail before work begins . A copy of such notice shall be submitted to Departmental Representative at the same time and another posted in full view at the site. During demobilization, a notice of site closing shall be submitted to the CSST, with copy to Departmental Representative.
- .11 Plans and certificates of compliance : Submit to the CSST and to Departmental Representative a copy signed and sealed by Departmental Representative of all plans and certificates of compliance required pursuant to the Construction Safety Code (S-2.1, r. 6), or by any other legislation or regulation or by any other clause in the specifications or in this contract. Copies of these documents must be on hand at the site at all times.
- .12 Certificate of compliance delivered by the CSST: The certificate of compliance is a document delivered by the CSST confirming that the contractor is in rule with the CSST, i.e. that he had pay out all the benefits concerning this contract. This document must be delivered to Departmental Representative at the end of the work.
- .13 Submit WHMIS MSDS - Material Safety Data Sheets in accordance with Section 02 81 01 - Hazardous Materials.

1.04 FILING OF NOTICE

- .1 File Notice of Project with Provincial authorities prior to beginning of Work.

1.05 SAFETY ASSESSMENT

- .1 Perform site specific safety hazard assessment related to project.
- .2 The contractor must plan and organize work so as to eliminate hazards at source or promote mutual protection so that reliance on individual protective gear can be kept to a minimum. Where individual protection against falling is required, workers shall use safety harness that meets standard Can - CSA- Z-259.10 - M90. Safety belts shall not be used as protection against

falling.

- .3 Equipment, tools and protective gear which cannot be installed, fitted or used without compromising the health or safety of workers or the public shall be deemed inadequate for the work to be executed.
- .4 For use of equipment for lifting persons or materials, ensure that the inspections required by the standards are met and be able to provide a copy of certificates of inspection upon request of Representative of the Ministry.

1.06 MEETINGS

- .1 Schedule and administer Health and Safety meeting with Departmental Representative prior to commencement of Work.

1.07 REGULATORY REQUIREMENTS

- .1 Do Work in accordance with Section 01 41 00 - Regulatory Requirements.
- .2 Comply with all legislation, regulations and standards applicable to the site and its related activities.

1.08 GENERAL REQUIREMENTS

- .1 Develop written site-specific Health and Safety Plan based on hazard assessment prior to beginning site Work and continue to implement, maintain, and enforce plan until final demobilization from site. Health and Safety Plan must address project specifications.
- .2 Departmental Representative may respond in writing, where deficiencies or concerns are noted and may request re-submission with correction of deficiencies or concerns.

1.09 RESPONSIBILITY

- .1 Be responsible for health and safety of persons on site, safety of property on site and for protection of persons adjacent to site and environment to extent that they may be affected by conduct of Work.
- .2 Comply with and enforce compliance by employees with safety requirements of Contract Documents, applicable federal, provincial, territorial and local statutes, regulations, and ordinances, and with site-specific Health and Safety Plan.

1.10 COMPLIANCE REQUIREMENTS

- .1 Comply with Occupational Health and Safety Act, Industrial and Commercial Establishments Regulation, applicable.

1.11 UNFORSEEN HAZARDS

- .1 When unforeseen or peculiar safety-related factor, hazard, or condition occur during performance of Work, follow procedures in place for Employee's Right to Refuse Work in accordance with Acts and Regulations of Province having jurisdiction and advise Departmental Representative

verbally and in writing.

1.12 POSTING OF DOCUMENTS

- .1 Ensure applicable items, articles, notices and orders are posted in conspicuous location on site in accordance with Acts and Regulations of Province having jurisdiction, and in consultation with Departmental Representative.

1.13 CORRECTION OF NON-COMPLIANCE

- .1 Immediately address health and safety non-compliance issues identified by authority having jurisdiction or by Departmental Representative.
- .2 Provide Departmental Representative with written report of action taken to correct non-compliance of health and safety issues identified.
- .3 Departmental Representative may stop Work if non-compliance of health and safety regulations is not corrected.

1.14 WORK STOPPAGE

- .1 Give precedence to safety and health of public and site personnel and protection of environment over cost and schedule considerations for Work.

2 PRODUCTS

2.01 NOT USED

- .1 Not used.

3 EXECUTION

3.01 NOT USED

- .1 Not used.

END OF SECTION

1 GENERAL

1.01 RELATED REQUIREMENTS

- .1 Are applicable to this Section the general conditions of the contract, including the general clauses, the special clauses and the specifications Sections of the Division 01.

1.02 REFERENCES

- .1 Definitions:
 - .1 Environmental Pollution and Damage: presence of chemical, physical, biological elements or agents which adversely affect human health and welfare; unfavourably alter ecological balances of importance to human life; affect other species of importance to humankind; or degrade environment aesthetically, culturally and/or historically.
 - .2 Environmental Protection: prevention/control of pollution and habitat or environment disruption during construction. Control of environmental pollution and damage requires consideration of land, water, and air; biological and cultural resources; and includes management of visual aesthetics; noise; solid, chemical, gaseous, and liquid waste; radiant energy and radioactive material as well as other pollutants.

1.03 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Prior to commencing construction activities or delivery of materials to site, provide Environmental Protection Plan for review and approval by Departmental Representative.
- .4 Ensure Environmental Protection Plan includes comprehensive overview of known or potential environmental issues to be addressed during construction.
- .5 Address topics at level of detail commensurate with environmental issue and required construction tasks.
- .6 Include in Environmental Protection Plan:
 - .1 Names of persons responsible for ensuring adherence to Environmental Protection Plan.
 - .2 Names and qualifications of persons responsible for manifesting hazardous waste to be removed from site.
 - .3 Names and qualifications of persons responsible for training site personnel.
 - .4 Descriptions of environmental protection personnel training program.
 - .5 Spill Control Plan including procedures, instructions, and reports to be used in event of unforeseen spill of regulated substance.
 - .6 Non-Hazardous solid waste disposal plan identifying methods and locations for solid waste disposal including clearing debris.
 - .7 Air pollution control plan detailing provisions to assure that dust, debris, materials, and trash, are contained on project site.
 - .8 Contaminant Prevention Plan identifying potentially hazardous substances to be used on job site; intended actions to prevent introduction of such materials into air, or water; and detailing provisions for compliance with Federal, Provincial, and Municipal laws and regulations for storage and handling of these materials.

- .9 Waste Water Management Plan identifying methods and procedures for management and/or discharge of waste waters which are directly derived from construction activities, such as clean-up water, disinfection water, hydrostatic test water, and water used in flushing of lines.

1.04 FIRES

- .1 Fires and burning of rubbish on site not permitted.

1.05 POLLUTION CONTROL

- .1 Control emissions from equipment and plant to local authorities' emission requirements.
- .2 Prevent sandblasting and other extraneous materials from contaminating air beyond application area.
 - .1 Provide temporary enclosures and protection on equipment in the work area to protect against dust produced by the work and as directed by Departmental Representative.

1.06 NOTIFICATION

- .1 Departmental Representative will notify Contractor in writing of observed noncompliance with Federal, Provincial or Municipal environmental laws or regulations, permits, and other elements of Contractor's Environmental Protection plan.
- .2 Contractor: after receipt of such notice, inform Departmental Representative of proposed corrective action and take such action for approval by Departmental Representative.
 - .1 Do not take action until after receipt of written approval by Departmental Representative.
- .3 Departmental Representative will issue stop order of work until satisfactory corrective action has been taken.
- .4 No time extensions granted or equitable adjustments allowed to Contractor for such suspensions.

2 PRODUCTS

2.01 NOT USED

- .1 Not Used.

3 EXECUTION

3.01 CLEANING

- .1 Clean in accordance with Section 01 74 11 - Cleaning.
- .2 Ensure public waterways, storm and sanitary sewers remain free of waste and volatile materials disposal.

END OF SECTION

1 GENERAL

1.01 RELATED REQUIREMENTS

- .1 Are applicable to this Section the general conditions of the contract, including the general clauses, the special clauses and the specifications Sections of the Division 01.

1.02 REFERENCES AND CODES

- .1 Perform Work in accordance with National Building Code of Canada (NBC 2015) including amendments up to tender closing date and other codes of provincial or local application provided that in case of conflict or discrepancy, more stringent requirements apply.
- .2 Meet or exceed requirements of:
 - .1 Contract documents.
 - .2 Specified standards, codes and referenced documents.

1.03 HAZARDOUS MATERIAL DISCOVERY

- .1 Asbestos: demolition of spray or trowel-applied asbestos is hazardous to health. Stop work immediately when material resembling spray or trowel-applied asbestos is encountered during demolition work. Notify Departmental Representative. Refer to the document for the removal insulation with asbestos, produced by the specialist in asbestos, provided by the Departmental Representative.
- .2 PCB: Polychlorinated Biphenyl: stop work immediately when material resembling Polychlorinated Biphenyl is encountered during demolition work. Notify Departmental Representative. Refer to the document for the removal insulation with asbestos, produced by the specialist in asbestos, provided by the Departmental Representative.
- .3 Mould: stop work immediately when material resembling mould is encountered during demolition work. Notify Departmental Representative. Refer to the document for the removal insulation with asbestos, produced by the specialist in asbestos, provided by the Departmental Representative.

1.04 BUILDING SMOKING ENVIRONMENT

- .1 Comply with smoking restrictions and municipal by-laws.

2 PRODUCTS

2.01 NOT USED

- .1 Not Used.

3 EXECUTION

3.01 NOT USED

.1 Not Used.

END OF SECTION

1 GENERAL

1.01 RELATED REQUIREMENTS

- .1 Are applicable to this Section the general conditions of the contract, including the general clauses, the special clauses and the specifications Sections of the Division 01.

1.02 REFERENCES

- .1 Not Used

1.03 INSPECTION

- .1 Allow Departmental Representative access to Work. If part of Work is in preparation at locations other than Place of Work, allow access to such Work whenever it is in progress.
- .2 Give timely notice requesting inspection if Work is designated for special tests, inspections or approvals by Departmental Representative instructions, or law of Place of Work.
- .3 If Contractor covers or permits to be covered Work that has been designated for special tests, inspections or approvals before such is made, uncover such Work, have inspections or tests satisfactorily completed and make good such Work.
- .4 Departmental Representative will order part of Work to be examined if Work is suspected to be not in accordance with Contract Documents. If, upon examination such work is found not in accordance with Contract Documents, correct such Work and pay cost of examination and correction.

1.04 ACCESS TO WORK

- .1 Allow inspection/testing agencies access to Work, off site manufacturing and fabrication plants.
- .2 Co-operate to provide reasonable facilities for such access.

1.05 PROCEDURES

- .1 Notify appropriate agency and Departmental Representative in advance of requirement for tests, in order that attendance arrangements can be made.
- .2 Submit samples and/or materials required for testing, as specifically requested in specifications. Submit with reasonable promptness and in orderly sequence to not cause delays in Work.
- .3 Provide labour and facilities to obtain and handle samples and materials on site. Provide sufficient space to store and cure test samples.

1.06 REJECTED WORK

- .1 Remove defective Work, whether result of poor workmanship, use of defective products or damage and whether incorporated in Work or not, which has been rejected by Departmental Representative as failing to conform to Contract Documents. Replace or re-execute in accordance

with Contract Documents.

- .3 Make good other Contractor's work damaged by such removals or replacements promptly.
- .4 If in opinion of Departmental Representative it is not expedient to correct defective Work or Work not performed in accordance with Contract Documents, Owner will deduct from Contract Price difference in value between Work performed and that called for by Contract Documents, amount of which will be determined by Departmental Representative.

2 PRODUCTS

2.01 NOT USED

- .1 Not Used.

3 EXECUTION

3.01 NOT USED

- .1 Not Used.

END OF SECTION

1 GENERAL

1.01 RELATED REQUIREMENTS

- .1 Are applicable to this Section the general conditions of the contract, including the general clauses, the special clauses and the specifications Sections of the Division 01.

1.02 REFERENCES

- .1 Canadian Standards Association (CSA International)
 - .1 CAN/CSA-Z321-96(R2001), Signs and Symbols for the Occupational Environment.

1.03 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.

1.04 INSTALLATION AND REMOVAL

- .1 Indicate use of supplemental or other staging area.
- .2 Provide construction facilities in order to execute work expeditiously.
- .3 Remove from site all such work after use.

1.05 SCAFFOLDING

- .1 Scaffolding in accordance with CAN/CSA-S269.2.
- .2 Provide and maintain scaffolding, ladders and platforms.

1.06 HOISTING

- .1 Provide, operate and maintain hoists cranes required for moving of workers, materials and equipment. Make financial arrangements with Subcontractors for their use of hoists.
- .2 Hoists cranes to be operated by qualified operator.

1.07 ELEVATORS

- .1 Designated existing elevators to be used by construction personnel and transporting of materials. Co-ordinate use with Departmental Representative.
- .2 Provide protective coverings for finish surfaces of cars and entrances.

1.08 SITE STORAGE/LOADING

- .1 Confine work and operations of employees by Contract Documents. Do not unreasonably encumber premises with products.
- .2 Do not load or permit to load any part of Work with weight or force that will endanger Work.

1.09 CONSTRUCTION PARKING

- .1 Parking will be permitted on site.

1.10 CLEAN-UP

- .1 Remove construction debris, waste materials, packaging material from work site daily.

2 PRODUCTS

2.01 NOT USED

- .1 Not Used.

3 EXECUTION

3.01 NOT USED

- .1 Not Used.

END OF SECTION

1 GENERAL

1.01 RELATED REQUIREMENTS

- .1 Are applicable to this Section the general conditions of the contract, including the general clauses, the special clauses and the specifications Sections of the Division 01.

1.02 INSTALLATION AND REMOVAL

- .1 Provide temporary controls in order to execute Work expeditiously.
- .2 Remove from site all such work after use.

1.03 DUST TIGHT SCREENS

- .1 Provide dust tight screens or insulated partitions to localize dust generating activities, and for protection of workers, finished areas of Work and public.
- .2 Maintain and relocate protection until such work is complete.

1.04 PROTECTION OF BUILDING FINISHES

- .1 Provide protection for finished and partially finished building finishes and equipment during performance of Work.
- .2 Provide necessary screens, covers, and hoardings.
- .3 Confirm with Departmental Representative locations and installation schedule 3 days prior to installation.
- .4 Be responsible for damage incurred due to lack of or improper protection.

2 PRODUCTS

2.01 NOT USED

- .1 Not Used.

3 EXECUTION

3.01 NOT USED

- .1 Not Used.

END OF SECTION

1 GENERAL

1.01 RELATED REQUIREMENTS

- .1 Are applicable to this Section the general conditions of the contract, including the general clauses, the special clauses and the specifications Sections of the Division 01.

1.02 REFERENCES

- .1 Conform to these reference standards, in whole or in part as specifically requested in specifications.
- .4 If there is question as to whether products or systems are in conformance with applicable standards, Departmental Representative reserves right to have such products or systems tested to prove or disprove conformance.
- .5 Cost for such testing will be born by Contactor in event of conformance with Contract Documents.

1.03 QUALITY

- .1 Products, materials, equipment and articles incorporated in Work shall be new, not damaged or defective, and of best quality for purpose intended. If requested, furnish evidence as to type, source and quality of products provided.
- .2 Procurement policy is to acquire, in cost effective manner, items containing highest percentage of recycled and recovered materials practicable consistent with maintaining satisfactory levels of competition. Make reasonable efforts to use recycled and recovered materials and in otherwise utilizing recycled and recovered materials in execution of work.
- .3 Defective products, whenever identified prior to completion of Work, will be rejected, regardless of previous inspections. Inspection does not relieve responsibility, but is precaution against oversight or error. Remove and replace defective products at own expense and be responsible for delays and expenses caused by rejection.
- .4 Should disputes arise as to quality or fitness of products, decision rests strictly with Departmental Representative based upon requirements of Contract Documents.
- .5 Unless otherwise indicated in specifications, maintain uniformity of manufacture for any particular or like item throughout building.
- .6 Permanent labels, trademarks and nameplates on products are not acceptable in prominent locations, except where required for operating instructions, or when located in mechanical or electrical rooms.

1.04 AVAILABILITY

- .1 Immediately upon signing Contract, review product delivery requirements and anticipate foreseeable supply delays for items. If delays in supply of products are foreseeable, notify

Departmental Representative of such, in order that substitutions or other remedial action may be authorized in ample time to prevent delay in performance of Work.

- .2 In event of failure to notify Departmental Representative at commencement of Work and should it subsequently appear that Work may be delayed for such reason, Departmental Representative reserves right to substitute more readily available products of similar character, at no increase in Contract Price or Contract Time.

1.05 STORAGE, HANDLING AND PROTECTION

- .1 Handle and store products in manner to prevent damage, adulteration, deterioration and soiling and in accordance with manufacturer's instructions when applicable.
- .2 Store packaged or bundled products in original and undamaged condition with manufacturer's seal and labels intact. Do not remove from packaging or bundling until required in Work.
- .3 Store cementitious products clear of earth or concrete floors, and away from walls.
- .4 Store and mix paints in heated and ventilated room. Remove oily rags and other combustible debris from site daily. Take every precaution necessary to prevent spontaneous combustion.
- .5 Remove and replace damaged products at own expense and to satisfaction of Departmental Representative.
- .6 Touch-up damaged factory finished surfaces to Departmental Representative's satisfaction. Use touch-up materials to match original. Do not paint over name plates.

1.06 TRANSPORTATION

- .1 Pay costs of transportation of products required in performance of Work.

1.07 MANUFACTURER'S INSTRUCTIONS

- .1 Unless otherwise indicated in specifications, install or erect products in accordance with manufacturer's instructions. Do not rely on labels or enclosures provided with products. Obtain written instructions directly from manufacturers.
- .2 Notify Departmental Representative in writing, of conflicts between specifications and manufacturer's instructions, so that Departmental Representative will establish course of action.
- .3 Improper installation or erection of products, due to failure in complying with these requirements, authorizes Departmental Representative to require removal and re-installation at no increase in Contract Price or Contract Time.

1.08 QUALITY OF WORK

- .1 Ensure Quality of Work is of highest standard, executed by workers experienced and skilled in respective duties for which they are employed. Immediately notify Departmental Representative if required Work is such as to make it impractical to produce required results.
- .2 Do not employ anyone unskilled in their required duties. Departmental Representative reserves

right to require dismissal from site, workers deemed incompetent or careless.

- .3 Decisions as to standard or fitness of Quality of Work in cases of dispute rest solely with Departmental Representative, whose decision is final.

1.09 CO-ORDINATION

- .1 Ensure co-operation of workers in laying out Work. Maintain efficient and continuous supervision.
- .2 Be responsible for coordination and placement of openings, sleeves and accessories.

1.10 CONCEALMENT

- .1 In finished areas conceal pipes, ducts and wiring in floors, walls and ceilings, except where indicated otherwise.
- .2 Before installation inform Departmental Representative if there is interference. Install as directed by Departmental Representative.

1.11 REMEDIAL WORK

- .1 Perform remedial work required to repair or replace parts or portions of Work identified as defective or unacceptable. Co-ordinate adjacent affected Work as required.
- .2 Perform remedial work by specialists familiar with materials affected. Perform in a manner to neither damage nor put at risk any portion of Work.

1.12 LOCATION OF FIXTURES

- .1 Consider location of fixtures, outlets, and mechanical and electrical items indicated as approximate.
- .2 Inform Departmental Representative of conflicting installation. Install as directed.

1.13 FASTENINGS

- .1 Provide metal fastenings and accessories in same texture, colour and finish as adjacent materials, unless indicated otherwise.
- .2 Prevent electrolytic action between dissimilar metals and materials.
- .3 Use non-corrosive hot dip galvanized steel fasteners and anchors for securing exterior work, unless stainless steel or other material is specifically requested in affected specification Section.
- .4 Space anchors within individual load limit or shear capacity and ensure they provide positive permanent anchorage. Wood, or any other organic material plugs are not acceptable.
- .5 Keep exposed fastenings to a minimum, space evenly and install neatly.
- .6 Fastenings which cause spalling or cracking of material to which anchorage is made are not acceptable.

1.14 FASTENINGS - EQUIPMENT

- .1 Use fastenings of standard commercial sizes and patterns with material and finish suitable for service.
- .2 Use heavy hexagon heads, semi-finished unless otherwise specified. Use No. 304 stainless steel for exterior areas.
- .3 Bolts may not project more than one diameter beyond nuts.
- .4 Use plain type washers on equipment, sheet metal and soft gasket lock type washers where vibrations occur. Use resilient washers with stainless steel.

1.15 PROTECTION OF WORK IN PROGRESS

- .1 Prevent overloading of parts of building. Do not cut, drill or sleeve load bearing structural member, unless specifically indicated without written approval of Departmental Representative.

1.16 EXISTING UTILITIES

- .1 When breaking into or connecting to existing services or utilities, execute Work at times directed by local governing authorities, with minimum of disturbance to Work, and/or building occupants.
- .2 Protect, relocate or maintain existing active services. When services are encountered, cap off in manner approved by authority having jurisdiction. Stake and record location of capped service.

2 PRODUCTS

2.01 NOT USED

- .1 Not Used.

3 EXECUTION

3.01 NOT USED

- .1 Not Used.

END OF SECTION

1 GENERAL

1.01 RELATED REQUIREMENTS

- .1 Are applicable to this Section the general conditions of the contract, including the general clauses, the special clauses and the specifications Sections of the Division 01.

1.02 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submittals: in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Submit written request in advance of cutting or alteration which affects:
 - .1 Structural integrity of elements of project.
 - .2 Integrity of weather-exposed or moisture-resistant elements.
 - .3 Efficiency, maintenance, or safety of operational elements.
 - .4 Visual qualities of sight-exposed elements.
 - .5 Work of Owner or separate contractor.
- .3 Include in request:
 - .1 Identification of project.
 - .2 Location and description of affected Work.
 - .3 Statement on necessity for cutting or alteration.
 - .4 Description of proposed Work, and products to be used.
 - .5 Alternatives to cutting and patching.
 - .6 Effect on Work of Owner or separate contractor.
 - .7 Written permission of affected separate contractor.
 - .8 Date and time work will be executed.

1.03 MATERIALS

- .1 Required for original installation.
- .2 Change in Materials: Submit request for substitution in accordance with Section 01 33 00 - Submittal Procedures.

1.04 PREPARATION

- .1 Inspect existing conditions, including elements subject to damage or movement during cutting and patching.
- .2 After uncovering, inspect conditions affecting performance of Work.
- .3 Beginning of cutting or patching means acceptance of existing conditions.
- .4 Provide supports to assure structural integrity of surroundings; provide devices and methods to protect other portions of project from damage.

1.05 EXECUTION

- .1 Execute cutting, fitting, and patching to complete Work.

- .2 Fit several parts together, to integrate with other Work.
- .3 Uncover Work to install ill-timed Work.
- .4 Remove and replace defective and non-conforming Work.
- .5 Provide openings in non-structural elements of Work for penetrations of mechanical and electrical Work.
- .6 Execute Work by methods to avoid damage to other Work, and which will provide proper surfaces to receive patching and finishing.
- .7 Employ original installer to perform cutting and patching for weather-exposed and moisture-resistant elements, and sight-exposed surfaces.
- .8 Cut rigid materials using masonry saw or core drill. Pneumatic or impact tools not allowed on masonry work without prior approval.
- .9 Restore work with new products in accordance with requirements of Contract Documents.
- .10 Fit Work airtight to pipes, sleeves, ducts, conduit, and other penetrations through surfaces.
- .11 Refinish surfaces to match adjacent finishes: Refinish continuous surfaces to nearest intersection. Refinish assemblies by refinishing entire unit.

2 PRODUCTS

2.01 NOT USED

- .1 Not Used.

3 EXECUTION

3.01 NOT USED

- .1 Not Used.

END OF SECTION

1 GENERAL

1.01 RELATED REQUIREMENTS

- .1 Are applicable to this Section the general conditions of the contract, including the general clauses, the special clauses and the specifications Sections of the Division 01.

1.02 PROJECT CLEANLINESS

- .1 Maintain Work in tidy condition, free from accumulation of waste products and debris, including that caused by Owner or other Contractors.
- .2 Remove waste materials from site at daily regularly scheduled times or dispose of as directed by Departmental Representative. Do not burn waste materials on site.
- .3 Make arrangements with and obtain permits from authorities having jurisdiction for disposal of waste and debris.
- .4 Provide on-site containers for collection of waste materials and debris.
- .5 Provide and use marked separate bins for recycling.
- .6 Dispose of waste materials and debris off site.
- .7 Clean interior areas prior to start of finishing work, and maintain areas free of dust and other contaminants during finishing operations.
- .8 Store volatile waste in covered metal containers, and remove from premises at end of each working day.
- .9 Provide adequate ventilation during use of volatile or noxious substances. Use of building ventilation systems is not permitted for this purpose.
- .10 Use only cleaning materials recommended by manufacturer of surface to be cleaned, and as recommended by cleaning material manufacturer.
- .11 Schedule cleaning operations so that resulting dust, debris and other contaminants will not fall on wet, newly painted surfaces nor contaminate building systems.

1.03 FINAL CLEANING

- .1 When Work is Substantially Performed remove surplus products, tools, construction machinery and equipment not required for performance of remaining Work.
- .2 Remove waste products and debris other than that caused by others, and leave Work clean and suitable for occupancy.
- .3 Prior to final review remove surplus products, tools, construction machinery and equipment.
- .4 Remove waste products and debris including that caused by Owner or other Contractors.

- .5 Remove waste materials from site at regularly scheduled times or dispose of as directed by Departmental Representative. Do not burn waste materials on site.
- .6 Make arrangements with and obtain permits from authorities having jurisdiction for disposal of waste and debris.
- .7 Clean and polish hardware and mechanical and electrical fixtures.
- .8 Remove stains, spots, marks and dirt from electrical and mechanical fixtures, walls, and floors.
- .9 Clean lighting reflectors, lenses, and other lighting surfaces.
- .10 Vacuum clean and dust building interiors, behind grilles, louvres and screens.
- .11 Inspect finishes, fitments and equipment and ensure specified workmanship and operation.
- .12 Remove dirt and other disfiguration from exterior surfaces.
- .13 Sweep and wash clean paved areas.
- .14 Clean equipment and fixtures to sanitary condition; clean or replace filters of mechanical equipment.

2 PRODUCTS

2.01 NOT USED

- .1 Not Used.

3 EXECUTION

3.01 NOT USED

- .1 Not Used.

END OF SECTION

1 GENERAL

1.01 RELATED REQUIREMENTS

- .1 Are applicable to this Section the general conditions of the contract, including the general clauses, the special clauses and the specifications Sections of the Division 01.

1.02 ADMINISTRATIVE REQUIREMENTS

- .1 Acceptance of Work Procedures:
 - .1 Contractor's Inspection: Contractor : conduct inspection of Work, identify deficiencies and defects, and repair as required to conform to Contract Documents.
 - .1 Notify Departmental Representative in writing of satisfactory completion of Contractor's inspection and submit verification that corrections have been made.
 - .2 Request Departmental Representative inspection.
 - .2 Departmental Representative Inspection:
 - .1 Departmental Representative and Contractor to inspect Work and identify defects and deficiencies.
 - .2 Contractor to correct Work as directed.
 - .3 Completion Tasks: submit written certificates in English and French that tasks have been performed as follows:
 - .1 Work: completed and inspected for compliance with Contract Documents.
 - .2 Defects: corrected and deficiencies completed.
 - .3 Equipment and systems: tested, adjusted and balanced and fully operational.
 - .4 Certificates required by Utility companies : submitted.
 - .5 Operation of systems: demonstrated to Owner's personnel.
 - .6 Commissioning of mechanical systems: completed in accordance with exigences des manufacturiers and copies of final Commissioning Report submitted to Departmental Representative.
 - .7 Work: complete and ready for final inspection.
 - .4 Final Inspection:
 - .1 When completion tasks are done, request final inspection of Work by Departmental Representative, and Contractor.
 - .2 When Work incomplete according to Owner and Departmental Representative, complete outstanding items and request re-inspection.

1.03 FINAL CLEANING

- .1 Clean in accordance with Section 01 74 11 - Cleaning.
 - .1 Remove surplus materials, excess materials, rubbish, tools and equipment.

2 PRODUCTS

2.01 NOT USED

- .1 Not Used.

3 EXECUTION

3.01 NOT USED

.1 Not Used.

END OF SECTION

1 GENERAL

1.01 RELATED REQUIREMENTS

- .1 Are applicable to this Section the general conditions of the contract, including the general clauses, the special clauses and the specifications Sections of the Division 01.

1.02 ADMINISTRATIVE REQUIREMENTS

- .1 Pre-warranty Meeting:
 - .1 Convene meeting one week prior to contract completion with contractor's representative and Departmental Representative, in accordance with Section 01 31 19 - Project Meetings to:
 - .1 Verify Project requirements.
 - .2 Review manufacturer's installation instructions and warranty requirements.
 - .2 Departmental Representative to establish communication procedures for:
 - .1 Notifying construction warranty defects.
 - .2 Determine priorities for type of defects.
 - .3 Determine reasonable response time.
 - .3 Contact information for bonded and licensed company for warranty work action: provide name, telephone number and address of company authorized for construction warranty work action.
 - .4 Ensure contact is located within local service area of warranted construction, is continuously available, and is responsive to inquiries for warranty work action.

1.03 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Two weeks prior to Substantial Performance of the Work, submit to the Departmental Representative, four final copies of operating and maintenance manuals in English and French.
- .3 Provide spare parts, maintenance materials and special tools of same quality and manufacture as products provided in Work.
- .4 Provide evidence, if requested, for type, source and quality of products supplied.

1.04 FORMAT

- .1 Organize data as instructional manual.
- .2 Binders: vinyl, hard covered, 3 'D' ring, loose leaf 219 x 279 mm with spine and face pockets.
- .3 When multiple binders are used correlate data into related consistent groupings.
 - .1 Identify contents of each binder on spine.
- .4 Cover: identify each binder with type or printed title 'Project Record Documents'; list title of project and identify subject matter of contents.

- .5 Arrange content by systems, under Section numbers and sequence of Table of Contents.
- .6 Provide tabbed fly leaf for each separate product and system, with typed description of product and major component parts of equipment.
- .7 Text: manufacturer's printed data, or typewritten data.
- .8 Drawings: provide with reinforced punched binder tab.
 - .1 Bind in with text; fold larger drawings to size of text pages.
- .9 Provide 1:1 scaled CAD files in dwg format on CD.

1.05 CONTENTS - PROJECT RECORD DOCUMENTS

- .1 Table of Contents for Each Volume: provide title of project;
 - .1 Date of submission; names.
 - .2 Addresses, and telephone numbers of Departmental Representative and Contractor with name of responsible parties.
 - .3 Schedule of products and systems, indexed to content of volume.
- .2 For each product or system:
 - .1 List names, addresses and telephone numbers of subcontractors and suppliers, including local source of supplies and replacement parts.
- .3 Product Data: mark each sheet to identify specific products and component parts, and data applicable to installation; delete inapplicable information.
- .4 Drawings: supplement product data to illustrate relations of component parts of equipment and systems, to show control and flow diagrams.
- .5 Typewritten Text: as required to supplement product data.
 - .1 Provide logical sequence of instructions for each procedure, incorporating manufacturer's instructions specified in Section 01 45 00 - Quality Control.
- .6 Training: refer to Section 01 79 00 - Demonstration and Training.

1.06 AS -BUILT DOCUMENTS AND SAMPLES

- .1 Maintain, in addition to requirements in General Conditions, at site for Departmental Representative and Owner one record copy of:
 - .1 Contract Drawings.
 - .2 Specifications.
 - .3 Addenda.
 - .4 Change Orders and other modifications to Contract.
 - .5 Reviewed shop drawings, product data, and samples.
 - .6 Field test records.
 - .7 Inspection certificates.
 - .8 Manufacturer's certificates.
- .2 Store record documents and samples in field office apart from documents used for construction.
 - .1 Provide files, racks, and secure storage.

- .3 Label record documents and file in accordance with Section number listings in List of Contents of this Project Manual.
 - .1 Label each document "PROJECT RECORD" in neat, large, printed letters.
- .4 Maintain record documents in clean, dry and legible condition.
 - .1 Do not use record documents for construction purposes.
- .5 Keep record documents and samples available for inspection by Departmental Representative.

1.07 RECORDING INFORMATION ON PROJECT RECORD DOCUMENTS

- .1 Record information on set of blue line opaque drawings, and in copy of Project Manual, provided by Departmental Representative.
- .2 Use felt tip marking pens, maintaining separate colours for each major system, for recording information.
- .3 Record information concurrently with construction progress.
 - .1 Do not conceal Work until required information is recorded.
- .4 Contract Drawings and shop drawings: mark each item to record actual construction, including:
 - .1 Measured locations of internal utilities and appurtenances, referenced to visible and accessible features of construction.
 - .2 Field changes of dimension and detail.
 - .3 Changes made by change orders.
 - .4 Details not on original Contract Drawings.
 - .5 References to related shop drawings and modifications.
- .5 Specifications: mark each item to record actual construction, including:
 - .1 Manufacturer, trade name, and catalogue number of each product actually installed, particularly optional items and substitute items.
 - .2 Changes made by Addenda and change orders.
- .6 Other Documents: maintain [manufacturer's certifications,] [inspection certifications,] [field test records,] required by individual specifications sections.
- .7 Provide digital photos, if requested, for site records.

1.08 EQUIPMENT AND SYSTEMS

- .1 For each item of equipment and each system include description of unit or system, and component parts.
 - .1 Give function, normal operation characteristics and limiting conditions.
 - .2 Include performance curves, with engineering data and tests, and complete nomenclature and commercial number of replaceable parts.
- .2 Operating Procedures: include start-up, break-in, and routine normal operating instructions and sequences.
 - .1 Include regulation, control, stopping, shut-down, and emergency instructions.
 - .2 Include summer, winter, and any special operating instructions.

- .3 Maintenance Requirements: include routine procedures and guide for trouble-shooting; disassembly, repair, and reassembly instructions; and alignment, adjusting, balancing, and checking instructions.
- .4 Provide servicing and lubrication schedule, and list of lubricants required.
- .5 Include manufacturer's printed operation and maintenance instructions.
- .6 Include sequence of operation by controls manufacturer.
- .7 Provide original manufacturer's parts list, illustrations, assembly drawings, and diagrams required for maintenance.
- .8 Provide installed control diagrams by controls manufacturer.
- .9 Provide Contractor's co-ordination drawings, with installed colour coded piping diagrams.
- .10 Provide charts of valve tag numbers, with location and function of each valve, keyed to flow and control diagrams.
- .11 Provide list of original manufacturer's spare parts, current prices, and recommended quantities to be maintained in storage.
- .12 Include test and balancing reports as specified in Section 01 45 00 - Quality Control.
- .13 Additional requirements: as specified in individual specification sections.

1.09 MATERIALS AND FINISHES

- .1 Building products, applied materials, and finishes: include product data, with catalogue number, size, composition, and colour and texture designations.
 - .1 [Provide information for re-ordering custom manufactured products].
- .2 Instructions for cleaning agents and methods, precautions against detrimental agents and methods, and recommended schedule for cleaning and maintenance.
- .3 Additional requirements: as specified in individual specifications sections.

1.10 MAINTENANCE MATERIALS

- .1 Special Tools:
 - .1 Provide special tools, in quantities specified in individual specification section.
 - .2 Provide items with tags identifying their associated function and equipment.
 - .3 Deliver to site, location as directed; place and store.
 - .4 Receive and catalogue items.
 - .1 Submit inventory listing to Departmental Representative.
 - .2 Include approved listings in Maintenance Manual.

1.11 DELIVERY, STORAGE AND HANDLING

- .1 Store special tools in manner to prevent damage or deterioration.

- .2 Store in original and undamaged condition with manufacturer's seal and labels intact.
- .3 Store paints and freezable materials in a heated and ventilated room.
- .5 Remove and replace damaged products at own expense and for review by Departmental Representative.

1.12 WARRANTIES AND BONDS

- .1 Develop warranty management plan to contain information relevant to Warranties.
- .2 Submit warranty management plan, 30 days before planned pre-warranty conference, to Departmental Representative approval.
- .3 Warranty management plan to include required actions and documents to assure that Departmental Representative receives warranties to which it is entitled.
- .4 Provide plan in narrative form and contain sufficient detail to make it suitable for use by future maintenance and repair personnel.
- .5 Submit, warranty information made available during construction phase, to Departmental Representative for approval prior to each monthly pay estimate.
- .6 Assemble approved information in binder, submit upon acceptance of work and organize binder as follows:
 - .1 Separate each warranty or bond with index tab sheets keyed to Table of Contents listing.
 - .2 List subcontractor, supplier, and manufacturer, with name, address, and telephone number of responsible principal.
 - .3 Obtain warranties and bonds, executed in duplicate by subcontractors, suppliers, and manufacturers, within ten days after completion of applicable item of work.
 - .4 Verify that documents are in proper form, contain full information, and are notarized.
 - .5 Co-execute submittals when required.
 - .6 Retain warranties and bonds until time specified for submittal.
- .7 Except for items put into use with Owner's permission, leave date of beginning of time of warranty until Date of Substantial Performance is determined.
- .8 Conduct joint 9 month warranty inspection, measured from time of acceptance, by Departmental Representative.
- .9 Include information contained in warranty management plan as follows:
 - .1 Roles and responsibilities of personnel associated with warranty process, including points of contact and telephone numbers within the organizations of Contractors, subcontractors, manufacturers or suppliers involved.
 - .2 Listing and status of delivery of Certificates of Warranty for extended warranty items, to include HVAC balancing, the new coils and the new humidifiers.
 - .3 Provide list for each warranted equipment, item, feature of construction or system indicating:
 - .1 Name of item.
 - .2 Model and serial numbers.
 - .3 Location where installed.

- .4 Name and phone numbers of manufacturers or suppliers.
- .5 Names, addresses and telephone numbers of sources of spare parts.
- .6 Warranties and terms of warranty: include one-year overall warranty of construction. Indicate items that have extended warranties and show separate warranty expiration dates.
- .7 Cross-reference to warranty certificates as applicable.
- .8 Starting point and duration of warranty period.
- .9 Summary of maintenance procedures required to continue warranty in force.
- .10 Cross-Reference to specific pertinent Operation and Maintenance manuals.
- .11 Organization, names and phone numbers of persons to call for warranty service.
- .12 Typical response time and repair time expected for various warranted equipment.
- .4 Contractor's plans for attendance at 9 month post-construction warranty inspections.
- .5 Procedure and status of tagging of equipment covered by extended warranties.
- .6 Post copies of instructions near selected pieces of equipment where operation is critical for warranty and/or safety reasons.
- .10 Respond in timely manner to oral or written notification of required construction warranty repair work.
- .11 Written verification to follow oral instructions.
 - .1 Failure to respond will be cause for the Departmental Representative to proceed with action against Contractor.

1.13 WARRANTY TAGS

- .1 Tag, at time of installation, each warranted item. Provide durable, oil and water resistant tag approved by Departmental Representative.
- .2 Attach tags with copper wire and spray with waterproof silicone coating.
- .3 Leave date of acceptance until project is accepted for occupancy.
- .4 Indicate following information on tag:
 - .1 Type of product/material.
 - .2 Model number.
 - .3 Serial number.
 - .4 Contract number.
 - .5 Warranty period.
 - .6 Inspector's signature.
 - .7 Construction Contractor.

2 PRODUCTS

2.01 NOT USED

- .1 Not Used.

3 EXECUTION

3.01 NOT USED

.1 Not Used.

END OF SECTION

1 GENERAL

1.01 RELATED REQUIREMENTS

- .1 Are applicable to this Section the general conditions of the contract, including the general clauses, the special clauses and the specifications Sections of the Division 01.

1.02 ADMINISTRATIVE REQUIREMENTS

- .1 Demonstrate scheduled operation and maintenance of equipment and systems to Owner's personnel two weeks prior to date of final inspection.
- .2 Owner: provide list of personnel to receive instructions, and co-ordinate their attendance at agreed-upon times.
- .3 Preparation:
 - .1 Verify conditions for demonstration and instructions comply with requirements.
 - .2 Verify designated personnel are present.
 - .3 Ensure equipment has been inspected and put into operation in accordance to manufacturers exigencies.
 - .4 Ensure testing, adjusting, and balancing has been performed and equipment and systems are fully operational.
- .4 Demonstration and Instructions:
 - .1 Demonstrate start-up, operation, control, adjustment, trouble-shooting, servicing, and maintenance of each item of equipment at agreed upon times, at the equipment location.
 - .2 Instruct personnel in phases of operation and maintenance using operation and maintenance manuals as basis of instruction.
 - .3 Review contents of manual in detail to explain aspects of operation and maintenance.
 - .4 Prepare and insert additional data in operations and maintenance manuals when needed during instructions.
- .5 Time Allocated for Instructions: ensure amount of time required for instruction of each item of equipment or system as follows:
 - .1 Section 23 - Heating Plant: 3 hours of instruction.
 - .2 Section 23 - Cooling and Ventilation System: 3 hours of instruction.

1.03 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Submit schedule of time and date for demonstration of each item of equipment and each system two weeks prior to designated dates, for Departmental Representative's approval.
- .3 Submit reports within one week after completion of demonstration, that demonstration and instructions have been satisfactorily completed.
- .4 Give time and date of each demonstration, with list of persons present.

- .5 Provide copies of completed operation and maintenance manuals for use in demonstrations and instructions.

1.04 QUALITY ASSURANCE

- .1 When specified in individual Sections requiring manufacturer to provide authorized representative to demonstrate operation of equipment and systems:
 - .1 Instruct Owner's personnel.
 - .2 Provide written report that demonstration and instructions have been completed.

2 PRODUCTS

2.01 NOT USED

- .1 Not Used.

3 EXECUTION

3.01 NOT USED

- .1 Not Used.

END OF SECTION

1 GENERAL

1.01 RELATED REQUIREMENTS

- .1 Are applicable to this Section the general conditions of the contract, including the general clauses, the special clauses and the specifications Sections of the Division 01.

1.02 REFERENCES

- .1 CSA International
 - .1 CSA S350-M1980(R2003), Code of Practice for Safety in Demolition of Structures.
- .2 U.S. Environmental Protection Agency (EPA)/Office of Water
 - .1 EPA 832/R-92-005, Storm Water Management for Construction Activities: Developing Pollution Prevention Plans and Best Management Practices.

1.03 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Submit demolition drawings:
 - .1 Submit for review and approval by Departmental Representative shoring and underpinning drawings stamped and signed by professional engineer registered or licensed in the Province of Quebec, showing proposed method.

1.04 SITE CONDITIONS

- .1 Review "Designated Substance Report" and take precautions to protect environment.
- .2 If material resembling spray or trowel-applied asbestos or other designated substance listed as hazardous be encountered, stop work, take preventative measures, and notify Departmental Representative immediately.
 - .1 Proceed only after receipt of written instructions have been received from Departmental Representative.
- .3 Notify Departmental Representative before disrupting building access or services.

2 PRODUCTS

2.01 NOT USED

- .1 Not used.

3 EXECUTION

3.01 EXAMINATION

- .1 Inspect building and site with Departmental Representative and verify extent and location of

items designated for removal, disposal, alternative disposal, recycling, salvage and items to remain.

- .2 Locate and protect utilities. Preserve active utilities traversing site in operating condition.
- .3 Notify and obtain approval of utility companies before starting demolition.

3.02 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 74 11 - Cleaning.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 - Cleaning.
- .3 Refer to demolition drawings and specifications for items to be salvaged for reuse.

END OF SECTION

1 GENERAL

1.01 RELATED REQUIREMENTS

- .1 Are applicable to this Section the general conditions of the contract, including the general clauses, the special clauses and the specifications Sections of the Division 01.

1.02 REFERENCES

- .1 Canadian Environmental Protection Act, 1999 (CEPA 1999).
- .2 Health Canada/Workplace Hazardous Materials Information System (WHMIS)
 - .1 Material Safety Data Sheets (MSDS).
- .3 National Fire Code of Canada, 2015.
- .4 Transportation of Dangerous Goods Act (TDGA), 1999 c. 34.
- .5 Transportation of Dangerous Goods Regulations (TDGR), T-19.01-SOR/2003-400.
- .6 Ozone-Depleting Substances Regulations, SOR/99-07.
- .7 Environmental Code of Practice on Halons, July 1996.
- .8 Environmental Code of Practice for Elimination of Fluorocarbon Emissions from Refrigeration and Air Conditioning Systems, March 1996.

1.03 DEFINITIONS

- .1 Toxic: substance is considered toxic if it is listed on Toxic Substances List found in Schedule 1 of CEPA.
- .2 List of Toxic Substances: found in Schedule 1 of CEPA, lists substances that have been assessed as toxic. Federal Government can make regulations with respect to a substance specified on List of Toxic Substances. Column II of this list identifies type of regulation applicable to each substance.
- .3 PCBs: includes chlorobiphenyls referred to in Column I of item 1 of the List of Toxic Substances in Schedule I of Canadian Environmental Protection Act.

1.04 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit WHMIS MSDS - Material Safety Data Sheets in accordance with Section 02 81 01 - Hazardous Materials.
 - .2 Submit photocopy of shipping documents and waste manifests to Departmental Representative when shipping toxic wastes off site.
 - .3 Maintain 1 copy of product data in readily accessible file on site.

1.05 DELIVERY, STORAGE, AND HANDLING

- .1 Store and handle toxic wastes in accordance with applicable federal and provincial laws, regulations, codes, and guidelines.
- .2 Store and handle flammable and combustible wastes in accordance with current National Fire Code of Canada requirements.
- .3 Co-ordinate storage of toxic wastes with Departmental Representative and follow internal requirements for labelling and storage of wastes.
- .4 Observe smoking regulations, smoking is prohibited in area where toxic wastes are stored, used, or handled.
- .5 Only certified persons who have successfully completed Environment Canada Environmental Awareness Course for Environmentally Safe Handling of Refrigerants are permitted to work on refrigeration and air conditioning systems.
- .6 Report spills or accidents involving toxic wastes immediately to Departmental Representative and to appropriate regulatory authorities. Take reasonable measures to contain the release while ensuring health and safety is protected.
- .7 Transport toxic wastes in accordance with federal Transportation of Dangerous Goods Act, Transportation of Dangerous Goods Regulations, and applicable provincial regulations.
- .8 Use authorized/licensed carrier to transport toxic waste.
- .9 Co-ordinate transportation and disposal of toxic wastes with Departmental Representative.
- .10 Notify appropriate regulatory authorities and obtain required permits and approvals prior to exporting toxic waste.
- .11 Dispose of toxic wastes generated on site in accordance with applicable federal and provincial acts, regulations, and guidelines.
- .12 Ensure toxic waste is shipped to authorized/licensed treatment or disposal facility and that liability insurance requirements are met.
- .13 Minimize generation of toxic waste to maximum extent practicable. Take necessary precautions to avoid mixing clean and contaminated wastes.

2 PRODUCTS

2.01 NOT USED

- .1 Not Used.

3 EXECUTION

3.01 NOT USED

.1 Not Used.

END OF SECTION

1 GENERAL

1.01 RELATED REQUIREMENTS

- .1 Are applicable to this Section the general conditions of the contract, including the general clauses, the special clauses and the specifications Sections of the Division 01.

1.02 REFERENCES

- .1 Definitions:
 - .1 Dangerous Goods: product, substance, or organism specifically listed or meets hazard criteria established in Transportation of Dangerous Goods Regulations.
 - .2 Hazardous Material: product, substance, or organism used for its original purpose; and is either dangerous goods or material that will cause adverse impact to environment or adversely affect health of persons, animals, or plant life when released into the environment.
 - .3 Hazardous Waste: hazardous material no longer used for its original purpose and that is intended for recycling, treatment or disposal.
- .2 Reference Standards:
 - .1 Canadian Environmental Protection Act, 1999 (CEPA 1999)
 - .1 Export and Import of Hazardous Waste and Hazardous Recyclable Material Regulations (SOR/2005-149).
 - .2 Department of Justice Canada (Jus)
 - .1 Transportation of Dangerous Goods Act, 1992 (TDG Act) 1992, (c. 34).
 - .2 Transportation of Dangerous Goods Regulations (T-19.01-SOR/2001-286).
 - .3 Green Seal Environmental Standards (GS)
 - .1 GS-11-2008, 2nd Edition, Paints and Coatings.
 - .2 GS-36-00, Commercial Adhesives.
 - .4 Health Canada / Workplace Hazardous Materials Information System (WHMIS)
 - .1 Material Safety Data Sheets (MSDS).
 - .5 National Research Council Canada Institute for Research in Construction (NRC-IRC)
 - .1 National Fire Code of Canada-2015.
- .3 South Coast Air Quality Management District (SCAQMD), California State, Regulation XI. Source Specific Standards
 - .1 SCAQMD Rule 1113-A2007, Architectural Coatings.
 - .2 SCAQMD Rule 1168-A2005, Adhesive and Sealant Applications.

1.03 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for hazardous materials and include product characteristics, performance criteria, physical size, finish and limitations.
 - .2 Submit two copies of WHMIS MSDS in accordance with Section 01 35 29.06 - Health and Safety Requirements and 01 35 43 - Environmental Procedures to Departmental

Representative for each hazardous material required prior to bringing hazardous material on site.

1.04 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements and with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Transport hazardous materials and wastes in accordance with Transportation of Dangerous Goods Act, Transportation of Dangerous Goods Regulations, and applicable provincial regulations.
- .4 Storage and Handling Requirements:
 - .1 Co-ordinate storage of hazardous materials with Departmental Representative and abide by internal requirements for labelling and storage of materials and wastes.
 - .2 Store and handle hazardous materials and wastes in accordance with applicable federal and provincial laws, regulations, codes, and guidelines.
 - .3 Store and handle flammable and combustible materials in accordance with National Fire Code of Canada requirements.
 - .4 Keep no more than 45 litres of flammable and combustible liquids such as gasoline, kerosene and naphtha for ready use.
 - .1 Store flammable and combustible liquids in approved safety cans bearing the Underwriters' Laboratory of Canada or Factory Mutual seal of approval.
 - .2 Storage of quantities of flammable and combustible liquids exceeding 45 litres for work purposes requires the written approval of the Departmental Representative.
 - .5 Transfer of flammable and combustible liquids is prohibited within buildings.
 - .6 Transfer flammable and combustible liquids away from open flames or heat-producing devices.
 - .7 Solvents or cleaning agents must be non-flammable or have flash point above 38 degrees C.
 - .8 Store flammable and combustible waste liquids for disposal in approved containers located in safe, ventilated area. Keep quantities to minimum.
 - .9 Observe smoking regulations, smoking is prohibited in areas where hazardous materials are stored, used, or handled.
 - .10 Storage requirements for quantities of hazardous materials and wastes in excess of 5 kg for solids, and 5 litres for liquids:
 - .1 Store hazardous materials and wastes in closed and sealed containers.
 - .2 Label containers of hazardous materials and wastes in accordance with WHMIS.
 - .3 Store hazardous materials and wastes in containers compatible with that material or waste.
 - .4 Segregate incompatible materials and wastes.
 - .5 Ensure that different hazardous materials or hazardous wastes are stored in separate containers.
 - .6 Store hazardous materials and wastes in secure storage area with controlled access.
 - .7 Maintain clear egress from storage area.
 - .8 Store hazardous materials and wastes in location that will prevent them from

- spilling into environment.
- .9 Have appropriate emergency spill response equipment available near storage area, including personal protective equipment.
- .10 Maintain inventory of hazardous materials and wastes, including product name, quantity, and date when storage began.
- .11 When hazardous waste is generated on site:
 - .1 Co-ordinate transportation and disposal with Departmental Representative.
 - .2 Comply with applicable federal, provincial and municipal laws and regulations for generators of hazardous waste.
 - .3 Use licensed carrier authorized by provincial authorities to accept subject material.
 - .4 Before shipping material obtain written notice from intended hazardous waste treatment or disposal facility it will accept material and it is licensed to accept this material.
 - .5 Label containers with legible, visible safety marks as prescribed by federal and provincial regulations.
 - .6 Only trained personnel handle, offer for transport, or transport dangerous goods.
 - .7 Provide photocopy of shipping documents and waste manifests to Departmental Representative.
 - .8 Track receipt of completed manifest from consignee after shipping dangerous goods. Provide photocopy of completed manifest to Departmental Representative.
 - .9 Report discharge, emission, or escape of hazardous materials immediately to Departmental Representative and appropriate provincial authority. Take reasonable measures to control release.
- .12 Ensure personnel have been trained in accordance with Workplace Hazardous Materials Information System (WHMIS) requirements.
- .13 Report spills or accidents immediately to Departmental Representative. Submit a written spill report to Departmental Representative within 24 hours of incident.
- .5 Develop Construction Waste Management Plan related to Work of this Section.
- .6 Packaging Waste Management: remove for reuse and return by manufacturer of pallets, crates, padding, and packaging materials as specified in Construction Waste Management Plan Waste Reduction Workplan.

2 PRODUCTS

2.01 MATERIALS

- .1 Description:
 - .1 Bring on site only quantities hazardous material required to perform Work.
 - .2 Maintain MSDS in proximity to where materials are being used. Communicate this location to personnel who may have contact with hazardous materials.

3 EXECUTION

3.01 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 74 11 - Cleaning.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 - Cleaning.
- .3 Waste Management: separate waste materials for recycling.
 - .1 Dispose of hazardous waste materials in accordance with applicable federal and provincial acts, regulations, and guidelines.
 - .2 Recycle hazardous wastes for which there is approved, cost effective recycling process available.
 - .3 Send hazardous wastes to authorized hazardous waste disposal or treatment facilities.
 - .4 Burning, diluting, or mixing hazardous wastes for purpose of disposal is prohibited.
 - .5 Disposal of hazardous materials in waterways, storm or sanitary sewers, or in municipal solid waste landfills is prohibited.
 - .6 Dispose of hazardous wastes in timely fashion in accordance with applicable provincial regulations.
 - .7 Minimize generation of hazardous waste to maximum extent practicable. Take necessary precautions to avoid mixing clean and contaminated wastes.
 - .8 Identify and evaluate recycling and reclamation options as alternatives to land disposal, such as:
 - .1 Hazardous wastes recycled in manner constituting disposal.
 - .2 Hazardous waste burned for energy recovery.
 - .3 Lead-acid battery recycling.
 - .4 Hazardous wastes with economically recoverable precious metals.

END OF SECTION

1 GENERAL

1.01 RELATED REQUIREMENTS

- .1 Are applicable to this Section the general conditions of the contract, including the general clauses, the special clauses and the specifications Sections of the Division 01.

1.02 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for all products and include product characteristics, performance criteria, physical size, finish and limitations.

1.03 CLOSEOUT SUBMITTALS

- .1 Submit in accordance with Section 01 78 00 - Closeout Submittals.
- .2 Operation and Maintenance Data: submit operation and maintenance data for incorporation into manual.
 - .1 Operation and maintenance manual approved by, and final copies deposited with, Departmental Representative before final inspection.
 - .2 Operation data to include:
 - .1 Control schematics for systems including environmental controls.
 - .2 Description of systems and their controls.
 - .3 Description of operation of systems at various loads together with reset schedules and seasonal variances.
 - .4 Operation instruction for systems and component.
 - .5 Description of actions to be taken in event of equipment failure.
 - .6 Valves schedule and flow diagram.
 - .7 Colour coding chart.
 - .3 Maintenance data to include:
 - .1 Servicing, maintenance, operation and trouble-shooting instructions for each item of equipment.
 - .2 Data to include schedules of tasks, frequency, tools required and task time.
 - .4 Performance data to include:
 - .1 Equipment manufacturer's performance datasheets with point of operation as left after commissioning is complete.
 - .2 Equipment performance verification test results.
 - .3 Special performance data as specified.
 - .5 Approvals:
 - .1 Submit 2 copies of draft Operation and Maintenance Manual to Departmental Representative for approval. Submission of individual data will not be accepted unless directed by Departmental Representative.
 - .2 Make changes as required and re-submit as directed by Departmental Representative.
 - .6 Additional data:

- .1 Prepare and insert into operation and maintenance manual additional data when need for it becomes apparent during specified demonstrations and instructions.
- .7 Site records:
 - .1 Departmental Representative will provide 1 set of reproducible mechanical drawings. Provide sets of white prints as required for each phase of work. Mark changes as work progresses and as changes occur. Include changes to existing mechanical systems, control systems and low voltage control wiring.
 - .2 Transfer information weekly to reproducibles, revising reproducibles to show work as actually installed.
 - .3 Use different colour waterproof ink for each service.
 - .4 Make available for reference purposes and inspection.
- .8 As-built drawings:
 - .1 Prior to start of Testing, Adjusting and Balancing for HVAC, finalize production of as-built drawings.
 - .2 Identify each drawing in lower right hand corner in letters at least 12 mm high as follows: - "AS BUILT DRAWINGS: THIS DRAWING HAS BEEN REVISED TO SHOW MECHANICAL SYSTEMS AS INSTALLED" (Signature of Contractor) (Date).
 - .3 Submit to Departmental Representative for approval and make corrections as directed.
 - .4 Perform testing, adjusting and balancing for HVAC using as-built drawings.
 - .5 Submit completed reproducible as-built drawings with Operating and Maintenance Manuals.
- .9 Submit copies of as-built drawings for inclusion in final TAB report.

1.04 MAINTENANCE MATERIAL SUBMITTALS

- .1 Submit in accordance with Section 01 78 00 - Closeout Submittals.
- .2 Furnish spare parts as follows:
 - .1 One set of packing for each pump.
 - .2 One casing joint gasket for each size pump.
 - .3 One glass for each gauge glass.
- .3 Provide one set of special tools required to service equipment as recommended by manufacturers.
- .4 Furnish one commercial quality grease gun, grease and adapters to suit different types of grease and grease fittings.

1.05 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements and with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
 - .1 Store materials off ground, indoors, in dry location and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Store and protect from nicks, scratches, and blemishes.

- .3 Replace defective or damaged materials with new.

2 PRODUCTS

2.01 NOT USED

- .1 Not used.

3 EXECUTION

3.01 EXAMINATION

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for installation in accordance with manufacturer's written instructions.
 - .1 Visually inspect substrate in presence of Departmental Representative.
 - .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.
 - .3 Proceed with installation only after unacceptable conditions have been remedied and after receipt of written approval to proceed from Departmental Representative.

3.02 PAINTING REPAIRS AND RESTORATION

- .1 Prime and touch up marred finished paintwork to match original.
- .2 Restore to new condition, finishes which have been damaged.

3.03 SYSTEM CLEANING

- .1 Clean interior and exterior of all systems including strainers. Vacuum interior of ductwork and air handling units.

3.04 FIELD QUALITY CONTROL

- .1 Site Tests: conduct following tests in accordance with Section 01 45 00 - Quality Control and submit report as described in PART 1 -ACTION AND INFORMATIONAL SUBMITTALS.
- .2 Manufacturer's Field Services:
 - .1 Obtain written report from manufacturer verifying compliance of Work, in handling, installing, applying, protecting and cleaning of product and submit Manufacturer's Field Reports as described in PART 1 - ACTION AND INFORMATIONAL SUBMITTALS.
 - .2 Provide manufacturer's field services consisting of product use recommendations and periodic site visits for inspection of product installation in accordance with manufacturer's instructions.

3.05 DEMONSTRATION

- .1 Departmental Representative will use equipment and systems for test purposes prior to acceptance. Supply labour, material, and instruments required for testing.

- .2 Trial usage to apply to following equipment and systems:
- .3 Supply tools, equipment and personnel to demonstrate and instruct operating and maintenance personnel in operating, controlling, adjusting, trouble-shooting and servicing of all systems and equipment during regular work hours, prior to acceptance.
- .4 Use operation and maintenance manual, as-built drawings, and audio visual aids as part of instruction materials.
- .5 Instruction duration time requirements as specified in appropriate sections.
- .6 Departmental Representative will record these demonstrations on video tape for future reference.

3.06 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 74 11 - Cleaning.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 - Cleaning.

3.07 PROTECTION

- .1 Protect equipment and systems openings from dirt, dust, and other foreign materials with materials appropriate to system.

END OF SECTION

1 GENERAL

1.01 RELATED REQUIREMENTS

- .1 Are applicable to this Section the general conditions of the contract, including the general clauses, the special clauses and the specifications Sections of the Division 01.

1.02 REFERENCES

- .1 Health Canada/Workplace Hazardous Materials Information System (WHMIS)
 - .1 Material Safety Data Sheets (MSDS).

2 PRODUCTS

2.01 DOMESTIC HOT WATER CIRCULATING PUMPS

- .1 Flow Rate: as indicated.
- .2 Pumps : closed-coupled, in-line centrifugal, all bronze construction, stainless steel shaft, stainless steel or bronze shaft sleeve, two oil lubricated bronze sleeves or ball bearings. Design for 1034 kPa and 105 degrees C continuous service.
- .3 Motor: 92 W, drip-proof, with thermal overload protection.
- .4 Supports: provide as recommended by manufacturer.

3 EXECUTION

3.01 MANUFACTURER'S INSTRUCTIONS

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and data sheet.

3.02 INSTALLATION

- .1 Make piping and electrical connections to pump and motor assembly and controls as indicated.
- .2 Ensure pump and motor assembly do not support piping.
- .3 Align vertical pit mounted pump assembly after mounting and securing cover plate.
- .4 Place 150 mm sand under sump pit tank.

3.03 FIELD QUALITY CONTROL

- .1 Site Tests/Inspection:
 - .1 Check power supply.
 - .2 Check starter protective devices.

- .2 Start-up, check for proper and safe operation.
- .3 Check settings and operation of hand-off-auto selector switch, operating, safety and limit controls, audible and visual alarms, over-temperature and other protective devices.
- .4 Adjust flow from water-cooled bearings.
- .5 Adjust impeller shaft stuffing boxes, packing glands.

3.04 START-UP

- .1 General:
 - .1 Procedures:
 - .1 Check power supply.
 - .2 Check starter O/L heater sizes.
 - .3 Start pumps, check impeller rotation.
 - .4 Check for safe and proper operation.
 - .5 Check settings, operation of operating, limit, safety controls, over-temperature, audible/visual alarms, other protective devices.
 - .6 Test operation of hands-on-auto switch.
 - .7 Test operation of alternator.
 - .8 Adjust leakage through water-cooled bearings.
 - .9 Adjust shaft stuffing boxes.
 - .10 Adjust leakage flow rate from pump shaft stuffing boxes to manufacturer's recommendations.
 - .11 Check base for free-floating, no obstructions under base.
 - .12 Run-in pumps for 12 continuous hours.
 - .13 Check installation, operation of mechanical seals, packing gland type seals. Adjust as necessary.
 - .14 Adjust alignment of piping and conduit to ensure full flexibility.
 - .15 Eliminate causes of cavitation, flashing, air entrainment.
 - .16 Measure pressure drop across strainer when clean and with flow rates as finally set.
 - .17 Replace seals if pump used to degrease system or if pump used for temporary heat.
 - .18 Verify lubricating oil levels.

3.05 REPORTS

- .1 Include:
 - .1 PV results on approved PV Report Forms.
 - .2 Product Information report forms.
 - .3 Pump performance curves (family of curves) with final point of actual performance.

END OF SECTION

1 GENERAL

1.01 RELATED REQUIREMENTS

- .1 Are applicable to this Section the general conditions of the contract, including the general clauses, the special clauses and the specifications Sections of the Division 01.

1.02 REFERENCE STANDARDS

- .1 ASTM International
 - .1 ASTM A 126-04(2009), Standard Specification for Gray Iron Castings for Valves, Flanges and Pipe Fittings.
 - .2 ASTM B 62-09, Standard Specification for Composition Bronze or Ounce Metal Castings.
- .2 American Water Works Association (AWWA)
 - .1 ANSI/AWWA C700-09, Standard for Cold Water Meters-Displacement Type, Bronze Main Case.
 - .2 ANSI/AWWA C701-12, Standard for Cold Water Meters-Turbine Type for Customer Service.
 - .3 ANSI/AWWA C702-10, Standard for Cold Water Meters-Compound Type.
- .3 CSA International
 - .1 CSA-B64 Series-11, Backflow Preventers and Vacuum Breakers.
 - .2 CSA B79-08, Commercial and Residential Drains and Cleanouts.
 - .3 CAN/CSA-B356-10, Water Pressure Reducing Valves for Domestic Water Supply Systems.
- .4 Efficiency Valuation Organization (EVO)
 - .1 International Performance Measurement and Verification Protocol (IPMVP).
 - .1 IPMVP 2007 Version.
- .5 National Research Council Canada (NRC)
 - .1 National Plumbing Code of Canada 2015 (NPC).
- .6 Plumbing and Drainage Institute (PDI)
 - .1 PDI-G101-R2010, Testing and Rating Procedure for Grease Interceptors with Appendix of Installation and Maintenance.
 - .2 PDI-WH201-R2010, Water Hammer Arresters Standard.

1.03 ADMINISTRATIVE REQUIREMENTS

- .1 Pre-installation Meetings:
 - .1 Convene pre-installation meeting 1 week prior to beginning work of this Section and on-site installation, with contractor's representative and Departmental Representative in accordance with Section 01 31 19 - Project Meetings to:
 - .1 Verify project requirements.
 - .2 Review installation and substrate conditions.
 - .3 Co-ordination with other building construction subtrades.

- .4 Review manufacturer's written installation instructions and warranty requirements.

1.04 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for plumbing products and include product characteristics, performance criteria, physical size, finish and limitations.
 - .2 Submit 2 copies of WHMIS MSDS in accordance with Section 01 35 29.06 - Health and Safety Requirements and 01 35 43 - Environmental Procedures. Indicate VOC's:
- .3 Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
- .4 Instructions: submit manufacturer's installation instructions.
- .5 Manufacturers' Field Reports: manufacturers' field reports specified.

1.05 CLOSEOUT SUBMITTALS

- .1 Submit in accordance with Section 01 78 00 - Closeout Submittals.
- .2 Operation and Maintenance Data: submit operation and maintenance data for plumbing specialties and accessories for incorporation into manual.
 - .1 Description of plumbing specialties and accessories, giving manufacturers name, type, model, year and capacity.
 - .2 Details of operation, servicing and maintenance.
 - .3 Recommended spare parts list.

1.06 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements and with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
 - .1 Store materials off ground, indoors, in dry location and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Store and protect plumbing materials from nicks, scratches, and blemishes.
 - .3 Replace defective or damaged materials with new.

2 PRODUCTS

2.01 BACK FLOW PREVENTERS

- .1 Preventers: to CSA-B64 Series, application as indicated, back flow preventer with intermediate

atmospheric vent or vacuum breaker.

3 EXECUTION

3.01 EXAMINATION

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for plumbing specialities and accessories installation in accordance with manufacturer's written instructions.
 - .1 Visually inspect substrate in presence of Departmental Representative.
 - .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.
 - .3 Proceed with installation only after unacceptable conditions have been remedied and after receipt of written approval to proceed from Departmental Representative.

3.02 MANUFACTURER'S INSTRUCTIONS

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and data sheet.

3.03 INSTALLATION

- .1 Install in accordance with provincial codes.
- .2 Install in accordance with manufacturer's instructions and as specified.

3.04 BACK FLOW PREVENTERS

- .1 Install in accordance with CSA-B64 Series, where indicated and elsewhere as required by code.

3.05 CHECK VALVES

- .1 Mount a check valve in specified location.

3.06 START-UP

- .1 Timing: start-up only after:
 - .1 Pressure tests have been completed.
 - .2 Disinfection procedures have been completed.
 - .3 Certificate of static completion has been issued.
 - .4 Water treatment systems operational.
- .2 Provide continuous supervision during start-up.

3.07 TESTING AND ADJUSTING

- .1 Timing:
 - .1 After start-up deficiencies rectified.
 - .2 After certificate of completion has been issued by authority having jurisdiction.
- .2 Application tolerances:

- .1 Pressure at fixtures: +/- 70 kPa.
- .2 Flow rate at fixtures: +/- 20%.
- .3 Adjustments:
 - .1 Verify that flow rate and pressure meet design criteria.
 - .2 Make adjustments while flow rate or withdrawal is (1) maximum and (2) 25% of maximum and while pressure is (1) maximum and (2) minimum.
- .4 Vacuum breakers, backflow preventers, backwater valves:
 - .1 Test tightness, accessibility for O&M of cover and of valve.
 - .2 Simulate reverse flow and back-pressure conditions to test operation of vacuum breakers, backflow preventers.
 - .3 Verify visibility of discharge from open ports.

3.08 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 74 11 - Cleaning.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 - Cleaning.

3.09 PROTECTION

- .1 Protect installed products and components from damage during construction.
- .2 Repair damage to adjacent materials caused by plumbing specialties and accessories installation.

END OF SECTION

1 GENERAL

1.01 RELATED REQUIREMENTS

- .1 Are applicable to this Section the general conditions of the contract, including the general clauses, the special clauses and the specifications Sections of the Division 01.

1.02 REFERENCE STANDARDS

- .1 Air-Conditioning and Refrigeration Institute (ARI)
 - .1 ARI 1010-02, Self-Contained, Mechanically Refrigerated Drinking-Water Coolers.
- .2 Canadian Standards Association (CSA International)
 - .1 CAN/CSA-B45 Series-02(R2008), CSA Standards on Plumbing Fixtures.
 - .2 CAN/CSA-B125.3-05, Plumbing Fittings.
 - .3 CAN/CSA-B651-04, Accessible Design for the Built Environment.
- .3 National Research Council Canada (NRC)
 - .1 National Building Code of Canada 2015 (NBC).

1.03 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for plumbing products and include product characteristics, performance criteria, physical size, finish and limitations.
 - .2 Submit 2 copies of WHMIS MSDS in accordance with Section 01 35 29.06 - Health and Safety Requirements and 01 35 43 - Environmental Procedures. Indicate VOC's:
- .3 Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
- .4 Instructions: submit manufacturer's installation instructions.
- .5 Manufacturers' Field Reports: manufacturers' field reports specified.

1.04 CLOSEOUT SUBMITTALS

- .1 Provide operation and maintenance data including monitoring requirements for incorporation into manuals specified in Section 01 78 00 - Closeout Submittals.
- .2 Include:
 - .1 Description of fixtures and trim, giving manufacturer's name, type, model, year, capacity.
 - .2 Details of operation, servicing, maintenance.
 - .3 List of recommended spare parts.

1.05 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle in accordance with Section 01 61 00 - Common Product Requirements.
- .2 Deliver materials to site in original factory packaging, labelled with manufacturer's name, address.

2 PRODUCTS

2.01 MANUFACTURED UNITS

- .1 Fixtures: manufacture in accordance with CAN/CSA-B45 series.
- .2 Trim, fittings: manufacture in accordance with CAN/CSA-B125.3.
- .3 Exposed plumbing brass to be chrome plated.
- .4 Number, locations: architectural drawings to govern.
- .5 Refrigerated water coolers:
 - .1 RWC-1: surface.
 - .1 Refrigeration system: packaged hermetic HFC-134a unit with pre-cooler, insulated double wall chiller, storage tank, air-cooled condenser, thermostatically controlled.
 - .2 Capacity: 33 L/h from 27 degrees C to 10 degrees C, with 32 degrees C ambient air. In accordance with ARI 1010.
 - .3 Cabinet: type 302 stainless steel, satin finish, integral back, strainer, access panel and grille, elevated bubbler base.
 - .4 Bubbler: pushbutton operated, self-regulating, angle stream, squirt-proof, with nozzle and guard.
 - .5 Push button type glass filler.
 - .6 Electrical: grounded electrical cord with plug: 120 V, 60 Hz. CSA certified.
- .6 Fixture piping:
 - .1 Hot and cold water supplies to each fixture:
 - .1 Chrome plated flexible supply pipes each with handwheel stop, reducers, escutcheon.
 - .2 Waste:
 - .1 Brass P trap with cleanout on each fixture not having integral trap.
 - .2 Chrome plated in all exposed places.
- .7 Chair carriers:
 - .1 Factory manufactured floor-mounted carrier systems for all wall-mounted fixtures.

3 EXECUTION

3.01 APPLICATION

- .1 Manufacturer's Instructions: comply with manufacturer's written recommendations, including product technical bulletins, handling, storage and installation instructions, and datasheets.

3.02 INSTALLATION

- .1 Wall-hung fixtures: as existant, measured from finished floor.
- .2 Physically handicapped: to comply with most stringent of either NBC or CAN/CSA B651.

3.03 ADJUSTING

- .1 Conform to water conservation requirements specified this Section.
- .2 Adjustments:
 - .1 Adjust water flow rate to design flow rates.
 - .2 Adjust water cooler, drinking fountain flow stream to ensure no spillage.
- .3 Checks:
 - .1 Refrigerated water coolers: operation, temperature settings.
- .4 Thermostatic controls:
 - .1 Verify temperature settings, operation of control, limit and safety controls.

3.04 CLEANING

- .1 Clean in accordance with Section 01 74 11 - Cleaning.
 - .1 Remove surplus materials, excess materials, rubbish, tools and equipment.

END OF SECTION

1 GENERAL

1.01 RELATED REQUIREMENTS

- .1 Are applicable to this Section the general conditions of the contract, including the general clauses, the special clauses and the specifications Sections of the Division 01.

1.02 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submittals: in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Shop drawings to show:
 - .1 Mounting arrangements.
 - .2 Operating and maintenance clearances.
- .3 Closeout Submittals:
 - .1 Provide operation and maintenance data for incorporation into manual specified in Section 01 78 00 - Closeout Submittals.
 - .2 Operation and maintenance manual approved by, and final copies deposited with, Departmental Representative before final inspection.
 - .3 Operation data to include:
 - .1 Control schematics for systems including environmental controls.
 - .2 Description of systems and their controls.
 - .3 Description of operation of systems at various loads together with reset schedules and seasonal variances.
 - .4 Operation instruction for systems and component.
 - .5 Description of actions to be taken in event of equipment failure.
 - .6 Valves schedule and flow diagram.
 - .7 Colour coding chart.
 - .4 Maintenance data to include:
 - .1 Servicing, maintenance, operation and trouble-shooting instructions for each item of equipment.
 - .2 Data to include schedules of tasks, frequency, tools required and task time.
 - .5 Performance data to include:
 - .1 Equipment manufacturer's performance datasheets with point of operation as left after commissioning is complete.
 - .2 Equipment performance verification test results.
 - .3 Special performance data as specified.
 - .4 Testing, adjusting and balancing reports.
- .4 Approvals:
 - .1 Submit 2 copies of draft Operation and Maintenance Manual to Departmental Representative for approval. Submission of individual data will not be accepted unless directed by Departmental Representative.
 - .2 Make changes as required and re-submit as directed by Departmental Representative.
- .5 Additional data:
 - .1 Prepare and insert into operation and maintenance manual additional data when

- need for it becomes apparent during specified demonstrations and instructions.
- .6 Site records:
 - .1 Departmental Representative will provide 1 set of reproducible mechanical drawings. Provide sets of white prints as required for each phase of work. Mark changes as work progresses and as changes occur. Include changes to existing mechanical systems, control systems and low voltage control wiring.
 - .2 Transfer information weekly to reproducibles, revising reproducibles to show work as actually installed.
 - .3 Use different colour waterproof ink for each service.
 - .4 Make available for reference purposes and inspection.
- .7 As-built drawings:
 - .1 Prior to start of Testing, Adjusting and Balancing for HVAC, finalize production of as-built drawings.
 - .2 Identify each drawing in lower right hand corner in letters at least 12 mm high as follows: - "AS BUILT DRAWINGS: THIS DRAWING HAS BEEN REVISED TO SHOW MECHANICAL SYSTEMS AS INSTALLED" (Signature of Contractor) (Date).
 - .3 Submit to Departmental Representative for approval and make corrections as directed.
 - .4 Perform testing, adjusting and balancing for HVAC using as-built drawings.
 - .5 Submit completed reproducible as-built drawings with Operating and Maintenance Manuals.
- .8 Submit copies of as-built drawings for inclusion in final TAB report.

1.03 QUALITY ASSURANCE

- .1 Quality Assurance: in accordance with Section 01 45 00 - Quality Control.
- .2 Health and Safety Requirements: do construction occupational health and safety in accordance with Section 01 35 29.06 - Health and Safety Requirements.

1.04 MAINTENANCE

- .1 Provide one set of special tools required to service equipment as recommended by manufacturers and in accordance with Section 01 78 00 - Closeout Submittals.

2 PRODUCTS

2.01 NOT USED

- .1 Not used.

3 EXECUTION

3.01 PAINTING REPAIRS AND RESTORATION

- .1 Prime and touch up marred finished paintwork to match original.
- .2 Restore to new condition, finishes which have been damaged.

3.02 CLEANING

- .1 Clean interior and exterior of all systems including strainers. Vacuum interior of ductwork and air handling units.

3.03 FIELD QUALITY CONTROL

- .1 Site Tests: conduct following tests in accordance with Section 01 45 00 - Quality Control and submit report as described in PART 1 - SUBMITTALS.

3.04 DEMONSTRATION

- .1 Departmental Representative will use equipment and systems for test purposes prior to acceptance. Supply labour, material, and instruments required for testing.
- .2 Supply tools, equipment and personnel to demonstrate and instruct operating and maintenance personnel in operating, controlling, adjusting, trouble-shooting and servicing of all systems and equipment during regular work hours, prior to acceptance.
- .3 Use operation and maintenance manual, as-built drawings, and audio visual aids as part of instruction materials.
- .4 Instruction duration time requirements as specified in appropriate sections.
- .5 Departmental Representative will record these demonstrations on video tape for future reference.

3.05 PROTECTION

- .1 Protect equipment and systems openings from dirt, dust, and other foreign materials with materials appropriate to system.

END OF SECTION

1 GENERAL

1.01 RELATED REQUIREMENTS

- .1 Are applicable to this Section the general conditions of the contract, including the general clauses, the special clauses and the specifications Sections of the Division 01.

1.02 REFERENCES

- .1 Canadian General Standards Board (CGSB)
 - .1 CAN/CGSB-1.181-99, Ready-Mixed Organic Zinc-Rich Coating.
- .2 Canadian Standards Association (CSA International)
 - .1 CSA B139-04, Installation Code for Oil Burning Equipment.
- .3 Green Seal Environmental Standards (GSES)
 - .1 Standard GS-11-2008, 2nd Edition, Environmental Standard for Paints and Coatings.
- .4 National Fire Code of Canada (NFCC 2015)

1.03 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Provide manufacturer's printed product literature, specifications and datasheets for piping and equipment and include product characteristics, performance criteria, physical size, finish and limitations.

1.04 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements and with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements:
 - .1 Deliver materials to site in original factory packaging, labelled with manufacturer's name, address.

2 PRODUCTS

2.01 MATERIAL

- .1 Paint: zinc-rich to CAN/CGSB-1.181.
 - .1 Paints and Coating: used, in accordance with manufacturer's recommendations for surface conditions.
- .2 Adhesives: maximum VOC limit to SCAQMD Rule 1168 to GSES GS-36.

3 EXECUTION

3.01 APPLICATION

- .1 Manufacturer's Instructions: comply with manufacturer's written recommendations, including product technical bulletins, handling, storage and installation instructions, and datasheets.

3.02 CONNECTIONS TO EQUIPMENT

- .1 In accordance with manufacturer's instructions unless otherwise indicated.
- .2 Use valves and either unions or flanges for isolation and ease of maintenance and assembly.
- .3 Use double swing joints when equipment mounted on vibration isolation and when piping subject to movement.

3.03 CLEARANCES

- .1 Provide clearance around systems, equipment and components for observation of operation, inspection, servicing, maintenance and as recommended by manufacturer and National Fire Code of Canada.
- .2 Provide space for disassembly, removal of equipment and components as recommended by manufacturer without interrupting operation of other system, equipment, components.

3.04 DRAINS

- .1 Install piping with grade in direction of flow except as indicated.
- .2 Install drain valve at low points in piping systems, at equipment and at section isolating valves.
- .3 Pipe each drain valve discharge separately to above floor drain.
 - .1 Discharge to be visible.
- .4 Drain valves: NPS 3/4 gate or globe valves unless indicated otherwise, with hose end male thread, cap and chain.

3.05 AIR VENTS

- .1 Install air vents to at high points in piping systems.
- .2 Install isolating valve at each automatic air valve.
- .3 Install drain piping to approved location and terminate where discharge is visible.

3.06 DIELECTRIC COUPLINGS

- .1 General: compatible with system, to suit pressure rating of system.
- .2 Locations: where dissimilar metals are joined.
- .3 NPS 2 and under: isolating unions or bronze valves.

- .4 Over NPS 2: isolating flanges.

3.07 PIPEWORK INSTALLATION

- .1 Install pipework to CSA B139.
- .2 Screwed fittings jointed with Teflon tape.
- .3 Protect openings against entry of foreign material.
- .4 Install to isolate equipment and allow removal without interrupting operation of other equipment or systems.
- .5 Assemble piping using fittings manufactured to ANSI standards.
- .6 Saddle type branch fittings may be used on mains if branch line is no larger than half size of main.
 - .1 Hole saw (or drill) and ream main to maintain full inside diameter of branch line prior to welding saddle.
- .7 Install exposed piping, equipment, rectangular cleanouts and similar items parallel or perpendicular to building lines.
- .8 Slope piping, except where indicated, in direction of flow for positive drainage and venting.
- .9 Install, except where indicated, to permit separate thermal insulation of each pipe.
- .10 Group piping wherever possible and as indicated.
- .11 Ream pipes, remove scale and other foreign material before assembly.
- .12 Use eccentric reducers at pipe size changes to ensure positive drainage and venting.
- .13 Provide for thermal expansion as indicated.
- .14 Valves:
 - .1 Install in accessible locations.
 - .2 Remove interior parts before soldering.
 - .3 Install with stems above horizontal position unless indicated.
 - .4 Valves accessible for maintenance without removing adjacent piping.
 - .5 Install globe valves in bypass around control valves.
 - .6 Use gate ball or butterfly valves at branch take-offs for isolating purposes except where specified.
 - .7 Install butterfly valves on chilled water and related condenser water systems only.
 - .8 Install butterfly valves between weld neck flanges to ensure full compression of liner.
 - .9 Install ball valves for glycol service.
 - .10 Use chain operators on valves NPS 2 1/2 and larger where installed more than 2400 mm above floor in Mechanical Rooms.

3.08 FLUSHING OUT OF PIPING SYSTEMS

- .1 Flush system in accordance with Section 23 08 02 - Cleaning and Start-up of Mechanical Piping Systems.
- .2 Preparatory to acceptance, clean and refurbish equipment and leave in operating condition, including replacement of filters in piping systems.

3.09 PRESSURE TESTING OF EQUIPMENT AND PIPEWORK

- .1 Advise Departmental Representative 48 hours minimum prior to performance of pressure tests.
- .2 Pipework: test as specified in relevant sections of heating, ventilating and air conditioning work.
- .3 Maintain specified test pressure without loss for 4 hours minimum unless specified for longer period of time in relevant mechanical sections.
- .4 Prior to tests, isolate equipment and other parts which are not designed to withstand test pressure or media.
- .5 Conduct tests in presence of Departmental Representative.
- .6 Pay costs for repairs or replacement, retesting, and making good. Departmental Representative to determine whether repair or replacement is appropriate.
- .7 Insulate or conceal work only after approval and certification of tests by Departmental Representative.

3.10 EXISTING SYSTEMS

- .1 Be responsible for damage to existing plant by this work.

3.11 CLEANING

- .1 Clean in accordance with Section 01 74 11 - Cleaning.
 - .1 Remove surplus materials, excess materials, rubbish, tools and equipment.

END OF SECTION

1 GENERAL

1.01 RELATED REQUIREMENTS

- .1 Are applicable to this Section the general conditions of the contract, including the general clauses, the special clauses and the specifications Sections of the Division 01.

1.02 REFERENCES

- .1 American National Standards Institute/American Society of Mechanical Engineers (ANSI/ASME)
 - .1 ANSI/ASME B31.1-1998, Power Piping.
 - .2 ANSI/ASME B31.3-2000, Process Piping.
- .2 American National Standards Institute/American Water Works Association (ANSI/AWWA)
 - .1 ANSI/AWWA C206-03, Field Welding of Steel Water Pipe.
- .3 American Welding Society (AWS)
 - .1 AWS C1.1M/C1.1-2000, Recommended Practices for Resistance Welding.
 - .2 AWS Z49.1-1999, Safety in Welding, Cutting and Allied Process.
 - .3 AWS W1-2000, Welding Inspection Handbook..
- .4 Canadian Standards Association (CSA International)
 - .1 CSA W47.2-M1987(R1998, Certification of Companies for Fusion Welding of Aluminum.
 - .2 CSA W48-series 01, Filler Metals and Allied Materials for Metal Arc Welding.
 - .3 CSA B51-1997, Boiler, Pressure Vessel and Pressure Piping Code.
 - .4 CSA-W117.2-01, Safety in Welding, Cutting and Allied Processes.
 - .5 CSA W178.1-02, Certification of Welding Inspection Organizations.
 - .6 CSA W178.2-01, Certification of Welding Inspectors.

1.03 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.

1.04 QUALITY ASSURANCE

- .1 Qualifications:
 - .1 Welders:
 - .1 Welding qualifications in accordance with CSA B51.
 - .2 Use qualified and licensed welders possessing certificate for each procedure performed from authority having jurisdiction.
 - .3 Submit welder's qualifications to Departmental Representative.
 - .4 Each welder to possess identification symbol issued by authority having jurisdiction.
 - .5 Certification of companies for fusion welding of aluminum in accordance with CSA W47.2.
 - .2 Inspectors:
 - .1 Inspectors qualified to CSA W178.2.

- .3 Certifications:
 - .1 Registration of welding procedures in accordance with CSA B51.
 - .2 Copy of welding procedures available for inspection.
 - .3 Safety in welding, cutting and allied processes in accordance with CSA-W117.2.

1.05 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle in accordance with Section 01 61 00 - Common Product Requirements.
- .2 Deliver materials to site in original factory packaging, labelled with manufacturer's name, address.
- .3 Packaging Waste Management: remove for reuse and return by manufacturer of pallets, crates, padding and packaging materials.

2 PRODUCTS

2.01 ELECTRODES

- .1 Electrodes: in accordance with CSA W48 Series.

3 EXECUTION

3.01 APPLICATION

- .1 Manufacturer's Instructions: comply with manufacturer's written recommendations, including product technical bulletins, handling, storage and installation instructions, and datasheets.

3.02 QUALITY OF WORK

- .1 Welding: in accordance with ANSI/ASME B31.1 and B31.3, ANSI/ASME Boiler and Pressure Vessel Code, Sections I and IX and ANSI/AWWA C206, using procedures conforming to AWS B3.0, AWS C1.1, and special procedures specified elsewhere in Division 15.

3.03 INSTALLATION REQUIREMENTS

- .1 Identify each weld with welder's identification symbol.
- .2 Backing rings:
 - .1 Where used, fit to minimize gaps between ring and pipe bore.
 - .2 Do not install at orifice flanges.
- .3 Fittings:
 - .1 NPS 2 and smaller: install welding type sockets.
 - .2 Branch connections: install welding tees or forged branch outlet fittings.

3.04 INSPECTION AND TESTS - GENERAL REQUIREMENTS

- .1 Review weld quality requirements and defect limits of applicable codes and standards with Departmental Representative before work is started.

- .2 Formulate "Inspection and Test Plan" in co-operation with Departmental Representative.
- .3 Do not conceal welds until they have been inspected, tested and approved by inspector.
- .4 Provide for inspector to visually inspect welds during early stages of welding procedures in accordance with Welding Inspection Handbook. Repair or replace defects as required by codes and as specified.

3.05 DEFECTS CAUSING REJECTION

- .1 As described in ANSI/ASME B31.1 and ANSI/ASME Boiler and Pressure Vessels Code.
- .2 In addition, chilled water systems :
 - .1 Undercutting greater than 0.8 mm adjacent to cover bead on outside of pipe.
 - .2 Undercutting greater than 0.8 mm adjacent to root bead on inside of pipe.
 - .3 Undercutting greater than 0.8 mm at combination of internal surface and external surface.
 - .4 Incomplete penetration and incomplete fusion greater than total length of 38 mm in 1500 mm length of weld depth of such defects being greater than 0.8 mm.
 - .5 Repair cracks and defects in excess of 0.8 mm in depth.
 - .6 Repair defects whose depth cannot be determined accurately on basis of visual examination or radiographic or particle tests.

3.06 REPAIR OF WELDS WHICH FAILED TESTS

- .1 Re-inspect and re-test repaired or re-worked welds at Contractor's expense.

3.07 CLEANING

- .1 Clean in accordance with Section 01 74 11 - Cleaning.

END OF SECTION

1 GENERAL

1.01 RELATED REQUIREMENTS

- .1 Are applicable to this Section the general conditions of the contract, including the general clauses, the special clauses and the specifications Sections of the Division 01.

1.02 REFERENCES

- .1 American Society of Mechanical Engineers (ASME).
 - .1 ASME B40.1, Pressure Gauges and Gauge Attachments.
- .2 Canadian General Standards Board (CGSB).
 - .1 CAN/CGSB-14.4, Thermometers, Liquid-in-Glass, Self Indicating, Commercial/Industrial Type.
 - .2 CAN/CGSB-14.5, Thermometers, Bimetallic, Self-Indicating, Commercial/Industrial Type.

1.03 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Submit shop drawings and product data.
- .3 Submit manufacturer's product data for following items:
 - .1 Thermometers.
 - .2 Pressure gauges.
 - .3 Stop cocks.
 - .4 Syphons.
 - .5 Wells.

1.04 HEALTH AND SAFETY

- .1 Do construction occupational health and safety in accordance with Section 01 35 29.06 - Health and Safety Requirements.

1.05 WASTE MANAGEMENT AND DISPOSAL

- .1 Collect, separate and place in designated containers for paper, plastic, polystyrene packaging Steel, Metal, Plastic in accordance with Waste Management Plan.
- .2 Fold up metal banding, flatten and place in designated area for recycling.
- .3 Place materials defined as hazardous or toxic waste in designated containers.
- .4 Ensure emptied containers are sealed, labelled and stored safely for disposal away from children.

2 PRODUCTS

2.01 GENERAL

- .1 Design point to be at mid point of scale or range.
- .2 Ranges: as indicated.

2.02 DIRECT READING THERMOMETERS

- .1 Industrial, variable angle type, liquid filled, 125 mm scale length: to CAN/CGSB 14.4.
 - .1 Products acceptable: ASMCROFT, MARSH, TRERICE, WINTERS.

2.03 THERMOMETER WELLS

- .1 Copper pipe: copper or bronze.
- .2 Steel pipe: stainless steel.

2.04 PRESSURE GAUGES

- .1 112 mm, dial type: to ASME B40.100, Grade 2A, stainless steel bourdon tube having 0.5% accuracy full scale unless otherwise specified.
 - .1 Products acceptable: ASMCROFT, MARSH, TRERICE, WINTERS.
- .2 Provide:
 - .1 Siphon for steam service.
 - .2 Snubber for pulsating operation.
 - .3 Diaphragm assembly for corrosive service.
 - .4 Gasketed pressure relief back with solid front.
 - .5 Bronze stop cock.

3 EXECUTION

3.01 GENERAL

- .1 Install so they can be easily read from floor or platform. If this cannot be accomplished, install remote reading units.
- .2 Install between equipment and first fitting or valve.

3.02 THERMOMETERS

- .1 Install in wells on piping. Provide heat conductive material inside well.
- .2 Install in locations as indicated and on inlet and outlet of:
 - .1 Water heating and cooling coils.
- .3 Use extensions where thermometers are installed through insulation.

3.03 PRESSURE GAUGES

- .1 Install in following locations:
 - .1 Upstream and downstream of PRV's.
 - .2 Upstream and downstream of control valves.
 - .3 Inlet and outlet of coils.
- .2 Use extensions where pressure gauges are installed through insulation.

3.04 NAMEPLATES

- .1 Install engraved lamicoid nameplates as specified in Section 23 05 53.01 - Mechanical Identification, identifying medium.

END OF SECTION

1 GENERAL

1.01 RELATED REQUIREMENTS

- .1 Are applicable to this Section the general conditions of the contract, including the general clauses, the special clauses and the specifications Sections of the Division 01.

1.02 REFERENCES

- .1 American National Standards Institute (ANSI)/American Society of Mechanical Engineers (ASME)
 - .1 ANSI/ASME B1.20.1-1983(R2006), Pipe Threads, General Purpose (Inch).
 - .2 ANSI/ASME B16.18-2001, Cast Copper Alloy Solder Joint Pressure Fittings.
- .2 ASTM International
 - .1 ASTM A 276-08, Standard Specification for Stainless Steel Bars and Shapes.
 - .2 ASTM B 62-02, Standard Specification for Composition Bronze or Ounce Metal Castings.
 - .3 ASTM B 283-08a, Standard Specification for Copper and Copper Alloy Die Forgings (Hot-Pressed).
 - .4 ASTM B 505/B 505M-08a, Standard Specification for Copper-Base Alloy Continuous Castings.
- .3 Manufacturers Standardization Society of the Valve and Fittings Industry, Inc. (MSS)
 - .1 MSS-SP-25-1998, Standard Marking System for Valves, Fittings, Flanges and Unions.
 - .2 MSS-SP-80-2008, Bronze Gate Globe, Angle and Check Valves.
 - .3 MSS-SP-110-1996, Ball Valves, Threaded, Socket-Welding, Solder Joint, Grooved and Flared Ends.

1.03 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Provide manufacturer's printed product literature and data sheets for equipment and systems and include product characteristics, performance criteria, physical size, finish and limitations.
 - .2 Submit WHMIS MSDS - Material Safety Data Sheets in accordance with Section 02 81 01 - Hazardous Materials.

1.04 CLOSEOUT SUBMITTALS

- .1 Provide maintenance data for incorporation into manual specified in Section 01 78 00 - Closeout Submittals.

1.05 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements and with manufacturer's written instructions.

- .2 Delivery and Acceptance Requirements:
 - .1 Deliver materials to site in original factory packaging, labelled with manufacturer's name, address.
- .3 Packaging Waste Management: remove for reuse and return by manufacturer of pallets, crates, padding, and packaging materials.

2 PRODUCTS

2.01 MATERIALS

- .1 Valves:
 - .1 Except for specialty valves, to be single manufacturer.
 - .2 Products to have CRN registration numbers.
- .2 End Connections:
 - .1 Connection into adjacent piping/tubing:
 - .1 Steel pipe systems: screwed ends to ANSI/ASME B1.20.1.
 - .2 Copper tube systems: solder ends to ANSI/ASME B16.18.
- .3 Lockshield Keys:
 - .1 Where lockshield valves are specified, provide 2 keys of each size: malleable iron cadmium plated.
- .4 Globe Valves:
 - .1 Butterfly Valves:
 - .1 NPS 2 1/2 through NPS 6, 2068 kPa with grooved ends.
 - .1 Body: cast bronze, with copper-tube dimensioned grooved ends.
 - .2 Disc: elastomer coated ductile iron with integrally cast stem.
 - .3 Operator: lever.
- .5 Check valves
 - .1 General Requirements concerning check valves unless otherwise noted.
 - .1 Reference standard : MSS SP-80.
 - .2 Nozzles : to be bolted

3 EXECUTION

3.01 INSTALLATION

- .1 Install rising stem valves in upright position with stem above horizontal.
- .2 Remove internal parts before soldering.
- .3 Install valves with unions at each piece of equipment arranged to allow servicing, maintenance, and equipment removal.

3.02 CLEANING

- .1 Clean in accordance with Section 01 74 11 - Cleaning.
- .1 Remove surplus materials, excess materials, rubbish, tools and equipment.

END OF SECTION

1 GENERAL

1.01 RELATED REQUIREMENTS

- .1 Are applicable to this Section the general conditions of the contract, including the general clauses, the special clauses and the specifications Sections of the Division 01.

1.02 REFERENCES

- .1 American Society of Mechanical Engineers (ASME)
 - .1 ASME B16.1-05, Cast Iron Pipe Flanges and Flanged Fittings.
- .2 ASTM International Inc.
 - .1 ASTM A 126-04, Standard Specification for Gray Iron Castings for Valves, Flanges, and Pipe Fittings.
 - .2 ASTM B 62-02, Standard Specification for Composition Bronze or Ounce Metal Castings.
 - .3 ASTM B 85/B 85M-08, Standard Specification for Aluminum-Alloy Die Castings.
- .3 Manufacturers Standardization Society of the Valve and Fittings Industry, Inc. (MSS)
 - .1 MSS SP-70-06, Grey Iron Gate Valves, Flanged and Threaded Ends.
 - .2 MSS SP-71-05, Grey Iron Swing Check Valves, Flanged and Threaded Ends.
 - .3 MSS SP-82-1992, Valve Pressure Testing Methods.
 - .4 MSS SP-85-2002, Cast Iron Globe and Angle Valves, Flanged and Threaded Ends.

1.03 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Provide manufacturer's printed product literature, specifications and datasheets for valves and include product characteristics, performance criteria, physical size, finish and limitations.

1.04 CLOSEOUT SUBMITTALS

- .1 Submit maintenance data for incorporation into manual specified in Section 01 78 00 - Closeout Submittals.

1.05 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements and with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements:
 - .1 Deliver materials to site in original factory packaging, labelled with manufacturer's name, address.

2 PRODUCTS

2.01 MATERIAL

- .1 Valves:
 - .1 Except for specialty valves, to be of single manufacturer.
- .2 Standard specifications:
 - .1 Gate valves: MSS SP-70.
 - .2 Globe valves: MSS SP-85.
 - .3 Check valves: MSS SP-71.
- .3 Requirements common to valves, unless specified otherwise:
 - .1 Body, bonnet: cast iron to ASTM B 209 Class B.
 - .2 Connections: flanged ends plain face to ANSI B16.1.
 - .3 Inspection and pressure testing: to MSS SP-82.
 - .4 Bonnet gasket: non-asbestos.
 - .5 Stem: to have precision-machined Acme or 60 degrees V threads, top screwed for handwheel nut.
 - .6 Stuffing box: non-galling two-piece ball-jointed packing gland, gland bolts and nuts.
 - .7 Gland packing: non-asbestos.
 - .8 Handwheel: die-cast aluminum alloy to ASTM B 85/B 85M or malleable iron to ASTM A 49. Nut of bronze to ASTM B 62.
 - .9 Identification tag: with catalogue number, size, other pertinent data.
- .4 All products to have CRN registration numbers.

2.02 CHECK VALVES

- .1 Swing check valves, Class 125:
 - .1 Body and bolted cover: with tapped and plugged opening on each side for hinge pin. Grooved or flanged ends: plain faced with smooth finish.
 - .1 Up to NPS 16: cast iron to ASTM A 126 Class B.
 - .2 Ratings:
 - .1 NPS 2 1/2 - 12: 860 kPa steam; 1.4 MPa CWP.
 - .3 Disc: rotating for extended life.
 - .1 Up to NPS 6: bronze to ASTM B 62.
 - .4 Seat rings: renewable bronze to ASTM B 62 screwed into body.
 - .5 Hinge pin, bushings: renewable bronze to ASTM B 62.
 - .6 Disc: A126 Class B, secured to stem, rotating for extended life.
 - .7 Seat: cast iron, integral with body.
 - .8 Hinge pin: exelloy; bushings: malleable iron.
 - .9 Identification tag: fastened to cover.
 - .10 Hinge: galvanized malleable iron.

3 EXECUTION

3.01 INSTALLATION

- .1 Install rising stem valves in upright position with stem above horizontal.

3.02 CLEANING

- .1 Clean in accordance with Section 01 74 11 - Cleaning.
- .2 Clean installed products in accordance to manufacturer's recommendation.

END OF SECTION

1 GENERAL

1.01 RELATED REQUIREMENTS

- .1 Are applicable to this Section the general conditions of the contract, including the general clauses, the special clauses and the specifications Sections of the Division 01.

1.02 REFERENCES

- .1 American National Standards Institute (ANSI)/American Society of Mechanical Engineers (ASME)
 - .1 ASME B1.20.1-1983(R2006), Pipe Threads, General Purpose (Inch).
 - .2 ASME B16.1-05, Gray Iron Pipe Flanges and Flanged Fittings: Classes 25,125 and 250.
 - .3 ANSI/ASME B16.5-03, Pipe Flanges and Flanged Fittings: NPS ½ through 24.
 - .4 ANSI/ASME B16.11-05, Forged Fittings, Socket-Welding and Threaded.
 - .5 ANSI/ASME B16.25-07, Buttwelding Ends.
 - .6 ANSI/ASME B16.34-04, Valves - Flanged, Threaded and Welding Ends.
- .2 American Petroleum Institute (API)
 - .1 API Std. 609-04, Butterfly Valves: Double Flanged, Lug- and Wafer-Type.
- .3 ASTM International Inc.
 - .1 ASTM A 126-04, Standard Specification for Gray Iron Castings for Valves, Flanges, and Pipe Fittings.
 - .2 ASTM A 536-84(2004)e1, Standard Specification for Ductile Iron Castings.
 - .3 ASTM B 62-02, Standard Specification for Composition Bronze or Ounce Metal Castings.
 - .4 ASTM B 209M-07, Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate Metric.
- .4 Manufacturers Standardization Society of the Valve and Fittings Industry, Inc. (MSS)
 - .1 MSS SP-67-02a, Butterfly Valves.

1.03 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's printed product literature, specifications and datasheets for valves and include product characteristics, performance criteria, physical size, finish and limitations.
 - .2 Submit data for valves specified in this section.

1.04 CLOSEOUT SUBMITTALS

- .1 Submit maintenance data for incorporation into manual specified in Section 01 78 00 - Closeout Submittals.

1.05 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements and with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements:
 - .1 Deliver materials to site in original factory packaging, labelled with manufacturer's name, address.
- .3 Packaging Waste Management: remove for reuse and return by manufacturer of pallets, crates, padding and packaging materials.

2 PRODUCTS

2.01 BUTTERFLY VALVES - RESILIENT SEAT - 200 PSIG

- .1 Except to specialty valves, to be of single manufacturer.
- .2 To be suitable for dead-end service.
- .3 CRN registration number required for products.
- .4 Sizes:
 - .1 Wafer, Lug type: NPS 2 to 30.
- .5 Pressure rating for tight shut-off at temperatures up to maximum for seat material.
 - .1 NPS 2 - 12: 200 psig.
 - .2 NPS 14 - 48: 200 psig.
- .6 Minimum seat temperature ratings to 135 degrees C.
- .7 Application: on-off operation.
- .8 Full lug body (threaded).
- .9 Operators:
 - .1 NPS 2 - 6: handles capable of locking in any of ten (10) positions - 0 degrees to 90 degrees. Handle and release trigger - ductile iron. Return spring and hinge pin: carbon steel. Latch plate and mounting hardware: cadmium plated carbon steel. Standard coating: black laquer.
 - .2 NPS 8 - 30: manual enclosed gear operator electric pneumatic actuators as specified elsewhere in this section.
- .10 Designed to comply with MSS SP-67 and API 609.
- .11 Compatible with ANSI Class 125/Class 150 flanges.
- .12 Construction:
 - .1 Body ductile iron.
 - .2 Disc: aluminum bronze.
 - .3 Seat: EPDM.

- .4 Shaft: 416 stainless steel.
- .5 Taper pin: 316 stainless steel.
- .6 Key: stainless steel.
- .7 O-Ring: EPDM.
- .8 Bushings: luberized bronze.

2.02 MOUNTING FLANGES

- .1 Class 125 cast iron to ANSI B16.1 or Class 150 steel to B16.5 pipe flanges.

3 EXECUTION

3.01 PREPARATION

- .1 Valve and mating flange preparation.
 - .1 Inspect adjacent pipeline, remove rust, scale, welding slag, other foreign material.
 - .2 Ensure that valve seats and pipe flange faces are free of dirt or surface irregularities which may disrupt flange seating and cause external leakage.
 - .3 Install butterfly valves with disc in almost closed position.
 - .4 Inspect valve disc seating surfaces and waterway and eliminate dirt or foreign material.

3.02 INSTALLATION OF VALVES

- .1 Install in accordance with manufacturer's instructions.
- .2 Do not use gaskets between pipe flanges and valves unless instructed otherwise by valve manufacturer.
- .3 Verify suitability of valve for application by inspection of identification tag.
- .4 Mount actuator on to valve prior to installation.
- .5 Handle valve with care so as to prevent damage to disc and seat faces.
- .6 Valves in horizontal pipe lines should be installed with stem in horizontal position to minimize liner and seal wear.
- .7 Ensure that valves are centered between bolts before bolts are tightened and then opened and closed to ensure unobstructed disc movement. If interference occurs due, for example to pipe wall thickness, taper bore adjacent piping to remove interference.

3.03 ACTUATOR INSTALLATION

- .1 Air hoses or electrical connections to be made by actuator manufacturer.
- .2 Cycle valve operation from fully closed to fully open then back to fully closed.
- .3 At same time, check travel stop settings for proper disc alignment.

3.04 CLEANING

- .1 Clean in accordance with Section 01 74 11 - Cleaning.
- .2 Clean installed products in accordance to manufacturer's recommendation.

END OF SECTION

1 GENERAL

1.01 RELATED REQUIREMENTS

- .1 Are applicable to this Section the general conditions of the contract, including the general clauses, the special clauses and the specifications Sections of the Division 01.

1.02 REFERENCES

- .1 American Society of Mechanical Engineers (ASME)
 - .1 ASME B31.1-07, Power Piping.
- .2 ASTM International
 - .1 ASTM A 125-1996(2007), Standard Specification for Steel Springs, Helical, Heat-Treated.
 - .2 ASTM A 307-07b, Standard Specification for Carbon Steel Bolts and Studs, 60,000 PSI Tensile Strength.
 - .3 ASTM A 563-07a, Standard Specification for Carbon and Alloy Steel Nuts.
- .3 Factory Mutual (FM)
- .4 Manufacturer's Standardization Society of the Valves and Fittings Industry (MSS)
 - .1 MSS SP 58-2002, Pipe Hangers and Supports - Materials, Design and Manufacture.
 - .2 MSS SP 69-2003, Pipe Hangers and Supports - Selection and Application.
 - .3 MSS SP 89-2003, Pipe Hangers and Supports - Fabrication and Installation Practices.
- .5 Underwriter's Laboratories of Canada (ULC)

1.03 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Provide manufacturer's printed product literature and data sheets for hangers and supports and include product characteristics, performance criteria, physical size, finish and limitations.
- .3 Certificates:
 - .1 Submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
- .4 Manufacturers' Instructions:
 - .1 Provide manufacturer's installation instructions.
 - .1 Departmental Representative will make available 1 copy of systems supplier's installation instructions.

1.04 CLOSEOUT SUBMITTALS

- .1 Provide maintenance data for incorporation into manual specified in Section 01 78 00 - Closeout

Submittals.

1.05 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements and with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements:
 - .1 Deliver materials to site in original factory packaging, labelled with manufacturer's name, address.
- .3 Packaging Waste Management: remove for reuse and return by manufacturer of pallets, crates, padding, and packaging materials.

2 PRODUCTS

2.01 SYSTEM DESCRIPTION

- .1 Design Requirements:
 - .1 Construct pipe hanger and support to manufacturer's recommendations utilizing manufacturer's regular production components, parts and assemblies.
 - .2 Base maximum load ratings on allowable stresses prescribed by ASME B31.1 or MSS SP 58.
 - .3 Ensure that supports, guides, anchors do not transmit excessive quantities of heat to building structure.
 - .4 Design hangers and supports to support systems under conditions of operation, allow free expansion and contraction, prevent excessive stresses from being introduced into pipework or connected equipment.
 - .5 Provide for vertical adjustments after erection and during commissioning. Amount of adjustment in accordance with MSS SP 58.
- .2 Performance Requirements:
 - .1 Design supports, platforms, catwalks, hangers to withstand seismic events as specified Section 23 05 48 – Vibration and Seismic Controls for HVAC Piping and Equipment.

2.02 GENERAL

- .1 Fabricate hangers, supports and sway braces in accordance with MSS SP 58. ANSI B31.1 and
- .2 Use components for intended design purpose only. Do not use for rigging or erection purposes.

2.03 PIPE HANGERS

- .1 Finishes:
 - .1 Pipe hangers and supports: galvanized after manufacture.
 - .2 Use electro-plating galvanizing process hot dipped galvanizing process.
 - .3 Ensure steel hangers in contact with copper piping are copper plated.
- .2 Upper attachment to concrete:
 - .1 Ceiling: carbon steel welded eye rod, clevis plate, clevis pin and cotters with weldless

- forged steel eye nut. Ensure eye 6 mm minimum greater than rod diameter.
- .2 Concrete inserts: wedge shaped body with knockout protector plate UL listed FM approved to MSS SP 69.
- .3 Hanger rods: threaded rod material to MSS SP 58:
 - .1 Ensure that hanger rods are subject to tensile loading only.
 - .2 Provide linkages where lateral or axial movement of pipework is anticipated.
 - .3 Do not use 22 mm or 28 mm rod.
- .4 Pipe attachments: material to MSS SP 58:
 - .1 Attachments for steel piping: carbon steel galvanized.
 - .2 Attachments for copper piping: copper plated black steel.
 - .3 Use insulation shields for hot pipework.
 - .4 Oversize pipe hangers and supports.
- .5 Adjustable clevis: material to MSS SP 69 UL listed FM approved, clevis bolt with nipple spacer and vertical adjustment nuts above and below clevis.
 - .1 Ensure "U" has hole in bottom for rivetting to insulation shields.
- .6 Yoke style pipe roll: carbon steel yoke, rod and nuts with cast iron roll, to MSS SP 69.
- .7 U-bolts: carbon steel to MSS SP 69 with 2 nuts at each end to ASTM A 563.
 - .1 Finishes for steel pipework: galvanized.
 - .2 Finishes for copper, glass, brass or aluminum pipework: galvanized, with formed portion plastic coated.
- .8 Pipe rollers: cast iron roll and roll stand with carbon steel rod to MSS SP 69.

2.04 INSULATION PROTECTION SHIELDS

- .1 Insulated cold piping:
 - .1 64 kg/m³ density insulation plus insulation protection shield to: MSS SP 69, galvanized sheet carbon steel. Length designed for maximum 3 m span.
- .2 Insulated hot piping:
 - .1 Curved plate 300 mm long, with edges turned up, welded-in centre plate for pipe sizes NPS 12 and over, carbon steel to comply with MSS SP 69.

2.05 EQUIPMENT ANCHOR BOLTS AND TEMPLATES

- .1 Provide templates to ensure accurate location of anchor bolts.

3 EXECUTION

3.01 MANUFACTURER'S INSTRUCTIONS

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheet.

3.02 INSTALLATION

- .1 Install in accordance with:
 - .1 Manufacturer's instructions and recommendations.
- .2 Clamps on riser piping:
 - .1 Support independent of connected horizontal pipework using riser clamps and riser clamp lugs welded to riser.
 - .2 Bolt-tightening torques to industry standards.
 - .3 Steel pipes: install below coupling or shear lugs welded to pipe.
 - .4 Cast iron pipes: install below joint.
- .3 Clevis plates:
 - .1 Attach to concrete with 4 minimum concrete inserts, one at each corner.
- .4 Provide supplementary structural steelwork where structural bearings do not exist or where concrete inserts are not in correct locations.

3.03 HANGER SPACING

- .1 Plumbing piping: to Provincial Code.
- .2 Copper piping: up to NPS 1/2: every 1.5 m.
- .3 Flexible joint roll groove pipe: in accordance with table below for steel, but not less than one hanger at joints. Table listings for straight runs without concentrated loads and where full linear movement is not required.

.4

Within 300 mm of each elbow.

Maximum Pipe Size : NPS	Maximum Spacing Steel	Maximum Spacing Copper
up to 1-1/4	2.4 m	1.8 m
1-1/2	3.0 m	2.4 m
2	3.0 m	2.4 m
2-1/2	3.7 m	3.0 m
3	3.7 m	3.0 m
3-1/2	3.7 m	3.3 m
4	3.7 m	3.6 m
5	4.3 m	
6	4.3 m	
8	4.3 m	
10	4.9 m	
12	4.9 m	

- .5 Pipework greater than NPS 12: to MSS SP 69.

3.04 HANGER INSTALLATION

- .1 Install hanger so that rod is vertical under operating conditions.
- .2 Adjust hangers to equalize load.

- .3 Support from structural members. Where structural bearing does not exist or inserts are not in suitable locations, provide supplementary structural steel members.

3.05 HORIZONTAL MOVEMENT

- .1 Angularity of rod hanger resulting from horizontal movement of pipework from cold to hot position not to exceed 4 degrees from vertical.
- .2 Where horizontal pipe movement is less than 13 mm, offset pipe hanger and support so that rod hanger is vertical in the hot position.

3.06 FINAL ADJUSTMENT

- .1 Adjust hangers and supports:
 - .1 Ensure that rod is vertical under operating conditions.
 - .2 Equalize loads.
- .2 Adjustable clevis:
 - .1 Tighten hanger load nut securely to ensure proper hanger performance.
 - .2 Tighten upper nut after adjustment.
- .3 C-clamps:
 - .1 Follow manufacturer's recommended written instructions and torque values when tightening C-clamps to bottom flange of beam.
- .4 Beam clamps:
 - .1 Hammer jaw firmly against underside of beam.

3.07 FIELD QUALITY CONTROL

- .1 Site Tests: conduct following tests [in accordance with Section [01 45 00 - Quality Control] and submit report as described in PART 1 - ACTION AND INFORMATIONAL SUBMITTALS.
- .2 Manufacturer's Field Services:
 - .1 Obtain written report from manufacturer verifying compliance of Work, in handling, installing, applying, protecting and cleaning of product and submit Manufacturer's Field Reports as described in PART 1 - ACTION AND INFORMATIONAL SUBMITTALS.
 - .2 Provide manufacturer's field services consisting of product use recommendations and periodic site visits for inspection of product installation in accordance with manufacturer's instructions.
 - .3 Schedule site visits, to review Work, as directed in PART 1 - QUALITY ASSURANCE.

3.08 CLEANING

- .1 Clean in accordance with Section 01 74 11 - Cleaning.
 - .1 Remove surplus materials, excess materials, rubbish, tools and equipment.

END OF SECTION

1 GENERAL

1.01 RELATED REQUIREMENTS

- .1 Are applicable to this Section the general conditions of the contract, including the general clauses, the special clauses and the specifications Sections of the Division 01.

1.02 REFERENCES

- .1 Canadian Gas Association (CGA)
 - .1 CSA/CGA B149.1-05, Natural Gas and Propane Installation Code.
- .2 Canadian General Standards Board (CGSB)
 - .1 CAN/CGSB-1.60-97, Interior Alkyd Gloss Enamel.
 - .2 CAN/CGSB-24.3-92, Identification of Piping Systems.

1.03 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit product data to include paint colour chips, other products specified in this section.
- .2 Samples:
 - .1 Submit samples in accordance with Section 01 33 00 - Submittal Procedures.
 - .2 Samples to include nameplates, labels, tags, lists of proposed legends.

1.04 QUALITY ASSURANCE

- .1 Quality assurance submittals: submit following in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Health and Safety:
 - .1 Do construction occupational health and safety in accordance with Section 01 35 29.06 - Health and Safety Requirements.

1.05 DELIVERY, STORAGE, AND HANDLING

- .1 Packing, shipping, handling and unloading:
 - .1 Deliver, store and handle in accordance with Section 01 61 00 - Common Product Requirements.
 - .2 Deliver, store and handle materials in accordance with manufacturer's written instructions.
- .2 Waste Management and Disposal:
 - .1 Dispose of unused paint and coating material at official hazardous material collections site approved by Departmental Representative.
 - .2 Do not dispose of unused paint and coating material into sewer system, into streams, lakes, onto ground or in locations where it will pose health or environmental hazard.

2 PRODUCTS

2.01 MANUFACTURER'S EQUIPMENT NAMEPLATES

- .1 Metal or plastic laminate nameplate mechanically fastened to each piece of equipment by manufacturer.
- .2 Lettering and numbers raised or recessed.
- .3 Information to include, as appropriate:
 - .1 Equipment: manufacturer's name, model, size, serial number, capacity.
 - .2 Motor: voltage, Hz, phase, power factor, duty, frame size.

2.02 SYSTEM NAMEPLATES

- .1 Colours:
 - .1 Elsewhere: black letters, white background (except where required otherwise by applicable codes).
- .2 Construction:
 - .1 3 mm thick laminated plastic, matte finish, with square corners, letters accurately aligned and machine engraved into core.
- .3 Sizes:
 - .1 Conform to following table:

Size #	mm	Sizes (mm)	No. of Lines	Height of Letters (mm)
1		10 x 50	1	3
2		13 x 75	1	5
3		13 x 75	2	3
4		20 x 100	1	8
5		20 x 100	2	5
6		20 x 200	1	8
7		25 x 125	1	12
8		25 x 125	2	8
9		35 x 200	1	20
 - .2 Use maximum of 25 letters/numbers per line.
- .4 Identification for PWGSC Preventive Maintenance Support System (PMSS):
 - .1 Use arrangement of Main identifier, Source identifier, Destination identifier.
 - .2 Equipment in Mechanical Room:
 - .1 Main identifier: size #9.
 - .2 Source and Destination identifiers: size #6.
 - .3 Terminal cabinets, control panels: size #5.
 - .3 Equipment elsewhere: sizes as appropriate.

2.03 EXISTING IDENTIFICATION SYSTEMS

- .1 Apply existing identification system to new work.

- .2 Where existing identification system does not cover for new work, use identification system specified this section.
- .3 Before starting work, obtain written approval of identification system from Departmental Representative.

2.04 IDENTIFICATION OF PIPING SYSTEMS

- .1 Identify contents by background colour marking, pictogram (as necessary), legend; direction of flow by arrows. To CAN/CGSB 24.3 except where specified otherwise.
- .2 Pictograms:
 - .1 Where required: Workplace Hazardous Materials Information System (WHMIS) regulations.
- .3 Legend:
 - .1 Block capitals to sizes and colours listed in CAN/CGSB 24.3.
- .4 Arrows showing direction of flow:
 - .1 Outside diameter of pipe or insulation less than 75 mm: 100 mm long x 50 mm high.
 - .2 Outside diameter of pipe or insulation 75 mm and greater: 150 mm long x 50 mm high.
 - .3 Use double-headed arrows where flow is reversible.
- .5 Extent of background colour marking:
 - .1 To full circumference of pipe or insulation.
 - .2 Length to accommodate pictogram, full length of legend and arrows.
- .6 Materials for background colour marking, legend, arrows:
 - .1 Pipes and tubing 20 mm and smaller: waterproof and heat-resistant pressure sensitive plastic marker tags.
 - .2 Other pipes: pressure sensitive plastic-coated cloth, vinyl with protective overcoating, waterproof contact adhesive undercoating, suitable for ambient of 100% RH and continuous operating temperature of 150 degrees C and intermittent temperature of 200 degrees C.
- .7 Colours and Legends:
 - .1 Where not listed, obtain direction from Departmental Representative.
 - .2 Colours for legends, arrows: to following table:

<u>Background colour:</u>	<u>Legend, arrows:</u>
Yellow	BLACK
Green	WHITE
Red	WHITE
 - .3 Background colour marking and legends for piping systems:

Contents	Background colour marking	Legend
Chilled water supply	Green	CH. WTR. SUPPLY
Chilled water return	Green	CH. WTR. RETURN
Steam 35 kPa	Yellow	35 kPa STEAM

2.05 VALVES, CONTROLLERS

- .1 Brass tags with 12 mm stamped identification data filled with black paint.
- .2 Include flow diagrams for each system, of approved size, showing charts and schedules with identification of each tagged item, valve type, service, function, normal position, location of tagged item.

2.06 CONTROLS COMPONENTS IDENTIFICATION

- .1 Identify all systems, equipment, components, controls, sensors with system nameplates specified in this section.
- .2 Inscriptions to include function and (where appropriate) fail-safe position.

2.07 LANGUAGE

- .1 Identification in English and French.
- .2 Use one nameplate and label for both languages.

3 EXECUTION

3.01 MANUFACTURER'S INSTRUCTIONS

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheet.

3.02 TIMING

- .1 Provide identification only after painting has been completed.

3.03 INSTALLATION

- .1 Perform work in accordance with CAN/CGSB-24.3 except as specified otherwise.
- .2 Provide ULC and/ or CSA registration plates as required by respective agency.
- .3 Identify systems, equipment to conform to PWGSC PMSS.

3.04 NAMEPLATES

- .1 Locations:
 - .1 In conspicuous location to facilitate easy reading and identification from operating floor.
- .2 Standoffs:
 - .1 Provide for nameplates on hot and/or insulated surfaces.
- .3 Protection:
 - .1 Do not paint, insulate or cover.

3.05 LOCATION OF IDENTIFICATION ON PIPING AND DUCTWORK SYSTEMS

- .1 On long straight runs in open areas in boiler rooms, equipment rooms, galleries, tunnels: at not more than 17 m intervals and more frequently if required to ensure that at least one is visible from any one viewpoint in operating areas and walking aisles.
- .2 Adjacent to each change in direction.
- .3 At least once in each small room through which piping or ductwork passes.
- .4 On both sides of visual obstruction or where run is difficult to follow.
- .5 On both sides of separations such as walls, floors, partitions.
- .6 Where system is installed in pipe chases, ceiling spaces, galleries, confined spaces, at entry and exit points, and at access openings.
- .7 At beginning and end points of each run and at each piece of equipment in run.
- .8 At point immediately upstream of major manually operated or automatically controlled valves, and dampers. Where this is not possible, place identification as close as possible, preferably on upstream side.
- .9 Identification easily and accurately readable from usual operating areas and from access points.
 - .1 Position of identification approximately at right angles to most convenient line of sight, considering operating positions, lighting conditions, risk of physical damage or injury and reduced visibility over time due to dust and dirt.

3.06 VALVES, CONTROLLERS

- .1 Valves and operating controllers, except at plumbing fixtures, radiation, or where in plain sight of equipment they serve: Secure tags with non-ferrous chains or closed "S" hooks.

3.07 CLEANING

- .1 Proceed in accordance with Section 01 74 11 - Cleaning.
- .2 Upon completion and verification of performance of installation, remove surplus materials, excess materials, rubbish, tools and equipment.

END OF SECTION

1 GENERAL

1.01 RELATED REQUIREMENTS

- .1 Are applicable to this Section the general conditions of the contract, including the general clauses, the special clauses and the specifications Sections of the Division 01.

1.02 SUMMARY

- .1 TAB is used throughout this Section to describe the process, methods and requirements of testing, adjusting and balancing for HVAC.
- .2 TAB means to test, adjust and balance to perform in accordance with requirements of Contract Documents and to do other work as specified in this section.

1.03 QUALIFICATIONS OF TAB PERSONNEL

- .1 Submit names of personnel to perform TAB to Departmental Representative within 15 days of award of contract.
- .2 Provide documentation confirming qualifications, successful experience.
- .3 TAB: performed in accordance with the requirements of standard under which TAB Firm's qualifications are approved:
 - .1 Associated Air Balance Council, (AABC) National Standards for Total System Balance, MN-1-2002.
 - .2 National Environmental Balancing Bureau (NEBB) TABES, Procedural Standards for Testing, Adjusting, Balancing of Environmental Systems-1998.
 - .3 Sheet Metal and Air Conditioning Contractors' National Association (SMACNA), HVAC TAB HVAC Systems - Testing, Adjusting and Balancing-2002.
- .4 Recommendations and suggested practices contained in the TAB Standard: mandatory.
- .5 Use TAB Standard provisions, including checklists, and report forms to satisfy Contract requirements.
- .6 Use TAB Standard for TAB, including qualifications for TAB Firm and Specialist and calibration of TAB instruments.
- .7 Where instrument manufacturer calibration recommendations are more stringent than those listed in TAB Standard, use manufacturer's recommendations.
- .8 TAB Standard quality assurance provisions such as performance guarantees form part of this contract.
 - .1 For systems or system components not covered in TAB Standard, use TAB procedures developed by TAB Specialist.
 - .2 Where new procedures, and requirements, are applicable to Contract requirements have been published or adopted by body responsible for TAB Standard used (AABC, NEBB, or TABB), requirements and recommendations contained in these procedures and

requirements are mandatory.

1.04 PURPOSE OF TAB

- .1 Test to verify proper and safe operation, determine actual point of performance, evaluate qualitative and quantitative performance of equipment, systems and controls at design, average and low loads using actual or simulated loads
- .2 Adjust and regulate equipment and systems to meet specified performance requirements and to achieve specified interaction with other related systems under normal and emergency loads and operating conditions.
- .3 Balance systems and equipment to regulate flow rates to match load requirements over full operating ranges.

1.05 EXCEPTIONS

- .1 TAB of systems and equipment regulated by codes, standards to satisfaction of authority having jurisdiction.

1.06 CO-ORDINATION

- .1 Schedule time required for TAB (including repairs, re-testing) into project construction and completion schedule to ensure completion before acceptance of project.
- .2 Do TAB of each system independently and subsequently, where interlocked with other systems, in unison with those systems.

1.07 PRE-TAB REVIEW

- .1 Review contract documents before project construction is started and confirm in writing to Departmental Representative adequacy of provisions for TAB and other aspects of design and installation pertinent to success of TAB.
- .2 Review specified standards and report to Departmental Representative in writing proposed procedures which vary from standard.
- .3 During construction, co-ordinate location and installation of TAB devices, equipment, accessories, measurement ports and fittings.

1.08 START-UP

- .1 Follow start-up procedures as recommended by equipment manufacturer unless specified otherwise.
- .2 Follow special start-up procedures specified elsewhere in Division 23.

1.09 OPERATION OF SYSTEMS DURING TAB

- .1 Operate systems for length of time required for TAB and as required by Departmental Representative for verification of TAB reports.

1.10 START OF TAB

- .1 Notify Departmental Representative 7 days prior to start of TAB.
- .2 Start TAB when building is essentially completed, including:
- .3 Installation of ceilings, doors, windows, other construction affecting TAB.
- .4 Application of weatherstripping, sealing, and caulking.
- .5 Pressure, leakage, other tests specified elsewhere Division 23.
- .6 Provisions for TAB installed and operational.
- .7 Start-up, verification for proper, normal and safe operation of mechanical and associated electrical and control systems affecting TAB including but not limited to:
 - .1 Proper thermal overload protection in place for electrical equipment.
 - .2 Air systems:
 - .1 Filters in place, clean.
 - .2 Duct systems clean.
 - .3 Ducts, air shafts, ceiling plenums are airtight to within specified tolerances.
 - .4 Correct fan rotation.
 - .5 Fire, smoke, volume control dampers installed and open.
 - .6 Coil fins combed, clean.
 - .7 Access doors, installed, closed.
 - .8 Outlets installed, volume control dampers open.
 - .3 Liquid systems:
 - .1 Flushed, filled, vented.
 - .2 Correct pump rotation.
 - .3 Strainers in place, baskets clean.
 - .4 Isolating and balancing valves installed, open.
 - .5 Calibrated balancing valves installed, at factory settings.
 - .6 Chemical treatment systems complete, operational.

1.11 APPLICATION TOLERANCES

- .1 Do TAB to following tolerances of design values:
 - .1 HVAC systems: plus 5 %, minus 5 %.
 - .2 Hydronic systems: plus or minus 10 %.

1.12 ACCURACY TOLERANCES

- .1 Measured values accurate to within plus or minus 2 % of actual values.

1.13 INSTRUMENTS

- .1 Prior to TAB, submit to Departmental Representative list of instruments used together with serial numbers.
- .2 Calibrate in accordance with requirements of most stringent of referenced standard for either applicable system or HVAC system.

- .3 Calibrate within 3 months of TAB. Provide certificate of calibration to Departmental Representative.

1.14 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit, prior to commencement of TAB:
- .2 Proposed methodology and procedures for performing TAB if different from referenced standard.

1.15 PRELIMINARY TAB REPORT

- .1 Submit for checking and approval of Departmental Representative, prior to submission of formal TAB report, sample of rough TAB sheets. Include:
 - .1 Details of instruments used.
 - .2 Details of TAB procedures employed.
 - .3 Calculations procedures.
 - .4 Summaries.

1.16 TAB REPORT

- .1 Format in accordance with referenced standard.
- .2 TAB report to show results in SI units and to include:
 - .1 Project record drawings.
 - .2 System schematics.
- .3 Submit 6 copies of TAB Report to Departmental Representative for verification and approval, in both official languages in D-ring binders, complete with index tabs.

1.17 VERIFICATION

- .1 Reported results subject to verification by Departmental Representative.
- .2 Provide personnel and instrumentation to verify up to 30 % of reported results.
- .3 Number and location of verified results as directed by Departmental Representative.
- .4 Pay costs to repeat TAB as required to satisfaction of Departmental Representative.

1.18 SETTINGS

- .1 After TAB is completed to satisfaction of Departmental Representative, replace drive guards, close access doors, lock devices in set positions, ensure sensors are at required settings.
- .2 Permanently mark settings to allow restoration at any time during life of facility. Do not eradicate or cover markings.

1.19 COMPLETION OF TAB

- .1 TAB considered complete when final TAB Report received and approved by Departmental Representative.

1.20 AIR SYSTEMS

- .1 Standard: TAB to most stringent of this section or TAB standards of ASHRAE.
- .2 Do TAB of systems, equipment, components, controls specified Division 23.
- .3 Qualifications: personnel performing TAB qualified to standards of AABC or NEBB.
- .4 Quality assurance: perform TAB under direction of supervisor qualified by to standards of AABC or NEBB.
- .5 Measurements: to include as appropriate for systems, equipment, components, controls: air velocity, static pressure, flow rate, pressure drop (or loss), temperatures (dry bulb, wet bulb, dewpoint), duct cross-sectional area, RPM, electrical power, voltage, noise, vibration.
- .6 Locations of equipment measurements: to include as appropriate:
 - .1 Inlet and outlet of dampers, filter, coil, humidifier, fan, other equipment causing changes in conditions.
 - .2 At controllers, controlled device.
- .7 Locations of systems measurements to include as appropriate: main ducts, main branch, sub-branch, run-out (or grille, register or diffuser).

1.21 OTHER TAB REQUIREMENTS

- .1 General requirements applicable to work specified this paragraph:
 - .1 Qualifications of TAB personnel: as for air systems specified this section.
 - .2 Quality assurance: as for air systems specified this section.

1.22 POST-OCCUPANCY TAB

- .1 Measure DBT, WBT (or %RH), air velocity, NC levels in the alimentation's ductwork in the exit of the system and also in the mechanical room on the two level.

2 PRODUCTS

2.01 NOT USED

- .1 Not used.

3 EXECUTION

3.01 NOT USED

- .1 Not used.

END OF SECTION

1 GENERAL

1.01 RELATED REQUIREMENTS

- .1 Are applicable to this Section the general conditions of the contract, including the general clauses, the special clauses and the specifications Sections of the Division 01.

1.02 REFERENCES

- .1 American Society of Heating, Refrigeration and Air Conditioning Engineers (ASHRAE)
 - .1 ASHRAE Standard 90.1-01, Energy Standard for Buildings Except Low-Rise Residential Buildings (IESNA co-sponsored; ANSI approved; Continuous Maintenance Standard).
- .2 American Society for Testing and Materials International (ASTM)
 - .1 ASTM B 209M-04, Standard Specification for Aluminum and Aluminum Alloy Sheet and Plate [Metric].
 - .2 ASTM C 335-04, Standard Test Method for Steady State Heat Transfer Properties of Horizontal Pipe Insulation.
 - .3 ASTM C 411-04, Standard Test Method for Hot-Surface Performance of High-Temperature Thermal Insulation.
 - .4 ASTM C 449/C 449M-00, Standard Specification for Mineral Fiber-Hydraulic-Setting Thermal Insulating and Finishing Cement.
 - .5 ASTM C 533-2004, Calcium Silicate Block and Pipe Thermal Insulation.
 - .6 ASTM C 547-2003, Mineral Fiber Pipe Insulation.
 - .7 ASTM C 795-03, Standard Specification for Thermal Insulation for Use in Contact with Austenitic Stainless Steel.
 - .8 ASTM C 921-03a, Standard Practice for Determining the Properties of Jacketing Materials for Thermal Insulation.
- .3 Canadian General Standards Board (CGSB)
 - .1 CGSB 51-GP-52Ma-89, Vapour Barrier, Jacket and Facing Material for Pipe, Duct and Equipment Thermal Insulation.
 - .2 CAN/CGSB-51.53-95, Poly (Vinyl Chloride) Jacketing Sheet, for Insulated Pipes, Vessels and Round Ducts
- .4 Department of Justice Canada (Jus)
 - .1 Canadian Environmental Assessment Act (CEAA), 1995, c. 37.
 - .2 Canadian Environmental Protection Act (CEPA), 1999, c. 33.
 - .3 Transportation of Dangerous Goods Act (TDGA), 1992, c. 34.
- .5 Health Canada/Workplace Hazardous Materials Information System (WHMIS)
 - .1 Material Safety Data Sheets (MSDS).
- .6 Manufacturer's Trade Associations
 - .1 Thermal Insulation Association of Canada (TIAC): National Insulation Standards (Revised 2004).
- .7 Underwriters' Laboratories of Canada (ULC)
 - .1 CAN/ULC-S102-03, Surface Burning Characteristics of Building Materials and

- Assemblies.
- .2 CAN/ULC-S701-01, Thermal Insulation, Polystyrene, Boards and Pipe Covering.
- .3 CAN/ULC-S702-1997, Thermal Insulation, Mineral Fibre, for Buildings
- .4 CAN/ULC-S702.2-03, Thermal Insulation, Mineral Fibre, for Buildings, Part 2: Application Guidelines.

1.03 DEFINITIONS

- .1 For purposes of this section:
 - .1 "CONCEALED" - insulated mechanical services in suspended ceilings and non-accessible chases and furred-in spaces.
 - .2 "EXPOSED" - will mean "not concealed" as specified.
- .2 TIAC ss:
 - .1 CRF: Code Rectangular Finish.
 - .2 CPF: Code Piping Finish.

1.04 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submittals: in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's printed product literature, specifications and datasheet in accordance with Section 01 33 00 - Submittal Procedures. Include product characteristics, performance criteria, and limitations.
 - .1 Submit two copies of Workplace Hazardous Materials Information System (WHMIS) Material Safety Data Sheets (MSDS) in accordance with Section 01 33 00 - Submittal Procedures.
- .3 Samples:
 - .1 Submit samples in accordance with Section 01 33 00 - Submittal Procedures.
 - .2 Submit for approval: complete assembly of each type of insulation system, insulation, coating, and adhesive proposed. Mount sample on 12 mm plywood board. Affix label beneath sample indicating service.
- .4 Quality assurance submittals: submit following in accordance with Section 01 33 00 - Submittal Procedures.
 - .1 Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
 - .2 Instructions: submit manufacturer's installation instructions.
 - .1 Departmental Representative will make available 1 copy of systems supplier's installation instructions.

1.05 QUALITY ASSURANCE

- .1 Qualifications:
- .2 Installer: specialist in performing work of this Section, and have at least 3 years successful experience in this size and type of project, qualified to standards member of TIAC.
- .3 Health and Safety:

- .1 Do construction occupational health and safety in accordance with Section 01 35 29.06 - Health and Safety Requirements.

1.06 DELIVERY, STORAGE AND HANDLING

- .1 Packing, shipping, handling and unloading:
 - .1 Deliver, store and handle in accordance with manufacturer's written instructions and Section 01 61 00 - Common Product Requirements.
 - .2 Deliver, store and handle materials in accordance with manufacturer's written instructions.
 - .3 Deliver materials to site in original factory packaging, labelled with manufacturer's name, address.
- .2 Storage and Protection:
 - .1 Protect from weather, construction traffic.
 - .2 Protect against damage.
 - .3 Store at temperatures and conditions required by manufacturer.
- .3 Waste Management and Disposal:
 - .1 Place excess or unused insulation and insulation accessory materials in designated containers.
 - .2 Divert unused metal materials from landfill to metal recycling facility approved by Departmental Representative.
 - .3 Dispose of unused adhesive material at official hazardous material collections site approved by Departmental Representative.

2 PRODUCTS

2.01 FIRE AND SMOKE RATING

- .1 In accordance with CAN/ULC-S102.
 - .1 Maximum flame spread rating: 25.
 - .2 Maximum smoke developed rating: 50.

2.02 INSULATION

- .1 Mineral fibre specified includes glass fibre, rock wool, slag wool.
- .2 Thermal conductivity ("k" factor) not to exceed specified values at 24 degrees C mean temperature when tested in accordance with ASTM C 335.
- .3 TIAC Code A-1: rigid moulded mineral fibre without factory applied vapour retarder jacket.
 - .1 Mineral fibre: to CAN/ULC-S702, ASTM C 547.
 - .2 Maximum "k" factor: to CAN/ULC-S702.
- .4 TIAC Code A-3: rigid moulded mineral fibre with factory applied vapour retarder jacket.
 - .1 Mineral fibre: to CAN/ULC-S702, ASTM C 547.
 - .2 Jacket: to CGSB 51-GP-52Ma.
 - .3 Maximum "k" factor: to CAN/ULC-S702, ASTM C 547.

2.03 INSULATION SECUREMENT

- .1 Tape: self-adhesive, aluminum, reinforced, 50 mm wide minimum.
- .2 Contact adhesive: quick setting.
- .3 Canvas adhesive: washable.
- .4 Tie wire: 1.5 mm diameter stainless steel.
- .5 Bands: stainless steel, 19mm wide, 0.5 mm thick.

2.04 VAPOUR RETARDER LAP ADHESIVE

- .1 Water based, fire retardant type, compatible with insulation.

2.05 INDOOR VAPOUR RETARDER FINISH

- .1 Vinyl emulsion type acrylic, compatible with insulation.

2.06 JACKETS

- .1 Canvas:
 - .1 220 gm/m² cotton, plain weave, treated with dilute fire retardant lagging adhesive to ASTM C 921.
 - .2 Lagging adhesive: compatible with insulation.
 - .3 Paint as the same color as the existing insulation.

3 EXECUTION

3.01 MANUFACTURER'S INSTRUCTIONS

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheet.

3.02 PRE-INSTALLATION REQUIREMENT

- .1 Pressure testing of piping systems and adjacent equipment to be complete, witnessed and certified.
- .2 Surfaces clean, dry, free from foreign material.

3.03 INSTALLATION

- .1 Install in accordance with TIAC National Standards.
- .2 Apply materials in accordance with manufacturers instructions and this specification.
- .3 Use two layers with staggered joints when required nominal wall thickness exceeds 75 mm.
- .4 Maintain uninterrupted continuity and integrity of vapour retarder jacket and finishes.

- .1 Install hangers, supports outside vapour retarder jacket.
- .5 Supports, Hangers:
 - .1 Apply high compressive strength insulation, suitable for service, at oversized saddles and shoes where insulation saddles have not been provided.

3.04 REMOVABLE, PRE-FABRICATED, INSULATION AND ENCLOSURES

- .1 Application: at expansion joints, valves, primary flow measuring elements flanges and unions at equipment.
- .2 Design: to permit movement of expansion joint and to permit periodic removal and replacement without damage to adjacent insulation.
- .3 Insulation:
 - .1 Insulation, fastenings and finishes: same as system.
 - .2 Jacket: high temperature fabric.

3.05 PIPING INSULATION SCHEDULES

- .1 Includes valves, valve bonnets, strainers, flanges and fittings unless otherwise specified.
- .2 TIAC Code: A-1.
 - .1 Securements: SS bands, Tape at 300 mm on centre.
 - .2 Seals: lap seal adhesive, lagging adhesive.
 - .3 Installation: TIAC Code 1501-H.
- .3 TIAC Code: A-3.
 - .1 Securements: SS bands, Tape at 300 mm on centre.
 - .2 Seals: VR lap seal adhesive, VR lagging adhesive.
 - .3 Installation: TIAC Code: 1501-C.
- .4 Thickness of insulation as listed in following table.
 - .1 Run-outs to individual units and equipment not exceeding 4000 mm long.
 - .2 Do not insulate exposed runouts to plumbing fixtures, chrome plated piping, valves, fittings.

Applic a-tion	Temp degree s C	TIAC code	Pipe sizes (NPS) and insulation thickness (mm)				
	Run out	to 1	1 1/4 to 2	2 1/2 to 4	5 to 6	8 & over	
Chilled Water	4 - 13	A-3	25	25	25	25	25
Chilled Water or Glycol	below 4	A-3	25	25	38	38	38

- .8 Finishes:
 - .1 Exposed indoors: canvas jacket.
 - .2 Exposed in mechanical rooms: canvas jacket.
 - .3 Concealed, indoors: canvas on valves, fittings. No further finish.
 - .4 Use vapour retarder jacket on TIAC code A-3 insulation compatible with insulation.
 - .5 Finish attachments: SS bands, at 150 mm on centre. Seals: wing.
 - .6 Installation: to appropriate TIAC code CRF/1 through CPF/5.

3.06 CLEANING

- .1 Proceed in accordance with Section 01 74 11 - Cleaning.
- .2 Upon completion and verification of performance of installation, remove surplus materials, excess materials, rubbish, tools and equipment.

END OF SECTION

1 GENERAL

1.01 RELATED REQUIREMENTS

- .1 Are applicable to this Section the general conditions of the contract, including the general clauses, the special clauses and the specifications Sections of the Division 01.

1.02 REFERENCES

- .1 American Society for Testing and Materials International (ASTM)
 - .1 ASTM E 202-00, Standard Test Methods for Analysis of Ethylene Glycols and Propylene Glycols.
- .2 Health Canada/Workplace Hazardous Materials Information System (WHMIS)
 - .1 Material Safety Data Sheets (MSDS).

1.03 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Product Data:
 - .1 Submit manufacturer's printed product literature, specifications and datasheet in accordance with Section 01 33 00 - Submittal Procedures. Include product characteristics, performance criteria, and limitations.
- .2 Quality assurance submittals: submit following in accordance with Section 01 33 00 - Submittal Procedures.
 - .1 Instructions: submit manufacturer's installation instructions.
 - .1 Departmental Representative will make available 1 copy of systems supplier's installation instructions.

1.04 QUALITY ASSURANCE

- .1 Health and Safety:
 - .1 Do construction occupational health and safety in accordance with Section 01 35 29.06 - Health and Safety Requirements.

1.05 DELIVERY, STORAGE, AND HANDLING

- .1 Packing, shipping, handling and unloading:
 - .1 Deliver, store and handle in accordance with manufacturer's written instructions and Section 01 61 00 - Common Product Requirements.

2 PRODUCTS

2.01 CLEANING SOLUTIONS

- .1 Tri-sodium phosphate: 0.40 kg per 100 L water in system.
- .2 Sodium carbonate: 0.40 kg per 100 L water in system.
- .3 Low-foaming detergent: 0.01 kg per 100 L water in system.

3 EXECUTION

3.01 MANUFACTURER'S INSTRUCTIONS

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheet.
- .2 Cleaning the pipe is limited to the new pipe supplied and installed during the present project.

3.02 CLEANING HYDRONIC SYSTEMS

- .1 Timing: systems operational, hydrostatically tested and with safety devices functional, before cleaning is carried out.
- .2 Cleaning Agency:
 - .1 Retain qualified water treatment specialist to perform system cleaning.
- .3 Cleaning procedures:
 - .1 Provide detailed report outlining proposed cleaning procedures at least 4 weeks prior to proposed starting date. Report to include:
 - .1 Cleaning procedures, flow rates, elapsed time.
 - .2 Chemicals and concentrations used.
 - .3 Inhibitors and concentrations.
 - .4 Specific requirements for completion of work.
 - .5 Special precautions for protecting piping system materials and components.
 - .6 Complete analysis of water used to ensure water will not damage systems or equipment.
- .4 Conditions at time of cleaning of systems:
 - .1 Systems: free from construction debris, dirt and other foreign material.
 - .2 Control valves: operational, fully open to ensure that terminal units can be cleaned properly.
 - .3 Strainers: clean prior to initial fill.
 - .4 Install pressure gauges on strainers to detect plugging.
- .5 Report on Completion of Cleaning:
 - .1 When cleaning is completed, submit report, complete with certificate of compliance with specifications of cleaning component supplier.
- .6 Hydronic Systems:
 - .1 Fill system with water, ensure air is vented from system.
 - .2 Fill expansion tanks 1/3 to 1/2 full, charge system with compressed air to at least 35 kPa (does not apply to diaphragm type expansion tanks).
 - .3 Use water metre to record volume of water in system to +/- 0.5%.
 - .4 Add chemicals under direct supervision of chemical treatment supplier.
 - .5 Closed loop systems: circulate system cleaner at 60 degrees C for at least 36 h. Drain as quickly as possible. Refill with water and inhibitors. Test concentrations and adjust to recommended levels.
 - .6 Flush velocity in system mains and branches to ensure removal of debris. System pumps may be used for circulating cleaning solution provided that velocities are adequate.
 - .7 Add chemical solution to system.

- .8 Establish circulation, raise temperature slowly to maximum design. Circulate for 12 h, ensuring flow in all circuits. Remove heat, continue to circulate until temperature is below 38 degrees C. Drain as quickly as possible. Refill with clean water. Circulate for 6 h at design temperature. Drain and repeat procedures specified above. Flush through low point drains in system. Refill with clean water adding to sodium sulphite (test for residual sulphite).
- .7 Glycol Systems:
 - .1 In addition to procedures specified above perform specified procedures.
 - .2 Test to prove concentration will prevent freezing to minus 40 degrees C. Test inhibitor strength and include in procedural report. Refer to ASTM E 202.
 - .3 It is acceptable to recover and reintegrate glycol in networks if the recovery is adequately safe from residue and impurity. This option does not release the contractor from its responsibility to upgrade the network losses during work.

3.03 START-UP OF HYDRONIC SYSTEMS

- .1 After cleaning is completed and system is filled:
 - .1 Establish circulation and expansion tank level, set pressure controls.
 - .2 Ensure air is removed.
 - .3 Check to be free from air, debris, possibility of cavitation when system is at design temperature.
 - .4 Dismantle system pumps used for cleaning, inspect, replace worn parts, install new gaskets and new set of seals.
 - .5 Check water level in expansion tank with cold water with circulating pumps OFF and again with pumps ON.
 - .6 Repeat with water at design temperature.
 - .7 Check pressurization to ensure proper operation and to prevent water hammer, flashing, cavitation. Eliminate water hammer and other noises.
 - .8 Bring system up to design temperature and pressure slowly.
 - .9 Adjust pipe supports, hangers, springs as necessary.
 - .10 Monitor pipe movement, performance of expansion joints, loops, guides, anchors.
 - .11 Re-tighten bolts using torque wrench, to compensate for heat-caused relaxation. Repeat several times during commissioning.
 - .12 Check operation of drain valves.
 - .13 Adjust valve stem packings as systems settle down.

3.04 CLEANING

- .1 Proceed in accordance with Section 01 74 11 - Cleaning.
- .2 Upon completion and verification of performance of installation, remove surplus materials, excess materials, rubbish, tools and equipment.

END OF SECTION

1 GENERAL

1.01 RELATED REQUIREMENTS

- .1 Are applicable to this Section the general conditions of the contract, including the general clauses, the special clauses and the specifications Sections of the Division 01.

1.02 REFERENCES

- .1 American Society of Mechanical Engineers (ASME).
 - .1 ASME B16.1-98, Cast Iron Pipe Flanges and Flanged Fittings.
 - .2 ASME B16.5-03, Pipe Flanges and Flanged Fittings.
 - .3 ASME B16.9-01, Factory-Made Wrought Butt welding Fittings.
 - .4 ASME B18.2.1-03, Square and Hex Bolts and Screws (Inch Series).
 - .5 ASME B18.2.2-87(R1999), Square and Hex Nuts (Inch Series).
- .2 American Society for Testing and Materials International, (ASTM).
 - .1 ASTM A 53/A 53M-02, Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc Coated Welded and Seamless.
 - .2 ASTM E 202-00, Standard Test Method for Analysis of Ethylene Glycols and Propylene Glycols.
- .3 American Water Works Association (AWWA).
 - .1 AWWA C111-00, Rubber-Gasket Joints for Ductile-Iron Pressure Pipe and Fittings.
- .4 Manufacturer's Standardization of the Valve and Fittings Industry (MSS).
 - .1 MSS-SP-67-025, Butterfly Valves.

1.03 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit shop drawings in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Closeout Submittals.
 - .1 Provide maintenance data for incorporation into manual specified in Section 01 78 00 - Closeout Submittals.

1.04 QUALITY ASSURANCE

- .1 Health and Safety.
 - .1 Do construction occupational health and safety in accordance with Section 01 35 29.06 - Health and Safety Requirements.

1.05 DELIVERY, STORAGE AND HANDLING

- .1 Waste Management and Disposal.
 - .1 Remove from site and dispose of packaging materials at appropriate recycling facilities.
 - .2 Collect and separate for disposal paper, plastic, polystyrene, corrugated cardboard packaging material in appropriate on-site bins for recycling in accordance with Waste Management Plan.

- .3 Fold up metal and plastic banding, flatten and place in designated area for recycling.

2 PRODUCTS

2.01 PIPE

- .1 Steel pipe: to ASTM A53/A53M, Grade B, as follows:
 - .1 To NPS6.
- .2 Glycoled water piping
 - .1 15 mm to 50 mm (1/2 in. to 2 in.)
 - .1 Black steel series 40, smooth wall, spigot ends, « CONTINUOUS WELD ».
 - .2 65 mm and higher (2-1/2 in.)
 - .1 Black steel series 40, smooth wall, bevelled ends « ELECTRIC WELD ».
- .3 Chemical injection pipes : conforming to the standard ASTM A 312/A 312M, grade B, addition to the following requirements.
 - .1 15 mm to 50 mm (1/2 in. à 2 in.)
 - .1 Series 40 stainless steel, smooth wall, spigot ends, « CONTINUOUS WELD ».

2.02 PIPE JOINTS

- .1 NPS2-1/2 and over: welding fittings and flanges to CAN/CSA W48, ANSI-B16.9.
- .2 Pipes with nominal diameter equal or smaller than NPS 2 : connections to be fastened in accordance with ANSI -B16.9 standards.
- .3 Flanges: plain, weld neck to AWWA C111 and ANSI-B-16.9.
- .4 Flange gaskets: to AWWA C111.
- .5 Bolts and nuts: to ASME B18.2.1 and ASME B18.2.2.

2.03 FITTINGS

- .1 Pipe flanges and flanged fittings:
 - .1 Cast iron: to ASME B16.1, Class 125.
 - .2 Steel: to ASME B16.5.
- .2 Butt-welding fittings: steel, to ASME B16.9.

2.04 VALVES

- .1 Connections:
 - .1 NPS2 and smaller: screwed ends.
 - .2 NPS2.1/2 and larger: Flanged ends.
- .2 Butterfly valves: to MSS-SP-67 Application: Isolating cells or section of multiple component equipment (eg. multi-section coils, multi-cell cooling towers):
 - .1 NPS21/2 and over: Lug type Grooved ends: as specified Section 23 05 17 - Pipe Welding.

- .3 Balancing, for TAB:
 - .1 Sizes: Calibrated balancing valves, as specified this section.
 - .2 NPS2 and under:
 - .1 Mechanical Rooms: Globe, with disc as specified Section 23 05 23.01 - Valves - Bronze.
- .4 Drain valves: Gate, Class 125, non-rising stem, solid wedge disc, as specified Section 23 05 23.01 - Valves - Bronze.

3 EXECUTION

3.01 PIPING INSTALLATION

- .1 Install pipework in accordance with Section 23 05 05 - Installation of Pipe Work

3.02 CLEANING, FLUSHING AND START-UP

- .1 In accordance with Section 23 08 02 - Cleaning and Start-Up of Mechanical Piping Systems.

3.03 TESTING

- .1 Test system in accordance with the norms and codes.
- .2 For glycol systems, retest with ethylene glycol to ASTM E 202, inhibited, for use in building system after cleaning. Repair leaking joints, fittings or valves.

END OF SECTION

1 GENERAL

1.01 RELATED REQUIREMENTS

- .1 Are applicable to this Section the general conditions of the contract, including the general clauses, the special clauses and the specifications Sections of the Division 01.

1.02 REFERENCES

- .1 American Society of Mechanical Engineers (ASME)
 - .1 ASME-04(2007), Boiler and Pressure Vessel Code.
- .2 ASTM International Inc.
 - .1 ASTM A 47/A 47M-99(2004), Standard Specification for Ferritic Malleable Iron Castings.
 - .2 ASTM A 278/A 278M-01(2006), Standard Specification for Gray Iron Castings for Pressure-Containing Parts for Temperatures up to 650 degrees F (350 degrees C).
 - .3 ASTM A 516/A 516M-06, Standard Specification for Pressure Vessel Plates, Carbon Steel, for Moderate - and Lower - Temperature Service.
 - .4 ASTM A 536-84(2004), Standard Specification for Ductile Iron Castings.
 - .5 ASTM B 62-02, Standard Specification for Composition Bronze or Ounce Metal Castings.
- .3 Canadian Standards Association (CSA International)
 - .1 CSA B51-03(R2003), Boiler, Pressure Vessel, and Pressure Piping Code.
 - .2 CSA B51-03(R2005), Boiler, Pressure Vessel, and Pressure Piping Code, Supplement #1.

1.03 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Provide manufacturer's printed product literature and datasheets for air vents, separators, valves, and strainers and include product characteristics, performance criteria, physical size, finish and limitations.

1.04 CLOSEOUT SUBMITTALS

- .1 Submit maintenance and operation data in accordance with Section 01 78 00 - Closeout Submittals.

1.05 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle in accordance with Section 01 61 00 - Common Product Requirements.
- .2 Deliver materials to site in original factory packaging, labelled with manufacturer's name, address.

2 PRODUCTS

2.01 AUTOMATIC AIR VENT

- .1 Industrial float vent: cast iron body and NPS 1/2 connection and rated at 860 kPa working pressure.

2.02 PIPING FILTERS

- .1 Filters with NPS 2 1/2 to NPS 12 : body in cast steel, in accordance with ASTM A 278/A 278M, standards class 30, flanged.
- .2 Purge connector : NPS 1.
- .3 Sleeve : Stainless steel, with 1.19 mm perforations.
- .4 Operating pressure : 860 kPa.

3 EXECUTION

3.01 APPLICATION

- .1 Manufacturer's Instructions: comply with manufacturer's written recommendations, including product technical bulletins, handling, storage and installation instructions, and datasheets.

3.02 GENERAL

- .1 Run drain lines and blow off connections to terminate above nearest drain.
- .2 Maintain adequate clearance to permit service and maintenance.
- .3 Should deviations beyond allowable clearances arise, request and follow Departmental Representative's directive.
- .4 Check shop drawings for conformance of tappings for ancillaries and for equipment operating weights.

3.03 AIR VENTS

- .1 Install at high points of systems.
- .2 Install gate valve on automatic air vent inlet. Run discharge to nearest drain.

3.04 FILTERS

- .1 Install filters in horizontal pipelines.
- .2 Foresee the necessary clearance to remove the basket.
- .3 Install a filter upstream in the indicated areas.

3.05 CLEANING

- .1 Clean in accordance with Section 01 74 11 - Cleaning.
- .1 Remove surplus materials, excess materials, rubbish, tools and equipment.

END OF SECTION

1 GENERAL

1.01 REFERENCES

- .1 Canadian Standards Association (CSA International)
 - .1 CSA C22.10.10, Québec Construction Code, Chapter V-Electricity Canadian Electrical Code, Part I (21st edition) with Québec Amendments (2010).
 - .2 CSA C22.2 188-M1983 (R1999), Splicing Wire and Cable Connectors.
 - .3 CAN3-C235-83(R2000), Preferred Voltage Levels for AC Systems, 0 to 50,000 V.
- .2 Electrical and Electronic Manufacturer's Association of Canada (EEMAC)
 - .1 EEMAC 2Y-1-1958, Light Gray Colour for Indoor Switch Gear.
- .3 Institute of Electrical and Electronics (IEEE)/National Electrical Safety Code Product Line (NESC)
 - .1 IEEE SP1122-2000, The Authoritative Dictionary of IEEE Standards Terms, 7th Edition.

1.02 DEFINITIONS

- .1 Electrical and electronic terms: unless otherwise specified or indicated, terms used in these specifications, and on drawings, are those defined by IEEE SP1122.

1.03 DESIGN REQUIREMENTS

- .1 Operating voltages: to CAN3-C235.
- .2 Motors, electric heating, control and distribution devices and equipment to operate satisfactorily at 60 Hz within normal operating limits established by above standard.
 - .1 Equipment to operate in extreme operating conditions established in above standard without damage to equipment.
- .3 Language operating requirements: provide identification nameplates and labels for control items in English and French.
- .4 Use one nameplate or label for both languages.

1.04 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submittals: in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Submit for review single line electrical diagrams under plexiglass and locate as indicated.
 - .1 Electrical distribution system in main electrical room.
 - .2 Electrical power generation and distribution systems in power plant rooms.
- .3 Shop drawings:
 - .1 Submit wiring diagrams and installation details of equipment indicating proposed location, layout and arrangement, control panels, accessories, piping, ductwork, and other items that must be shown to ensure coordinated installation.

- .2 Identify on wiring diagrams circuit terminals and indicate internal wiring for each item of equipment and interconnection between each item of equipment.
- .3 Indicate of drawings clearances for operation, maintenance, and replacement of operating equipment devices.
- .4 Quality Control: in accordance with Section 01 45 00 - Quality Control.
 - .1 Provide CSA certified equipment and material.
 - .2 Where CSA certified equipment and material is not available, submit such equipment and material to inspection authorities for special approval before delivery to site.
 - .3 Submit test results of installed electrical systems and instrumentation.
 - .4 Permits and fees: in accordance with General Conditions of contract.
 - .5 Submit, upon completion of Work, load balance report as described in PART 3 - LOAD BALANCE.
 - .6 Submit certificate of acceptance from authority having jurisdiction upon completion of Work to Departmental Representative.
 - .7 Test reports.

1.05 QUALITY ASSURANCE

- .1 Quality Assurance: in accordance with Section 01 45 00 - Quality Control.
- .2 Qualifications: electrical Work to be carried out by qualified, licensed electricians who hold valid Master Electrical Contractor license or apprentices as per the conditions of Provincial Act respecting manpower vocational training and qualification.
 - .1 Employees registered in provincial apprentices program: permitted, under direct supervision of qualified licensed electrician, to perform specific tasks.
 - .2 Permitted activities: determined based on training level attained and demonstration of ability to perform specific duties.
- .3 Health and Safety Requirements: do construction occupational health and safety in accordance with Section 01 35 29.06 - Health and Safety Requirements.

1.06 DELIVERY, STORAGE AND HANDLING

- .1 Material Delivery Schedule: provide Departmental Representative with schedule within 2 weeks after award of Contract.

1.07 SYSTEM STARTUP

- .1 Instruct Departmental Representative and operating personnel in operation, care and maintenance of systems, system equipment and components.
- .2 Arrange and pay for services of manufacturer's factory service Departmental Representative to supervise start-up of installation, check, adjust, balance and calibrate components and instruct operating personnel.
- .3 Provide these services for such period, and for as many visits as necessary to put equipment in operation, and ensure that operating personnel are conversant with aspects of its care and operation.

1.08 OPERATING INSTRUCTIONS

- .1 Provide for each system and principal item of equipment as specified in technical sections for use by operation and maintenance personnel.
- .2 Operating instructions to include following:
 - .1 Wiring diagrams, control diagrams, and control sequence for each principal system and item of equipment.
 - .2 Start up, proper adjustment, operating, lubrication, and shutdown procedures.
 - .3 Safety precautions.
 - .4 Procedures to be followed in event of equipment failure.
 - .5 Other items of instruction as recommended by manufacturer of each system or item of equipment.
- .3 Print or engrave operating instructions and frame under glass or in approved laminated plastic.
- .4 Post instructions where directed.
- .5 For operating instructions exposed to weather, provide weather-resistant materials or weatherproof enclosures.
- .6 Ensure operating instructions will not fade when exposed to sunlight and are secured to prevent easy removal or peeling.

2 PRODUCTS

2.01 MATERIALS AND EQUIPMENT

- .1 Provide material and equipment in accordance with Section 01 61 00 - Common Product Requirements.
- .2 Material and equipment to be CSA certified. Where CSA certified material and equipment are not available, obtain special approval from inspection authorities before delivery to site and submit such approval as described in PART 1 - SUBMITTALS.
- .3 Factory assemble control panels and component assemblies.

2.02 ELECTRIC MOTORS, EQUIPMENT AND CONTROLS

- .1 Verify installation and co-ordination responsibilities related to motors, equipment and controls, as indicated.
- .2 Control wiring and conduit: in accordance with Section 26 29 03 - Control Devices except for conduit, wiring and connections below 50 V which are related to control systems specified in mechanical sections and as shown on mechanical drawings.

2.03 WARNING SIGNS

- .1 Warning Signs: in accordance with requirements of inspection authorities.
- .2 Porcelain enamel signs, minimum size 175 x 250 mm.

2.04 WIRING TERMINATIONS

- .1 Ensure lugs, terminals, screws used for termination of wiring are suitable for either copper or aluminum conductors.

2.05 EQUIPMENT IDENTIFICATION

- .1 Identify electrical equipment with nameplates and labels as follows:
 - .1 Nameplates: lamicoid 3 mm melamine, black face, white core, lettering accurately aligned and engraved into core mechanically attached with self-tapping screws.
 - .2 Sizes as follows:

NAMEPLATE SIZES

Size 1	10 x 50 mm	1 line	3 mm high letters
Size 2	12 x 70 mm	1 line	5 mm high letters
Size 3	12 x 70 mm	2 lines	3 mm high letters
Size 4	20 x 90 mm	1 line	8 mm high letters
Size 5	20 x 90 mm	2 lines	5 mm high letters
Size 6	25 x 100 mm	1 line	12 mm high letters
Size 7	25 x 100 mm	2 lines	6 mm high letters

- .2 Labels: embossed plastic labels with 6 mm high letters unless specified otherwise.
- .3 Wording on nameplates and labels to be approved by Departmental Representative prior to manufacture.
- .4 Allow for minimum of twenty-five (25) letters per nameplate and label.
- .5 Nameplates for terminal cabinets and junction boxes to indicate system and/or voltage characteristics.
- .6 Identify equipment with Size 3 labels engraved "ASSET INVENTORY NO." as directed by Departmental Representative.
- .7 Disconnects, starters and contactors: indicate equipment being controlled and voltage.

- .8 Terminal cabinets and pull boxes: indicate system and voltage.
- .9 Transformers: indicate capacity, primary and secondary voltages.

2.06 WIRING IDENTIFICATION

- .1 Identify wiring with permanent indelible identifying markings, numbered, on both ends of phase conductors of feeders and branch circuit wiring.
- .2 Maintain phase sequence and colour coding throughout.
- .3 Colour coding: to CSA C22.10.
- .4 Use colour coded wires in communication cables, matched throughout system.

2.07 CONDUIT AND CABLE IDENTIFICATION

- .1 Colour code conduits, boxes and metallic sheathed cables.
- .2 Code with plastic tape or paint at points where conduit or cable enters wall, ceiling, or floor, and at 15 m intervals.
- .3 Colours: 25 mm wide prime colour and 20 mm wide auxiliary colour.

	<u>Prime</u>	<u>Auxiliary</u>
up to 250 V	Yellow	
up to 600 V	Yellow	Green
up to 5 kV	Yellow	Blue
up to 15 kV	Yellow	Red
Telephone	Green	
Other	Green	Blue
Communication Systems		
Fire Alarm	Red	
Emergency	Red	Blue
Voice		
Other	Red	Yellow
Security Systems		

2.08 FINISHES

- .1 Shop finish metal enclosure surfaces by application of rust resistant primer inside and outside, and at least two coats of finish enamel.
 - .1 Paint outdoor electrical equipment "equipment green" finish to EEMAC 2Y-1.
 - .2 Paint indoor switchgear and distribution enclosures light gray to EEMAC 2Y-1.

3 EXECUTION

3.01 INSTALLATION

- .1 Do complete installation in accordance with CSA C22.10 except where specified otherwise.
- .2 Do overhead and underground systems in accordance with CSA C22.3 No.1 except where specified otherwise.

3.02 NAMEPLATES AND LABELS

- .1 Ensure manufacturer's nameplates, CSA labels and identification nameplates are visible and legible after equipment is installed.

3.03 CONDUIT AND CABLE INSTALLATION

- .1 Install conduit and sleeves prior to pouring of concrete.
 - .1 Sleeves through concrete: plastic, sized for free passage of conduit, and protruding 50 mm.
- .2 If plastic sleeves are used in fire rated walls or floors, remove before conduit installation.
- .3 Install cables, conduits and fittings embedded or plastered over, close to building structure so furring can be kept to minimum.
- .4 Install underground cables in accordance with manufacturer's requirements. Submit to the Departmental Representative a written certification from the cable manufacturer stating that the installation conforms to their requirements prior and after the installation of subgrade and backfill material in each trench (see article 3.07.5).

3.04 LOCATION OF OUTLETS

- .1 Locate outlets in accordance with Section 26 05 32 - Outlet Boxes, Conduit Boxes and Fittings.
- .2 Do not install outlets back-to-back in wall; allow minimum 150 mm horizontal clearance between boxes.
- .3 Change location of outlets at no extra cost or credit, providing distance does not exceed 3000 mm, and information is given before installation.
- .4 Locate light switches on latch side of doors.

3.05 MOUNTING HEIGHTS

- .1 Mounting height of equipment is from finished floor to centreline of equipment unless specified or indicated otherwise.
- .2 If mounting height of equipment is not specified or indicated, verify before proceeding with installation.

- .3 Install electrical equipment at following heights unless indicated otherwise.
 - .1 Local switches: 1400 mm.
 - .2 Wall receptacles:
 - .1 General: 300 mm.
 - .2 Above top of counters or counter splash backs: 175 mm.
 - .3 In mechanical rooms: 1400 mm.
 - .3 Panelboards: as required by Code or as indicated.
 - .4 Telephone and interphone outlets: 300 mm.
 - .5 Wall mounted telephone and interphone outlets: 1500 mm.
 - .6 Fire alarm stations: 1500 mm.
 - .7 Fire alarm bells: 2100 mm.
 - .8 Television outlets: 300 mm.

3.06 CO-ORDINATION OF PROTECTIVE DEVICES

- .1 Ensure circuit protective devices such as overcurrent trips, relays and fuses are installed to required values and settings.
- .2 Submit to the Departmental Representative an electrical coordination study report for the main electrical distribution (1 200A and above).

3.07 FIELD QUALITY CONTROL

- .1 Load Balance:
 - .1 Measure phase current to panelboards with normal loads (lighting) operating at time of acceptance; adjust branch circuit connections as required to obtain best balance of current between phases and record changes.
 - .2 Measure phase voltages at loads and adjust transformer taps to within 2% of rated voltage of equipment.
 - .3 Provide upon completion of work, load balance report as directed in PART 1 - SUBMITTALS: phase and neutral currents on panelboards and dry-core transformers, operating under normal load, as well as hour and date on which each load was measured, and voltage at time of test.
- .2 Conduct following tests in accordance with Section 01 45 00 - Quality Control.
 - .1 Power generation and distribution system including phasing, voltage, grounding and load balancing.
 - .2 Circuits originating from branch distribution panels.
 - .3 Lighting and its control.
 - .4 Motors, heaters and associated control equipment including sequenced operation of systems where applicable.
 - .5 Systems: fire alarm system communications.
 - .6 Insulation resistance testing:
 - .1 Megger circuits, feeders and equipment up to 350 V with a 500 V instrument.
 - .2 Megger 350-600 V circuits, feeders and equipment with a 1000 V instrument.
 - .3 Check resistance to ground before energizing.

- .3 Carry out tests in presence of Departmental Representative.
- .4 Provide instruments, meters, equipment and personnel required to conduct tests during and at conclusion of project.
- .5 Manufacturer's Field Services:
 - .1 Obtain written report from manufacturer verifying compliance of Work, in handling, installing, applying, protecting and cleaning of product and submit Manufacturer's Field Reports as described in PART 1 - SUBMITTALS.
 - .2 Provide manufacturer's field services consisting of product use recommendations and periodic site visits for inspection of product installation in accordance with manufacturer's instructions.
 - .3 Schedule site visits, to review Work, as directed in PART 1 - QUALITY ASSURANCE.

3.08 CLEANING

- .1 Clean and touch up surfaces of shop-painted equipment scratched or marred during shipment or installation, to match original paint.
- .2 Clean and prime exposed non-galvanized hangers, racks and fastenings to prevent rusting.

END OF SECTION

1 GENERAL

1.01 WIRE AND BOX CONNECTORS

- .1 Wire and box connectors, materials and accessories including their installation.

1.02 REFERENCES

- .1 Canadian Standards Association (CSA International)
 - .1 CAN/CSA-C22.2 No.18-98, Outlet Boxes, Conduit Boxes, Fittings and Associated Hardware.
 - .2 CSA C22.2 No.65-93(R1999), Wire Connectors.
- .2 National Electrical Manufacturers Association (NEMA)

2 PRODUCTS

2.01 MATERIALS

- .1 Pressure type wire connectors to: CSA C22.2 No.65, with current carrying parts of copper sized to fit copper conductors as required.
- .2 Fixture type splicing connectors to: CSA C22.2 No.65, with current carrying parts of copper sized to fit copper conductors 10 AWG or less.
- .3 Compression type conductor splicing connector in aluminum for single conductors and TECK cables at 1000V to: CSA C22.2 No.65, with current carrying parts of copper sized to conductor or TECK cable caliber and with appropriate insulated 1000V shrink tubing.
- .4 Bushing stud connectors: to EEMAC 1Y-2 to consist of:
 - .1 Connector body and stud clamp for stranded, copper, conductors.
 - .2 Clamp for stranded, round, copper, conductors.
 - .3 Stud clamp bolts.
 - .4 Bolts for copper bar.
 - .5 Sized for conductors, bars as indicated.
- .5 Clamps or connectors for armoured cable, flexible conduit as required to: CAN/CSA-C22.2 No.18.

3 EXECUTION

3.01 INSTALLATION

- .1 Remove insulation carefully from ends of conductors and:
 - .1 Install mechanical pressure type connectors and tighten screws with appropriate compression tool recommended by manufacturer. Installation shall meet secureness tests in accordance with CSA C22.2 No.65.

- .2 Install fixture type connectors and tighten. Replace insulating cap.
- .3 Install insulated tubing and compression type connectors; secure connector to conductor with appropriate compression tool as recommended by manufacturer and then overlap insulated shrink tubing over connector. Follow manufacturer's recommendations to render shrink tubing electrically sound in accordance with CSA C22.2 No.65.
- .3 Install bushing stud connectors in accordance with EEMAC 1Y-2.

3.02 CABLE SPLICES

- .1 Add cable splices to extend existing cables to remain, as indicated; splices are to be enclosed in boxes.

END OF SECTION

1 GENERAL

1.01 RELATED SECTIONS

- .1 Section 26 05 20 - Wire and Box Connectors - 0 - 1000 V.

1.02 REFERENCES

- .1 CSA C22.2 No .0.3-96, Test Methods for Electrical Wires and Cables.
- .2 CAN/CSA-C22.2 No. 131-M89(R1994), Type TECK 90 Cable.

1.03 PRODUCT DATA

- .1 Submit product data in accordance with Section 01 33 00 - Submittal Procedures.

2 PRODUCTS

2.01 BUILDING WIRES

- .1 Conductors: stranded for 10 AWG and larger. Minimum size: 12 AWG.
- .2 Copper conductors: size as indicated, with 600, 1000 V insulation of chemically cross-linked thermosetting polyethylene material rated RW90, RWU90. Use RWU90 conductors in underground and exterior installations.

2.02 COPPER TECK CABLE

- .1 Cable: to CAN/CSA-C22.2 No. 131.
- .2 Conductors:
 - .1 Circuit conductors: copper, size as indicated.
- .3 Insulation:
 - .1 Chemically cross-linked thermosetting polyethylene rated type RW90XLPE, 1000 V.
- .4 Inner jacket: polyvinyl chloride material.
- .5 Armour: flat, interlocking, galvanized steel, aluminum.
- .6 Overall covering: polyvinyl chloride material.
- .7 Fastenings:
 - .1 One hole steel straps to secure surface cables 50 mm and smaller. Two hole steel straps for cables larger than 50 mm.
 - .2 Channel type supports for two or more cables at 50 mm centers.
 - .3 Threaded rods: 6 mm dia. to support suspended channels.

- .8 Connectors:
 - .1 Watertight approved for TECK cable.

2.03 ARMOURED CABLES

- .1 Conductors: insulated, copper, size as indicated.
- .2 Type: AC90.
- .3 Armour: interlocking type fabricated from galvanized steel or aluminum strip.
- .4 Type: ACWU90 - PVC flame retardant jacket over thermoplastic armour meeting requirements of Vertical Tray Fire Test of CSA C22.2 No. 0.3 with maximum flame travel of 1.2 m.
- .5 Connectors: anti-short-circuit.

3 EXECUTION

3.01 INSTALLATION OF BUILDING WIRES

- .1 Install wiring as follows:
 - .1 In conduit systems in accordance with Section 26 05 34 – Conduits, Conduit Fastenings and Conduit Fittings.

3.02 INSTALLATION OF COPPER TECK CABLE 0 -1000 V

- .1 Install cables for powering existing services as indicated.
 - .1 Group cables wherever possible on channels and cable trays.
- .2 Terminate cables in accordance with Section 26 05 20 - Wire and Box Connectors - 0 - 1000 V.

3.03 INSTALLATION OF ARMOURED CABLES

- .1 Group cables wherever possible.
- .2 Terminate cables in accordance with Section 26 05 20 - Wire and Box Connectors - 0 - 1000 V.

END OF SECTION

1 GENERAL

1.01 REFERENCES

- .1 American National Standards Institute (ANSI)/Institute of Electrical and Electronics Engineers (IEEE)
 - .1 ANSI/IEEE 837-1989(R1996), Qualifying Permanent Connections Used in Substation Grounding.
- .2 Canadian Standards Association, (CSA International)
- .3 CSA C22.2, no 41-M1987 (R2003) Grounding and Bonding Equipment.

2 PRODUCTS

2.01 EQUIPMENT

- .1 Grounding conductors: bare stranded copper, soft annealed, size as indicated.
- .2 Insulated grounding conductors: green, type RW 90.
- .3 Non-corroding accessories necessary for grounding system, type, size, material as indicated, including but not necessarily limited to:
 - .1 Grounding and bonding bushings.
 - .2 Protective type clamps.
 - .3 Bolted type conductor connectors.
 - .4 Thermit welded type conductor connectors.
 - .5 Bonding jumpers, straps.
 - .6 Pressure wire connectors.

3 EXECUTION

3.01 INSTALLATION GENERAL

- .1 Install complete permanent, continuous grounding system including, conductors, connectors, accessories. Where EMT is used, run ground wire in conduit.
- .2 Install connectors in accordance with manufacturer's instructions.
- .3 Protect exposed grounding conductors from mechanical injury.
- .4 Use mechanical connectors for grounding connections to equipment provided with lugs.
- .5 Soldered joints not permitted.
- .6 Install bonding wire for flexible conduit, connected at both end to grounding bushing, solderless

lug, clamp or cup washer and screw. Neatly cleat bonding wire to exterior of flexible conduit.

3.02 SYSTEM AND CIRCUIT GROUNDING

- .1 Install system and circuit grounding connections to neutral of primary 600 V system, secondary 120/208 V system.

3.03 EQUIPMENT GROUNDING

- .1 Install grounding connections to typical equipment included in, but not necessarily limited to following list. Service equipment, transformers, switchgear, duct systems, frames of motors, motor control centres, starters, control panels, building steel work, generators and escalators, distribution panels, outdoor lighting.

3.04 FIELD QUALITY CONTROL

- .1 Perform tests in accordance with Section 26 05 00 - Common Work Results - Electrical.
- .2 Perform ground continuity and resistance tests using method appropriate to site conditions and to approval of Departmental Representative and local authority having jurisdiction over installation.
- .3 Perform tests before energizing electrical system.
- .4 Disconnect ground fault indicator during tests.

END OF SECTION

1 GENERAL

1.01 RELATED REQUIREMENTS

- .1 Section 26 05 34 – Conduits, Conduit Fastenings and Conduit Fittings.

2 PRODUCTS

2.01 SUPPORT CHANNELS

- .1 U shape, size 41 x 41 mm, 2.5 mm thick, surface mounted, suspended.

3 EXECUTION

3.01 INSTALLATION

- .1 Secure equipment to poured concrete with expandable inserts.
- .2 Secure equipment to hollow masonry walls or suspended ceilings with toggle bolts.
- .3 Support equipment, conduit or cables using clips, spring loaded bolts, cable clamps designed as accessories to basic channel members.
- .4 Fasten exposed conduit or cables to building construction or support system using straps.
 - .1 One-hole malleable iron, steel straps to secure surface conduits and cables 50 mm and smaller.
 - .2 Two-hole steel straps for conduits and cables larger than 50 mm.
 - .3 Beam clamps to secure conduit to exposed steel work.
- .5 Suspended support systems.
 - .1 Support individual cable or conduit runs with 6 mm dia threaded rods and spring clips.
 - .2 Support 2 or more cables or conduits on channels supported by 6 mm dia threaded rod hangers where direct fastening to building construction is impractical.
- .6 For surface mounting of two or more conduits use channels at 1.5 m on centre spacing.
- .7 Provide metal brackets, frames, hangers, clamps and related types of support structures where indicated or as required to support conduit and cable runs.
- .8 Ensure adequate support for raceways and cables dropped vertically to equipment where there is no wall support.
- .9 Do not use wire lashing or perforated strap to support or secure raceways or cables.
- .10 Do not use supports or equipment installed for other trades for conduit or cable support except with

permission of other trade and approval of Departmental Representative.

- .11 Install fastenings and supports as required for each type of equipment cables and conduits, and in accordance with manufacturer's installation recommendations.

END OF SECTION

1 GENERAL

1.01 REFERENCE

- .1 CSA C22.2 no 40 m1999 (R1999), Cutout, Junction and Pull Boxes.
- .2 CSA C22.2 no 76 m92 (R2002), Splitters.

1.02 RELATED REQUIREMENTS

- .1 Section 26 05 34 – Conduits, Conduit Fastenings and Conduit Fittings.

1.03 SHOP DRAWINGS AND PRODUCT DATA

- .1 Submit shop drawings and product data for cabinets in accordance with Section 01 33 00 - Submittal Procedures.

2 PRODUCTS

2.01 JUNCTION AND PULL BOXES

- .1 Welded steel construction with screw-on flat covers for surface mounting.
- .2 Covers with 25 mm minimum extension all around, for flush-mounted pull and junction boxes.
- .3 NEMA 4 when installed in tunnels and adjacent areas open to tunnels.

3 EXECUTION

3.01 JUNCTION, PULL BOXES AND CABINETS INSTALLATION

- .1 Install pull boxes in inconspicuous but accessible locations.
- .2 Only main junction and pull boxes are indicated. Install pull boxes so as not to exceed 30 m of conduit run between pull boxes.

3.02 IDENTIFICATION

- .1 Provide equipment identification in accordance with Section 26 05 00 - Common Work Results - Electrical.
- .2 Install size 2 identification labels indicating system name, voltage and phase.

END OF SECTION

1 GENERAL

1.01 REFERENCES

- .1 Association canadienne de normalization (CSA)/CSA International.
 - .1 CSA C22.10.10-2010, Code canadien de l'électricité, Première partie et modifications du Québec.
- .2 CSA C22.2 no 18-98(R2003), Outlet Boxes, Conduit Boxes, Fittings and Associated Hardware.

2 PRODUCTS

2.01 OUTLET AND CONDUIT BOXES GENERAL

- .1 Size boxes in accordance with CSA C22.10.
- .2 102 mm square or larger outlet boxes as required for special devices.
- .3 Gang boxes where wiring devices are grouped.
- .4 Blank cover plates for boxes without wiring devices.
- .5 347 V outlet boxes for 347 V switching devices.
- .6 Combination boxes with barriers where outlets for more than one system are grouped.

2.02 SHEET STEEL OUTLET BOXES

- .1 Electro-galvanized steel single gang flush device boxes for flush installation, minimum size 76 x 50 x 63 mm or as indicated. 102 mm square outlet boxes when more than one conduit enters one side with extension and plaster rings as required.
- .2 102 mm square or octagonal outlet boxes for lighting fixture outlets.
- .3 102 mm square outlet boxes with extension and plaster rings for flush mounting devices in finished plaster walls.

2.03 CONDUIT BOXES

- .1 Cast FS or FD aluminum boxes with factory-threaded hubs and mounting feet for surface wiring of devices.

2.04 FITTINGS - GENERAL

- .1 Bushing and connectors with nylon insulated throats.

- .2 Knock-out fillers to prevent entry of debris.
- .3 Conduit outlet bodies for conduit up to 32 mm and pull boxes for larger conduits.
- .4 Double locknuts and insulated bushings on sheet metal boxes.

3 EXECUTION

3.01 INSTALLATION

- .1 Support boxes independently of connecting conduits.
- .2 Fill boxes with paper, sponges or foam or similar approved material to prevent entry of debris during construction. Remove upon completion of work.
- .3 For flush installations mount outlets flush with finished wall using plaster rings to permit wall finish to come within 6 mm of opening.
- .4 Provide correct size of openings in boxes for conduit, mineral insulated and armoured cable connections. Reducing washers are not allowed.

END OF SECTION

1 GENERAL

1.01 RELATED REQUIREMENTS

- .1 Section 26 05 21 – Wires and Cables (0-1000V).
- .2 Section 26 05 29 – Hangers and Supports for Electrical Systems.

1.02 REFERENCES

- .1 Canadian Standards Association (CSA International)
 - .1 CAN/CSA C22.2 No. 18-98 (R2003), Outlet Boxes, Conduit Boxes, Fittings and Associated Hardware, A National Standard of Canada.
 - .2 CSA C22.2 No. 45-M1981 (R2003), Rigid Metal Conduit.
 - .3 CSA C22.2 No. 56-04, Flexible Metal Conduit and Liquid-Tight Flexible Metal Conduit.
 - .4 CSA C22.2 No. 83-M1985 (R2003), Electrical Metallic Tubing.
 - .5 CSA C22.2 No. 211.2-M1984 (R2003), Rigid PVC (Unplasticized) Conduit.
 - .6 CAN/CSA C22.2 No. 227.3-05, Nonmetallic Mechanical Protection Tubing (NMPT), A National Standard of Canada (February 2006).

1.03 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product data: submit manufacturer's printed product literature, specifications and datasheets.
 - .1 Submit cable manufacturing data.
- .3 Quality assurance submittals:
 - .1 Test reports: submit certified test reports.
 - .2 Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
 - .3 Instructions: submit manufacturer's installation instructions.

2 PRODUCTS

2.01 CABLES AND REELS

- .1 Provide cables on reels or coils.
 - .1 Mark or tag each cable and outside of each reel or coil, to indicate cable length, voltage rating, conductor size, and manufacturer's lot number and reel number.
- .2 Each coil or reel of cable to contain only one continuous cable without splices.

2.02 CONDUITS

- .1 Rigid metal conduit: to CSA C22.2 No. 45, threaded.
- .2 Electrical metallic tubing (EMT): to CSA C22.2 No. 83, with couplings, with expanded ends.
- .3 Rigid pvc conduit: to CSA C22.2 No. 211.2.
- .4 Flexible metal conduit: to CSA C22.2 No. 56, steel, liquid-tight flexible metal.

2.03 CONDUIT FASTENINGS

- .1 One hole steel straps to secure surface conduits 50 mm and smaller.
 - .1 Two hole steel straps for conduits larger than 50 mm.
- .2 Beam clamps to secure conduits to exposed steel work.
- .3 Channel type supports for two or more conduits at 1.5 m on centre.
- .4 Threaded rods, 6 mm diameter, to support suspended channels.

2.04 CONDUIT FITTINGS

- .1 Fittings: to CAN/CSA C22.2 No. 18, manufactured for use with conduit specified. Coating: same as conduit.
- .2 Ensure factory "ells" where 90 degrees bends for 25 mm and larger conduits.
- .3 Watertight connectors and couplings for EMT.
 - .1 Set-screws are not acceptable.

2.05 EXPANSION FITTINGS FOR RIGID CONDUIT

- .1 Watertight expansion fittings with integral bonding jumper suitable for linear expansion and 19 mm deflection.
- .2 Weatherproof expansion fittings for linear expansion at entry to panel.

2.06 FISH CORD

- .1 Polypropylene.

3 EXECUTION

3.01 MANUFACTURER'S INSTRUCTIONS

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including

product technical bulletins, handling, storage and installation instructions, and datasheets.

3.02 INSTALLATION

- .1 Install conduits to conserve headroom in exposed locations and cause minimum interference in spaces through which they pass.
- .2 Conceal conduits except in mechanical and electrical service rooms, in unfinished areas.
- .3 Use electrical metallic tubing (EMT) except in cast concrete and when above 2.4 m and not subject to mechanical injury.
- .4 Use rigid pvc conduit underground and in cast concrete.
- .5 Use flexible metal conduit for connection to motors in dry areas, connection to surface or recessed fluorescent fixtures, work in movable metal partitions.
- .6 Use liquid tight flexible metal conduit for connection to motors or vibrating equipment, in tunnels, in damp, wet or corrosive locations.
- .7 Install conduit sealing fittings in hazardous areas.
 - .1 Fill with compound.
- .8 Minimum conduit size for lighting and power circuits: 19 mm.
- .9 Bend conduit cold:
 - .1 Replace conduit if kinked or flattened more than 1/10th of its original diameter.
- .10 Mechanically bend steel conduit over 19 mm diameter.
- .11 Field threads on rigid conduit must be of sufficient length to draw conduits up tight.
- .12 Install fish cord in empty conduits.
- .13 Remove and replace blocked conduit sections.
 - .1 Do not use liquids to clean out conduits.
- .14 Dry conduits out before installing wire.

3.03 SURFACE CONDUITS

- .1 Run parallel or perpendicular to building lines.
- .2 Locate conduits behind infrared or gas fired heaters with 1.5 m clearance.
- .3 Run conduits in flanged portion of structural steel.
- .4 Group conduits wherever possible on suspended surface channels.

- .5 Do not pass conduits through structural members except as indicated.
- .6 Do not locate conduits less than 75 mm parallel to steam or hot water lines with minimum of 25 mm at crossovers.

3.04 CONCEALED CONDUITS

- .1 Run parallel or perpendicular to building lines.
- .2 Do not install horizontal runs in masonry walls.
- .3 Do not install conduits in terrazzo or concrete toppings.

3.05 CLEANING

- .1 Proceed in accordance with Section 01 74 11 - Cleaning.
- .2 On completion and verification of performance of installation, remove surplus materials, excess materials, rubbish, tools and equipment.

END OF SECTION

1 GENERAL

1.01 RELATED REQUIREMENTS

- .1 Section 31 23 33.01 – Excavating, Trenching and Backfilling.
- .2 Section 26 05 00 – Common Work Results for Electrical.

1.02 REFERENCES

- .1 Canadian Standards Association, (CSA International).
- .2 Insulated Cable Engineers Association, Inc. (ICEA).

2 PRODUCTS

2.01 CABLE PROTECTION

- .1 38 x 140 mm plywood pressure treated with clear, coloured or copper naphthenate or 5% pentachlorophenol solution, water repellent preservative.
- .2 Ruban indicateur métallisé, selon les indications.

3 EXECUTION

3.01 CABLE INSTALLATION IN DUCTS

- .1 Install cables as indicated in ducts.
 - .1 Do not pull spliced cables inside ducts.
- .2 Install multiple cables in duct simultaneously.
- .3 Use CSA approved lubricants of type compatible with cable jacket to reduce pulling tension.
- .4 To facilitate matching of colour coded multiconductor control cables reel off in same direction during installation.
- .5 Before pulling cable into ducts and until cables are properly terminated, seal ends of lead covered cables with wiping solder; seal ends of non-leaded cables with moisture seal tape.
- .6 After installation of cables, seal duct ends with duct sealing compound.

3.02 FIELD QUALITY CONTROL

- .1 Perform tests in accordance with Section 26 05 00 - Common Work Results - Electrical.
- .2 Perform tests using qualified personnel. Provide necessary instruments and equipment.

- .3 Check phase rotation and identify each phase conductor of each feeder.
- .4 Check each feeder for continuity, short circuits and grounds. Ensure resistance to ground of circuits is not less than 50 megohms.
- .5 Pre-acceptance tests.
 - .1 After installing cable but before splicing and terminating, perform insulation resistance test with 1000 V megger on each phase conductor.
 - .2 Check insulation resistance after each splice and/or termination to ensure that cable system is ready for acceptance testing.
- .6 Acceptance Tests
 - .1 Ensure that terminations and accessory equipment are disconnected.
 - .2 Ground shields, ground wires, metallic armour and conductors not under test.
 - .3 High Potential (Hipot) Testing.
 - .1 Conduct hipot testing at original factory test voltage in accordance with manufacturer's ICEA recommendations.
- .7 Provide Departmental Representative with list of test results showing location at which each test was made, circuit tested and result of each test.
- .8 Remove and replace entire length of cable if cable fails to meet any of test criteria.

END OF SECTION

1 GENERAL

1.01 RELATED SECTIONS

- .1 Section 26 05 00 - Common Work Results - Electrical.

1.02 REFERENCES

- .1 C22.2 no. 14-F95 (2001), Industrial Control Equipment.

1.03 SHOP DRAWINGS AND PRODUCT DATA

- .1 Submit shop drawings in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Indicate:
 - .1 Mounting method and dimensions.
 - .2 Starter size and type.
 - .3 Layout of identified internal and front panel components.
 - .4 Enclosure types.
 - .5 Wiring diagram for each type of starter.
 - .6 Interconnection diagrams.

1.04 CLOSEOUT SUBMITTALS

- .1 Provide operation and maintenance data for motor starters for incorporation into manual specified in Section 01 78 00 - Closeout Submittals.
- .2 Include operation and maintenance data for each type and style of starter.

1.05 EXTRA MATERIALS

- .1 Provide maintenance materials in accordance with Section 01 78 00 - Closeout Submittals.

2 PRODUCTS

2.01 MATERIALS

- .1 Starters: to NEMA standard.

2.02 MANUAL MOTOR STARTERS

- .1 Single phase manual motor starters of size, type, rating, and enclosure type as indicated, with components as follows:
 - .1 Switching mechanism, quick make and break.
 - .2 One overload heater, manual reset, trip indicating handle.

- .2 Accessories:
 - .1 Toggle switch labelled as indicated.
 - .2 Indicating light: standard type and colour as indicated.
 - .3 Locking tab to permit padlocking in "ON" or "OFF" position.
- .3 Product : Square D, class 2510 or approved equivalent.

2.03 FINISHES

- .1 Apply finishes to enclosure in accordance with Section 26 05 00 - Common Work Results - Electrical.

2.04 EQUIPMENT IDENTIFICATION

- .1 Provide equipment identification in accordance with Section 26 05 00 - Common Work Results - Electrical.
- .2 Manual starter designation label, white plate, black letters, size 1, engraved as indicated.
- .3 Magnetic starter designation label, white plate, black letters, size 4 engraved as indicated.

3 EXECUTION

3.01 INSTALLATION

- .1 Install starters, connect power and control as indicated.
- .2 Ensure correct fuses and overload devices elements installed.

3.02 FIELD QUALITY CONTROL

- .1 Perform tests in accordance with Section 26 05 00 - Common Work Results - Electrical and manufacturer's instructions.
- .2 Check that sequence controls, interlocking with other separate related starters, equipment, control devices, operate as indicated.

END OF SECTION