

ASBESTOS NOTIFICATION AND ACKNOWLEDGEMENT

ACKNOWLEDGMENT:

THE CONTRACTOR WILL AGREE IN UNDERTAKING THE WORK OF THIS PROJECT TO PERFORM THE WORK IN SUCH A MANNER SO AS NOT TO DISTURB ANY EXISTING ASBESTOS CONTAINING MATERIALS WITHOUT:

1. REVIEWING THE MOST RECENT ASBESTOS SURVEY REPORT; AND
2. GIVING NOTICE TO THE APPROPRIATE SUPERVISOR, INDIVIDUAL MANAGER AND/OR PROJECT COORDINATOR THAT KNOWN OR SUSPECTED ASBESTOS-CONTAINING MATERIAL(S) WILL BE/NEEDS TO BE DISTURBED, OR
3. HALTING WORK AND GIVING NOTICE TO THE APPROPRIATE INDIVIDUAL MANAGER AND/OR PROJECT COORDINATOR WHEN UNFORESEEN SUSPECTED ASBESTOS-CONTAINING MATERIALS ARE UNCOVERED.

GENERAL NOTES AND CONDITIONS:

1. WHERE MATERIAL IS ENCOUNTERED BY TRADES AND CONTRACTORS THAT IS SUSPECT OR SUSPICIOUS, THE TRADE/CONTRACTOR/SUBCONTRACTOR IS TO CONFIRM WITH THE MOST CURRENT ASBESTOS REPORT.
2. IN THE EVENT THE MOST CURRENT ASBESTOS REPORT DOES NOT CLARIFY THE SUSPICIOUS MATERIAL, THE CONTRACTOR IS TO CONTACT THE DEPARTMENTAL REPRESENTATIVE AND IDENTIFY THE SUSPECT OR SUSPICIOUS MATERIAL AND LOCATION WHERE THE MATERIAL IS FOUND FOR FURTHER DIRECTION.
3. REGULATIONS AND GUIDELINES STATE THAT ANY DISTURBANCE OF ASBESTOS-CONTAINING MATERIALS MAY ONLY BE PERFORMED BY WORKERS OR BY AN OUTSIDE CONTRACTOR WHO HAVE FIRST RECEIVED THE REQUIRED TRAINING IN ASBESTOS-RELATED PRECAUTIONS.
4. THE DEPARTMENTAL REPRESENTATIVE(S) WILL NOT BE HELD RESPONSIBLE FOR ANY EXPOSURE TO ANY POTENTIAL ASBESTOS CONTAINING MATERIALS DURING THE CONSTRUCTION PERIOD.
5. THE CONTRACTOR TAKES FULL RESPONSIBILITY FOR REVIEWING AND UNDERSTANDING ALL ASBESTOS RELATED PROJECT DOCUMENTATION, CURRENT ASBESTOS REGULATIONS AND GUIDELINES, AND ANY POTENTIAL ASBESTOS RELATED RISKS ASSOCIATED WITH THE PROJECT WORKS

LEAD NOTIFICATION AND ACKNOWLEDGEMENT

ACKNOWLEDGMENT:

THE CONTRACTOR WILL AGREE IN UNDERTAKING THE WORK OF THIS PROJECT TO PERFORM THE WORK IN SUCH A MANNER SO AS NOT TO DISTURB ANY EXISTING LEAD CONTAINING MATERIALS WITHOUT:

1. REVIEWING THE MOST RECENT LEAD SURVEY REPORT; AND
2. GIVING NOTICE TO THE APPROPRIATE SUPERVISOR, INDIVIDUAL MANAGER AND/OR PROJECT COORDINATOR THAT KNOWN OR SUSPECTED LEAD-CONTAINING MATERIAL(S) WILL BE/NEEDS TO BE DISTURBED, OR
3. HALTING WORK AND GIVING NOTICE TO THE APPROPRIATE INDIVIDUAL MANAGER AND/OR PROJECT COORDINATOR WHEN UNFORESEEN SUSPECTED LEAD-CONTAINING MATERIALS ARE UNCOVERED.

GENERAL NOTES AND CONDITIONS:

1. WHERE MATERIAL IS ENCOUNTERED BY TRADES AND CONTRACTORS THAT IS SUSPECT OR SUSPICIOUS, THE TRADE/CONTRACTOR/SUBCONTRACTOR IS TO CONFIRM WITH THE MOST CURRENT LEAD REPORT.
2. IN THE EVENT THE MOST CURRENT LEAD REPORT DOES NOT CLARIFY THE SUSPICIOUS MATERIAL, THE CONTRACTOR IS TO CONTACT THE DEPARTMENTAL REPRESENTATIVE AND IDENTIFY THE SUSPECT OR SUSPICIOUS MATERIAL AND LOCATION WHERE THE MATERIAL IS FOUND FOR FURTHER DIRECTION.
3. REGULATIONS AND GUIDELINES STATE THAT ANY DISTURBANCE OF LEAD-CONTAINING MATERIALS MAY ONLY BE PERFORMED BY WORKERS OR BY AN OUTSIDE CONTRACTOR WHO HAVE FIRST RECEIVED THE REQUIRED TRAINING IN LEAD-RELATED PRECAUTIONS.
4. THE DEPARTMENTAL REPRESENTATIVE(S) WILL NOT BE HELD RESPONSIBLE FOR ANY EXPOSURE TO ANY POTENTIAL LEAD CONTAINING MATERIALS DURING THE CONSTRUCTION PERIOD.
5. THE CONTRACTOR TAKES FULL RESPONSIBILITY FOR REVIEWING AND UNDERSTANDING ALL LEAD RELATED PROJECT DOCUMENTATION, CURRENT LEAD REGULATIONS AND GUIDELINES, AND ANY POTENTIAL LEAD RELATED RISKS ASSOCIATED WITH THE PROJECT WORKS

DEMOLITION GENERAL NOTES









- A. FLOOR ACCESS VIA ELEVATOR AND/OR STAIR TO BE COORDINATED WITH DEPARTMENTAL REPRESENTATIVE AT START UP.
- B. REMOVE ALL EXISTING CLOCKS, HOOKS, WALL FITMENTS, ART, SIGNAGE NOT SHOWN TO BE RETAINED IN AREA OF WORK. NOTIFY THE CONSULTANT AND/OR DEPARTMENTAL REPRESENTATIVE FOR FURTHER INSTRUCTION.
- C. REFER TO MECHANICAL & ELECTRICAL DRAWINGS FOR FURTHER DEMOLITION.
- D. WHEN DEMOLISHING EXISTING CEILINGS, REFER ALSO TO MECHANICAL AND ELECTRICAL DRAWINGS FOR ITEMS TO BE RETAINED AND/OR SALVAGED. NOTE THAT ALL EXISTING LIGHT FIXTURES THAT ARE "DEMOLISHED" SHALL BE CAREFULLY REMOVED AND TURNED OVER TO DEPARTMENTAL REPRESENTATIVE. ALSO, ALL EXISTING VAV BOXES NOT RETAINED FOR RE-USE SHALL BE TURNED OVER TO DEPARTMENTAL REPRESENTATIVE.
- E. NOTE THAT CARE MUST BE TAKEN WHEN REMOVING EXISTING CEILINGS WHERE SPRINKLERS ARE PRESENT. SPRINKLERS SHALL REMAIN FUNCTIONAL UNTIL REQUIRED TO BE REMOVED OR RELOCATED. REFER TO MECHANICAL DRAWINGS FOR FURTHER INFORMATION. ALSO REFER TO SPECIFICATIONS FOR FIRE PROTECTION REQUIREMENTS DURING SPRINKLER WORK (e.g. "FIRE WATCH" REQUIREMENTS).
- F. WHEN REMOVING INTERIOR WALLS & CEILINGS, TAKE CARE NOT TO DAMAGE EXISTING INTERIOR OR EXTERIOR WALLS. EXISTING EXTERIOR OR INTERIOR WALL FINISHES ARE NOT TO BE DAMAGED OR REMOVED.
- G. FIRE STOP ALL ACTIVE OR ABANDONED PENETRATIONS OF FLOOR ASSEMBLY DISCOVERED DURING DEMOLITION & CONSTRUCTION.
- H. TAKE PRECAUTIONS TO MINIMIZE DUST DURING DEMOLITION TO PREVENT DUST FROM CONTAMINATING EXISTING EQUIPMENT AND H.V.A.C. SYSTEM. SEAL WITH POLY ALL POTENTIAL AREAS AND EQUIPMENT.

DEMOLITION KEYNOTES

1. REMOVE PORTION OF EXISTING WALL FOR NEW OPENINGS. SEE FLOOR PLAN A1.0
2. REMOVE EXISTING DOOR
3. REMOVE EXISTING WINDOW
4. REMOVE EXISTING CASEWORK
5. RELOCATE EXISTING CASEWORK. SEE FLOOR PLAN A1.1.
6. REMOVE EXISTING SHOOTING STALLS
7. REMOVE EXISTING BULLET TRAP, CEILING SLOPE SHEETS AND WALL DEFLECTOR PLATES, INCLUDING ALL STRUCTURE AND MOUNTING HARDWARE
8. REMOVE EXISTING CEILING MOUNTED SHOOTING BAFFLES INCLUDING ALL MOUNTING HARDWARE.
9. REMOVE EXISTING TARGET SYSTEM INCLUDING ALL MOUNTING HARDWARE.
10. REMOVE SAFETY CEILING INCLUDING ALL STRUCTURE AND MOUNTING HARDWARE.
11. ALL EXISTING SUSPENDED CEILINGS AND BULKHEADS TO BE REMOVED
12. NOT USED
13. ALL VINYL FLOORING TO BE REMOVED
14. REMOVE ALL EXISTING ACOUSTIC WALL PANELS

DEMOLITION DRAWING LEGEND

- ===== DEMOLISHED WALL
 --- DEMOLISHED DOOR
 [Hatched Area] AREA NOT IN CONTRACT (UNLESS NOTED OTHERWISE)



Revision	Description	Date
5		
4		
3		
2	ISSUED FOR CONSTRUCTION	2015/02/23
1	ISSUED FOR 99% REVIEW	2014/12/22
0	ISSUED FOR 50% REVIEW	2014/10/20

Client client

ROYAL CANADIAN MOUNTED POLICE
 D-DIVISION
 1091 PORTAGE AVENUE
 WINNIPEG, MANITOBA

Project Project
 WINNIPEG, MANITOBA
 1091 PORTAGE AVENUE
 D-DIVISION HEADQUARTERS
 FIRING RANGE UPGRADE

Designed by Conçu par
 S. Shaw

Drawn by Dessiné par
 C. Falkenberg

Approved by Approuvé par
 M. Duhaux

PWSSC Project Manager Administrateur de Projets TPSGC
 P. Ducharme

Drawing title Titre du dessin
 WINNIPEG FIRING RANGE
 SUB BASEMENT
 DEMOLITION PLAN

Project no./No. du projet Drawing no./No. du dessin Revision no.
 AD1.0 0