



The following changes are effective immediately and shall be incorporated into the tender documents.

SPECIFICATIONS:

Section 01 01 00 – General Requirements

3.14 Disruption of Site

Add .2 All fence, sign, silt curtain, etc. posts to be supported by means of bracing counter balanced above the ground level with ground protection at all surface bearing installations. Installations shall not utilize stakes, pins, or any ground penetrating anchors or anchoring systems.

Section 01 54 22 – Site Access and Conveyance Systems

1.2 Access to the Work

Add .4 Contractor shall provide boat access from the mainland to and from the site as required to facilitate consultant and Parks staff to visit for periodic inspection and regular bi-weekly project meetings.

Section 01 54023 – Access and Protection

3.1. Scaffolding, Hoarding and Barriers

.4 Revise to read: ...suitable ladders **or stairs** to scaffolding....Access from the ladder(s) **or stairs** to the scaffolding....

DRAWINGS:

S1 - Scope of Work item 12: Revise to read; Paint railing **and cannon**. Note existing paint contains lead.

S2 - Plan:

- .1 Access corridor and limit of ground protection: it is required to protect the ground as indicated, however the extent of the area may be adjusted to suit the actual required work area around the perimeter of the Cairn and all related areas to facilitate and access the work.
- .2 Temporary dock structure: the indicated temporary dock structure may be substituted with a temporary barge with shore access providing that the following measures are implemented:
 - if the barge is secured with spuds or riverbed disturbing measures a perimeter turbidity curtain shall be installed as indicated
 - the existing shoreline protection (stones, etc.) shall not be disturbed
- .3 Construction fence: fence shall be installed around the entire work area (ie. beyond the perimeter of the indicated straw bales)

END OF ADDENDUM NO.1
