

1 General

1.1 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submittals: in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Shop drawings to show:
 - .1 Mounting arrangements.
 - .2 Operating and maintenance clearances.
- .3 Shop drawings and product data accompanied by:
 - .1 Detailed drawings of bases, supports, and anchor bolts.
 - .2 Acoustical sound power data, where applicable.
 - .3 Points of operation on performance curves.
 - .4 Manufacturer to certify current model production.
 - .5 Certification of compliance to applicable codes.
- .4 In addition to transmittal letter referred to in Section 01 33 00 - Submittal Procedures: use MCAC "Shop Drawing Submittal Title Sheet". Identify section and paragraph number.
- .5 Closeout Submittals:
 - .1 Provide operation and maintenance data for incorporation into manual specified in Section 01 78 00 - Closeout Submittals.
 - .2 Operation and maintenance manual approved by, and final copies deposited with, Departmental Representative before final inspection.
 - .3 Operation data to include:
 - .1 Control schematics for systems including environmental controls.
 - .2 Description of systems and their controls.
 - .3 Description of operation of systems at various loads together with reset schedules and seasonal variances.
 - .4 Operation instruction for systems and component.
 - .5 Description of actions to be taken in event of equipment failure.
 - .6 Valves schedule and flow diagram.
 - .7 Colour coding chart.
 - .4 Maintenance data to include:
 - .1 Servicing, maintenance, operation and trouble-shooting instructions for each item of equipment.
 - .2 Data to include schedules of tasks, frequency, tools required and task time.
 - .5 Performance data to include:
 - .1 Equipment manufacturer's performance datasheets with point of operation as left after commissioning is complete.
 - .2 Equipment performance verification test results.
 - .3 Special performance data as specified.
 - .4 Testing, adjusting and balancing reports as specified in Section 23 05 93 - Testing, Adjusting and Balancing for HVAC.
 - .6 Approvals:
 - .1 Submit 2 copies of draft Operation and Maintenance Manual to Departmental Representative for approval. Submission of individual data will not be accepted unless directed by Departmental Representative

- .2 Make changes as required and re-submit as directed by Departmental Representative.
- .7 Additional data:
 - .1 Prepare and insert into operation and maintenance manual additional data when need for it becomes apparent during specified demonstrations and instructions.
- .8 Site records:
 - .1 Departmental Representative will provide 1 set of reproducible mechanical drawings. Provide sets of white prints as required for each phase of work. Mark changes as work progresses and as changes occur. Include changes to existing mechanical systems, control systems and low voltage control wiring.
 - .2 Transfer information weekly to reproducibles, revising reproducibles to show work as actually installed.
 - .3 Use different colour waterproof ink for each service.
 - .4 Make available for reference purposes and inspection.
- .9 As-built drawings:
 - .1 Prior to start of Testing, Adjusting and Balancing for HVAC, finalize production of as-built drawings.
 - .2 Identify each drawing in lower right hand corner in letters at least 12 mm high as follows: - "AS BUILT DRAWINGS: THIS DRAWING HAS BEEN REVISED TO SHOW MECHANICAL SYSTEMS AS INSTALLED" (Signature of Contractor) (Date).
 - .3 Submit to Departmental Representative for approval and make corrections as directed.
 - .4 Perform testing, adjusting and balancing for HVAC using as-built drawings.
 - .5 Submit completed reproducible as-built drawings with Operating and Maintenance Manuals.
- .10 Submit copies of as-built drawings for inclusion in final TAB report.

1.2 QUALITY ASSURANCE

- .1 Quality Assurance: in accordance with Section 01 45 00 - Quality Control.
- .2 Health and Safety Requirements: do construction occupational health and safety in accordance with Section 01 35 29.06 - Health and Safety Requirements.

1.3 MAINTENANCE

- .1 Furnish spare parts in accordance with Section 01 78 00 - Closeout Submittals as follows:
 - .1 One filter cartridge or set of filter media for each filter or filter bank in addition to final operating set.

1.4 DELIVERY, STORAGE, AND HANDLING

- .1 Waste Management and Disposal:
 - .1 Construction/Demolition Waste Management and Disposal: separate waste materials for reuse and recycling in accordance with Section 01 74 21 - Construction/Demolition Waste Management and Disposal.

2 Products

2.1 MATERIALS

- .1 Do verification requirements in accordance with Section 01 47 17 - Sustainable Requirements: Contractor's Verification.

3 Execution

3.1 PAINTING REPAIRS AND RESTORATION

- .1 Prime and touch up marred finished paintwork to match original.
- .2 Restore to new condition, finishes which have been damaged.

3.2 CLEANING

- .1 Clean interior and exterior of all systems including strainers. Vacuum interior of ductwork and air handling units.

3.3 FIELD QUALITY CONTROL

- .1 Manufacturer's Field Services:
 - .1 Obtain written report from manufacturer verifying compliance of Work, in handling, installing, applying, protecting and cleaning of product and submit Manufacturer's Field Reports as described in PART 1 - SUBMITTALS.
 - .2 Provide manufacturer's field services consisting of product use recommendations and periodic site visits for inspection of product installation in accordance with manufacturer's instructions.
 - .3 Schedule site visits, to review Work, as directed in PART 1 - QUALITY ASSURANCE.

3.4 DEMONSTRATION

- .1 Departmental Representative will use equipment and systems for test purposes prior to acceptance. Supply labour, material, and instruments required for testing.
- .2 Supply tools, equipment and personnel to demonstrate and instruct operating and maintenance personnel in operating, controlling, adjusting, trouble-shooting and servicing of all systems and equipment during regular work hours, prior to acceptance.
- .3 Use operation and maintenance manual, as-built drawings, and audio visual aids as part of instruction materials.
- .4 Instruction duration time requirements as specified in appropriate sections.
- .5 Departmental Representative will record these demonstrations on video tape for future reference.

3.5 PROTECTION

- .1 Protect equipment and systems openings from dirt, dust, and other foreign materials with materials appropriate to system.

END OF SECTION

1 General

1.1 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submittals: in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Shop drawings to show:
 - .1 Mounting arrangements.
 - .2 Operating and maintenance clearances.
- .3 Shop drawings and product data accompanied by:
 - .1 Detailed drawings of bases, supports, and anchor bolts.
 - .2 Acoustical sound power data, where applicable.
 - .3 Points of operation on performance curves.
 - .4 Manufacturer to certify current model production.
 - .5 Certification of compliance to applicable codes.
- .4 In addition to transmittal letter referred to in Section 01 33 00 - Submittal Procedures: use MCAC "Shop Drawing Submittal Title Sheet". Identify section and paragraph number.
- .5 Closeout Submittals:
 - .1 Provide operation and maintenance data for incorporation into manual specified in Section 01 78 00 - Closeout Submittals.
 - .2 Operation and maintenance manual approved by, and final copies deposited with, Departmental Representative before final inspection.
 - .3 Operation data to include:
 - .1 Control schematics for systems including environmental controls.
 - .2 Description of systems and their controls.
 - .3 Description of operation of systems at various loads together with reset schedules and seasonal variances.
 - .4 Operation instruction for systems and component.
 - .5 Description of actions to be taken in event of equipment failure.
 - .6 Valves schedule and flow diagram.
 - .7 Colour coding chart.
 - .4 Maintenance data to include:
 - .1 Servicing, maintenance, operation and trouble-shooting instructions for each item of equipment.
 - .2 Data to include schedules of tasks, frequency, tools required and task time.
 - .5 Performance data to include:
 - .1 Equipment manufacturer's performance datasheets with point of operation as left after commissioning is complete.
 - .2 Equipment performance verification test results.
 - .3 Special performance data as specified.
 - .4 Testing, adjusting and balancing reports as specified in Section 23 05 93 - Testing, Adjusting and Balancing for HVAC.
 - .6 Approvals:
 - .1 Submit 2 copies of draft Operation and Maintenance Manual to Departmental Representative for approval. Submission of individual data will not be accepted unless directed by Departmental Representative.
 - .2 Make changes as required and re-submit as directed by Departmental Representative.

- .7 Additional data:
 - .1 Prepare and insert into operation and maintenance manual additional data when need for it becomes apparent during specified demonstrations and instructions.
- .8 Site records:
 - .1 Departmental Representative will provide 1 set of reproducible mechanical drawings. Provide sets of white prints as required for each phase of work. Mark changes as work progresses and as changes occur. Include changes to existing mechanical systems, control systems and low voltage control wiring.
 - .2 Transfer information weekly to reproducibles, revising reproducibles to show work as actually installed.
 - .3 Use different colour waterproof ink for each service.
 - .4 Make available for reference purposes and inspection.
- .9 As-Built drawings:
 - .1 Prior to start of Testing, Adjusting and Balancing for HVAC, finalize production of as-built drawings.
 - .2 Identify each drawing in lower right hand corner in letters at least 12 mm high as follows: - "AS BUILT DRAWINGS: THIS DRAWING HAS BEEN REVISED TO SHOW MECHANICAL SYSTEMS AS INSTALLED" (Signature of Contractor) (Date).
 - .3 Submit to Departmental Representative for approval and make corrections as directed.
 - .4 Perform testing, adjusting and balancing for HVAC using as-built drawings.
 - .5 Submit completed reproducible as-built drawings with Operating and Maintenance Manuals.
- .10 Submit copies of as-built drawings for inclusion in final TAB report.

1.2 QUALITY ASSURANCE

- .1 Quality Assurance: in accordance with Section 01 45 00 - Quality Control.
- .2 Health and Safety Requirements: do construction occupational health and safety in accordance with Section 01 35 29.06 - Health and Safety Requirements.

2 Products N/A

3 Execution

3.1 PAINTING REPAIRS AND RESTORATION

- .1 Prime and touch up marred finished paintwork to match original.
- .2 Restore to new condition, finishes which have been damaged.

3.2 FIELD QUALITY CONTROL

- .1 Manufacturer's Field Services:
 - .1 Obtain written report from manufacturer verifying compliance of Work, in handling, installing, applying, protecting and cleaning of product and submit Manufacturer's Field Reports as described in PART 1 - SUBMITTALS.

- .2 Provide manufacturer's field services consisting of product use recommendations and periodic site visits for inspection of product installation in accordance with manufacturer's instructions.
- .3 Schedule site visits, to review Work, as directed in PART 1 - QUALITY ASSURANCE.

3.3 DEMONSTRATION

- .1 Departmental Representative will use equipment and systems for test purposes prior to acceptance. Supply labour, material, and instruments required for testing.
- 2 Supply tools, equipment and personnel to demonstrate and instruct operating and maintenance personnel in operating, controlling, adjusting, trouble-shooting and servicing of all systems and equipment during regular work hours, prior to acceptance.
- .2 Use operation and maintenance manual, as-built drawings, and audio visual aids as part of instruction materials.
- .3 Instruction duration time requirements as specified in appropriate sections.
- .4 Departmental Representative will record these demonstrations on video tape for future reference.

3.4 PROTECTION

- .1 Protect equipment and systems openings from dirt, dust, and other foreign materials with materials appropriate to system.

END OF SECTION

1 General

1.1 REFERENCES

- .1 National Fire Prevention Association (NFPA)
 - .1 NFPA 13-2013, Standard for the Installation of Sprinkler Systems.

1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Provide manufacturer's printed product literature and data sheets, and include product characteristics, performance criteria, physical size, finish and limitations.
- .3 Shop Drawings:
 - .1 Submit drawings stamped and signed by professional engineer registered or licensed in Province of Nova Scotia, Canada.
 - .2 Indicate:
 - .1 Materials.
 - .2 Finishes.
 - .3 Method of anchorage
 - .4 Number of anchors.
 - .5 Supports.
 - .6 Reinforcement.
 - .7 Assembly details.
 - .8 Accessories.
- .4 Samples:
 - .1 Submit samples of following:
 - .1 Each type of sprinkler head.
 - .2 Signs.
- .5 Test reports:
 - .1 Submit certified test reports for wet pipe fire protection sprinkler systems from approved independent testing laboratories, indicating compliance with specifications for specified performance characteristics and physical properties.
- .6 Certificates:
 - .1 Submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
- .7 Manufacturers' Instructions:
 - .1 Provide manufacturer's installation instructions.
- .8 Field Quality Control Submittals:
 - .1 Manufacturer's Field Reports: manufacturer's field reports specified.

1.3 CLOSEOUT SUBMITTALS

- .1 Manufacturer's Catalog Data, including specific model, type, and size for:

- .1 Pipe and fittings.
- .2 Valves, including gate, check, and globe.
- .3 Sprinkler heads.
- .4 Pipe hangers and supports.
- .5 Mechanical couplings.
- .2 Drawings:
 - .1 Sprinkler heads and piping system layout.
 - .1 Prepare 760 mm by 1050 mm detail working drawings of system layout in accordance with NFPA 13, "Working Drawings (Plans)".
 - .2 Show data essential for proper installation of each system.
 - .3 Show details, plan view, elevations, and sections of systems supply and piping.
 - .4 Show piping schematic of systems supply, devices, valves, pipe, and fittings. Show point to point electrical wiring diagrams.
 - .2 Electrical wiring diagrams.
- .3 Design Data:
 - .1 Calculations of sprinkler system design.
 - .2 Indicate type and design of each system and certify that each system has performed satisfactorily in the manner intended for not less than 18 months.
- .4 Field Test Reports:
 - .1 Preliminary tests on piping system.
- .5 Records:
 - .1 As-built drawings of each system.
 - .1 After completion, but before final acceptance, submit complete set of as-built drawings of each system for record purposes.
 - .2 Submit 760 mm by 1050 mm drawings on reproducible Mylar film with title block similar to full size contract drawings.
- .6 Operation and Maintenance Manuals:
 - .1 Provide detailed hydraulic calculations including summary sheet, and Contractors Material and Test Certificate for aboveground and underground piping and other documentation for incorporation into manual in accordance with NFPA 13.

1.4 QUALITY ASSURANCE

- .1 Supply grooved joint couplings, fittings, valves, grooving tools and specialties from a single manufacturer. Use date stamped castings for coupling housings, fittings, valve bodies, for quality assurance and traceability.

1.5 MAINTENANCE MATERIAL SUBMITTALS

- .1 Extra Materials:
 - .1 Provide maintenance materials in accordance with Section 01 78 00 - Closeout Submittals.
 - .2 Provide spare sprinklers and tools in accordance with NFPA 13.

1.6 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements and with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements:
 - .1 Deliver materials to site in original factory packaging, labelled with manufacturer's name, address.
- .3 Storage and Protection:
 - .1 Store materials indoors in dry location.
 - .2 Store and protect materials from exposure to harmful weather conditions and at temperature and humidity conditions recommended by manufacturer.

2 Products

2.1 DESIGN REQUIREMENTS

- .1 Design automatic wet pipe fire suppression sprinkler systems in accordance with required and advisory provisions of NFPA 13, by for hydraulic calculations for uniform distribution of water over design area.
- .2 Include with each system materials, accessories, and equipment inside and outside building to provide each system complete and ready for use.
- .3 Design and provide each system to give full consideration to blind spaces, piping, electrical equipment, ducts, and other construction and equipment in accordance with detailed shop drawings.
- .4 Locate sprinkler heads in consistent pattern with ceiling grid, lights, and air supply diffusers.
- .5 Devices and equipment for fire protection service: ULC approved for use in wet pipe sprinkler systems.
- .6 Design systems for earthquake protection for buildings in seismic zones 3 and 4, and only essential and high risk buildings in seismic zone 2.
- .7 Location of Sprinkler Heads:
 - .1 Locate heads in relation to ceiling and spacing of sprinkler heads not to exceed that permitted by NFPA 13 for ordinary hazard occupancy
 - .2 Uniformly space sprinklers on branch.
- .8 Water Distribution:
 - .1 Make distribution uniform throughout the area in which sprinkler heads will open.
 - .2 Discharge from individual heads in hydraulically most remote area to be 100 % of specified density.
- .9 Density of Application of Water:
 - .1 Size pipe to provide specified density when system is discharging specified total maximum required flow.

- .10 Sprinkler Discharge Area:
 - .1 Area: hydraulically most remote m² area as defined in NFPA 13.
- .11 Friction Losses:
 - .1 Calculate losses in piping in accordance with Hazen-Williams formula with 'C' value of 120 for steel piping, 150 for copper tubing, and 140 for cement-lined ductile-iron piping.
- .12 Water Supply:
 - .1 Base hydraulic calculations on static pressure of kPa with lpm available at residual pressure of kPa at junction with water distribution piping system base of sprinkler piping riser.

2.2 ABOVE GROUND PIPING SYSTEMS

- .1 Provide fittings for changes in direction of piping and for connections.
 - .1 Make changes in piping sizes through tapered reducing pipe fittings, bushings will not be permitted.
- .2 Conceal piping in areas with suspended ceiling.

2.3 PIPE, FITTINGS AND VALVES

- .1 Pipe:
 - .1 Ferrous: to NFPA 13.
 - .2 Copper tube: to NFPA 13.
- .2 Fittings and joints to NFPA 13:
 - .1 Ferrous: screwed, welded, flanged or roll grooved.
 - .1 Grooved joints designed with two ductile iron housing segments, pressure responsive gasket, and zinc-electroplated steel bolts and nuts. Cast with offsetting angle-pattern bolt pads for rigidity and visual pad-to-pad offset contact.
 - .2 Copper tube: screwed, soldered, brazed, grooved.
 - .3 Provide threaded, grooved-end type fittings into which sprinkler heads, sprinkler head riser nipples, or drop nipples are threaded.
 - .4 Plain-end fittings with mechanical couplings and fittings which use steel gripping devices to bite into pipe when pressure is applied will not be permitted.
 - .5 Rubber gasketed grooved-end pipe and fittings with mechanical couplings are permitted in pipe sizes 32 mm and larger.
 - .6 Fittings: ULC approved for use in wet pipe sprinkler systems.
 - .7 Ensure fittings, mechanical couplings, and rubber gaskets are supplied by same manufacturer.
 - .8 Side outlet tees using rubber gasketed fittings are not permitted.
 - .9 Sprinkler pipe and fittings: metal.
- .3 Valves:
 - .1 ULC listed for fire protection service.
 - .2 Gate valves: open by counterclockwise rotation.
 - .3 Provide rising stem OS & Y wall indicator valve beneath each alarm valve in each riser when more than one alarm valve is supplied from same water supply pipe.

- .4 Check valves: flanged clear opening swing or spring actuated check type with flanged inspection and access cover plate for sizes 10 cm and larger.
- .4 Pipe hangers:
 - .1 ULC listed for fire protection services in accordance with NFPA.

2.4 SPRINKLER HEADS

- .1 General: to NFPA 13 and ULC listed for fire services.
- .2 Sprinkler Head Type:
 - .1 recessed polished chrome glass bulb type with ring and cup.
- .3 Provide nominal 1.2 cm orifice sprinkler heads.
 - .1 Release element of each head to be of intermediate temperature rating or higher as suitable for specific application.
 - .2 Provide polished stainless steel ceiling plates or chromium-plated finish on copper alloy ceiling plates, and chromium-plated pendent sprinklers below suspended ceilings.
 - .3 Provide corrosion-resistant sprinkler heads and sprinkler head guards in accordance with NFPA 13.
 - .4 Deflector: not more than 75 mm below suspended ceilings.

2.5 ESCUTCHEON PLATES

- .1 Provide one piece split hinge type metal plates for piping passing through walls, floors, and ceilings in exposed spaces.
- .2 Provide polished stainless steel plates chromium-plated finish on copper alloy plates in finished spaces.
- .3 Provide paint finish on metal plates in unfinished spaces.

3 Execution

3.1 MANUFACTURER'S INSTRUCTIONS

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheet.

3.2 INSTALLATION

- .1 Install, inspect and test to acceptance in accordance with NFPA 13.

3.3 PIPE INSTALLATION

- .1 Install piping straight and true to bear evenly on hangers and supports. Do not hang piping from plaster ceilings.

- .2 Keep interior and ends of new piping and existing piping thoroughly cleaned of water and foreign matter.
- .3 Keep piping systems clean during installation by means of plugs or other approved methods. When work is not in progress, securely close open ends of piping to prevent entry of water and foreign matter.
- .4 Inspect piping before placing into position.

3.4 FIELD QUALITY CONTROL

- .1 Site Test, Inspection:
 - .1 Perform test to determine compliance with specified requirements in presence of Departmental Representative.
 - .2 Test, inspect, and approve piping before covering or concealing.
 - .3 Preliminary Tests:
 - .1 Hydrostatically test each system at 200 psig for a 2 hour period with no leakage or reduction in pressure.
 - .2 Flush piping with potable water in accordance with NFPA 13.
 - .3 Piping above suspended ceilings: tested, inspected, and approved before installation of ceilings.
 - .4 Test alarms and other devices.
 - .5 Test water flow alarms by flowing water through inspector's test connection. When tests have been completed and corrections made, submit signed and dated certificate in accordance with NFPA 13.
 - .4 Formal Tests and Inspections:
 - .1 Do not submit request for formal test and inspection until preliminary test and corrections are completed and approved.
 - .2 Submit written request for formal inspection at least 15 days prior to inspection date.
 - .3 Repeat required tests as directed.
 - .4 Correct defects and make additional tests until systems comply with contract requirements.
- .2 Manufacturer's Field Services:
 - .1 Obtain written report from manufacturer verifying compliance of Work, in handling, installing, applying, protecting and cleaning of product and submit Manufacturer's Field Reports as described in PART 1 - ACTION AND INFORMATIONAL SUBMITTALS.
 - .2 Provide manufacturer's field services consisting of product use recommendations and periodic site visits for inspection of product installation in accordance with manufacturer's instructions.
 - .3 Schedule site visits, to review Work, as directed in PART 1 - QUALITY ASSURANCE.

3.5 CLEANING

- .1 Clean in accordance with Section 01 74 11 - Cleaning.
 - .1 Remove surplus materials, excess materials, rubbish, tools and equipment.

END OF SECTION