

Part 1 General

1.1 References

- .1 American Society of Heating, Refrigeration and Air-Conditioning Engineers (ASHRAE)
 - .1 ASHRAE 90.1, Energy Standard for Buildings except Low-Rise Residential Buildings
- .2 Electrical Equipment Manufacturers' Advisory Council (EEMAC)
- .3 Canadian Standards Association (CSA)
 - .1 CAN/CSA-C22.2 No. 100, Motors and Generators
 - .2 CAN/CSA-C747, Energy Efficiency for Single- and Three-Phase Small Motors
 - .3 CAN/CSA-C390, Energy Efficiency Test Methods for Three-Phase Induction Motors
- .4 Underwriter's Laboratories of Canada (ULC)
- .5 SMACNA
 - .1 HVAC Air Duct Leakage Test Manual
 - .2 HVAC Duct Construction Standards – Metal and Flexible

1.2 Regulatory Requirements

- .1 Refer carefully to other parts of the specifications.
- .2 Conform to the requirements and recommendations of all local municipal, provincial and federal codes, by-laws and ordinances.
- .3 Do not reduce the quality of work specified and/or shown on the drawings because of the Regulatory requirements.

1.3 Applicable Codes And Standards

- .1 In general and as applicable, the physical and chemical properties, the characteristics and the performance of items in this Division shall be as noted in the following:
 - .1 Canadian Standards Association.
 - .2 American National Standards Institute.
 - .3 National Building Code of Canada
 - .4 National Plumbing Code of Canada
 - .5 National Fire Code of Canada
 - .6 Occupational Health and Safety Act
 - .7 Worker's Compensation Board Requirements.
 - .8 American Society for Testing and Materials.
 - .9 Canadian Government Specifications Board.
 - .10 National Fire Protection Association.

- .11 Canadian Council of Ministers of the Environment Codes.
- .12 Underwriters' Laboratories of Canada.

1.4 Latest Editions

- .1 The latest edition of all codes and standards, of the date of tender submission, shall apply; except for specific editions referenced by overriding codes.

1.5 Action And Informational Submittals

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for specified equipment and include product characteristics, performance criteria, physical size, finish and limitations.
- .3 Shop drawings:
 - .1 Submit drawings stamped and signed by professional engineer registered or licensed in the Province where work is taking place.
 - .2 Drawings to show:
 - .1 Mounting arrangements.
 - .2 Operating and maintenance clearances.
 - .3 Drawings and product data accompanied by:
 - .1 Detailed drawings of bases, supports, and anchor bolts.
 - .2 Acoustical sound power data, where applicable.
 - .3 Points of operation on performance curves.
 - .4 Manufacturer to certify current model production.
 - .5 Certification of compliance to applicable codes.
 - .4 In addition to transmittal letter referred to in Section 01 33 00 - Submittal Procedures: use MCAC "Shop Drawing Submittal Title Sheet". Identify section and paragraph number.

1.6 QUALITY ASSURANCE

- .1 Pre-Installation Meeting:
 - .1 Convene pre-installation meeting one week prior to beginning on-site installations
 - .1 Verify project requirements.
 - .2 Review installation and substrate conditions.
 - .3 Co-ordination with other building subtrades.
 - .4 Review manufacturer's installation instructions and warranty requirements.
- .2 Health and Safety:
 - .1 Do construction occupational health and safety in accordance with Section 01 35 29.06 - Health and Safety Requirements.

1.7 Authorities Having Jurisdiction (Ahj)

- .1 Comply with all requirements of Authorities with competent jurisdiction, AHJ, including authorized inspectors, without additional compensation.

1.8 Permits, Fees And Certificates

- .1 In addition to the requirements in Division 01, obtain all required Certificates of Inspection for the work and deliver same to the Departmental Representative before request for substantial performance. These include but are not limited to:
 - .1 Equipment start-up reports.
 - .2 Fire, smoke, and combination fire/smoke damper test reports.
- .2 Correct installed work as directed by the local Authorized Inspector of the Regulatory body without extra compensation.

1.9 Equipment List

- .1 Compile a complete list of HVAC equipment and materials to be used on this project and forming part of tender documents by adding manufacturer's name, model number and details of materials, and submit for approval.
- .2 Submit for review within ten (10) days after award of contract.

1.10 Specified Equipment Availability

- .1 If specified equipment is not available (due to delays in delivery) at scheduled installation time an acceptable alternate shall be installed AT THE CONTRACTOR'S EXPENSE and replaced with the specified equipment when the specified equipment becomes available with no additional compensation.

1.11 Electrical Work

- .1 Division 23 is responsible for the supply, physical installation, and operation of all electric motors, temperature and humidity controls systems, combustion controls systems, and other electrical devices and systems specified under its portion of the work. Bear full responsibility for factory installed wiring and equipment on packaged equipment, be responsible where detailed in equipment requirements for controlling devices such as, but not restricted to, pump and liquid level controls, multi-speed motor controllers, boiler controls, etc., which are necessarily integrally mounted on packaged equipment.
- .2 Submit detailed composite wiring diagrams for all control systems as specified and as required for the HVAC work for review by the Departmental Representative. Distribute copies of reviewed drawings to the Electrical Division for their reference.
- .3 Provide all wiring in approved rigid conduit to suit temperature and moisture conditions of area through which wire is to run. All wiring is in accordance with the relevant Electrical Codes, and in no case smaller than #12 AWG. Comply fully with the electrical specifications for all electrical work.

1.12 Electrical Characteristics

- .1 Check with the electrical trade and provide all mechanical items with correct electrical characteristics to suit the electrical work.

- .2 If correct characteristics are not available from the specified equipment manufacturer, contact the Departmental Representative prior to the close of tenders.
- .3 At time of ordering HVAC equipment, confirm electrical characteristics with the electrical contractor, and ensure that they have been confirmed with the power authority.
- .4 No additional compensation will be paid for problems arising from incorrect electrical characteristics.

1.13 Cutting, Patching, Repairing, Making Good

- .1 In addition to the requirements in Division 01, each trade requiring such work shall be responsible for necessary cutting. Patching by appropriate trade. All work to be performed by experienced tradesmen.
- .2 Neatly perform cutting and patching work to blend smoothly with surrounding surfaces.
- .3 Patch and make good disturbed surfaces to match existing adjacent work. Leave finished, neat, to Departmental Representative's approval.
- .4 Perform X-ray examination of wall and floors prior to making openings, where required to avoid damage to structural reinforcements and electrical conduits.

1.14 Tests

- .1 In addition to the requirements in Division 01, carry out all tests hereinafter noted, as required by the regulatory agencies and as requested by the Departmental Representative and furnish all labour and equipment required for such tests without extra compensation.
- .2 Before activating systems, recheck equipment, check all connections, set all controls for proper start-up, obtain necessary clearances from the electrical division, etc.
- .3 Submit to the Departmental Representative, legible report for all tests conducted, within one week of the test.
- .4 Notify the Departmental Representative at least two (2) working days ahead of all tests, so that the tests can be witnessed on a random basis.

1.15 Trial Usage

- .1 Departmental Representative may use equipment and systems for test purposes prior to acceptance. Supply labour, material, and instruments required for testing.

1.16 Functional Testing

- .1 Test all HVAC equipment, devices and systems. Test as required by the AHJ and Departmental Representative, submitting comprehensive reports. Example forms are available from the Departmental Representative.
- .2 Ensure all tests demonstrate compliance with the specified and manufacturers' shop drawing and catalogued performance, as well as compliance with applicable standards.

1.17 Demonstration And Operating And Maintenance Instructions

- .1 In addition to the requirements in Division 01, supply tools, equipment and personnel to demonstrate and instruct operating and maintenance personnel in operating, controlling, adjusting, trouble-shooting and servicing of all systems and equipment during regular work hours, prior to acceptance.
- .2 Manufacturers, or expert suppliers, to provide demonstrations and instructions.
- .3 Use operation and maintenance manual, as-built drawings, audio visual aids, etc. as part of instruction materials.
- .4 Instruction duration time requirements as specified in appropriate sections.
- .5 Where deemed necessary, Departmental Representative or Owner may record these demonstrations on videotape for future reference.
- .6 Submit training schedule and scope description to the Departmental Representative for review and approval for each training topic. Training shall not commence until approval of training schedule and scope if given by the Departmental Representative.

1.18 Spare Parts

- .1 Furnish spare parts in accordance with Section 01 78 00 - Closeout Submittals and as follows:
 - .1 Two set of filter media/cartridges, for each filter or filter bank in addition to final operating set.
 - .2 Two set of belts for each piece of belt-driven equipment.

1.19 Special Tools

- .1 Provide one set of special tools required to service equipment in accordance with Section 01 78 00 - Closeout Submittals and as recommended by manufacturers.
- .2 Furnish one commercial quality grease gun, grease and adapters to suit different types of grease and grease fittings.

1.20 Closeout Submittals

- .1 Submit in accordance with Section 01 78 00 - Closeout Submittals.
- .2 Operation and Maintenance Data: submit operation and maintenance data for incorporation into manual.
 - .1 Operation and maintenance manual approved by, and final copies deposited with, Departmental Representative before final inspection.
 - .2 Operation data to include:
 - .1 Control schematics for systems including environmental controls.
 - .2 Description of systems and their controls.
 - .3 Description of operation of systems at various loads together with reset schedules and seasonal variances.
 - .4 Operation instruction for systems and component.
 - .5 Description of actions to be taken in event of equipment failure.
 - .6 Valves schedule and flow diagram.
 - .7 Colour coding chart.

- .3 Maintenance data to include:
 - .1 Servicing, maintenance, operation and trouble-shooting instructions for each item of equipment.
 - .2 Data to include schedules of tasks, frequency, tools required and task time.
- .4 Performance data to include:
 - .1 Equipment manufacturer's performance datasheets with point of operation as left after commissioning is complete.
 - .2 Equipment performance verification test results.
 - .3 Special performance data as specified.
 - .4 Testing, adjusting and balancing reports as specified in Section 23 05 93 - Testing, Adjusting and Balancing for HVAC.
- .5 Approvals:
 - .1 Submit 2 copies of draft Operation and Maintenance Manual to Departmental Representative for approval. Submission of individual data will not be accepted unless directed by Departmental Representative.
 - .2 Make changes as required and re-submit as directed by Departmental Representative.
- .6 Additional data:
 - .1 Prepare and insert into operation and maintenance manual additional data when need for it becomes apparent during specified demonstrations and instructions.
- .7 Site records:
 - .1 Departmental Representative will provide 1 set of reproducible mechanical drawings. Provide sets of white prints as required for each phase of work. Mark changes as work progresses and as changes occur.
 - .2 Transfer information weekly to reproducibles, revising reproducibles to show work as actually installed.
 - .3 Use different colour waterproof ink for each service.
 - .4 Make available for reference purposes and inspection.
- .8 As-built drawings:
 - .1 Prior to start of Testing, Adjusting and Balancing for HVAC, finalize production of as-built drawings.
 - .2 Identify each drawing in lower right hand corner in letters at least 12 mm high as follows: - "AS BUILT DRAWINGS: THIS DRAWING HAS BEEN REVISED TO SHOW MECHANICAL SYSTEMS AS INSTALLED" (Signature of Contractor) (Date).
 - .3 Submit to Departmental Representative for approval and make corrections as directed.
 - .4 Perform testing, adjusting and balancing for HVAC using as-built drawings.
 - .5 Submit completed reproducible as-built drawings with Operating and Maintenance Manuals.

- .9 Submit copies of as-built drawings for inclusion in final TAB report.

1.21 Maintenance Material Submittals

- .1 Submit in accordance with Section 01 78 00 - Closeout Submittals.
- .2 Provide one set of special tools required to service equipment as recommended by manufacturers.
- .3 Furnish one commercial quality grease gun, grease and adapters to suit different types of grease and grease fittings.

1.22 Delivery, Storage And Handling

- .1 Deliver, store and handle materials in accordance with Section with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
 - .1 Store materials indoors in dry location and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Replace defective or damaged materials with new.
- .4 Develop Construction Waste Management Plan related to Work of this Section.
- .5 Packaging Waste Management: remove for reuse as specified in Construction Waste Management Plan.

1.23 Substantial Completion / Certification By Engineer / Life Safety Submissions

- .1 Provide minimum notice of ten (10) working days to the Departmental Representative prior to request to declare project substantially complete. Failure to do so may result in site review by Engineer being delayed.
- .2 In addition to the requirements of Division 01 submit the following (as applicable) a minimum of five (5) working days ahead of required proposed date of substantial completion (unless a longer period of time is dictated by Authorities Having Jurisdiction):
 - .1 All certificates and documentation required by Authorities Having Jurisdiction.
 - .2 Fire and smoke damper test reports.
 - .3 Smoke exhaust/management systems commissioning reports
 - .4 Equipment start-up reports.
 - .5 Control systems commissioning reports pertaining to equipment/systems required for life safety system operation (i.e. ventilation interlocks/unit operation, CO detection/exhaust systems, etc.).
 - .6 Test reports for backflow prevention devices with test taps.
 - .7 Written confirmation that propane system is approved by the utility and/or Authority Having Jurisdiction, and turned on.
 - .8 Record ('As-Built') drawings.
 - .9 Operation and Maintenance Manuals, complete with revisions as directed.

- .10 Written confirmation that all life safety and health systems are fully functional, including but not limited to ventilation, both supply and exhaust.
- .11 Written confirmation that all HVAC equipment is operational and under control, indicating exceptions and temporary controls/arrangements.
- .12 All other life safety and health reports and certificates.
- .3 Confirm, in writing, systems are ready for occupancy and use for intended purpose in every respect.
- .4 Before certification date submit detailed written confirmation of completion of deficient life safety work noted in the documentation listed above, including date completed.
- .5 Before certification date submit detailed written confirmation of completion of deficient non-life safety work, including that noted in Departmental Representative reports, listing each deficient item. Submit schedule for completion of all deficient non-life safety work that will not be completed prior to the certification date, listing each deficient item for consideration.
- .6 These requirements apply to each phase of a phased project.

1.24 Fan Connections

- .1 Inlet and discharge conditions are critical to proper fan performance. Review proposed fan installations and ensure that proper conditions are provided; add straightening vanes or turning vanes where required.
- .2 In general, provide a minimum of three (3) wheel diameters of straight duct immediately upstream of the fan inlet.
- .3 Review special cases with the Departmental Representative and TAB Contractor prior to installation.

Part 2 Products

2.1 Motors

- .1 Motors to be high efficiency, in accordance with local Hydro company standards and the requirements of ASHRAE 90.1.
- .2 Comply with all Canadian Electrical Code requirements, and in particular CSA C22.2 No. 100, c/w CSA label, unless otherwise specified.
- .3 Motors included in the scope of CAN/CSA-C747 shall have a nominal full-load efficiency not less than the minimum specified in that standard. Efficiency ratings of motors included in the scope of this standard shall be based on a statistically valid quality control procedure conforming to the standard. Nameplates shall list the nominal full-load motor efficiency.
- .4 Motors included in the scope of CAN/CSA-C390 shall have a nominal full-load efficiency not less than the minimum specified in that standard. Efficiency ratings of motors included in the scope of this standard shall be based on a statistically valid quality control procedure conforming to the standard. Nameplates shall list the nominal full-load motor efficiency.

- .5 In general, motors are EEMAC Class B (for standard torque applications), 1,800 RPM, continuous duty, open drip proof, ball bearing, 40°C temperature rise above 40°C ambient, 1.15 service factor. Motors are squirrel cage induction unless specifically noted otherwise. Special motors are specified with the equipment driven.
- .6 Single-phase motors shall be equipped with integral thermal overload protection.
- .7 Provide adequate capacity on each motor to operate the associated driven device under all conditions of load and service without overloading and be of at least the power specified.
- .8 Refer to Division 26 and provide motor characteristics within +5% of power source, or get written approval from the Departmental Representative.
- .9 Co-operate with Division 26 during start-up and provide all necessary assistance in commissioning.
- .10 Acceptable motor manufacturers may be listed under the Section 23 05 03 – Acceptable HVAC Manufacturers/Contractors.
- .11 If delivery of specified motor will delay delivery or installation of equipment, install motor approved by Departmental Representative for temporary use. Final acceptance of equipment will not occur until specified motor is installed.

2.2 Coupling For Direct Drive Equipment

- .1 Couplings shall be sized such that it will endure an infinite number of starts when equipment is fully loaded. All couplings shall be covered with a removable safety guard.

2.3 Belt Drives

- .1 Fit reinforced belts in sheave matched to drive. Multiple belts to be matched sets.
- .2 Use cast iron or steel sheaves secured to shafts with removable keys unless otherwise specified.
- .3 For motors under 7.5 kW: standard adjustable pitch drive sheaves, having plus or minus 10% range. Use mid-position of range for specified r/min.
- .4 For motors 7.5 kW and over: sheave with split tapered bushing and keyway having fixed pitch unless specifically required for item concerned. Provide sheave of correct size to suit balancing.
- .5 Correct size of sheave to be determined during commissioning.
- .6 Minimum drive rating: 1.5 times nameplate rating on motor. Keep overhung loads within manufacturer's design requirements on prime mover shafts.
- .7 Motor slide rail adjustment plates to allow for centre line adjustment.
- .8 Supply one set of spare belts for each set installed.

2.4 Guards

- .1 Provide guards for all drives as specified and required by Authorities Having Jurisdiction.
- .2 Guards for belt drives (minimum requirements):

- .1 Expanded galvanized metal screen welded to galvanized steel frame.
- .2 Minimum 1.2 mm thick galvanized sheet metal tops and bottoms.
- .3 Prime coat for painting.
- .4 38 mm diameter holes on both shaft centres for insertion of tachometer.
- .5 Allow movement of motors for adjusting belt tension.
- .3 Guards for flexible couplings (minimum requirements):
 - .1 "U" shaped, minimum 1.6 mm thick galvanized mild steel.
 - .2 Prime coat for painting.
- .4 Guards are to be readily removable to permit servicing of equipment.
- .5 Provide means to permit lubrication and use of test instruments with guards in place.
- .6 Ensure that all guards are securely fastened in place, sufficiently sturdy to provide the required safety and free of rattles and excess vibration.

2.5 Fire Separation Repair

- .1 Refer to Section 07 84 00 – Firestopping.
- .2 Cooperate fully with other trades to ensure maintenance of the rating of fire separations that are penetrated, in strict compliance with the manufacturer's recommendations and requirements of the AHJ.

2.6 Accessibility

- .1 Refer to Section 10 90 00 – Miscellaneous Specialties for access door specification.
 - .1 Standard Type:
 - .1 Door and Trim: 14 gauge steel. Trim 1-1/2 inches wide.
 - .2 Return Frame: 18 gauge steel. Depth 1-3/4 inches.
 - .3 Hinges: Fully-concealed. Opens 170 degrees. On long side of door. Number of hinges
 - .4 varies with size of door.
 - .5 Latches: Flush, stainless steel cam-operated with screwdriver. Positioned opposite hinge
 - .6 and at top and bottom on larger sizes.
 - .7 Finish: Electrostatically-applied, baked grey enamel coat over rust-inhibiting phosphate
 - .8 treated steel.
 - .9 Masonry Anchor Straps: Minimum of 4 straps per door, where required
 - .10 Cylinder Lock: Keyed alike with 2 keys per lock.
 - .11 Gaskets: Weather-resistant and air-tight neoprene gaskets.
 - .2 Fire Rated Type:
 - .1 UL Listed: rating to match assembly being installed in, 250 degrees C (450 degrees F) maximum temperature rise in 30 minutes for vertical wall installations.
 - .2 Frame: 16 gauge steel, 2 1/2 inches deep.

- .3 Insulation: 2 inches thick mineral wool in between 2 pieces of 22 gauge steel.
- .4 Hinge: Continuous piano hinge allows opening to 180 degrees. Hinge is on long side of door.
- .5 Latches: Specially designed Ultra Lock-self-latching keyed cylinder paddle latch opposite hinge.
- .6 Automatic panel closer on all doors. Vertical position only. Ceiling position has self-assisted closing.
- .7 Inside panel release on all doors.
- .8 rust-inhibiting phosphate treated steel. This coating can be used as a finish or as a prime coat.
- .9 Finish: Electrostatically-applied, baked grey enamel coat over rust-inhibiting phosphate treated steel.
- .10 Hot smoke seal gasketing for 4 sides.
- .2 Be responsible for supplying and locating all access panels in the ceiling, wall, partitions, etc., where openings are necessary for the inspection, servicing and/or removal of equipment, valves and other items that require periodic access. Panel type to suit the construction of the ceilings, walls, partitions, etc., in which they are located. Determine the location subject to the approval of the Departmental Representative. Access panels to be installed by trade experienced in work with surface in which the panel is to be installed.
- .3 Mark mechanical access points in accessible ceilings with distinctive but inconspicuous tags properly attached to the ceiling grid. Obtain sample approval before purchase and installation. Indicate on record drawings.
- .4 Accessibility shall be defined as:
 - .1 Ability to place both hands on equipment or device, with no duct, pipe or other equipment in the way.
 - .2 Must be accessible while standing on maximum 2400 mm high stepladder.
 - .3 Must be in plain view.
- .5 Mark mechanical access points in accessible ceilings with distinctive but inconspicuous tags properly attached to the ceiling grid. Obtain sample approval before purchase and installation. Indicate on record drawings.

2.7 Sleeves And Penetrations

- .1 Install sleeves for all piping passing through floors and walls.
- .2 Sleeves as specifically noted, or through structural walls shall be Schedule 40 steel. All other sleeves are 6 mm galvanized sheet steel.
- .3 Fit sleeves flush on either side of the wall through which they pass, extend sleeves through floors and terminate 50 mm above finished floor. Adjust as necessary to accommodate the requirements of through-penetration fire-stopping systems.
- .4 Where passing through walls, make sleeves a minimum 6 mm clear of the piping, through floors make sleeves a minimum of 20 mm clear of the piping. Pack for full depth with fiberglass insulation & finish with a lagging compound. Penetrations through fire separations shall be repaired to maintain rating.

- .5 Provide escutcheon plates with setscrews to completely cover openings for all exposed pipes passing through walls, subject to the approval of the Departmental Representative. Provide chrome-plated plates in finished areas unless otherwise approved.
- .6 Be responsible for maintaining integrity of building envelope when making penetration to install equipment or devices. Enlist services of qualified trade to make openings in and/or repairs to building envelope.
- .7 Sleeving through steel beams shall be permitted only where approved by the Departmental Representative in writing or where expressly indicated on the Contract Documents. Sleeves are NOT permitted in concrete beams.
- .8 Seal all sleeves to make watertight.

2.8 Counter Flashings

- .1 In addition to the requirements in Division 01, provide watertight, non-corroding, counter flashings for all penetrations of the building envelope, painted to match adjacent materials after proper preparation and painting. Refer to drawings, including building drawings, for additional information.
- .2 Installation to allow for movement and accommodate high temperatures where necessary.
- .3 For short pipes, the flashing may overlap the end, in lieu of attachment to the pipe. Minimum 300 mm high above the roof, c/w water break above maximum water level on the roof, to negate wind effects.
- .4 All galvanized material to be 0.7 mm thick minimum.
- .5 In exposed locations, flashings must be aesthetically acceptable to the Departmental Representative.
- .6 Co-ordinate with all other trades including roofer and metal wall panel installer.
- .7 For copper pipe use 0.82 mm sheet copper, soldered to pipe end c/w solder joints.
- .8 For galvanized ducts use galvanized sheet metal soldered to the duct and c/w soldered joints.
- .9 For cast iron and steel pipes at normal temperature, use manufactured stretch fit heavy neoprene flashings c/w galvanized protective layer.
- .10 For hot pipes clamp galvanized to the pipe with a temperature rated gasket and stainless steel worm gear clamp.
- .11 For aluminum and stainless steel, use the same materials for the flashing.
- .12 For manufactured hoods, fans and rooftop unit mounting, apply a low density neoprene gasket all around and fasten securely.

Part 3 Execution

3.1 General

- .1 All Drawings are diagrammatic and indicate the general arrangement of systems and work included in the Contract. Do not scale the Drawings. Consult the Architectural

Drawings and details for exact locations of fixtures and equipment; where some are not definitely located, obtain this information from the Departmental Representative.

- .2 Follow Drawings as closely as possible in laying out work and check Drawings of all other trades to verify spaces in which work will be installed. Maintain maximum headroom and space conditions at all points. When headroom or space conditions appear inadequate, notify the Departmental Representative before proceeding with the installation.
- .3 Make reasonable modifications in the layout as needed without extra compensation to prevent conflicts with work of other trades or for proper execution of the work. This shall include, but not necessarily be confined to, offsets in piping or ducts, transformation in ductwork and relocation of ducts and piping up to 3.0 m either way on each item as required to suit on site job conditions.
- .4 Where variances occur between the Drawings and Specifications or within either document itself, include in the contract, the item or arrangement of better quality, greater quantity, and higher cost or clarify before tenders close. The final decision on the item and manner in which work is installed rests with the Departmental Representative.
- .5 Provide, with all trades involved, marked-up drawings, when requested, of mechanical spaces indicating all dimensions for all installations prior to the work being done. Report any discrepancies to the Departmental Representative. Any conflicts arising that may have been resolved by laying the work out in this manner will be resolved WITHOUT ADDITIONAL COMPENSATION.
- .6 Provide 48 hours minimum notice to Departmental Representative and Owner of all work before it is concealed. Expose concealed work for inspection, upon request, when proper notice was not provided and pay all costs therefore, including making good other trades' work.

3.2 Surveys And Measurements

- .1 Base all measurements, both horizontal and vertical from established bench marks. All work shall agree with these established lines and levels. Verify all measurements shown on the Drawings at the site, and check the correctness of same as related to the work.
- .2 Notify the Departmental Representative if any discrepancy is discovered between the actual measurements and those indicated which prevent following good practice or the intent of the Drawings & Specifications. Do not proceed with the work until receiving instructions from the Departmental Representative.

3.3 Co-Ordination

- .1 Give full co-operation to those doing work under other Divisions of the specifications and furnish in writing with copies to the Departmental Representative any information necessary to permit the work of all Divisions to be installed satisfactorily and with least possible interference or delay.
- .2 Discuss work with other Divisions prior to installation. Confirm proposed locations for equipment installed by this Division will not interfere with work installed by others.

- .3 If work is installed before coordinating with other trades or so as to interfere with work of other trades, make necessary changes in the work to correct the conditions without extra compensation.
- .4 When requested, provide marked up drawings indicating required clearances for installation of plumbing equipment. Provide section drawings indicating location of other equipment not installed by Division 23, such as other equipment and piping,, cable trays, etc. Report any discrepancies to the Departmental Representative.

3.4 Accessibility

- .1 Locate all equipment that must be serviced, operated or maintained in fully accessible positions, with minimum interference and maximum usable space. If required for better accessibility, furnish access doors for this purpose. Make deviations from Drawings to allow for good accessibility, obtaining prior approval for changes of magnitude.

3.5 Scaffolding, Rigging, Hoisting

- .1 Unless otherwise specified, furnish all scaffolding, rigging, hoisting and services necessary for erection and delivery into the premises of any equipment apparatus furnished. Remove same from the premises when no longer required.
- .2 Take precautions not to overload the structure in any manner nor provide inadequate scaffolding and rigging so as to endanger the safety of personnel on the site whether under this Division's employ or otherwise.

3.6 Cutting And Patching

- .1 Cutting shall be performed neatly by this trade. No hammering or other methods are permitted without approval of the Departmental Representative and other trades affected. Utilize a rebar detector and stud finder to ensure cutting does not damage other elements.
- .2 Patching is to be done by the appropriate trade. Arrange and pay for all patching not specifically specified elsewhere in these specifications, including fire rated patching at fire separations.
- .3 Fill voids around pipes and ducts with fiberglass batt insulation and sheet metal closure strips. For fire separations, install fire stop material in accordance with manufacturer's details as required to meet the UL classification and to match separation rating. Ventilate adequately during curing. Provide adequate structural support in larger spaces. Install slightly above floors to provide positive drainage away from pipe or duct.
- .4 Provide a structural shop drawing stamped by a Professional Engineer showing all reinforcements required for openings through the structure. Allow for all costs of the reinforcement.

3.7 Supports

- .1 Provide all necessary and recommended supports for all equipment furnished under this Division. Co-ordinate and facilitate all necessary and recommended foundations, pads, bases and piers provided under other Divisions for equipment furnished or installed under this Division.

3.8 Waterproofing

- .1 Obtain approval for the installation method employed where any work pierces waterproofing concrete and waterproofing. Furnish all necessary grout rings sleeves, caulking, curbs, counter flashing and flashing required to make openings through roofs, walls, floors, etc., absolutely watertight. This applies to, but is not restricted to, roof exhausters, relief vents, penthouses, ducts, grilles, pipes, etc. Work involving the roofing is done in conjunction with the roofing Division. Work passing through roofing is to be done in accordance with applicable C.R.C.A. "FL" Series details.

3.9 Protection

- .1 Protect the work and material of all other sections from damage and make good all damage thus caused, to the satisfaction of the Departmental Representative.
- .2 Protect equipment and systems openings from dirt, dust, and other foreign materials with materials appropriate to system.

3.10 Examination

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for installation in accordance with manufacturer's written instructions.
 - .1 Visually inspect substrate.
 - .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.
 - .3 Proceed with installation only after unacceptable conditions have been remedied.

3.11 Painting Repairs And Restoration

- .1 Do painting in accordance with Section 09 91 23 - Interior Painting.
- .2 Prime and touch up marred finished paintwork to match original.
- .3 Restore to new condition, finishes which have been damaged.

3.12 System Cleaning

- .1 Clean interior and exterior of all systems including strainers.
- .2 Duct Cleaning:
 - .1 Applicable to systems within the area of work and systems that may be affected by the work taking place in this project.
 - .1 Isolate all systems exterior to the area of work where possible.
 - .2 Thoroughly clean all new and existing ductwork.
 - .3 Segregate points of access to fan chambers, plenums, larger diameter ducting etc. from adjacent occupied areas.
 - .4 Supply and install access doors in ductwork, plenums, etc. at locations required to complete work specified.
 - .5 Work shall include the cleaning of plenums, diffusers, air handling units, fans and all other mechanical equipment which combined forms part of the

buildings ventilation system. This shall include, but not limited to the following:

- .1 Interior surfaces of all ductwork
- .2 Interior surfaces of air handling units to include but not limited to plenums, fan(s), fan chambers, coils, dampers, filters, motor(s), louvres, etc.
- .3 Surfaces of coils, dampers, louvres, turning vanes, diffusers, registers, grilles and all other equipment present with or which forms part of the air systems
- .6 Provide drop sheet beneath all points where access to ducting or equipment will be made.
- .7 Seal openings in ducting and equipment using polyethylene and tape to prevent the spread of dust and to assist in establishing negative pressure.
- .8 Ensure each branch line is cleaned from each diffuser or grill, along with the entire length of the duct back to the main inclusive.
- .9 Portable vacuum system may only be used on ducting with a circumference less than 48 in or less; use truck mounted vacuum system on ducting with larger circumference.
- .10 Coils, fan blades, etc. shall be pressure washed with non toxic, non corrosive approved detergent germicide solution applied with low volume, high pressure wash unit. In addition, coils will be brushed, scraped and vacuumed as necessary.
- .11 Dust and film build-up shall be cleaned from all surfaces of the building ventilation system which come into contact with circulating air.
- .12 Provide necessary access openings in ductwork at locations required to complete the work. Repair openings following completion of work as follows:
 - .1 Access holes smaller than 10"x10" shall be re-sealed in an airtight manner using 24 gauge cross broken sheet metal, sheet metal screws and duct sealant.
 - .2 Supply and install specified access doors to re-seal openings greater than 12"x12".
- .13 Establish negative pressure within system prior to and throughout the cleaning process.
- .14
- .15 Schedule work following the complete of all work by other trades that may generate airborne construction debris. Ensure work of this section is completed prior to starting or testing of building systems.
- .16 Ensure electrical power supply to all air handling equipment is locked out and tagged. System to remain inoperable during cleaning process
- .17 Use of compressed air to aid the cleaning process is only permitted where access by the worker is not possible and the use can safely be controlled by the worker from the exterior of the ducting. Use of compressed air by a worker or while a worker is present within larger diameter ducting, air handler, plenums, etc is prohibited for safety reasons.

3.13 Field Quality Control

- .1 Site Tests: conduct following tests in accordance with Section 01 45 00 - Quality Control and submit report.
- .2 Manufacturer's Field Services:
 - .1 Obtain written report from manufacturer verifying compliance of Work, in handling, installing, applying, protecting and cleaning of product and submit Manufacturer's Field Reports.
 - .2 Provide manufacturer's field services consisting of product use recommendations and periodic site visits for inspection of product installation in accordance with manufacturer's instructions.

3.14 Cleaning

- .1 Progress Cleaning: clean in accordance with Section 01 74 11 – Cleaning.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 - Cleaning.
- .3 Waste Management: separate waste materials for reuse and recycling.
 - .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

3.15 Protection

- .1 Protect equipment and systems openings from dirt, dust, and other foreign materials with materials appropriate to system.

3.16 Equipment Start-Up

- .1 HVAC contractor shall ensure that all electrical/HVAC components match and that it is safe to start-up HVAC equipment.
- .2 All support such as electrical contractor, controls contractor, etc., shall be arranged by the mechanical and all trades directly involved in equipment being started shall be present for start-up.

3.17 Manufacturers' Recommendations

- .1 Install, adjust, test, start-up, and maintain all equipment in strict accordance with the manufacturer's recommendations. If in conflict with the drawings and specifications, contact the Departmental Representative for clarification.
- .2 Ensure that the manufacturer recommends the product for its intended use. If in doubt, contact the Departmental Representative.

3.18 Personnel Protection

- .1 In addition to the requirements in Division 01, provide visual warning signs and/or markers and mechanical protection devices for all mechanical items mounted below the minimum limits listed below and suspended more than 1500mm clear of the floor.
 - .1 Occupied spaces 2286 mm (7'-6").

- .2 Service spaces 2133 mm (7'-0").
- .3 Crawl spaces 1524 mm (5'-0").
- .2 Visual warning devices to be yellow tape with black stripes adhered to the entire perimeter of the item infringing on the occupied space. This will include but not be limited to:
 - .1 Length of pipes or equipment below specified height.
- .3 Mechanical protection devices to be 7 mm (1/4") wire mesh guard and/or 25 mm thick 'Armaflex' type insulation. This will include but not be limited to:
 - .1 Pipe and equipment hangers.
 - .2 Valves.

END OF SECTION

Part 1 General

1.1 References

- .1 American Society of Mechanical Engineers (ASME)
 - .1 ASME B31.1, Power Piping.
- .2 ASTM International
 - .1 ASTM A125, Standard Specification for Steel Springs, Helical, Heat-Treated.
 - .2 ASTM A307, Standard Specification for Carbon Steel Bolts and Studs, 60,000 PSI Tensile Strength.
 - .3 ASTM A563, Standard Specification for Carbon and Alloy Steel Nuts.
- .3 Factory Mutual (FM)
- .4 Manufacturer's Standardization Society of the Valves and Fittings Industry (MSS)
 - .1 MSS SP58, Pipe Hangers and Supports - Materials, Design and Manufacture.
 - .2 MSS SP69, Pipe Hangers and Supports - Selection and Application.
 - .3 MSS SP89, Pipe Hangers and Supports - Fabrication and Installation Practices.
- .5 Underwriter's Laboratories of Canada (ULC)

1.2 Action And Informational Submittals

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for specified equipment and include product characteristics, performance criteria, physical size, finish and limitations.

1.3 Closeout Submittals

- .1 Provide maintenance data for incorporation into manual specified in Section 01 78 00 - Closeout Submittals.

1.4 Delivery, Storage And Handling

- .1 Deliver, store and handle materials in accordance with Section with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
 - .1 Store materials indoors in dry location and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Replace defective or damaged materials with new.

Part 2 Products

2.1 Scope Of Work

- .1 Scope of work for piping supports includes plumbing and fire protection piping modifications.

2.2 System Description

- .1 Design Requirements:
 - .1 Construct pipe hanger and support to manufacturer's recommendations utilizing manufacturer's regular production components, parts and assemblies.
 - .2 Base maximum load ratings on allowable stresses prescribed by ASME B31.1 or MSS SP58.
 - .3 Ensure that supports, guides, anchors do not transmit excessive quantities of heat to building structure.
 - .4 Design hangers and supports to support systems under conditions of operation, allow free expansion and contraction, prevent excessive stresses from being introduced into pipework or connected equipment.
 - .5 Provide for vertical adjustments after erection and during commissioning. Amount of adjustment in accordance with MSS SP58.

2.3 General

- .1 Fabricate hangers, supports and sway braces in accordance with MSS SP58.
- .2 Finishes:
 - .1 Pipe hangers and supports: galvanized after manufacture.
 - .2 Ensure steel hangers in contact with copper piping are copper plated or epoxy coated.
- .3 Upper attachment structural: Suspension from lower flange of I-Beam.
 - .1 Cold piping NPS 2 maximum: Malleable iron C-clamp with hardened steel cup point setscrew, locknut and carbon steel retaining clip.
 - .1 Rod: 9mm.
 - .2 Cold piping NPS 2 1/2 or greater, all hot piping: Malleable iron beam clamp, eye rod, jaws and extension with carbon steel retaining clip, tie rod, nuts and washers, UL/ULC listed to MSS-SP69.
- .4 Upper attachment structural: Suspension from upper flange of I-Beam.
 - .1 Cold piping NPS 2 maximum: Ductile iron top-of-beam C-clamp with hardened steel cup point setscrew, locknut and carbon steel retaining clip, ULC listed to MSS SP69.
 - .2 Cold piping NPS 2 1/2 or greater, all hot piping: Malleable iron top-of-beam jaw-clamp with hooked rod, spring washer, plain washer and nut ULC listed.
- .5 Upper attachment to concrete.

- .1 Ceiling: Carbon steel welded eye rod, clevis plate, clevis pin and cotters with weldless forged steel eye nut. Ensure eye 6 mm minimum greater than rod diameter.
- .2 Concrete inserts: wedge shaped body with knockout protector plate ULC listed to MSS SP69.
- .6 Shop and field-fabricated assemblies.
 - .1 Trapeze hanger assemblies: steel, sized to suit load.
 - .2 Steel brackets: sized to suit load.
- .7 Hanger rods: threaded rod material to MSS SP58.
 - .1 Ensure that hanger rods are subject to tensile loading only.
 - .2 Provide linkages where lateral or axial movement of pipework is anticipated.
 - .3 Size based on the following schedule:
 - .1 10 mm rod for pipes up to 50 mm diameter.
 - .2 12 mm rod for 65 mm and 75 mm diameter.
 - .3 16 mm rod for 100 mm diameter.
 - .4 20 mm rod for 150 mm diameter.
 - .5 22 mm rod for 200 mm to 300 mm diameter.
- .8 Pipe attachments: material to MSS SP58.
 - .1 Attachments for steel piping: carbon steel, galvanized.
 - .2 Attachments for copper piping: copper plated black steel.
 - .3 Use insulation shields for hot pipework.
 - .4 Oversize pipe hangers and supports.
- .9 Adjustable clevis: material to MSS SP69, ULC listed, clevis bolt with nipple spacer and vertical adjustment nuts above and below clevis.
 - .1 Ensure "U" has hole in bottom for riveting to insulation shields.
- .10 Yoke style pipe roll: carbon steel yoke, rod and nuts with cast iron roll, to MSS SP69.
- .11 U-bolts: carbon steel to MSS SP69 with 2 nuts at each end to ASTM A563.
 - .1 Finishes for steel pipework: galvanized.
 - .2 Finishes for copper, glass, brass or aluminum pipework: epoxy coated.
- .12 Pipe rollers: cast iron roll and roll stand with carbon steel rod to MSS SP69.
- .13 For refrigerant piping use a manufactured support system consisting of:
 - .1 U-shaped channel of gauge and size as recommended by manufacturer to support the load.
 - .2 Thermoplastic elastomer cushion that surrounds piping and hinges open for easy insertion of piping.
 - .3 Clamp with electro chromate finish that secures cushion to channel by means of shaped end tabs that fit into the U-shaped channel and a tightening bolt at the top.

2.4 Wall Support

- .1 For piping supported off wall, roof or floor, use a manufactured support system consisting of:
 - .1 U-shaped channel of gauge and size as recommended by manufacturer to support the load.
 - .2 Thermoplastic elastomer cushion that surrounds piping and hinges open for easy insertion of piping.
 - .3 Clamp with electro chromate finish that secures cushion to channel by means of shaped end tabs that fit into the U-shaped channel and a tightening bolt at the top.
- .2 Spacing shall be as recommended by manufacturer for load being supported.
- .3 For groups of piping that are arranged perpendicular to wall, install Unistrut to form a triangular angle bracket.

2.5 Riser Clamps

- .1 Steel or cast iron pipe: galvanized carbon steel to MSS SP58, type 42, ULC listed.
- .2 Copper pipe: carbon steel copper plated to MSS SP58, type 42.
- .3 Bolts: to ASTM A307.
- .4 Nuts: to ASTM A563.

2.6 Insulation Protection Shields

- .1 Insulated cold piping:
 - .1 64 kg/m³ density insulation plus insulation protection shield to: MSS SP69, galvanized sheet carbon steel. Length designed for maximum 3 m span.
- .2 Insulated hot piping:
 - .1 Curved plate 300 mm long, with edges turned up, welded-in centre plate for pipe sizes NPS 12 and over, carbon steel to comply with MSS SP69.

2.7 Constant Support Spring Hangers

- .1 Springs: alloy steel to ASTM A125, shot-peened, magnetic particle inspected, with +/-5% spring rate tolerance, tested for free height, spring rate, loaded height and provided with Certified Mill Test Report (CMTR).
- .2 Load adjustability: 10 % minimum adjustability each side of calibrated load. Adjustment without special tools. Adjustments not to affect travel capabilities.
- .3 Provide upper and lower factory set travel stops.
- .4 Provide load adjustment scale for field adjustments.
- .5 Total travel to be actual travel + 20%. Difference between total travel and actual travel 25 mm minimum.
- .6 Individually calibrated scales on each side of support calibrated prior to shipment, complete with calibration record.

2.8 Variable Support Spring Hangers

- .1 Vertical movement: 13 mm minimum, 50 mm maximum, use single spring pre-compressed variable spring hangers.
- .2 Vertical movement greater than 50 mm: use double spring pre-compressed variable spring hanger with 2 springs in series in single casing.
- .3 Variable spring hanger to be complete with factory calibrated travel stops. Provide certificate of calibration for each hanger.
- .4 Steel alloy springs: to ASTM A125, shot-peened, magnetic particle inspected, with +/-5 % spring rate tolerance, tested for free height, spring rate, loaded height and provided with CMTR.

2.9 Equipment Supports

- .1 Fabricate equipment supports not provided by equipment manufacturer from structural grade steel meeting requirements of Division 05 - Structural Steel for Buildings.
- .2 Submit calculations with shop drawings.

2.10 Equipment Anchor Bolts And Templates

- .1 Provide templates to ensure accurate location of anchor bolts.
- .2 Submit structural calculations with shop drawings.

Part 3 Execution

3.1 Manufacturer's Instructions

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheet.

3.2 Installation

- .1 Install in accordance with:
 - .1 Manufacturer's instructions and recommendations.
- .2 Vibration Control Devices:
 - .1 Install on piping systems at pumps, boilers, chillers, cooling towers, and as indicated.
- .3 Clamps on riser piping:
 - .1 Support independent of connected horizontal pipework using riser clamps and riser clamp lugs welded to riser.
 - .2 Bolt-tightening torques to industry standards.
 - .3 Steel pipes: install below coupling or shear lugs welded to pipe.
 - .4 Cast iron pipes: install below joint.
- .4 Clevis plates:

- .1 Attach to concrete with 4 minimum concrete inserts, one at each corner.
- .5 Provide supplementary structural steelwork where structural bearings do not exist or where concrete inserts are not in correct locations.
- .6 Use approved constant support type hangers where:
 - .1 Vertical movement of pipework is 13 mm or more,
 - .2 Transfer of load to adjacent hangers or connected equipment is not permitted.
- .7 Use variable support spring hangers where:
 - .1 Transfer of load to adjacent piping or to connected equipment is not critical.
 - .2 Variation in supporting effect does not exceed 25 % of total load.

3.3 Hanger Spacing

- .1 Plumbing piping: to National Plumbing Code of Canada and t Provincial Code.
- .2 Fire protection: to applicable fire code.
- .3 Gas and fuel oil piping: up to NPS 1/2: every 1.8 m.
- .4 Copper piping: up to NPS 1/2: every 1.5 m.
- .5 Flexible joint roll groove pipe: in accordance with table below for steel, but not less than one hanger at joints. Table listings for straight runs without concentrated loads and where full linear movement is not required.
- .6 Within 300 mm of each elbow.

Maximum Pipe Size : NPS	Maximum Spacing Steel	Maximum Spacing Copper
up to 1-1/4	2.4 m	1.8 m
1-1/2	3.0 m	2.4 m
2	3.0 m	2.4 m
2-1/2	3.7 m	3.0 m
3	3.7 m	3.0 m
3-1/2	3.7 m	3.3 m
4	3.7 m	3.6 m
5	4.3 m	
6	4.3 m	
8	4.3 m	
10	4.9 m	
12	4.9 m	

- .7 Pipework greater than NPS 12: to MSS SP69.

3.4 Hanger Installation

- .1 Install hanger so that rod is vertical under operating conditions.
- .2 Adjust hangers to equalize load.
- .3 Support from structural members. Where structural bearing does not exist or inserts are not in suitable locations, provide supplementary structural steel members.

3.5 Horizontal Movement

- .1 Angularity of rod hanger resulting from horizontal movement of pipework from cold to hot position not to exceed 4 degrees from vertical.
- .2 Where horizontal pipe movement is less than 13 mm, offset pipe hanger and support so that rod hanger is vertical in the hot position.

3.6 Final Adjustment

- .1 Adjust hangers and supports:
 - .1 Ensure that rod is vertical under operating conditions.
 - .2 Equalize loads.
- .2 Adjustable clevis:
 - .1 Tighten hanger load nut securely to ensure proper hanger performance.
 - .2 Tighten upper nut after adjustment.
- .3 C-clamps:
 - .1 Follow manufacturer's recommended written instructions and torque values when tightening C-clamps to bottom flange of beam.
- .4 Beam clamps:
 - .1 Hammer jaw firmly against underside of beam.

3.7 Cleaning

- .1 Progress Cleaning: clean in accordance with Section 01 74 11 – Cleaning.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 - Cleaning.
- .3 Waste Management: separate waste materials for reuse and recycling.
 - .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

END OF SECTION

Part 1 General

1.1 Summary

- .1 Section Includes:
 - .1 Materials and requirements for the identification of piping systems, duct work, valves and controllers, including the installation and location of identification systems.
 - .2 Sustainable requirements for construction and verification.

1.2 References

- .1 Canadian Gas Association (CGA)
 - .1 CSA/CGA B149.1, Natural Gas and Propane Installation Code.
- .2 Canadian General Standards Board (CGSB)
 - .1 CAN/CGSB-1.60, Interior Alkyd Gloss Enamel.
 - .2 CAN/CGSB-24.3, Identification of Piping Systems.
- .3 National Fire Protection Association (NFPA)
 - .1 NFPA 13, Standard for the Installation of Sprinkler Systems.
 - .2 NFPA 14, Standard for the Installation of Standpipe and Hose Systems.

1.3 Action And Informational Submittals

- .1 Product Data:
- .2 Submittals: in accordance with Section 01 33 00 - Submittal Procedures.
- .3 Product data to include paint colour chips, other products specified in this section.
- .4 Samples:
 - .1 Submit samples in accordance with Section 01 33 00 - Submittal Procedures.
 - .2 Samples to include nameplates, labels, tags, lists of proposed legends.

1.4 Quality Assurance

- .1 Quality assurance submittals: submit following in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Health and Safety:
 - .1 Do construction occupational health and safety in accordance with Section 01 35 29.06 - Health and Safety Requirements.

1.5 Delivery, Storage And Handling

- .1 Deliver, store and handle materials in accordance with Section with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.

- .3 Storage and Handling Requirements:
 - .1 Store materials indoors in dry location and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Replace defective or damaged materials with new.

Part 2 Products

2.1 Manufacturer's Equipment Nameplates

- .1 Metal or plastic laminate nameplate mechanically fastened to each piece of equipment by manufacturer.
- .2 Lettering and numbers raised or recessed.
- .3 Information to include, as appropriate:
 - .1 Equipment: manufacturer's name, model, size, serial number, capacity.
 - .2 Motor: voltage, Hz, phase, power factor, duty, frame size.

2.2 System Nameplates

- .1 Colours:
 - .1 Hazardous: red letters, white background.
 - .2 Elsewhere: black letters, white background (except where required otherwise by applicable codes).
- .2 Construction:
 - .1 3 mm thick laminated plastic, matte finish, with square corners, letters accurately aligned and machine engraved into core.
- .3 Sizes:
 - .1 Conform to following table:

Size # mm	Sizes (mm)	No. of Lines	Height of Letters (mm)
1	10 x 50	1	3
2	13 x 75	1	5
3	13 x 75	2	3
4	20 x 100	1	8
5	20 x 100	2	5
6	20 x 200	1	8
7	25 x 125	1	12
8	25 x 125	2	8
9	35 x 200	1	20

- .2 Use maximum of 25 letters/numbers per line.
- .4 Locations:
 - .1 Terminal cabinets, control panels: use size # 5.
 - .2 Equipment in Mechanical Rooms: use size # 9.
- .5 Identification for PWGSC Preventive Maintenance Support System (PMSS):
 - .1 Use arrangement of Main identifier, Source identifier, Destination identifier.

- .2 Equipment in Mechanical Room:
 - .1 Main identifier: size #9.
 - .2 Source and Destination identifiers: size #6.
 - .3 Terminal cabinets, control panels: size #5.
- .3 Equipment elsewhere: sizes as appropriate.

2.3 Existing Identification Systems

- .1 Apply existing identification system to new work.
- .2 Where existing identification system does not cover for new work, use identification system specified this section.
- .3 Before starting work, obtain written approval of identification system from Departmental Representative.

2.4 Piping Systems Governed By Codes

- .1 Identification:
 - .1 Natural gas: to CSA/CGA B149.1.
 - .2 Propane gas: to CSA/CGA B149.1.
 - .3 Sprinklers: to NFPA 13.
 - .4 Standpipe and hose systems: to NFPA 14.

2.5 Identification Of Piping Systems

- .1 Identify contents by background colour marking, pictogram (as necessary), legend; direction of flow by arrows. To CAN/CGSB 24.3 except where specified otherwise.
- .2 Pictograms:
 - .1 Where required: Workplace Hazardous Materials Information System (WHMIS) regulations.
- .3 Legend:
 - .1 Block capitals to sizes and colours listed in CAN/CGSB 24.3.
- .4 Arrows showing direction of flow:
 - .1 Outside diameter of pipe or insulation less than 75 mm: 100 mm long x 50 mm high.
 - .2 Outside diameter of pipe or insulation 75 mm and greater: 150 mm long x 50 mm high.
 - .3 Use double-headed arrows where flow is reversible.
- .5 Extent of background colour marking:
 - .1 To full circumference of pipe or insulation.
 - .2 Length to accommodate pictogram, full length of legend and arrows.
- .6 Materials for background colour marking, legend, arrows:
 - .1 Pipes and tubing 20 mm and smaller: waterproof and heat-resistant pressure sensitive plastic marker tags.

- .2 Other pipes: pressure sensitive vinyl with protective overcoating, waterproof contact adhesive undercoating, suitable for ambient of 100% RH and continuous operating temperature of 150 degrees C and intermittent temperature of 200 degrees C.

.7 Colours and Legends:

- .1 Where not listed, obtain direction from Departmental Representative.
- .2 Colours for legends, arrows: to following table:

Background colour:	Legend, arrows:
Yellow	BLACK
Green	WHITE
Red	WHITE

.3 Background colour marking and legends for piping systems:

Contents	Background colour marking	Legend
Domestic hot water supply	Green	DOM. HW SUPPLY
Dom. HWS recirculation	Green	DOM. HW CIRC
Domestic cold water supply	Green	DOM. CWS
Sanitary	Green	SAN
Plumbing vent	Green	SAN. VENT

2.6 Identification Ductwork Systems

- .1 50 mm high stencilled letters and directional arrows 150 mm long x 50 mm high.
- .2 Colours: back, or co-ordinated with base colour to ensure strong contrast.

2.7 Valves, Controllers

- .1 Brass tags with 12 mm stamped identification data filled with black paint.
- .2 Include flow diagrams for each system, of approved size, showing charts and schedules with identification of each tagged item, valve type, service, function, normal position, location of tagged item.

2.8 Controls Components Identification

- .1 Identify all systems, equipment, components, controls, sensors with system nameplates specified in this section.
- .2 Inscriptions to include function and (where appropriate) fail-safe position.

2.9 Language

- .1 Identification in English.

Part 3 Execution

3.1 Manufacturer's Instructions

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheet.

3.2 Timing

- .1 Provide identification only after painting specified Section 09 91 23 - Interior Painting has been completed.

3.3 Installation

- .1 Perform work in accordance with CAN/CGSB-24.3 except as specified otherwise.
- .2 Provide ULC, CSA registration plates as required by respective agency.
- .3 Identify systems, equipment to conform to PWGSC PMSS.

3.4 Nameplates

- .1 Locations:
 - .1 In conspicuous location to facilitate easy reading and identification from operating floor.
- .2 Standoffs:
 - .1 Provide for nameplates on hot and/or insulated surfaces.
- .3 Protection:
 - .1 Do not paint, insulate or cover.

3.5 Location Of Identification On Piping And Ductwork Systems

- .1 On long straight runs in open areas in boiler rooms, equipment rooms, galleries, tunnels: at not more than 17 m intervals and more frequently if required to ensure that at least one is visible from any one viewpoint in operating areas and walking aisles.
- .2 Adjacent to each change in direction.
- .3 At least once in each small room through which piping or ductwork passes.
- .4 On both sides of visual obstruction or where run is difficult to follow.
- .5 On both sides of separations such as walls, floors, partitions.
- .6 Where system is installed in pipe chases, ceiling spaces, galleries, confined spaces, at entry and exit points, and at access openings.
- .7 At beginning and end points of each run and at each piece of equipment in run.
- .8 At point immediately upstream of major manually operated or automatically controlled valves, and dampers. Where this is not possible, place identification as close as possible, preferably on upstream side.
- .9 Identification easily and accurately readable from usual operating areas and from access points.
 - .1 Position of identification approximately at right angles to most convenient line of sight, considering operating positions, lighting conditions, risk of physical damage or injury and reduced visibility over time due to dust and dirt.

3.6 Valves, Controllers

- .1 Valves and operating controllers, except at plumbing fixtures, radiation, or where in plain sight of equipment they serve: Secure tags with non-ferrous chains or closed "S" hooks.
- .2 Install one copy of flow diagrams, valve schedules mounted in frame behind non-glare glass where directed by Departmental Representative. Provide one copy (reduced in size if required) in each operating and maintenance manual.
- .3 Number valves in each system consecutively.

3.7 Cleaning

- .1 Progress Cleaning: clean in accordance with Section 01 74 11 – Cleaning.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 - Cleaning.
- .3 Waste Management: separate waste materials for reuse and recycling.
 - .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

END OF SECTION

Part 1 General

1.1 Summary

- .1 TAB is used throughout this Section to describe the process, methods and requirements of testing, adjusting and balancing for HVAC.
- .2 TAB means to test, adjust and balance to perform in accordance with requirements of Contract Documents and to do other work as specified in this section.

1.2 Qualifications Of Tab Personnel

- .1 Submit names of personnel to perform TAB to Departmental Representative within 30 days of award of contract.
- .2 Provide documentation confirming qualifications, successful experience.
- .3 TAB: performed in accordance with the requirements of standard under which TAB Firm's qualifications are approved:
 - .1 Associated Air Balance Council, (AABC) National Standards for Total System Balance, MN-1.
 - .2 National Environmental Balancing Bureau (NEBB) TABES, Procedural Standards for Testing, Adjusting, Balancing of Environmental Systems.
 - .3 Sheet Metal and Air Conditioning Contractors' National Association (SMACNA), HVAC TAB HVAC Systems - Testing, Adjusting and Balancing.
- .4 Recommendations and suggested practices contained in the TAB Standard: mandatory.
- .5 Use TAB Standard provisions, including checklists, and report forms to satisfy Contract requirements.
- .6 Use TAB Standard for TAB, including qualifications for TAB Firm and Specialist and calibration of TAB instruments.
- .7 Where instrument manufacturer calibration recommendations are more stringent than those listed in TAB Standard, use manufacturer's recommendations.
- .8 TAB Standard quality assurance provisions such as performance guarantees form part of this contract.
 - .1 For systems or system components not covered in TAB Standard, use TAB procedures developed by TAB Specialist.
 - .2 Where new procedures, and requirements, are applicable to Contract requirements have been published or adopted by body responsible for TAB Standard used (AABC, NEBB, or TABB), requirements and recommendations contained in these procedures and requirements are mandatory.

1.3 Purpose Of Tab

- .1 Test to verify proper and safe operation, determine actual point of performance, evaluate qualitative and quantitative performance of equipment, systems and controls at design, average and low loads using actual or simulated loads

- .2 Adjust and regulate equipment and systems to meet specified performance requirements and to achieve specified interaction with other related systems under normal and emergency loads and operating conditions.
- .3 Balance systems and equipment to regulate flow rates to match load requirements over full operating ranges.

1.4 Exceptions

- .1 TAB of systems and equipment regulated by codes, standards to satisfaction of authority having jurisdiction.

1.5 Co-Ordination

- .1 Schedule time required for TAB (including repairs, re-testing) into project construction and completion schedule to ensure completion before acceptance of project.
- .2 Do TAB of each system independently and subsequently, where interlocked with other systems, in unison with those systems.

1.6 Pre-Tab Review

- .1 Review contract documents before project construction is started confirm in writing to Departmental Representative adequacy of provisions for TAB and other aspects of design and installation pertinent to success of TAB.
- .2 Review specified standards and report to Departmental Representative in writing proposed procedures which vary from standard.
- .3 During construction, co-ordinate location and installation of TAB devices, equipment, accessories, measurement ports and fittings.

1.7 Start-Up

- .1 Follow start-up procedures as recommended by equipment manufacturer unless specified otherwise.
- .2 Follow special start-up procedures specified elsewhere in Division 23.

1.8 Operation Of Systems During Tab

- .1 Operate systems for length of time required for TAB and as required by Departmental Representative for verification of TAB reports.

1.9 Start Of Tab

- .1 Notify Departmental Representative 7 days prior to start of TAB.
- .2 Start TAB when building is essentially completed, including:
- .3 Installation of ceilings, doors, windows, other construction affecting TAB.
- .4 Application of weatherstripping, sealing, and caulking.
- .5 Pressure, leakage, other tests specified elsewhere Division 23.
- .6 Provisions for TAB installed and operational.

- .7 Start-up, verification for proper, normal and safe operation of mechanical and associated electrical and control systems affecting TAB including but not limited to:
 - .1 Proper thermal overload protection in place for electrical equipment.
 - .2 Air systems:
 - .1 Filters in place, clean.
 - .2 Duct systems clean.
 - .3 Ducts, air shafts, ceiling plenums are airtight to within specified tolerances.
 - .4 Correct fan rotation.
 - .5 Fire, smoke, volume control dampers installed and open.
 - .6 Coil fins combed, clean.
 - .7 Access doors, installed, closed.
 - .8 Outlets installed, volume control dampers open.

1.10 Application Tolerances

- .1 Do TAB to following tolerances of design values:
 - .1 Laboratory HVAC systems: plus 10 %, minus 0 %.
 - .2 Other HVAC systems: plus 5 %, minus 5 %.
 - .3 Hydronic systems: plus or minus 10 %.

1.11 Accuracy Tolerances

- .1 Measured values accurate to within plus or minus 2 % of actual values.

1.12 Instruments

- .1 Prior to TAB, submit to Departmental Representative list of instruments used together with serial numbers.
- .2 Calibrate in accordance with requirements of most stringent of referenced standard for either applicable system or HVAC system.
- .3 Calibrate within 3 months of TAB. Provide certificate of calibration to Departmental Representative.

1.13 Action And Informational Submittals

- .1 Submit, prior to commencement of TAB:
- .2 Proposed methodology and procedures for performing TAB if different from referenced standard.

1.14 Preliminary Tab Report

- .1 Submit for checking and approval of Departmental Representative, prior to submission of formal TAB report, sample of rough TAB sheets. Include:
 - .1 Details of instruments used.
 - .2 Details of TAB procedures employed.
 - .3 Calculations procedures.

.4 Summaries.

1.15 Tab Report

- .1 Format in accordance with referenced standard.
- .2 TAB report to show results in SI units and to include:
 - .1 Project record drawings.
 - .2 System schematics.
- .3 Submit 6 copies of TAB Report to Departmental Representative for verification and approval, in English in D-ring binders, complete with index tabs.

1.16 Verification

- .1 Reported results subject to verification by Departmental Representative.
- .2 Provide personnel and instrumentation to verify up to 30% of reported results.
- .3 Number and location of verified results as directed by Departmental Representative.
- .4 Pay costs to repeat TAB as required to satisfaction of Departmental Representative.

1.17 Settings

- .1 After TAB is completed to satisfaction of Departmental Representative, replace drive guards, close access doors, lock devices in set positions, and ensure sensors are at required settings.
- .2 Permanently mark settings to allow restoration at any time during life of facility. Do not eradicate or cover markings.

1.18 Completion Of Tab

- .1 TAB considered complete when final TAB Report received and approved by Departmental Representative.

1.19 Air Systems

- .1 Standard: TAB to most stringent of TAB standards of AABC, NEBB, SMACNA ASHRAE.
- .2 Do TAB of systems, equipment, components, controls specified Division 23 and as follows:
 - .1 All effected supply air systems including all outlets.
 - .2 All effected and new exhaust air systems.
- .3 Qualifications: personnel performing TAB current member in good standing of AABC and NEBB.
- .4 Quality assurance: perform TAB under direction of supervisor qualified by AABC and NEBB.
- .5 Measurements: to include as appropriate for systems, equipment, components, controls: air velocity, static pressure, flow rate, pressure drop (or loss), temperatures (dry bulb, wet bulb, dewpoint), duct cross-sectional area, RPM, electrical power, voltage, noise, vibration.

- .6 Locations of equipment measurements: to include as appropriate:
 - .1 Inlet and outlet of dampers, filter, coil, humidifier, fan, other equipment causing changes in conditions.
 - .2 At controllers, controlled device.
- .7 Locations of systems measurements to include as appropriate: main ducts, main branch, sub-branch, run-out (or grille, register or diffuser).

Part 2 Products

2.1 Not Used

- .1 Not used.

Part 3 Execution

3.1 Not Used

- .1 Not used.

END OF SECTION

Part 1 General

1.1 Summary

.1 Section Includes:

- .1 Materials and methods for pressure testing ducts over 5 m in length, forming part of a supply, return or exhaust ductwork system directly or indirectly connected to air handling equipment.

1.2 References

- .1 Health Canada/Workplace Hazardous Materials Information System (WHMIS)
 - .1 Material Safety Data Sheets (MSDS).
- .2 Sheet Metal and Air Conditioning Contractor's National Association (SMACNA)
 - .1 SMACNA HVAC Air Duct Leakage Test Manual, 1985.

1.3 Action And Informational Submittals

- .1 Make submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Test Reports: submit certified test reports from approved independent testing laboratories indicating compliance with specifications for specified performance characteristics and physical properties. Include pressure test information and results as follows:
 - .1 Submit proposed report form and test report format to Departmental Representative for approval at least three months before proposed date of first series of tests. Do not start tests until approval received in writing.
 - .2 Prepare report of results and submit to Departmental Representative within 24 hours of completion of tests. Include:
 - .1 Schematic of entire system.
 - .2 Schematic of section under test showing test site.
 - .3 Required and achieved static pressures.
 - .4 Orifice differential pressure at test sites.
 - .5 Permissible and actual leakage flow rate (L/s) for test sites.
 - .6 Witnessed certification of results.
 - .3 Include test reports in final TAB report.
 - .4 Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
 - .5 Instructions: submit manufacturer's installation instructions.
 - .6 Manufacturer's field reports specified.

Part 2 Products

2.1 Test Instruments

- .1 Test apparatus to include:
 - .1 Fan capable of producing required static pressure.
 - .2 Duct section with calibrated orifice plate mounted and accurately located pressure taps.
 - .3 Flow measuring instrument compatible with the orifice plate.
 - .4 Calibration curves for orifice plates used.
 - .5 Flexible duct for connecting to ductwork under test.
 - .6 Smoke bombs for visual inspections.
- .2 Test apparatus: accurate to within +/- 3 % of flow rate and pressure.
- .3 Submit details of test instruments to be used to Departmental Representative at least three months before anticipated start date.
- .4 Test instruments: calibrated and certificate of calibration deposited with Departmental Representative no more than 28 days before start of tests.
- .5 Re-calibrated every six months thereafter.

Part 3 Execution

3.1 Manufacturer's Instructions

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheet.

3.2 Test Procedures

- .1 Maximum lengths of ducts to be tested consistent with capacity of test equipment.
- .2 Section of duct to be tested to include:
 - .1 Fittings, branch ducts, tap-ins.
- .3 Repeat tests until specified pressures are attained. Bear costs for repairs and repetition to tests.
- .4 Base partial system leakage calculations on SMACNA HVAC Air Duct Leakage Test Manual.
- .5 Seal leaks that can be heard or felt, regardless of their contribution to total leakage.

3.3 Site Tolerances

- .1 System leakage tolerances specified are stated as percentage of total flow rate handled by system. Pro-rate specified system leakage tolerances. Leakage for sections of duct systems: not to exceed total allowable leakage.
- .2 Leakage tests on following systems not to exceed specified leakage rates.
 - .1 Small duct systems up to 250 Pa: leakage 2%.

- .2 Large low pressure duct systems up to 500 Pa: leakage 2%.
- .3 Evaluation of test results to use surface area of duct and pressure in duct as basic parameters.

3.4 Testing

- .1 Test ducts before installation of insulation or other forms of concealment.
- .2 Test after seals have cured.
- .3 Test when ambient temperature will not affect effectiveness of seals, and gaskets.
- .4 Flexible connections to VAV boxes.

3.5 Cleaning

- .1 Upon completion and verification of performance of installation, remove surplus materials, excess materials, rubbish, tools and equipment.

END OF SECTION

Part 1 General

1.1 References

- .1 Definitions:
 - .1 For purposes of this section:
 - .1 "CONCEALED" - insulated mechanical services and equipment in suspended ceilings and non-accessible chases and furred-in spaces.
 - .2 "EXPOSED" - means "not concealed" as previously defined.
 - .3 Insulation systems - insulation material, fasteners, jackets, and other accessories.
 - .2 TIAC Codes:
 - .1 CRD: Code Round Ductwork,
 - .2 CRF: Code Rectangular Finish.
- .2 Reference Standards:
 - .1 American Society of Heating, Refrigeration and Air Conditioning Engineers (ASHRAE)
 - .1 ANSI/ASHRAE/IESNA 90.1, SI; Energy Standard for Buildings Except Low-Rise Residential Buildings.
 - .2 ASTM International Inc.
 - .1 ASTM B209M, Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate (Metric).
 - .2 ASTM C335, Standard Test Method for Steady State Heat Transfer Properties of Pipe Insulation.
 - .3 ASTM C411, Standard Test Method for Hot-Surface Performance of High-Temperature Thermal Insulation.
 - .4 ASTM C449/C449M, Standard Specification for Mineral Fiber-Hydraulic-Setting Thermal Insulating and Finishing Cement.
 - .5 ASTM C547, Standard Specification for Mineral Fiber Pipe Insulation.
 - .6 ASTM C553, Standard Specification for Mineral Fiber Blanket Thermal Insulation for Commercial and Industrial Applications.
 - .7 ASTM C612, Standard Specification for Mineral Fiber Block and Board Thermal Insulation.
 - .8 ASTM C795, Standard Specification for Thermal Insulation for Use in Contact with Austenitic Stainless Steel.
 - .9 ASTM C921, Standard Practice for Determining the Properties of Jacketing Materials for Thermal Insulation.
 - .3 Canadian General Standards Board (CGSB)
 - .1 CGSB 51-GP-52Ma, Vapour Barrier, Jacket and Facing Material for Pipe, Duct and Equipment Thermal Insulation.
 - .4 Green Seal Environmental Standards (GSES)
 - .1 Standard GS-36, Commercial Adhesives.
 - .5 South Coast Air Quality Management District (SCAQMD), California State

- .1 SCAQMD Rule 1168, Adhesive and Sealant Applications.
- .6 Thermal Insulation Association of Canada (TIAC): National Insulation Standards (2005).
- .7 Underwriters Laboratories of Canada (ULC)
 - .1 CAN/ULC-S102, Method of Test for Surface Burning Characteristics of Building Materials and Assemblies.
 - .2 CAN/ULC-S701, Standard for Thermal Insulation, Polystyrene, Boards and Pipe Covering.

1.2 Action And Informational Submittals

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Provide manufacturer's printed product literature and datasheets for duct insulation, and include product characteristics, performance criteria, physical size, finish and limitations.
 - .1 Description of equipment giving manufacturer's name, type, model, year and capacity.
 - .2 Details of operation, servicing and maintenance.
 - .3 Recommended spare parts list.
- .3 Samples:
 - .1 Submit for approval: complete assembly of each type of insulation system, insulation, coating, and adhesive proposed.
 - .2 Mount sample on 12 mm plywood board.
 - .3 Affix typewritten label beneath sample indicating service.
- .4 Manufacturers' Instructions:
 - .1 Provide manufacture's written duct insulation jointing recommendations and special handling criteria, installation sequence, cleaning procedures.

1.3 Quality Assurance

- .1 Qualifications:
 - .1 Installer: specialist in performing work of this section, and have at least 3 years successful experience in this size and type of project, qualified to standards, member of TIAC.

1.4 Delivery, Storage And Handling

- .1 Deliver, store and handle materials in accordance with Section with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
 - .1 Store materials indoors in dry location and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.

- .2 Replace defective or damaged materials with new.

Part 2 Products

2.1 Fire And Smoke Rating

- .1 To CAN/ULC-S102:
 - .1 Maximum flame spread rating: 25.
 - .2 Maximum smoke developed rating: 50.

2.2 Insulation

- .1 Mineral fibre: as specified includes glass fibre, rock wool, slag wool.
- .2 Thermal conductivity ("k" factor) not to exceed specified values at 24 degrees C mean temperature when tested in accordance with ASTM C335.
- .3 TIAC Code C-1: Rigid mineral fibre board to ASTM C612, with factory applied vapour retarder jacket to CGSB 51-GP-52Ma (as scheduled in PART 3 of this Section).
- .4 TIAC Code C-2: Mineral fibre blanket to ASTM C553 faced with factory applied vapour retarder jacket to CGSB 51-GP-52Ma (as scheduled in PART 3 of this section).
 - .1 Mineral fibre: to ASTM C553.
 - .2 Jacket: to CGSB 51-GP-52Ma.
 - .3 Maximum "k" factor: to ASTM C553.

2.3 Jackets

- .1 Canvas:
 - .1 220 gm/m2 fire resistant cotton, plain weave, to ASTM C921 and ULC listed.
 - .2 Lagging adhesive: inorganic, water-based fire-resistive lagging adhesive and coating, ULC listed.
- .2 Aluminium:
 - .1 Jacket: To ASTM B209, minimum H-14 temper with heat-laminated moisture barrier liner.
 - .2 Thickness: 0.50 mm sheet.
 - .3 Finish: Stucco embossed.
 - .4 Joining: Longitudinal and circumferential slip joints with 50 mm laps.
 - .5 Fittings: 0.5 mm thick die-shaped fitting covers with factory-attached protective liner.
 - .6 Metal jacket banding and mechanical seals: stainless steel, 19 mm wide, 0.5 mm thick at 300 mm spacing.

2.4 Accessories

- .1 Vapour retarder lap adhesive:
 - .1 Water based, fire retardant type, compatible with insulation.

- .2 Indoor Vapour Retarder Finish:
 - .1 Vinyl emulsion type acrylic, compatible with insulation.
- .3 Insulating Cement: hydraulic setting on mineral wool, to ASTM C449.
- .4 Outdoor Vapour Retarder Mastic:
 - .1 Vinyl emulsion type acrylic, compatible with insulation.
 - .2 Reinforcing fabric: Fibrous glass, untreated 305 g/m2.
- .5 Tape: self-adhesive, aluminum, plain, 50 mm wide minimum.
- .6 Contact adhesive: quick-setting
- .7 Canvas adhesive: washable.
- .8 Tie wire: 1.5 mm stainless steel.
- .9 Banding: 19 mm wide, 0.5 mm thick stainless steel.
- .10 Fasteners: 14 gauge diameter pins with 30mm diameter or 927 mm2 square clips, pin length to suit thickness of insulation.

Part 3 Execution

3.1 Application

- .1 Manufacturer's Instructions: comply with manufacturer's written recommendations, including product technical bulletins, handling, storage and installation instructions, and datasheets.

3.2 Pre-Installation Requirements

- .1 Pressure test ductwork systems complete, witness and certify.
- .2 Ensure surfaces are clean, dry, free from foreign material.

3.3 Installation

- .1 Install in accordance with TIAC National Standards.
- .2 Apply materials in accordance with manufacturer's instructions and as indicated.
- .3 Use 2 layers with staggered joints when required nominal thickness exceeds 75 mm.
- .4 Maintain uninterrupted continuity and integrity of vapour retarder jacket and finishes.
 - .1 Ensure hangers, and supports are outside vapour retarder jacket.
- .5 Hangers and supports in accordance with Section 23 05 29 - Hangers and Supports for HVAC Piping and Equipment.
 - .1 Apply high compressive strength insulation where insulation may be compressed by weight of ductwork.
- .6 Fasteners: install at 300 mm on centre in horizontal and vertical directions, minimum 2 rows each side.

3.4 Ductwork Insulation Schedule

- .1 Insulation types and thicknesses: conform to following table:

	TIAC Code	Vapour Retarder	Thickness (mm)
Rectangular cold and dual temperature supply air ducts	C-1	yes	50
Round cold and dual temperature supply air ducts	C-2	yes	50
Rectangular warm air ducts	C-1	no	25
Round warm air ducts	C-1	no	25
Supply, return and exhaust ducts exposed in space being served	none		
Outside air ducts to mixing plenum	C-1	yes	25
Mixing plenums	C-1	yes	25
Exhaust duct between dampers and louvres	C-1	no	25
Rectangular ducts outside	C-1	special	50
Round ducts outside	C-1	special	50
Acoustically lined ducts	C-1		

- .2 Exposed round ducts 600 mm and larger, smaller sizes where subject to abuse:

- .1 Use TIAC code C-1 insulation, scored to suit diameter of duct.

- .1 Finishes: conform to following table:

	TIAC Code	
	Rectangular	Round
Indoor, concealed	none	none
Indoor, exposed within mechanical room	CRF/1	CRD/2
Indoor, exposed elsewhere	CRF/2	CRD/3
Outdoor, exposed to precipitation	CRF/3	CRD/4
Outdoor, elsewhere	CRF/4	CRD/5

3.5 Cleaning

- .1 Progress Cleaning: clean in accordance with Section 01 74 11 – Cleaning.
- .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 - Cleaning.
- .3 Waste Management: separate waste materials for reuse and recycling.
- .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

END OF SECTION

Part 1 General

1.1 Summary

1.2 References

- .1 American Society of Heating, Refrigerating and Air-Conditioning Engineers, Inc. (ASHRAE).
 - .1 ASHRAE Handbook – Fundamentals.
- .2 American Society for Testing and Materials International (ASTM)
 - .1 ASTM A653/A653M, Standard Specification for Steel Sheet, Zinc Coated (Galvanized) or Zinc-Iron Alloy Coated (Galvannealed) by the Hot-Dip Process.
 - .2 ASTM A924/A924M, Standard Specification for General Requirements for Steel Sheet, Metallic-Coated by the Hot-Dip Process.
- .3 Canadian Standards Association (CSA International)
 - .1 CAN/ULC-S109M, Standard for Flame Tests of Flame-Resistant Fabrics and Films.
- .4 Sheet Metal and Air Conditioning Contractors' National Association (SMACNA)
 - .1 HVAC Duct Construction Standards - Metal and Flexible.
 - .2 HVAC Air Duct Leakage Test Manual.

1.3 Shop Drawings And Product Data

- .1 Submit shop drawings and product data in accordance with Section 01 33 00 - Submittal Procedures.

1.4 Closeout Submittals

- .1 Provide maintenance data for incorporation into manual specified in Section 01 78 00 - Closeout Submittals.

Part 2 Products

2.1 Galvanized Steel

- .1 Lock forming quality: to ASTM A653/A653M, G90/Z275 zinc coating, with tolerances to ASTM A924/A924M.
- .2 Thickness, fabrication and reinforcement: to SMACNA HVAC Duct Construction Standards.
- .3 Joints: to SMACNA HVAC Duct Construction Standards.

2.2 Pressure Classification

- .1 Pressure Class: Class 1 (400 Pa)

2.3 Ductwork

- .1 Construction - round and oval.
 - .1 Ducts: factory fabricated, spiral wound, with matching fittings and specials to SMACNA HVAC Duct Construction Standards.
 - .2 Transverse joints up to 900 mm: slip type with tape and sealants.
 - .3 Transverse joints over 900 mm: Vanstone flanges.
- .2 Construction - rectangular:
 - .1 Ducts: factory fabricated to SMACNA HVAC Duct Construction Standards.
 - .2 Transverse joints: to SMACNA HVAC Duct Construction Standards.

2.4 Fittings

- .1 Fabrication: to SMACNA HVAC Duct Construction Standards.
- .2 Radiused elbows:
 - .1 Rectangular: smooth radius. Centreline radius: 1.5 times width of duct.
 - .2 Round and oval: smooth radius or five-piece (for 90 degrees) and three-piece (for 45 degrees). Centreline radius: 1.5 times duct diameter.
- .3 Mitred elbows:
 - .1 To 750 mm duct height in plane of turn: with single-thickness turning vanes.
 - .2 Over 750 mm duct height in plane of turn: with double-thickness turning vanes.
- .4 Branches:
 - .1 Rectangular main and branch: connection with 45 degree entry.
 - .2 Round main and branch: conical connection.
 - .3 Provide volume control damper in branch duct near connection to main duct.
- .5 Transitions:
 - .1 Diverging: 10 degrees maximum angle each side; 20 degrees maximum included angle for symmetrical fittings.
 - .2 Converging: 22.5 degrees maximum angle each side; 45 degrees maximum included angle for symmetrical fittings.
- .6 Offsets:
 - .1 Full radiused or mitred elbows: as specified above.
- .7 Obstruction deflectors: maintain full cross-sectional area of duct.
 - .1 Maximum included angles: as for transitions.

2.5 Seal Classification

.1 Seal class:

Systems	Pressure Class (Pa)	Seal class
RUT Supply fan – discharge	+250	B
Exhaust fan – suction	-250	B

.2 Seal Classification:

- .1 Class B: longitudinal seams, transverse joints and connections made airtight with sealant and tape or combination thereof.
- .2 Class C: transverse joints and connections made air tight with sealant and tape or combination thereof. Longitudinal seams unsealed.

2.6 Sealant

- .1 Sealant: oil resistant, water-based, polymer type flame resistant duct sealant.
- .2 Flame spread rating shall not exceed 25 and smoke developed classification shall not exceed 50.
- .3 Operational temperature range of minus 32 degree C to plus 93 degree C. Application temperature range of plus 4 degree C to plus 43 degree C.

2.7 Reinforcing Tape

- .1 Tape: polyvinyl treated, open weave fiberglass tape, 50 mm wide.
- .2 Meets the flame-resistance requirements of CAN/ULC-S109M.

2.8 Hangers And Supports

- .1 Hangers and Supports:
 - .1 Hanger configuration, design, and construction: to SMACNA HVAC Duct Construction Standards.
 - .2 Strap hangers: Maximum rectangular duct size supported by strap hanger: 500 mm on longest side.
 - .1 Straps of same material as duct but next sheet metal thickness heavier than duct.
 - .2 Hanger Rods for Noncorrosive Environments: Cadmium-plated steel rods and nuts.
 - .3 Hanger Rods for Corrosive Environments: Electrogalvanized, all-thread rods or galvanized rods with threads painted with zinc-chromate primer after installation.

- .3 Band hangers: of same material as duct but next sheet metal thickness heavier than duct.
 - .1 Maximum round or oval duct size supported by strap hanger: 500mm diameter.
- .4 Trapeze hangers and Riser Supports: ducts over 500 mm diameter or longest side, to SMACNA HVAC Duct Construction Standards.
 - .1 Supports for Galvanized-Steel Ducts: Galvanized-steel shapes and plates.
 - .2 Supports for Stainless-Steel Ducts: Stainless-steel shapes and plates.
 - .3 Supports for Aluminum Ducts: Aluminum or galvanized steel coated with zinc chromate.
- .5 Hangers: galvanized steel angle with galvanized steel rods to SMACNA HVAC Duct Construction Standards.
- .6 Upper hanger attachments:
 - .1 For concrete: manufactured concrete inserts.
 - .2 For steel joist: manufactured joist clamps.
 - .3 For steel beams: manufactured beam clamps.
- .7 Duct Attachments: Sheet metal screws, blind rivets, or self-tapping metal screws; compatible with duct materials.

Part 3 Execution

3.1 General

- .1 Do work in accordance with SMACNA HVAC Duct Construction Standards unless directed otherwise by Engineer.
- .2 First class workmanship is required for fabrication and installation. Submit samples and/or detailed shop drawings of different types of fittings, joints, supports, sealants, etc, when requested by the Engineer.
- .3 Locate ductwork approximately as shown on drawings unless otherwise prevented by jobsite conditions. Carefully coordinate duct layouts with other services, particularly where exposed in occupied spaces. Conceal all ductwork unless otherwise directed and approved by the Engineer. Report all layout deviations to the Engineer for approval prior to installation.
- .4 Construct ducts in accordance with the dimensions shown on the drawings. Alter the duct dimensions, while maintaining the equivalent round duct diameter, where necessitated by jobsite conditions. Equivalent duct dimensions to be determined using ASHRAE Handbook duct design procedures.
- .5 Duct dimension shown on drawings are inside dimensions. If ducts are internally lined or insulated, increase duct size such that clear dimensions after application of lining/insulation are equal to those shown on drawings.
- .6 Adjust duct dimensions to suit standard control damper sizes.

- .7 Install proprietary manufactured flanged duct joints in accordance with manufacturer's instructions.
- .8 Support risers at each floor penetration. Provide neoprene pads between riser supports and the building structure. On exposed ductwork, provide galvanized angle collars to conceal the above work on both sides of the floor penetration.
- .9 Lap all joints in the direction of air flow wherever possible.
- .10 Provide a smooth interior surface at all seams and joints.
- .11 Provide a straight collar, not less than 300 mm long, at the connection to each diffuser. Where this is not possible provide adjustable multi-blade type flow equalizing grid in the diffuser neck.

3.2 Fittings

- .1 Fitting geometry to be in accordance with specifications and drawing details unless otherwise directed and approved by the Engineer.
- .2 Provide mitred elbows with turning vanes where jobsite conditions prevent installation of radiused elbows.

3.3 Hangers

- .1 Strap and band hangers: install in accordance with SMACNA HVAC Duct Construction Standards.
- .2 Angle hangers: install in accordance with SMACNA HVAC Duct Construction Standards, complete with locking nuts and washers.
- .3 Hanger spacing: in accordance with SMACNA HVAC Duct Construction Standards.
- .4 Do not break continuity of insulation vapour barrier with hangers or rods.

3.4 Sealing And Taping

- .1 Apply sealant to outside of joint in accordance with SMACNA HVAC Duct Construction Standards and to manufacturer's recommendations.
- .2 Use reinforcing tape on all ducts with seal Class A; ducts with seal Class B or C and a pressure classification in excess of 500 Pa; and for larger gaps.
- .3 Bed reinforcing tape in sealant and recoat with minimum of one coat of sealant to manufacturer's recommendations.
- .4 Seal all joints including, but not limited to, at coils, terminal units, grilles and diffusers.
- .5 Eliminate all audible noise caused by air leakage.
- .6 Duct tapes as sealing method are not permitted

3.5 Watertight Duct And Drip Pans

- .1 Provide watertight duct for:
 - .1 Intake and relief air outlets.
 - .1 Ductwork connect from ERV unit to outdoors
 - .2 Outside air intakes.
 - .3 As directed by Engineer.
- .2 Provide watertight evaporative pan below:
 - .1 Intake and relief air outlets.
 - .1 Beneath roof hoods for ERV unit
- .3 Form bottom of horizontal duct or drip pan without longitudinal seams.
 - .1 Solder or weld joints of bottom and side sheets.
 - .2 Seal other joints with duct sealer.
- .4 Slope horizontal branch ductwork down towards hoods served.
 - .1 Slope header ducts down toward risers.
- .5 Fit base of riser with 150 mm deep drain sump and 25 mm drain, with deep seal trap and trap primer, discharging to open funnel or hub drain.
- .6 Drip pan to be 75 mm wider all around ductwork or equipment served and complete with 75 mm deep drain sump. Elevated drip pans to be provided with 25 mm drain discharging to open funnel or hub drain. Provide sufficient clearance above drip pan to facilitate access and to permit unimpeded airflow to equipment or intake above.
- .7 Provide angle iron supports under sumps and drip pans adequate to support weight when full.
- .8 Install drip pans level to maximize holding capacity.
- .9 Fill sumps and drip pans with water to demonstrate strength, level and waterproof, when requested by Engineer.

3.6 Leakage Tests

- .1 Conduct tests in accordance with SMACNA HVAC Duct Leakage Test Manual.
- .2 Conduct tests at static pressures equal to maximum design pressure of system or section being tested. If static-pressure classes are not indicated, test system at maximum system design pressure. Do not pressurize systems above maximum design operating pressure.
- .3 Coordinate testing requirements with the TAB contractor who will perform leakage tests. Provide temporary caps and make duct modifications required to conduct the tests.
- .4 Do leakage tests in sections.

- .5 Leakage testing shall include HVAC equipment and terminal units. Where sections include equipment and terminal units, do not perform leakage testing until final connections have been made.
- .6 Conduct trial leakage tests to demonstrate workmanship.
- .7 Do not install additional ductwork until trial tests have been passed.
- .8 Complete testing before installation of insulation or concealment Work.
- .9 Give seven days' advance notice for testing.

END OF SECTION

Part 1 General

1.1 References

- .1 Sheet Metal and Air Conditioning Contractors' National Association (SMACNA)
 - .1 SMACNA - HVAC Duct Construction Standards - Metal and Flexible.

1.2 Action And Informational Submittals

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for air duct accessories and include product characteristics, performance criteria, physical size, finish and limitations.
 - .2 Indicate:
 - .1 Flexible connections.
 - .2 Duct access doors.
 - .3 Turning vanes.
 - .4 Instrument test ports.

1.3 Delivery, Storage And Handling

- .1 Deliver, store and handle materials in accordance with Section with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
 - .1 Store materials indoors in dry location and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Replace defective or damaged materials with new.

Part 2 Products

2.1 General

- .1 Manufacture in accordance with SMACNA - HVAC Duct Construction Standards.

2.2 Flexible Connections

- .1 Frame: galvanized sheet metal frame thick with fabric clenched by means of double locked seams.
- .2 Material:
 - .1 Fire resistant, self extinguishing, neoprene coated glass fabric, temperature rated at minus 40 degrees C to plus 90 degrees C, density of 1.3 kg/m2.

2.3 Access Doors In Ducts

- .1 Non-Insulated Ducts: sandwich construction of same material as duct, one sheet metal thickness heavier, minimum 0.6 mm thick complete with sheet metal angle frame.
- .2 Insulated Ducts: sandwich construction of same material as duct, one sheet metal thickness heavier, minimum 0.6 mm thick complete with sheet metal angle frame and 25 mm thick rigid glass fibre insulation.
- .3 Gaskets: neoprene.
- .4 Hardware:
 - .1 Up to 300 x 300 mm: two sash locks complete with safety chain.
 - .2 301 to 450 mm: four sash locks complete with safety chain.
 - .3 451 to 1000 mm: piano hinge and minimum two sash locks.
 - .4 Doors over 1000 mm: piano hinge and two handles operable from both sides.
 - .5 Hold open devices.
 - .6 300 x 300 mm glass viewing panels.

2.4 Turning Vanes

- .1 Factory or shop fabricated double thickness with trailing edge, to recommendations of SMACNA and as indicated.

2.5 Instrument Test

- .1 1.6 mm thick steel zinc plated after manufacture.
- .2 Cam lock handles with neoprene expansion plug and handle chain.
- .3 28 mm minimum inside diameter. Length to suit insulation thickness.
- .4 Neoprene mounting gasket.

2.6 Spin-In Collars

- .1 Conical galvanized sheet metal spin-in collars with lockable butterfly damper.
- .2 Sheet metal thickness to co-responding round duct standards.

Part 3 Execution

3.1 Examination

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for installation in accordance with manufacturer's written instructions.
 - .1 Visually inspect substrate.
 - .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.
 - .3 Proceed with installation only after unacceptable conditions have been remedied.

3.2 Installation

- .1 Flexible Connections:
 - .1 Install in following locations:
 - .1 Inlets and outlets to supply air units and fans.
 - .2 Inlets and outlets of exhaust and return air fans.
 - .3 As indicated.
 - .2 Length of connection: 100 mm.
 - .3 Minimum distance between metal parts when system in operation: 75 mm.
 - .4 Install in accordance with recommendations of SMACNA.
 - .5 When fan is running:
 - .1 Ducting on sides of flexible connection to be in alignment.
 - .2 Ensure slack material in flexible connection.
- .2 Access Doors and Viewing Panels:
 - .1 Size:
 - .1 900 x 900 mm for person size entry.
 - .2 600 x 600 mm for servicing entry.
 - .3 300 x 300 mm for viewing.
 - .4 As indicated.
 - .2 Locations:
 - .1 Fire and smoke dampers.
 - .2 Control dampers.
 - .3 Devices requiring maintenance.
 - .4 Required by code.
 - .5 Reheat coils.
 - .6 Elsewhere as indicated.
- .3 Instrument Test Ports:
 - .1 General:
 - .1 Install in accordance with recommendations of SMACNA and in accordance with manufacturer's instructions.
 - .2 Locate to permit easy manipulation of instruments.
 - .3 Install insulation port extensions as required.
 - .4 Locations:
 - .1 For traverse readings:
 - .1 Ducted inlets to roof and wall exhausters.
 - .2 Inlets and outlets of other fan systems.
 - .3 Main and sub-main ducts.
 - .4 And as indicated.
 - .2 For temperature readings:
 - .1 At outside air intakes.

- .2 In mixed air applications in locations as approved by Departmental Representative.
 - .3 At inlet and outlet of coils.
 - .4 Downstream of junctions of two converging air streams of different temperatures.
 - .5 And as indicated.
- .4 Turning Vanes:
 - .1 Install in accordance with recommendations of SMACNA and as indicated.

3.3 Cleaning

- .1 Progress Cleaning: clean in accordance with Section 01 74 11 – Cleaning.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 - Cleaning.
- .3 Waste Management: separate waste materials for reuse and recycling.
 - .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

END OF SECTION

Part 1 General

1.1 References

- .1 Air Diffusion Council (ADC).
 - .1 Flexible Duct Performance & Installation Standards.
- .2 American Society for Testing and Materials International (ASTM).
 - .1 ASTM C518, Standard Test Method for Steady-State Thermal Transmission Properties by Means of the Heat Flow Meter Apparatus.
- .3 American Society of Heating, Refrigerating and Air-Conditioning Engineers, Inc. (ASHRAE)
- .4 National Fire Protection Association (NFPA)
 - .1 NFPA 90A, Standard for the Installation of Air-Conditioning and Ventilating Systems.
 - .2 NFPA 90B, Standard for Installation of Warm Air Heating and Air-Conditioning Systems.
- .5 Sheet Metal and Air-Conditioning Contractors' National Association (SMACNA)
 - .1 SMACNA HVAC Duct Construction Standards - Metal and Flexible.
 - .2 SMACNA IAQ Guideline for Occupied Buildings under Construction.
- .6 Underwriters' Laboratories (UL)
 - .1 UL 181, Standard for Factory-Made Air Ducts and Air Connectors.
- .7 Underwriters' Laboratories of Canada (ULC)
 - .1 CAN/ULC-S110, Standard Methods of Tests for Air Ducts.

1.2 Action And Informational Submittals

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for flexible ducts and include product characteristics, performance criteria, physical size, finish and limitations.
 - .2 Indicate:
 - .1 Thermal properties.
 - .2 Friction loss.
 - .3 Acoustical loss.
 - .4 Leakage.
 - .5 Fire rating.
- .3 Test and Evaluation Reports:

- .1 Catalogue or published ratings to be those obtained from tests carried out by manufacturer or independent testing agency signifying adherence to codes and standards.

1.3 Delivery, Storage And Handling

- .1 Deliver, store and handle materials in accordance with Section with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
 - .1 Store materials indoors in dry location and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Replace defective or damaged materials with new.

Part 2 Products

2.1 General

- .1 Factory fabricated Class 1 flexible air ducts conforming to the requirements UL 181 and CAN/ULC-S110.
- .2 Joint mastics and tapes: listed and labelled in accordance with UL 181B and complying with CAN/ULC-S110.
- .3 Duct clamps: stainless steel construction with worm gear operators.
- .4 Pressure drop coefficients listed below are based on relative sheet metal duct pressure drop coefficient of 1.00.
- .5 Flame spread rating not to exceed 25. Smoke developed classification not to exceed 50.
- .6 Thermal resistance properties determined in accordance with ADC Flexible Duct Performance & Installation Standards using ASTM C518. Products shall bear the ADC Seal of Certification.

2.2 Non-Metallic – Uninsulated

- .1 Type NM-UN: non-collapsible, heavy duty vinyl-impregnated woven fibreglass cloth permanently bonded to, and supported by, corrosion resistant spring steel wire helix.
- .2 Performance:
 - .1 Factory tested to 2.5 kPa without leakage.
 - .2 Operating static pressure limits: 2.5 kPa positive, 0.25 kPa negative.
 - .3 Maximum relative pressure drop coefficient: 2.

2.3 Non-Metallic – Insulated (Lined)

- .1 Type NM-IL: non-collapsible, chlorinated polyethylene core (CPE) core permanently bonded to, and supported by, corrosion resistant spring steel wire helix with factory applied flexible mineral fibre acoustic insulation and encased in metallized polyester film (MPF) vapour barrier jacket reinforced with fibreglass scrim.

- .2 Performance:
 - .1 Factory tested to 2.5 kPa without leakage.
 - .2 Operating static pressure limits: 2.5 kPa positive, 0.25 kPa negative.
 - .3 Maximum relative pressure drop coefficient: 2.
 - .4 Thermal resistance: 0.74 W/m²-degrees C mean.
 - .5 Acoustical performance: Minimum insertion loss (dB/m of straight duct @ no flow) to following table:

Duct Diam:	Frequency (Hz)				
(mm)	125	250	500	1000	2000
150	4.9	6.6	11.8	12.8	12.8
200	2.6	3.9	9.5	11.5	11.8
300	6.6	8.5	8.5	11.5	9.8

Part 3 Execution

3.1 Examination

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for installation in accordance with manufacturer's written instructions.
 - .1 Visually inspect substrate.
 - .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.
 - .3 Proceed with installation only after unacceptable conditions have been remedied

3.2 Uct Installation

- .1 Install in accordance with SMACNA and ADC standards.
- .2 Joints shall be made up using mastic and duct clamps. Insulation and vapour barrier on type NM-IL flexible ducts shall be secured with a combination of tape and duct clamps.
- .3 Use to accommodate misalignment of branch ducts and diffusers. Provide type NM-IL flexible duct where connecting rigid duct is insulated internally or externally. Provide type NM-UN flexible duct where connecting rigid duct is not insulated.
- .4 Maximum length at each diffuser: 1,000 mm.
- .5 Maximum turn allowed: 30°. Otherwise use a rigid elbow.

3.3 Cleaning

- .1 Progress Cleaning: clean in accordance with Section 01 74 11 – Cleaning.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 - Cleaning.
- .3 Waste Management: separate waste materials for reuse and recycling.

- .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

END OF SECTION

Part 1 General

1.1 References

- .1 ASTM International
 - .1 ASTM C423, Standard Test Method for Sound Absorption and Sound Absorption Coefficients by the Reverberation Room Method.
 - .2 ASTM C916, Standard Specification for Adhesives for Duct Thermal Insulation.
 - .3 ASTM C1071, Standard specification for Fibrous Glass Duct Lining Insulation (Thermal and Sound Absorbing Material).
 - .4 ASTM C1338, Standard Test Method for Determining Fungi Resistance of Insulation Materials and Facings.
 - .5 ASTM G21, Standard Practice for Determining Resistance of Synthetic Polymeric Materials to Fungi.
- .2 National Fire Protection Association (NFPA)
 - .1 NFPA 90A, Standard for the Installation of Air Conditioning and Ventilating Systems.
 - .2 NFPA 90B, Standard for the Installation of Warm Air Heating and Air Conditioning Systems.
- .3 North American Insulation Manufacturers Association (NAIMA)
 - .1 NAIMA AH116, Fibrous Glass Duct Construction Standards.
- .4 Sheet Metal and Air Conditioning Contractor's National Association (SMACNA)
 - .1 SMACNA, HVAC Duct Construction Standards, Metal and Flexible.
 - .2 SMACNA IAQ Guideline for Occupied Buildings Under Construction.
- .5 Underwriter's Laboratories of Canada (ULC)
 - .1 CAN/ULC-S102, Standard Method of Test for Surface Burning Characteristics of Building Materials and Assemblies.

1.2 Action And Informational Submittals

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Provide manufacturer's printed product literature and datasheets for insulation and adhesives, and include product characteristics, performance criteria, physical size, finish and limitations.

1.3 Closeout Submittals:

- .1 Provide maintenance data for incorporation into manual specified in Section 01 78 00 - Closeout Submittals.

1.4 Delivery, Storage And Handling

- .1 Deliver, store and handle materials in accordance with Section with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
 - .1 Store materials indoors in dry location and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Replace defective or damaged materials with new.

Part 2 Products

2.1 Duct Liner

- .1 General:
 - .1 Mineral fibre duct liner: air surface coated with smooth matt acrylic polymer.
 - .2 Temperature limit: 121EC.
 - .3 Flame spread rating shall not exceed 25 and smoke development rating shall not exceed 50 when tested in accordance with CAN/ULC-S102.
 - .4 Water sorption: less than 3% by weight when tested in accordance with ASTM C1104.
 - .5 Fungi resistance: to ASTM C1338 and ASTM G21.
- .2 Rigid:
 - .1 Use on flat surfaces.
 - .2 25 mm thick, to ASTM C1071, Type II, fibrous glass rigid board duct liner.
 - .3 Density: 48 kg/m³ minimum.
 - .4 Thermal resistance to be minimum 0.76 (m². EC)/W for 25 mm thickness when tested in accordance with ASTM C177 or C518, at 24EC mean temperature.
 - .5 Maximum velocity on faced air side: 30 m/sec.
 - .6 Minimum NRC of 0.70 at 25 mm thickness based on Type "A" mounting to ASTM C423.
- .3 Flexible:
 - .1 Use on round or oval surfaces and where otherwise directed by Engineer.
 - .2 25 mm thick, to ASTM C1071 Type 1, fibrous glass blanket duct liner.
 - .3 Density: 24 kg/m³ minimum.
 - .4 Thermal resistance to be minimum 0.74 (m². EC)/W for 25 mm thickness when tested in accordance with ASTM C177 or C518, at 24EC mean temperature.
 - .5 Maximum velocity on coated air side: 30 m/sec.
 - .6 Minimum NRC of 0.65 at 25 mm thickness based on Type "A" mounting to ASTM C423.

2.2 Adhesive And Sealant

- .1 Adhesive and sealant: to ASTM C916.
- .2 Flame spread rating shall not exceed 25 and smoke developed classification shall not exceed 50. Temperature range minus 29EC to plus 93EC.
- .3 Water-based fire retardant type.

2.3 Fasteners

- .1 Weld pins 2.0 mm diameter, length to suit thickness of insulation. Metal retaining clips, 32 mm square.

2.4 Joint Tape

- .1 Poly-Vinyl treated open weave fiberglass membrane 50 mm wide.

2.5 Sealer

- .1 Meet requirements of NFPA 90A.
- .2 Flame spread rating shall not exceed 25. Smoke development rating shall not exceed 50. Temperature range minus 68 degrees C to plus 93 degrees C.

Part 3 Execution

3.1 Examination

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for installation in accordance with manufacturer's written instructions.
 - .1 Visually inspect substrate.
 - .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.
 - .3 Proceed with installation only after unacceptable conditions have been remedied.

3.2 General

- .1 Do work in accordance with SMACNA HVAC Duct Construction Standards except as specified otherwise.
- .2 Line inside of ducts where indicated.
- .3 Duct dimensions, as indicated, are clear inside duct lining.

3.3 Duct Liner

- .1 Install in accordance with manufacturer's recommendations, and as follows:
 - .1 Fasten to interior sheet metal surface with 100% coverage of adhesive.
 - .1 Exposed leading edges and transverse joints to be factory coated or coated with adhesive during fabrication.

- .2 In addition to adhesive, install weld pins not less than 2 rows per surface and not more than 450 mm on centres to compress duct liner sufficiently to hold it firmly in place.
 - .1 Spacing of mechanical fasteners in accordance with NAIMA AH124, Fibrous Glass Duct Liner Standard.
- .2 All joints to be tightly butted together with no interruptions or gaps.
- .3 Seal butt joints, exposed edges, weld pin and clip penetrations and damaged areas of liner.
- .4 Replace damaged areas of liner at discretion of Engineer.
- .5 Provide metal nosing over transverse oriented liner edges facing the airstream at the discharge of fans, at any section of lined duct preceded by unlined duct and where the continuity of liner is interrupted by duct mounted devices (e.g. fire dampers, coils).
- .6 Where duct air velocities exceed 20 m/sec provide sheet metal nosing on the leading edge of duct liner at every transverse joint.
- .7 Turning vane assemblies, dampers and other devices located inside lined ductwork shall be installed using insulated "build outs" secured to the duct wall.

3.4 Joints

- .1 Seal butt joints, exposed edges, weld pin and clip penetrations and damaged areas of liner with joint tape and sealer. Install joint tape in accordance with manufacturer's written recommendations, and as follows:
 - .1 Bed tape in sealer.
 - .2 Apply 2 coats of sealer over tape.
- .2 Replace damaged areas of liner at discretion of Departmental Representative.
- .3 Protect leading and trailing edges of duct sections with sheet metal nosing having 15 mm overlap and fastened to duct.

3.5 Cleaning

- .1 Progress Cleaning: clean in accordance with Section 01 74 11 – Cleaning.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 - Cleaning.
- .3 Waste Management: separate waste materials for reuse and recycling.
 - .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

END OF SECTION

Part 1 General

1.1 References

- .1 American National Standards Institute/Air Movement and Control Association (ANSI/AMCA)
 - .1 ANSI/AMCA Standard 99, Standards Handbook.
 - .2 ANSI/AMCA Standard 210/(ANSI/ASHRAE 51-07), Laboratory Methods of Testing Fans for Aerodynamic Performance Rating.
 - .3 ANSI/AMCA Standard 300, Reverberant Room Method for Sound Testing of Fans.
 - .4 ANSI/AMCA Standard 301, Methods for Calculating Fan Sound Ratings from Laboratory Test Data.

1.2 Action And Informational Submittals

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for HVAC fans and include product characteristics, performance criteria, physical size, finish and limitations.
- .3 Shop Drawings:
 - .1 Provide:
 - .1 Fan performance curves showing point of operation, bhp and efficiency.
 - .2 Sound rating data at point of operation.
 - .2 Indicate:
 - .1 Motors, sheaves, bearings, shaft details.
 - .2 Minimum performance achievable with variable speed controllers where applicable.

1.3 Maintenance Material Submittals

- .1 Extra Materials:
 - .1 Submit in accordance with Section 01 78 00 - Closeout Submittals.
 - .1 Provide:
 - .1 Matched sets of belts.
 - .2 Furnish list of individual manufacturer's recommended spare parts for equipment, include:
 - .1 Bearings and seals.
 - .2 Addresses of suppliers.
 - .3 List of specialized tools necessary for adjusting, repairing or replacing.

1.4 Delivery, Storage And Handling

- .1 Deliver, store and handle materials in accordance with Section with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
 - .1 Store materials indoors in dry location and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Replace defective or damaged materials with new.

Part 2 Products

2.1 System Description

- .1 Performance Requirements:
 - .1 Catalogued or published ratings for manufactured items: obtained from tests carried out by manufacturer or those ordered by manufacturer from independent testing agency signifying adherence to codes and standards in force.
 - .2 Capacity: flow rate, static pressure, W, efficiency, revolutions per minute, power, model, size, sound power data and as indicated on schedule.
 - .3 Fans: statically and dynamically balanced, constructed in conformity with ANSI/AMCA Standard 99.
 - .4 Sound ratings: comply with ANSI/AMCA Standard 301, tested to ANSI/AMCA Standard 300. Performance ratings: based on tests performed in accordance with ANSI/AMCA Standard 210.

2.2 Belt Drive Roof Downblast Centrifugal Exhaust Fans

- .1 General Description:
 - .1 Downblast fan shall be for roof mounted applications
 - .2 Maximum continuous operating temperature is 180 Fahrenheit (82.2 Celsius)
 - .3 Each fan shall bear a permanently affixed manufacture's engraved metal nameplate containing the model number and individual serial number.
- .2 Wheel:
 - .1 Constructed of aluminum
 - .2 Non-overloading, backward inclined centrifugal
 - .3 Statically and dynamically balanced in accordance to AMCA Standard 204-05
 - .4 The wheel cone and fan inlet will be matched and shall have precise running tolerances for maximum performance and operating efficiency
- .3 Motors:
 - .1 Motor enclosures: Open dripproof

- .2 Motors are permanently lubricated, heavy duty ball bearing type to match with the fan load and furnished at the specific voltage and phase.
- .3 Mounted on vibration isolators, out of the airstream.
- .4 For motor cooling there shall be fresh air drawn into the motor compartment through an area free of discharge contaminants.
- .5 Accessible for maintenance
- .4 Shafts and Bearings:
 - .1 Fan shaft shall be ground and polished solid steel with an anti corrosive coating
 - .2 Permanently sealed bearings or pillow block ball bearings
 - .3 Bearing shall be selected for a minimum L10 life in excess of 100,000 hours
 - .4 Bearings are 100 percent factory tested.
 - .5 Fan Shaft first critical speed is at least 25 percent over maximum operating speed.
- .5 Housing:
 - .1 Motor cover, shroud, curb cap, and lower windband shall be constructed of heavy gauge aluminum.
 - .2 Shroud shall have a integral rolled bead for extra strength.
 - .3 Shroud shall be drawn from a disc and direct air downward.
 - .4 Lower windband shall have a formed edge for added strength.
 - .5 Motor cover shall be drawn from a disc.
 - .6 All housing components shall have final thicknesses equal to or greater then preformed thickness.
 - .7 Curb cap shall have pre-punched mounting holes to ensure correct attachment.
 - .8 Rigid internal support structure.
 - .9 Leak proof
- .6 Housing Supports and Drive Frame:
 - .1 Drive frame assemblies shall be constructed of heavy gauge steel and mounted on vibration isolators
- .7 Vibration Isolation:
 - .1 Double studded or pedestal mount true isolators
 - .2 No metal to metal contact
 - .3 Sized to match the weight of each fan
- .8 Disconnect Switches:
 - .1 NEMA rated: 4
 - .2 Positive electrical shut-off
 - .3 Wired from fan motor to junction box installed within motor compartment
 - .4 Drive Assembly
 - .5 Belts, pulleys, and keys oversized for a minimum of 150 percent of driven horsepower

- .6 Belts: Static free and oil resistant
- .7 Fully machined cast iron type, keyed and securely attached to the wheel and motor shafts
- .8 The motor pulley shall be adjustable for final system balancing
- .9 Readily accessible for maintenance
- .9 Options/Accessories:
 - .1 Auto Belt Tensioner:
 - .2 Automatic tensioning device that adjusts for the correct belt tension, only for single drives
 - .3 Birdscreen:
 - .1 Material Type: Galvanized
 - .2 Protects fan discharge
 - .4 Roof Curbs:
 - .1 Mounted onto roof with fan
 - .2 Material: Aluminum
 - .3 Insulation thickness: 2 inches
 - .4 Coating Type: Baked Enamel
 - .5 Dampers:
 - .1 Type: Motorized, insulated
 - .2 Prevents outside air from entering back into the building when fan is off
 - .3 Balanced for minimal resistance to flow
 - .4 Galvanized frames with prepunched mounting holes

Part 3 Execution

3.1 Examination

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for installation in accordance with manufacturer's written instructions.
 - .1 Visually inspect substrate.
 - .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.
 - .3 Proceed with installation only after unacceptable conditions have been remedied.

3.2 Fan Installation

- .1 Install fans as indicated.
- .2 Provide sheaves and belts required for final air balance.
- .3 Bearings and extension tubes to be easily accessible.
- .4 Access doors and access panels to be easily accessible.

3.3 Anchor Bolts And Templates

- .1 Size anchor bolts to withstand and velocity forces anticipated

3.4 Cleaning

- .1 Progress Cleaning: clean in accordance with Section 01 74 11 – Cleaning.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 - Cleaning.
- .3 Waste Management: separate waste materials for reuse and recycling.
 - .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

END OF SECTION

Part 1 General

1.1 References

- .1 American Society of Heating, Refrigerating and Air-Conditioning Engineers, Inc. (ASHRAE).
 - .1 ASHRAE Standard 70, Method of Testing for Rating the Performance of Air Outlets and Inlets

1.2 Action And Informational Submittals

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for diffusers, registers and grilles and include product characteristics, performance criteria, physical size, finish and limitations.
 - .2 Indicate following:
 - .1 Capacity.
 - .2 Throw and terminal velocity.
 - .3 Noise criteria.
 - .4 Pressure drop.
 - .5 Neck velocity.

1.3 Maintenance Material Submittals

- .1 Extra Materials:
 - .1 Provide maintenance materials in accordance with Section 01 78 00 - Closeout Submittals.
 - .2 Include:
 - .1 Keys for volume control adjustment.
 - .2 Keys for air flow pattern adjustment.

1.4 Delivery, Storage And Handling

- .1 Deliver, store and handle materials in accordance with Section with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
 - .1 Store materials indoors in dry location and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Replace defective or damaged materials with new.

Part 2 Products

2.1 System Description

- .1 Performance Requirements:
 - .1 Catalogued or published ratings for manufactured items: obtained from tests carried out by manufacturer or those ordered by manufacturer from independent testing agency signifying adherence to codes and standards.

2.2 General

- .1 To meet capacity, pressure drop, terminal velocity, throw, noise level, neck velocity as indicated.
- .2 Frames:
 - .1 Full perimeter gaskets.
 - .2 Plaster frames where set into plaster or gypsum board.
 - .3 Concealed fasteners.
- .3 Concealed manual volume control damper operators.
- .4 Colour: as per schedule.

2.3 Manufactured Units

- .1 Grilles, registers and diffusers of same generic type, products of one manufacturer.

2.4 Diffusers, Grilles And Registers

- .1 Refer to schedule.
- .2 General requirements:
 - .1 To meet the features, capacity, pressure drop, terminal velocity, throw, noise level, and neck velocity of the scheduled product.
 - .2 Frames:
 - .1 Appropriate to surrounding construction material.
 - .2 Plaster frames where set into plaster or gypsum board and where otherwise specified.
 - .3 Full perimeter gaskets.
 - .4 Concealed fasteners.
 - .3 Concealed manual volume control damper operators.
 - .4 Flow Equalizing Grids: provide in the neck of all ceiling diffusers.
 - .5 Colour: baked off-white epoxy enamel unless otherwise directed by the Engineer.
 - .6 Grilles, registers and diffusers of same generic type to be the product of one manufacturer.
- .3 Features and performance: as scheduled. Scheduled characteristics govern where they conflict with the general requirements herein.

Part 3 Execution

3.1 Examination

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for installation in accordance with manufacturer's written instructions.
 - .1 Visually inspect substrate.
 - .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.
 - .3 Proceed with installation only after unacceptable conditions have been remedied.

3.2 Installation

- .1 Install in accordance with manufacturer's instructions.
- .2 Install with] screws in countersunk holes where fastenings are visible.
- .3 Bolt grilles, registers and diffusers, in place, in gymnasium and similar game rooms.
- .4 Provide concealed safety chain on each grille, register and diffuser in gymnasium and similar game rooms.

3.3 Cleaning

- .1 Progress Cleaning: clean in accordance with Section 01 74 11 – Cleaning.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 - Cleaning.
- .3 Waste Management: separate waste materials for reuse and recycling.
 - .1 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

END OF SECTION