REMOVE EXISTING CONVECTOR IN ALL RESPECTS. BREAK WALL TO CUT PIPE INSIDE WALL. RESTORE WALL TO MATCH ADJACENT CONDITIONS. CAP PIPING ABOVE CEILING.

RETAIN ALL DIFFUSERS AND GRILLES FOR REINSTALLATION. REFER TO M102 FOR NEW LOCATIONS OF ALL GRILLES AND DIFFUSERS.

CONTRACTOR TO COORDINATE SHUT-DOWNS WITH THE DEPARTMENTAL REPRESENTATIVE AS REQUIRED IN ORDER TO CUT AND CAP SERVICES.

ALL DIFFUSERS AND GRILLES WITHIN THE PROJECT CONSTRUCTION AREA SHALL BE REMOVED AND DUCT CAPPED AND SEALED DURING CONSTRUCTION. ALL GRILLE/DIFFUSERS SHOWN AS EXISTING TO REMAIN SHALL BE REINSTALLED AFTER CONSTRUCTION AND REBALANCED.

REMOVE EXISTING CONVECTOR IN ALL RESPECTS. BREAK WALL TO CUT PIPE INSIDE WALL. RESTORE WALL TO MATCH ADJACENT CONDITIONS. CAP PIPING ABOVE CEILING.

REMOVE EXISTING AIR LINE TO ABOVE THE CEILING AND CAP.

FIRE HOSE

3-AF T'STAT

CAP

HVAC DEMOLITION PLAN

1 / H1

SCALE/ÉCHELLE : 1:50

0m 1m 2m 3m 4m 5m

Public Works and Government Services Canada
Travaux Publics et Services gouvernementaux Canada

ARCHITECTURE + SUSTAINABLE DESIGN
SableARC STUDIOS
49 Water Street, Charlottetown PE C1A 1A3 - t. 902.816.0216
rhaggis@sablearc.com / www.sablearc.com

ORANGE DOOR ENGINEERING
49 Water Street, Charlottetown PE C1A 1A3 - t. 902.388.7685
joe@orangedoor.org / www.orangedoor.org

revisions		date
1.	ISSUED FOR TENDER	17.10.03
2.	ISSUED FOR ADDENDUM #1	17.10.26

project / projet

CID OFFICE RENOVATION – JOSEPH A. GHIZ BUILDING SUMMERSIDE, PE PRINCE COUNTY

drawing / dessin

HVAC LAYOUT DEMOLITION

designed / conçu	Joe Bystryk	
date	2017.08.02	
drawn / dessiné	Joe Bystryk	
date	2017.08.02	
approved / approuvé	Joe Bystryk	
date	2017.08.02	

Tender / Soumission
2017.08.02
PWGSC Project Manager / Administrateur de projets TPSGC

project number / no. du projet
R.090981.001

drawing no. / no. du dessin
H2 of 3