



## RETURN BIDS TO:

## RETOURNER LES SOUMISSIONS À:

Bid Receiving Public Works and Government  
Services Canada/Réception des soumissions Travaux  
publics et Services gouvernementaux Canada  
800 Burrard Street, Room 219  
800, rue Burrard, pièce 219  
Vancouver  
British Columbia  
V6Z 0B9  
Bid Fax: (604) 775-9381

## SOLICITATION AMENDMENT MODIFICATION DE L'INVITATION

The referenced document is hereby revised; unless otherwise  
indicated, all other terms and conditions of the Solicitation  
remain the same.

Ce document est par la présente révisé; sauf indication contraire,  
les modalités de l'invitation demeurent les mêmes.

### Comments - Commentaires

Vendor/Firm Name and Address  
Raison sociale et adresse du  
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution  
Public Works and Government Services Canada - Pacific  
Region  
800 Burrard Street, Room 219  
800, rue Burrard, pièce 219  
Vancouver  
British C  
V6Z 0B9

<b>Title - Sujet</b> Existing Utility Rehabilitation	
<b>Solicitation No. - N° de l'invitation</b> EZ899-181161/A	<b>Amendment No. - N° modif.</b> 003
<b>Client Reference No. - N° de référence du client</b>	<b>Date</b> 2017-10-31
<b>GETS Reference No. - N° de référence de SEAG</b> PW-\$PWY-036-8183	
<b>File No. - N° de dossier</b> PWY-7-40222 (036)	<b>CCC No./N° CCC - FMS No./N° VME</b>
<b>Solicitation Closes - L'invitation prend fin</b> <b>at - à 02:00 PM</b> <b>on - le 2017-11-06</b>	<b>Time Zone</b> <b>Fuseau horaire</b> Pacific Daylight Saving Time PDT
<b>F.O.B. - F.A.B.</b> <b>Plant-Usine:</b> <input type="checkbox"/> <b>Destination:</b> <input checked="" type="checkbox"/> <b>Other-Autre:</b> <input type="checkbox"/>	
<b>Address Enquiries to: - Adresser toutes questions à:</b> Martin (PWY), Delia	<b>Buyer Id - Id de l'acheteur</b> pwy036
<b>Telephone No. - N° de téléphone</b> (778) 707-2139 ( )	<b>FAX No. - N° de FAX</b> (604) 775-6633
<b>Destination - of Goods, Services, and Construction:</b> <b>Destination - des biens, services et construction:</b> Parks Canada (PCA) - Fort Rodd Hill National Historic Site - Colwood, BC	

Instructions: See Herein

Instructions: Voir aux présentes

<b>Delivery Required - Livraison exigée</b>	<b>Delivery Offered - Livraison proposée</b>
<b>Vendor/Firm Name and Address</b> <b>Raison sociale et adresse du fournisseur/de l'entrepreneur</b>	
<b>Telephone No. - N° de téléphone</b> <b>Facsimile No. - N° de télécopieur</b>	
<b>Name and title of person authorized to sign on behalf of Vendor/Firm</b> <b>(type or print)</b> <b>Nom et titre de la personne autorisée à signer au nom du fournisseur/</b> <b>de l'entrepreneur (taper ou écrire en caractères d'imprimerie)</b>	
<b>Signature</b>	<b>Date</b>

Solicitation. - N° de l'off. à comm.  
EZ899-181161/A

Amd. No. - N° de la modif.  
003

Buyer ID - Id de l'acheteur  
pwy036

Client Ref. No. - N° de réf. du client

File No. - N° du dossier  
PWY-7-40222

CCC No./N° CCC - FMS No/ N° VME

---

This Amendment #003 is raised to issue Addendum #03.

Please see Addendum #03 herein.

The addendum will form part of the contract documents.

**All other terms and conditions remain unchanged.**

The following changes in the tender documents are effective immediately. This addendum will form part of the contract documents
---

### **Tender Questions**

During the tender period Public Services and Procurement Canada has received various questions from Contractors. The following section lists the questions and the responses. The cost implication of the responses provided are to be included in the tender price.

- 1. Is the schedule of quantities in the specification to be used as the basis for payment or is this a lump sum tender?**

The schedule of quantities is provided for Contractor guidance only. Tender price shall be lump sum.

- 2. The schedule of quantities appears inconsistent with the drawings?**

Quantities indicated on Drawings govern.

- 3. The schedule of quantities has 100 cubic metres of rock removal. If additional rock is encountered will that be addressed by change order?**

Additional rock removal exceeding 100 cubic metres will be considered for additional payment.

- 4. Please confirm that we are allowed to blast trench rock?**

Rock removal shall be by machine breaker. Trench blasting will not be accepted for this contract at Fort Rodd Hill.

- 5. Sheet 2 and Addendum 1 say that the temporary water services is to be HDPE DR11 while another drawing calls for HDPE DR17?**

The temporary water service is to be a 150mm HDPE DR 11.

- 6. What are the requirements for winter protection of the temporary water service?**

The Contractor shall provide measures to prevent freezing of the temporary water service as required.

- 7. Does the lid for the backflow chamber require a true H20 load rating or is an occasional load rating acceptable?**

An occasional H20 load rating will be acceptable.

- 8. Is the opening for the backflow chamber required to be clear span?**

The opening for the irrigation backflow service box shall be clear span. The service box interior dimensions may be reduced to 860mm by 560mm.

**9. Is the culvert to be 300mm diameter as on sheet 2 or 375mm diameter as shown on the culvert outlet detail on sheet 10?**

The culvert shall be 300mm diameter CSP as per sheet 2.

**10. Are there details for the tie-ins to the CWO and next to CWO?**

There are no records for service details. Contractor to expose to confirm tie in requirements.

**11. Is the asphalt restoration meant to the full width of the path or strictly replacement of the asphalt removed for trenching?**

The asphalt restoration shall be provided for full path width for areas disturbed and indicated on the Drawings.

**12. Please confirm if the valves are to be place in pre-cast chambers or a nelson type box**

Gate valves to include Nelson type box per detail.

**13. Can we use the existing hydrant at the tie-in for flushing?**

The existing hydrant shall not be used for flushing purposes.

----End of Addendum----