SPECIFICATION

Lower Terra Nova Infrastructure Upgrades DFO Project No. F6879-179013 (Issued for Tender)



Meridian Engineering Inc.

To practice Professional Engineering in Newfoundland and Labrador.

Permit No. as issued by PEG <u>N0453</u> which is valid for the year <u>2017</u>



PREPARED FOR

Department of Fisheries & Oceans

DATE

October, 2017

SECTION	TITLE PAGE(S)	
	Title Page	1
	List of Drawings	1
01 10 10	General Instructions	10
01 16 10	Material Supplied by Canada	3
01 29 83	Payment Procedures for Testing Laboratory Services	2
01 32 18	Construction Progress Schedules - Bar (GANTT) Chart	3
01 33 00	Submittal Procedures	5
01 35 24	Special Procedures on Fire Safety Requirements	4
01 35 25	Special Procedures on Lockout Requirements	6
01 35 29	Health & Safety Requirements	10
01 35 43	Environmental Procedures	7
01 45 00	Testing and Quality Control	4
01 50 00	Temporary Facilities	2
01 56 00	Temporary Barriers and Enclosures	1
01 61 00	Common Product Requirements	4
01 74 11	Cleaning	2
01 74 21	Construction/Demolition Waste Management & Disposal	5
01 77 00	Closeout Procedures	2
01 78 00	Closeout Submittals	5
02 41 16	Demolition and Removal	1
03 10 00	Concrete Formwork	2
03 20 00	Concrete Reinforcement	2
03 30 00	Cast-in-Place Concrete	8
03 35 00	Concrete Finish	2
06 10 00	Rough Carpentry	5
13 34 23.01	Building Structures & Equipment	7
32 01 91	Tree & Shrub Preservation	2
32 11 23	Aggregate Base Courses	2
35 00 00	Dewatering	2

List of Appendices

PROJECT NO. F6879-179013

Appendix A	-	Contractor's	Сору о	f the	Regulatory	Approvals

Appendix B - Photos

DFO	LIST OF DRAWINGS	PAGE 1 OF 1
Lower Terra Nova		
Infrastructure Upgrades		
PROJECT NO. F6879-179013		

DRAWING NUMBER	DRAWING TITLE
C1 of 7	Existing Site Plan with Demolition
C2 of 7	Existing Accommodations Building with Demolition
C3 of 7	New Site Plan
C4 of 7	New Repairs - Accommodations Building
C5 of 7	New Equipment Shed
C6 of 7	New Patio Deck/Boardwalk Sections & Details
C7 of 7	Miscellaneous Details

DFO General Instructions Section 01 10 10
Lower Terra Nova
Infrastructure Upgrades Page 1 of 10
Project No. F6879-179013

PART 1 - GENERAL

1.1 SCOPE

.1 The work covered under this project consists of the furnishing of all plant, labour, equipment, hardware and materials, complete and in strict accordance with specifications and accompanying drawings and subject to all terms and conditions of contract. Bidders are advised that opportunities and requirements may arise that may warrant changes to the work that are in keeping with this general scope of work. Such changes will be made through the change order processes as outlined in the contract documents.

1.2 DESCRIPTION

- .1 The work will generally consist of but will not necessarily be limited to the following:
 - .1 Demolition and removal of the existing timber boardwalks, patio decks, and equipment shed, as indicated on the drawings;
 - .2 Removal of the existing formwork tie rods located at the existing fishway entrance, as indicated on the drawings;
 - .3 Repairs to the accommodations building, including replacement of underlying footings and new metal roofing, as indicated on the drawings;
 - .4 Construction of new timber boardwalks and patio decks, as indicated on the drawings;
 - .5 Construction of a new equipment shed, as indicated on the drawings;
 - .6 Replacement of the existing on-demand propane water heater and propane space heater, as indicated on the drawings;
 - .7 Upgrades to the off-grid power supply system (solar power system), as indicated on the drawings, including replacement of the charge controller/regulator, batteries and insulated enclosure, and inverter power board assembly;
 - .8 Repairs to the concrete diversion wall, as indicated on the drawings, including construction and maintenance of temporary dewatering devices and structures as required;
 - .9 Construction of handrailing on one side of existing timber bridge approach, as indicated on the drawings;
 - .10 Site clean-up;
 - .11 Note: See Part 1.7 Examination of Site and Part 1.16 Site Access for details regarding DFO provided helicopter services.
 - .12 Note: See part 1.5 scheduling and work methodology for construction deadline details.

DFO Lower Terra Nova		General Instructions Section 01 10 10
Infrastructure Upgrades Project No. F6879-179013		Page 2 of 10
1.3 FISH HABITAT/DOMESTIC USAGE	.1	Contractors are advised that this project is being carried out in an area where fish habitat may be affected. The contractor will perform the work to conform with all rules and regulations governing fish habitat and in accordance with governing authorities.
	.2	There shall be no fishing in and around the construction site during the regulated fishing season, even if the employees are in possession of a legal fishing license
	.3	The Contractor shall confirm the times, dates, ar extent of work required with local fish habita authorities.
	. 4	Contact the Department of Fisheries and Oceans (DFC at least 48 hours in advance of starting any work of site.
	.5	For inquiries regarding fish habitat please contacthe Departmental Representative (Contracting Officer).
1.4 SITE OF WORK	.1	Work will be carried out at the existing site at Lower Terra Nova Fishway, NL, in the location as shown of the accompanying drawings. The Lower Terra Nova Fishwasite is located on the Terra Nova River approximatel 9km upstream from Glovertown, NL. The work site is remote and not accessible by road. For the purpos of this work, DFO will be providing helicopter services Refer to part 1.16 of this section for additional information.
1.5 SCHEDULING AND WORK METHODOLOGY	.1	Construction must be substantially complete by Marc 31, 2018, which requires work to be completed during the winter of 2017/2018.
	.2	All work must be carried out in the dry. Where bern are required to accomplish this, the design of subberns is to be carried out by a professional engined licensed to practice in Newfoundland and Labrador Drawings of the bern design, stamped by the engineer are to be submitted to the Departmental Representative before any work starts.
1.6 DATUM	.1	All bearings on the Drawings are grid based on NF1 3 Transverse Mercator Projection. Coordinates as derived from static GPS referenced from control static 637001 (N 5,374,798.968 E 215,351.423). PWC contropoint coordinates are listed on the drawing.

DFO	General Instructions	Section 01 10 10
Lower Terra Nova		
Infrastructure Upgrades		Page 3 of 10
Project No. F6879-179013		_

.2 Bidders are advised to consult the Department of Environment and Conservation and the Government of Canada Wateroffice in order to make sure of changing water level conditions affecting work.

1.7 EXAMINATION OF SITE

. 1

- Before submitting a bid, it is mandatory that bidders visit the site and its surroundings to review and verify the form, nature and extend of work, materials necessary for the completion of the works, the means of access to the site, severity, exposure and uncertainty of weather, soil conditions, accommodations they may require, and in general shall obtain all necessary information as to risks, contingencies and other circumstances which may influence or affect their bid. No allowance shall be made subsequently in this connection on account of error or negligence to properly observe and determine the conditions that will apply. DFO will provide helicopter services for the mandatory pre-tender site visit. See below.
- .2 DFO will schedule a site visit during the tender period. The site visit will occur over a one day period with helicopter flights leaving from and returning to Clarenville. Contractor is responsible for all costs associated with getting to and from Clarenville. Specific meeting location will be clarified at the tender stage. Departmental Representative will pay for helicopter services associated with the one day site visit held during the tender period. Contractors wishing to visit site shall contact the Departmental Representative to obtain flight times/schedule. Please note the following:
 - If weather doesn't permit flying on the scheduled site visit day, it will occur on the following day.
 - A maximum of 1 person per Contractor will be permitted.
 - Time allocated on site will be a maximum of 2 hours.
 - 2 days advance notice is to be given to the Departmental Representative with respect to the company and individuals attending the visit.
 - The Site visit will occur within 8 calendars days after the project is tendered.
- .3 Contractors, bidders or those they invite to site are to review specification Section 01 35 29 Health and Safety Requirements before visiting site. Take all appropriate safety measures for any visit to site, either before or after acceptance of bid.

DFO			General Instructions	Section 01 10 10	
Lower Terra Nova Infrastructure Upgrades Project No. F6879-179013				Page 4 of 10	
contractors an appreciation of site condi general understanding of the project scope These photos should in no way be cons replacement to an actual site visit. Contra required to visit the site as per part 1.			otos are intended to give the tion of site conditions and the project scope of work. In no way be considered a site visit. Contractors are ite as per part 1.7 of this Any interpretations and/or spect to these photos are the		
1.9	TERMS	.1	Engineer where used in t Drawings shall mean the	tated otherwise, the term he Specifications and on the Department Representative as onditions of the Contract.	
		. 2	under seal of a profes	s are required to be submitted sional Engineer licensed to es refer to an Engineer, and resentative.	
1.10	COST BREAKDOWN	. 1		st progress claim submit ice in detail as directed by ive and aggregating contract	
		. 2	and subject title system	n same format as the numerical used in this specification ed into major work components tal Representative.	
		. 3		mental Representative, cost basis for progress payment.	
		. 4	This project will be lump to be included.	sum. All work items and costs	
1.11	WORK SCHEDULE	. 1	of acceptance of bid, a commencement and completi	working days of notification construction schedule showing on of all work within the time stance form and the date stated tter.	
		. 2	illustrate entire implem efficient coordination o achieve completion of wor	entation plan, depicting f tasks and resources, to k on time and permit effective ess in relation to established	

DFO General Instructions Section 01 10 10
Lower Terra Nova
Infrastructure Upgrades Page 5 of 10
Project No. F6879-179013

milestones.

- As a minimum, work schedule to be prepared and submitted in the form of bar (GANTT) charts, indicating work activities, tasks and other project elements, their anticipated durations and planned dates for achieving key activities and major project milestones provided in sufficient details and supported by narratives to demonstrate a reasonable plan for completion of project within designated time (e.g., show target dates for completion of each structure element, if applicable). Breakdown the structure elements to indicate target dates for completion of each element. Generally, bar charts derived from commercially available computerized project management systems are preferred but not mandatory.
- .4 Submit schedule updates on a minimum monthly basis and more often, when requested by Departmental Representative, due to frequent changing project conditions. Provide a narrative explanation of necessary changes and schedule revisions at each update.
- .5 The schedule, including all updates, shall be to the Departmental Representative's approval. Take necessary measures to complete work within approved time. Do not change schedule without Departmental Representative's approval.
- All work on the project will be completed within the time indicated on the Bid and Acceptance Form.
- .7 Should contractor find that he cannot maintain schedule as originally intended, he will immediately submit a revised schedule without being requested to do so by Departmental Representative.
- .8 Work schedule to be consistent with scheduling and methodology restrictions previously noted in Part 1.5.

1.12 ABBREVIATIONS

- 1 Following abbreviations of standard specifications have been used in this specification and on drawings.
 - CGSB Canadian Government Specifications Board CSA - Canadian Standards Association NLGA - National Lumber Grades Authority
 - ASTM American Society for Testing and Materials.
- .2 Where these abbreviations and standards are used in this project, latest edition in effect on date of tender call will be considered as applicable.

DFO	Conoral		Section 01 10 10
Lower Terra Nova Infrastructure Upgrades Project No. F6879-179013	General	l Instructions	Page 6 of 10
1.13 LAYOUT OF WORK .			in detail from control points Departmental Representative.
	layout indica		y for and execute complete ns, lines and elevations by Departmental
	3 Provid	de devices needed to	layout and construct work.
	requi		raight edges and templates partmental Representative's
		y stakes and other s g out work.	survey markers required for
		ractor will be responsilt survey of all new	sible to complete and submit w work.
1.14 QUARRY AND . EXPLOSIVES	authon quarry and ma	rities and owners of ying and transportati	arrangements with Provincial private properties, for the on of rock and all materials or work over their property, may be.
1.15 SITE OPERATIONS	for co so on. public for sp to the All co prese	onduct of operations . Exercise care so a c or private property pace and access will e approval of the De clearing and grubb	ace adjacent to project site s, storage of materials and as not to obstruct or damage v in area. All arrangements be made by contractor and epartmental Representative. ing work, including tree accordance with applicable
. 2	condit repain mater:	tion. Damage to gr red by contractor. ials, residue, exces	estore area to its original round and property will be Remove all construction s, etc., and leave site in Departmental Representative.
. :	in a r		aired to maintain safe access damage existing structures rations of others.
1.16 SITE ACCESS .	is not access	t accessible by road s will be approved fo	is in a remote location that way. Therefore, helicopter or site access. The Helicopter Site Access

DFO	General Instructions	Section 01 10 10
Lower Terra Nova Infrastructure Upgrades Project No. F6879-179013		Page 7 of 10
	Plan/Timeline to the Departr later than seven (7) days fol	
•	DFO will provide helicopter purposes, to a maximum of 50 time. Any additional helicopter complete the work in accordadocuments will be at the Corcoordinate all helicopter separtmental Representative	O hours helicopter flying oter time required to ance with the contract attractor's expense.
	3 The Contractor may require to measures, once at the site. The period of the removed upon completion of distributed features must be existing conditions. If any measures require approval from these approvals/permits and Departmental Representative period of the second of the secon	hese on-site measures must of the project, and all e reinstated, as per the temporary on-site access om governing authorities, the Contractor to obtain submit them to the
1.17 PROJECT MEETING .	1 Departmental Representative meetings and assume responsand recording minutes.	
	2 Project meetings will take pl so directed by Departmental	
	3 Departmental Representative of for recording minutes of meet to all parties present at me	ings and forwarding copies
	4 Have a responsible member of f Meetings.	firm present at all Project
1.18 PROTECTION .1	Store all materials and equinto work to prevent damage	
.2	Repair or replace all mater in transit or storage to the no cost to, the Departmental	e satisfaction of, and at
1.19 DOCUMENTS REQUIRED .	<pre>1 Maintain at job site, one (1) o .1 Contract drawings. .2 Specifications. .3 Addenda. .4 Reviewed shop drawings. .5 List of outstanding sho .6 Change Orders. .7 Other modifications to</pre>	op drawings.

DFO	General Instructions Section 01 10 10
Lower Terra Nova Infrastructure Upgrades Project No. F6879-179013	Page 8 of 10
	 .8 Field test reports. .9 Copy of approved work schedule. .10 Site specific Health and Safety Plan and other safety related documents. .11 Permits and Regulatory Approvals and Requirements. .12 Other documents as stipulated elsewhere in the Contract Documents.
1.20 TAXES AND PERMITS .1	Obtain and pay for all permits, certificates and licenses as required by Municipal, Provincial, Federal and other authorities.
. 2	Provide appropriate notifications of project to Municipal and Provincial inspection authorities.
. 3	Obtain compliance certificates as prescribed by legislative and regulatory provisions of Municipal, Provincial and Federal authorities as applicable to the performance of work.
. 4	Submit to Departmental Representative, copy of application submissions and approval documents received for above referenced authorities.
. 5	Submit to Departmental Representative, copy of quarry permit, if applicable, prior to start of quarry operations.
. 6	Comply with all requirements, recommendations and advice by all regulatory authorities unless otherwise agreed in writing by Departmental Representative. Make requests for such deviations to these requirements sufficiently in advance of related work.
.7	See Appendices for Regulatory Approvals and Responses already obtained by Canada for this project.
1.21 EXISTING .1 SUB-SURFACE CONDITIONS	There is no previous information pertaining to the existing sub-surface conditions.
1.22 CONTRACTOR'S USE .1 OF SITE	The contractor is advised that the construction operations, including storage of materials, for this contract must not interfere with the normal operations at the site.
. 2	The contractor will be solely responsible for arranging the storage of materials on or off the site.

Exercise care so as not to obstruct or damage public

DEO			General Instructions	Section 01 10 10
DFO Lower Terra Nova Infrastructure Upgrades			General Instructions	Section UI 10 10
				Page 9 of 10
Project No. F6879-179013				10.30 7 01 10
			or private property in the ar	cea.
1.23 WORK COMMENCEMENT		.1	Mobilization to project site is after acceptance of bid and sub Safety Plan, unless otherwise Representative.	omission of site specific
		. 2	Construction activities/proje as soon as possible after noti a continuous reasonable workf directed by Departmental Repr	ce of tender award, with force unless otherwise
		.3	Weather conditions, winter corestrictions, delivery challe deadlines (substantially compand the location of the work of longer working days and accomplete the project within time.	nges, project completion lete by March 31, 2018), site may require the use dditional workforce to
		. 4	Make every effort to ensure tand equipment is delivered to possible date after acceptances required.	to site at the earliest
1.24	ACCEPTANCE	.1	Prior to the issuance of the Ce Performance, in company with Representative, make a check of discrepancies before final in	Departmental of all work. Correct all
1.25	WORKS COORDINATION	.1	Responsible for coordinating trades, where the work of such each other.	
		.2	Convene meetings between trad and ensure that they are full the extent of where interfaci- each trade with the plans and interfacing trade, as require planning and carrying out the	y aware of the areas and ng is required. Provide d specifications of the ed, to assist them in
		.3	Canada will not be responsible for any extra costs incurred a to carry out coordination work various trades as a result of of the areas and extent of int sole responsibility of the Genebe resolved at no extra cost	s a result of the failure k. Disputes between the their not being informed terface work shall be the eral Contractor and shall

DFO	General Instructions	Section 01 10 10
Lower Terra Nova		
Infrastructure Upgrades		Page 10 of 10
Project No. F6879-179013		

. 1

1.26 INTERPRETATION OF DOCUMENTS

Supplementary to the General Conditions, the Division 01 sections of the specifications take precedence over technical specification in other divisions of the specifications.

1.27 BIODEGRADABLE HYDRAULIC OILS

.1 Equipment working in and adjacent to water way shall be equipped with biodegradable hydraulic oils specifically intended for environmentally sensitive areas. Contractor shall submit MSDS and Technical Data sheets on hydraulic oil to be used for approval by the Departmental Representative.

PART 2 - PRODUCTS

2.1 NOT USED

PART 3 - EXECUTION

3.1 NOT USED

PART 1 - GENERAL

1.1 GENERAL

DFO

Canada will supply certain materials . 1 in the Contract for installation and incorporation into the Work by the Contractor.

1.2 MATERIAL SUPPLIED

Canada will supply: New . 1 Solar Batteries 12 X Deca Solar Photovoltaic Batteries, Cell Type AVR95-25L.

> The above materials supplied by Canada is not a complete list required to complete the work in accordance with drawings and specifications. Additional accessories mav required, including wiring, conduit, etc., any of these items are the responsibility of the Contractor, and may not be supplied by Canada.

. 2 The materials supplied by Canada are to be picked-up by the Contractor and delivered to the site. The location of all Canada supplied materials to be picked-up, is at the CCG Base in Stephenville, NL. The contact person Jackie Rodway (709-772-6409). Contractor to provide three (3) day notice prior to pick-up of materials.

1.3 DELIVERY REQUIREMENTS

- .1 Materials supplied by Canada will be available for pick-up following acceptance of Bid. Once turned over to the Contractor, the Contractor will be responsible for delivery to the work site.
- . 2 The Contractor will become responsible to supply all missing materials and repair or replace damaged items and missing parts discovered during transportation to site.
- Failure of the Contractor to make a . 3 complete check of the Canada-supplied material and to acknowledge receipt of same once picked up at the DFO storage

Lower Terra Nova Infrastructure Upgrades PROJECT NO. F6879-179013

Page 2 of 3

facility in Mount Pearl, shall not relieve him of this contractual responsibility to replace or repair any item subsequently found to be missing or damaged.

.4 Departmental Representative will make final determination as to whether an item can be repaired or must be replaced.

1.4 CONTRACTOR'S DUTIES

- .1 Pick-up Canada-supplied material, at the CCG Base in Stephenville, NL.
- .2 Take possession of Canada-supplied material immediately upon pick-up and be responsible for transportation to site.
- .3 Obtain and pay for services to load and transport to site.
- .4 Unload and handle at site, including lifting, uncrating, etc.
- .5 Store material on site at a location approved by Departmental Representative. Provide protection against inclement weather and site damage by use of appropriate covers.
- .6 Be responsible for the protection of such material against damage, loss, theft and fire from date of receipt, during transportation, loading, unloading, temporary storage and until final installation of work is accepted by the Departmental Representative.
- .7 Any damage or loss of such material shall result in the Contractor being responsible for replacement or repair of equipment at no cost to Canada.
- .8 The decision as to whether damaged items may be repaired or must be replaced with new equipment shall be the Departmental Representative's decision.
- .9 Install such material and incorporate into the work. Perform assembly and

									_
DFO	Material	Supplied k	оу	Canada	SECTION	01	16	1	0
Lower Terra Nova									
Infrastructure Upgrade	es								
PROJECT NO. F6879-179	013				Pac	re .	3 o	f	3

make all connections as required to make item functional.

.10 Dispose of containers, crating and protective covering off site as directed by the Departmental Representative.

DFO		Payment Procedures for	Section 01 29 83
Lower Terra Nova Infrastructure Upgrades Project No. F6879-179013		Testing Laboratory Services	Page 1 of 2
PART 1 - GENERAL			
1.1 SECTION INCLUDES		Inspecting and testing by insp laboratories approved by Depa Representative.	
	.2	Contractor shall submit for an Representative the name any contractor independent testing companies carry out testing as specifications.	qualifications of s/agencies required to
1.2 RELATED REQUIREMENTS SPECIFIED ELSEWHERE	3.1	Particular requirements for in be carried out by testing ager by Departmental Representation various sections.	ncy/laboratory approved
1.3 APPOINTMENT AND PAYMENT	.1	agency/laboratory reveal work contract requirements, pay cos	required by orders of erformed exclusively for ates of compliance. The remarks of Departmental remembers of Departmental Representative ecifications when the solumentation or test fied in the following by approved testing not in accordance with sts for additional tests ared by Departmental

1.4 CONTRACTOR'S RESPONSIBILITIES

- .1 Provide labour, equipment and facilities to:
 - .1 Provide access to work to be inspected and tested.
 - .2 Facilitate inspections and tests.
 - .3 Make good work disturbed by inspection and test.

DFO		Payment Procedures for Section 01 29 83
Lower Terra Nova Infrastructure Upgrades Project No. F6879-179013		Page 2 of 2 Testing Laboratory Services
110 Jeec No. 10075 175015		.4 Provide storage on site for laboratory's exclusive use to store equipment and cure test samples.
	. 2	Notify Departmental Representative sufficiently in advance of operations to allow for assignment of laboratory personnel and scheduling of test.
	.3	Where materials are specified to be tested, deliver representative samples in required quantity to testing laboratory.
	. 4	Pay costs for uncovering and making good Work that is covered before required inspection or testing is completed and approved by Departmental Representative.
PART 2 - PRODUCTS		
2.1 NOT USED	.1	Not Used.
PART 3 - EXECUTION		
3.1 NOT USED	.1	Not Used.

DFO	Construction Progress	Section 01 32 18
Lower Terra Nova Infrastructure Upgrades		Page 1 of 3
Project No. F6879-179013	Schedules - Bar (GANTT)Chart	1430 1 01 0
PART 1 - GENERAL		
1.1 PRECEDENCE .	For Federal Government projects take precedence over technical s in other Divisions of this Proj	pecification sections
1.2 DEFINITIONS .	Activity: An element of Work per of Project. An activity normall duration, and expected cost and requirements. Activities can be s	y has an expected expected resource
	Bar Chart (GANTT Chart). A graph schedule-related information. It activities or other Project elements ide of chart, dates are stactivity durations are shown as departed bars. Generally Bar Chart should commercially available computer management system.	n typical bar chart, ments are listed down hown across top, and ate-placed horizontal d be derived from
	Baseline: Original approved plate package, or activity), plus or changes.	
	Construction Work Week: Monday to will provide five day work week calendar working days as part o submission.	and define schedule
	Duration: Number of work period holidays or other nonworking pe complete an activity or other Pro expressed as workdays or workwe	riods) required to pject element. Usually
	Master Plan: A summary-level sch major activities and key milest	
	Milestone: A significant event completion of major deliverable	
	Project Schedule: The planned d activities and the planned date milestones. A dynamic, detailed activities that must be accomplis objectives. Monitoring and cont using Project Schedule in execu activities and is used as basis throughout project life cycle.	s for meeting record of tasks or hed to satisfy Project rol process involves ting and controlling

.9

Project Planning, Monitoring and Control System:

established milestones.

Overall system operated by Departmental Representative to enable monitoring of project work in relation to

DFO		Construction Progress	Section 01 32 18
Lower Terra Nova Infrastructure Upgrades Project No. F6879-179013		Schedules - Bar (GANTT)Chart	Page 2 of 3
1.3 REQUIREMENTS .	1	Ensure Master Plan and Detail Sc and remain within specified Con	
	2	Plan to complete Work in accord milestones and time frame.	ance with prescribed
	3	Ensure that it is understood th or time of beginning, rate of p Certificate and Final Certificat completion are of essence of th	rogress, Interim ce as defined times of
1.4 SUBMITTALS .	1	Submit to Departmental Represent days of Award of Contract Bar (GPlan for planning, monitoring and progress.	ANTT) Chart as Master
	2	Submit Project Schedule to Depart within 5 working days of receipt of Plan.	
1.5 PROJECT . MILESTONES .	1	Project milestones form interim Schedule. Identify and submit t Representative.	
1.6 MASTER PLAN .	1	Structure schedule to allow ord organizing and execution of Work	
	2	Departmental Representative wil revised schedules within 5 work	
	3	Revise impractical schedule and working days.	resubmit within 5
	4	Accepted revised schedule will be used as baseline for updates	
1.7 PROJECT . SCHEDULE	1	Develop detailed Project Schedul Plan.	e derived from Master
	2	Ensure detailed Project Schedul milestone and activity types as .1 Award2 Shop Drawings, Samples3 Permits4 Mobilization5 Dewatering.	

DFO	Construction Progress	Section 01 32 18
Lower Terra Nova		- 2 5 2
Infrastructure Upgrades	G lead de la	Page 3 of 3
Project No. F6879-179013	Schedules - Bar (GANTT)Cha	rt
	.6 Site Access.	
	.7 Demolition and Remova	1.
	.8 Debris Removal.	
	.9 Rock Removal.	
	.10 Concrete Work.	
	.11 Site Clean-up/Site Re	
	.12 Close-out Documentati	on
	.13 Demobilize.	
1.8 PROJECT	l Update Project Schedule eve	ry 2 wooks roflosting
SCHEDULE REPORTING	activity changes and complete	
	in progress.	
•	Include as part of Project S identifying Work status to progress to baseline, prese	date, comparing current
	defining problem areas, anti with possible mitigation.	cipated delays and impact
1.9 PROJECT	Discuss Project Schedule at identify activities that ar provide measures to regain	e behind schedule and
	considered behind schedule start or completion dates la dates shown on baseline sch	are those with projected ter than current approved
PART 2 - PRODUCTS		
PART 2 - PRODUCTS		
2.1 NOT USED	l Not used.	
PART 3 - EXECUTION		
3.1 NOT USED	L Not used.	

DFO	Submittal Procedures	Section 01 33 00
DFO	Submittal Procedures	Section of 33 of
Lower Terra Nova		
Infrastructure Upgrades		Page 1 of 5
Project No. F6879-179013		

PART 1 - GENERAL

1.1 SECTION INCLUDES

- .1 Shop drawings and product data.
- .2 Samples.
- .3 Certificates.

1.2 SUBMITTAL GENERAL REQUIREMENTS

- .1 Submit to Departmental Representative for review submittals listed, including shop drawings, samples, certificates and other data, as specified in other sections of the Specifications.
- .2 Submit with reasonable promptness and in orderly sequence so as to allow for Departmental Representative's review and not cause delay in Work. Failure to submit in ample time will not be considered sufficient reason for an extension of Contract time and no claim for extension by reason of such default will be allowed.
- .3 Do not proceed with work until relevant submissions are reviewed by Departmental Representative.
- .4 Present shop drawings, product data, samples and mock-ups in SI Metric units.
- .5 Where items or information is not produced in SI Metric units, provide soft converted values.
- Review submittals prior to submission to Departmental Representative. Ensure during review that necessary requirements have been determined and verified, required field measurements or data have been taken, and that each submittal has been checked and co-ordinated with requirements of Work and Contract Documents.
 - .1 Submittals not stamped, signed, dated and identified as to specific project will be returned unexamined by Departmental Representative and considered rejected.
- .7 Notify Departmental Representative, in writing at time of submission, identifying deviations from requirements of Contract Documents stating reasons for deviations.
- .8 Verify field measurements and affected adjacent work and coordinate.
- .9 Contractor's responsibility for errors and omissions in submission is not relieved by Departmental

DFO	Sı	ubmittal Procedures	Section 01 33 00
Lower Terra Nova			
Infrastructure Upgrades			Page 2 of 5
Project No. F6879-179013			
		Representative's review of s	ubmittals.
	.10	Submittal format: paper original clear and fully legible photographic paper are not acceptable circumstances pre-approved Representative. Poorly photocopies or facsimiles with the returned for resubmission	tocopies of originals. ble, except in special d by Departmental printed non-legible ll not be accepted and
	.11	Make changes or revisions Departmental Representative rewith Contract Documents and representative Departmental Representative notify Departmental Representative revisions other than those re-	may require, consistent resubmit as directed by . When resubmitting, ative in writing of any
	.12	Keep one reviewed copy of eac site for duration of Work.	h submittal document on

1.3 SHOP DRAWINGS AND PRODUCT DATA

- .1 The term "shop drawings" means drawings, diagrams, illustrations, schedules, performance charts, product data, brochures and other data which are to be provided by Contractor to illustrate details of a portion of Work.
- .2 Number of Shop Drawings: submit sufficient copies of shop drawings which are required by the General Contractor and sub-contractors plus four (4) copies which will be retained by Departmental Representative. Ensure sufficient numbers are submitted to enable one complete set to be included in each of the maintenance manuals specified, if applicable.
- .3 Shop Drawings Content and Format:
 - .1 Indicate materials, methods of construction and attachment or anchorage, erection diagrams, connections, explanatory notes and other information necessary for completion of Work. Where items or equipment attach or connect to other items or equipment, confirm that all interrelated work has been coordinated, regardless of section or trade from which the adjacent work is being supplied and installed.
 - .2 Shop Drawings Format:
 - .1 Opaque white prints or photocopies of original drawings or standard drawings modified to clearly illustrate work specific to project requirements. Maximum sheet size to be $1000 \times 707 \text{ mm}$.
 - .2 Product Data from manufacturer's standard catalogue sheets, brochures, literature, performance charts and diagrams, used to

DFO	Submittal Procedures	Section 01 33 00
Lower Terra Nova		
Infrastructure Upgrades		Page 3 of 5
Project No. F6879-179013		

- illustrate standard manufactured products, to be original full colour brochures, clearly marked indicating applicable data and deleting information not applicable to project.
- .3 Non or poorly legible drawings, photocopies or facsimiles will not be accepted and returned not reviewed.
- .3 Supplement manufacturer's standard drawings and literature with additional information to provide details applicable to project.
- .4 Delete information not applicable to project on all submittals.
- .4 Allow ten (10) calendar days for Departmental Representative's review of each submission.
- .5 Adjustments or corrections made on shop drawings by Departmental Representative are not intended to change Contract Price. If adjustments affect value of Work, advise Departmental Representative in writing prior to proceeding with Work.
- .6 If upon review by Departmental Representative, no errors or omissions are discovered or if only minor corrections and comments are made, fabrication and installation may proceed upon receipt of shop drawings. If shop drawings are rejected and noted to be resubmitted, do not proceed with that portion of work until resubmission and review of corrected shop drawings, through same submission procedures indicated above.
- .7 Accompany each submission with transmittal letter, containing:
 - .1 Date.
 - .2 Project title and project number.
 - .3 Contractor's name and address.
 - .4 Identification and quantity of each shop drawing, product data and sample.
 - .5 Other pertinent data.
- .8 Submissions shall include:
 - .1 Date and revision dates.
 - .2 Project title and project number.
 - .3 Name and address of:
 - .1 Subcontractor.
 - .2 Supplier.
 - .3 Manufacturer.
 - .4 Contractor's stamp, signed by Contractor's authorized representative certifying approval of submissions, verification of field measurements and compliance with Contract Documents.
 - .5 Cross references to particular details of contract drawings and specifications section number for which shop drawing submission

DFO	Submittal Procedures	Section 01 33 00
Lower Terra Nova		Dans 1 of [
Infrastructure Upgrades Project No. F6879-179013		Page 4 of 5
	addresses.	

- Details of appropriate portions of Work as . 6 applicable:
 - . 1 Fabrication.
 - . 2 Layout, showing dimensions, including identified field dimensions, and clearances.
 - . 3 Setting or erection details.
 - Capacities. . 4
 - .5 Performance characteristics.
 - .6 Standards.
 - .7 Operating weight.
 - Wiring diagrams. . 8
 - Single line and schematic diagrams. . 9
 - .10 Relationship to adjacent work.
- . 9 After Departmental Representative's review, distribute copies.
- The review of shop drawings by the Departmental .10 Representative or their delegated representative is for sole purpose of ascertaining conformance with general concept. This review shall not mean that the Departmental Representative approves the detail design inherent in the shop drawings, responsibility for which shall remain with Contractor submitting same, and such review shall not relieve Contractor of responsibility for errors or omissions in shop drawings or of responsibility for meeting all requirements of the construction and Contract Documents. Without restricting generality of foregoing, Contractor is responsible for dimensions to be confirmed and correlated at job site, for information that pertains solely to fabrication processes or to techniques of construction and installation and for co-ordination of Work of all sub-trades.

SCHEDULES, PERMITS AND CERTIFICATES

- . 1 Upon acceptance of bid, submit to Departmental Representative copy of Work Schedule and various other schedules, permits, certification documents project management plans as specified in other sections of the Specifications.
- . 2 Submit copy of permits, notices, compliance Certificates received from Regulatory Agencies having jurisdiction and as applicable to the Work.
- .3 Submission of above documents to be in accordance with Submittal General Requirements procedures specified in this section.

DFO	Submittal Procedures	Section 01 33 00
Lower Terra Nova		
Infrastructure Upgrades		Page 5 of 5
Project No. F6879-179013		

PART 2 - PRODUCTS

2.1 NOT USED

PART 3 - EXECUTION

3.1 NOT USED

DFO	Special Procedures on	Section 01 35 24
Lower Terra Nova	Special Flocedules on	SCCCIOII OI 33 24
Infrastructure Upgrades		Page 1 of 4
Project No. F6879-179013	Fire Safety Requirements	3
PART 1 - GENERAL		
1.1 SECTION INCLUDES	Fire Safety Requirements	
.:	2 Hot Work Permit	
1.2 RELATED WORK	Section 01 35 29 - Health an	d Safety Requirements.
1.3 REFERENCES	National Fire Code - latest of may also be viewed at the Regi located at Baine Johnson Oplace, St. John's, NL, 1-800-641-4049; fax 1-709-7	onal Labour Canada Office Centre, 10 Fort William AlC 1K4; Telephone
1.4 DEFINITIONS	.1 Welding work.2 Cutting of materials be open flame devices	by use of torch or other t which produces sparks.
1.5 SUBMITTALS	work permit to Departmental Re	
.:	Submit in accordance with Requirements specified in Sec	
1.6 FIRE SAFETY REQUIREMENTS	Comply with following: .1 National Fire Code, 1a .2 Fire Protection Standa	atest edition ards FCC 301 and FCC 302. Occupational Health and
	In event of conflict between authorities the most stringe Should a dispute arise in stringent requirement, Department advise on the course of	ent provision will apply. In determining the most artmental Representative

DFO	Special Procedures on	Section 01 35 24
Lower Terra Nova	_	
Infrastructure Upgrades		Page 2 of 4
Project No. F6879-179013	Fire Safety Requirements	_

1.7 HOT WORK AUTHORIZATION

- .1 Obtain Departmental Representative's written "Authorization to Proceed" before conducting any form of Hot Work on site.
- .2 To obtain authorization submit to Departmental Representative:
 - .1 Contractor's typewritten Hot Work Procedures to be followed on site as specified below.
 - .2 Description of the type and frequency of Hot Work required.
 - .3 Sample Hot Work permit to be used.
- .3 Upon review and confirmation that effective fire safety measures will be implemented during performance of hot work, Departmental Representative will provide authorization to proceed as follows:
 - .1 Issue one (1) written "Authorization to Proceed" covering the entire project for duration of work; or .2 Separate work, or segregate certain parts of work, into individual entities. Each entity requiring a separately written "Authorization to Proceed" from Departmental Representative. Follow Departmental Representative's directives in this regard.
- .4 Requirement for individual authorization based on:
 - .1 Nature or phasing of work;
 - .2 Risk to Facility operations;
 - .3 Quantity of various trades needing to perform hot work on project; or
 - .4 Other situation deemed necessary by Departmental Representative to ensure fire safety on premises.
- .5 Do not perform any Hot Work until receipt of Departmental Representative's written "Authorization to Proceed" for that portion of work.
- .6 In tenant occupied facility, coordinate performance of Hot Work with Facility Manager through the Departmental Representative. When directed perform Hot Work only during non-operative hours of Facility. Follow Departmental Representative's directives in this regard.

1.8 HOT WORK PROCEDURES

- .1 Develop and implement safety procedures and work practices to be followed during the performance of Hot Work.
- .2 Procedures to include:
 - .1 Requirement to perform hazard assessment of site and immediate hot work area for each hot work event in accordance with Hazard Assessment and Safety Plan requirements of Section 01 35 28.

DFO	Specia	l Procedures on	Section 01 35 24
Lower Terra Nova	_		
Infrastructure Upgrades			Page 3 of 4
Project No. F6879-179013	Fire	Safety Requirements	
	. 2	Use of a Hot Work Perevent.	rmit system for each hot work
	.3	The step-by-step pr issue permit.	ocess of how to prepare and
	. 4	Permit shall be is Superintendent, or designated by Contr	ssued by Contractor's site other authorized person actor, granting permission tractor to proceed with hot
	.5	Provision of a desi a Fire Safety Watch immediately upon com	gnated person to carry out for a minimum of 30 minutes appletion of the hot work.
	.6	specified herein an	e safety codes and standards ad occupational health and specified in Section 01 35
.3	supp refl	used, must be edited and nt information tailored to conditions. Clearly label ocedures applicable to this	
. 4		ructions and allocate Worker(s).	ssuing the Hot Work Permit.
.5	Proc Str	edures and Permit syst ingently enforce compl Failure to compl procedures may res Non-Compliance Not Representative's	ab-contractors on Hot Work em established for project. liance. y with the established sult in the issuance of a dification at Departmental discretion with possible res imposed as specified in
1.9 HOT WORK PERMIT .1	Hot data .1 .2	: Project name and pro Building name, addre	, as a minimum, the following oject number; ass and specific floor, room ork will be performed;

- Date when permit issued; .3
- . 4 Description of hot work to be performed;
- .5 Special precautions required, including type of fire extinguisher needed;
- Name and signature of person authorized issue .6 the permit;
- .7 Name of worker(s) (clearly printed) to whom the permit is being issued;

DFO	Special Procedures on	Section 01 35 24
Lower Terra Nova Infrastructure Upgrades Project No. F6879-179013	Fire Safety Requirements	Page 4 of 4
	8 hours). Indicate "S "Completion" time & date .9 Worker signature with date termination; .10 Specified period of time .11 Name and signature of period safety Watcher, complete safety watch terminated	requiring Safety Watch; erson designated as Fire with time and date when d, certifying that the as under continual ion during the full time permit and commenced
. 2	Permit to be in typewritten f forms shall only be used if a is included on form.	-
.3	<pre>as follows: .1 Authorized person issuir commences; .2 Worker(s) upon completi</pre>	ng Permit before hot work on of Hot Work; n termination of safety

1.10 DOCUMENTS ON SITE

- .1 Keep Hot Work Permits and hazard assessment documentation on site for duration of work.
- .2 Upon request, make available to Departmental Representative or to authorized safety representative for inspection.

PART 2 - PRODUCTS

2.1 NOT USED

PART 3 - EXECUTION

3.1 NOT USED

DFO Lower Terra Nova Infrastructure Upgrades PROJECT NO. F6879-179013	Special Procedures on Section 01 35 25 Lockout Requirements Page 1 of 6			
PART 1 - GENERAL				
1.1 SECTION INCLUDES .1	Procedures to isolate and lockout electrical facility or other equipment from energy source.			
1.2 RELATED WORK .1	Section 01 35 24 - Special Procedures on Fire Safety Requirements.			
. 2	Section 01 35 28 - Health and Safety Requirements.			
1.3 REFERENCES .1	CSA C22.1-06 - Canadian Electrical Code, Part 1, Safety Standard for Electrical Installations.			
. 2	CAN/CSA C22.3 No. 1-06 - Overhead Systems.			
.3	CAN/CSA C22.3 No. 7-06 - Underground Systems.			
. 4	COSH, Canada Occupational Health and Safety Regulations made under Part II of the Canada Labour Code.			
1.4 DEFINITIONS	Electrical Facility: means any system, equipment, device, apparatus, wiring, conductor, assembly or part thereof that is used for the generation, transformation, transmission, distribution, storage, control, measurement or utilization of electrical energy, and that has an amperage and voltage that is dangerous to persons.			
	Guarantee of Isolation: means a guarantee by a competent person in control or in charge that a particular facility or equipment is isolated.			
	De-energize: in the electrical sense, that a piece of equipment is isolated and grounded, e.g. if the equipment is not grounded, it cannot be considered de-energized (DEAD).			
	Guarded: means that an equipment or facility is covered, shielded, fenced, enclosed, inaccessible by location, or otherwise protected in a manner that, to the extent that is reasonably practicable, will prevent or reduce danger to any person who might touch or go near such item			

near such item.

DFO Lower Terra Nova Infrastructure Upgrades PROJECT NO. F6879-179013	_	Procedures on Requirements	Section 01 Page 2 of	
. 5	Isolate: means that an electrical facility, mechanic equipment or machinery is separated or disconnecte from every source of electrical, mechanical, hydrauli pneumatic or other kind of energy that is capable making it dangerous.			
. 6	contai source and vol pneuma	Live/alive: means that an electrical facility produces, contains, stores or is electrically connected to a source of alternating or direct current of an amperage and voltage that is dangerous or contains any hydraulic, pneumatic or other kind of energy that is capable of making the facility dangerous to persons.		
1.5 COMPLIANCE .1 REQUIREMENTS .1	.1 Ca .2 Fe Safety 01 35 .3 Re mechan de-ene	rm lockouts in complian nadian Electrical Code deral and Provincial (Acts and Regulations 28. gulations and code of ical equipment or other rgized.	e. Doccupational Heal as specified in practice as appli er machinery bein	Section icable to
	author Should requir	ent of conflict betwee ities the most stringe a dispute arise in determent, Departmental Recourse of action to be	ent provision wil ermining the most s epresentative wil	l apply. stringent
		t copy of proposed Lock f lockout permit for i		nd sample
	of acc submit	t documentation within eptance of bid. Do no tal has been reviewed entative.	t proceed with wo	
.:		t above documents in acc ements specified in Se		submittal
·		mit Lockout Procedures sult from Departmental		
1.7 ISOLATION OF EXISTING SERVICES	author active of the	n Departmental Represe ization prior to condu , energized service or work and before procee es or facility.	cting work on an facility require	existing d as part

- .2 To obtain authorization, submit to Departmental Representative following documentation:
 - .1 Written Request for Isolation of the service or facility and;
 - .2 Copy of Contractor's Lockout Procedures.
 - .3 Make a Request for Isolation for each event, unless directed otherwise by Departmental Representative, and as follows:
 - .1 Fill-out standard forms in current use at the facility when so directed by Departmental Representative or;
 - .2 Where no form exists at facility, make request in writing identifying:
 - .1 Identification of system or equipment to be isolated, including its location;
 - .2 Time duration, indicating start time and date and completion time and date when isolation will be in effect.
 - .3 Voltage of service feed to system or equipment being isolated.
 - .4 Name of person making the request.
 - .3 Document to be in typewritten format.
 - .4 Do not proceed until receipt of written notification from Departmental Representative granting the isolation request and authorization to proceed with the isolation of designated equipment or facility. Departmental Representative may designate other individual at the facility as the person authorized to grant the isolation request.
 - .5 Conduct safe, orderly shut down of equipment or facilities, de-energize and isolate power and other sources of energy and lockout items in accordance with requirement of clause 1.8 below.
 - .6 Plan and schedule shut down of existing services in consultation with the Departmental Representative and the Facility Manager. Minimize impact and downtime of facility operations.
 - .7 Determine in advance, as much as possible, in cooperation with the Departmental Representative, the type and frequency of situations which will require a Request for Isolation. Follow Departmental Representative's directives in this regard.
 - .8 Conduct hazard assessment as part of the planning process of isolating existing equipment and facilities. Hazard assessments to conform with requirements of Health and Safety Requirements Section 01 35 28.

1.8 LOCKOUTS

- .1 Isolate and lockout electrical facilities, mechanical equipment and machinery from all potential energy sources prior to starting work on such items.
- .2 Develop and implement lockout procedures to be followed on site as an integral part of the work.
- .3 Use energy isolation lockout devices specifically designed and appropriate for type of facility or equipment being locked out.
- .4 Use industry standard lockout tags.
- .5 Provide appropriate safety grounding and guards as required.
- .6 Prepare Lockout Procedures in writing. Describe safe work practices, work functions and sequence of activities to be followed on site to safely isolate all potential energy sources and lockout/tagout facilities and equipment.
- .7 Include within procedures a system of worker request and issuance of individual lockout permit by a person, employed by Contractor, designated to be "in-charge" and being responsible for:
 - .1 Controlling issuance of permits or tags to workers.
 - .2 Determining permit duration.
 - .3 Maintaining record of permits and tags issued.
 - .4 Submitting a Request for Isolation to Departmental Representative when required in accordance with Clause 1.7 above.
 - .5 Designating a Safety Watcher, when one is required based on type of work.
 - .6 Ensuring equipment or facility has been properly isolated, providing a Guarantee of Isolation to worker(s) prior to proceeding with work.
 - .7 Collecting and safekeeping lockout tags, returned by workers, as a record of the event.
- .8 Clearly establish, describe and allocate, within procedures, the responsibilities of:
 - .1 Workers.
 - .2 Designated person controlling issuance of lockout tags/permits.
 - .3 Safety Watcher.
 - .4 Subcontractors and General Contractor.
- .9 Procedures shall meet the requirements of Codes and Regulations specified in clause 1.5 above.
- .10 Generic procedures, if used, must be edited, supplemented with pertinent information and tailored

DFO	_		Procedures on	Section 01 35	25
Lower Terra Nova	Lo	ckout	Requirements	Page 5 of 6	
Infrastructure Upgrades					
PROJECT NO. F6879-179013					
		label contr	flect specific project as being the procedur act. Incorporate site speciestablished by Facili at site. Obtain such Departmental Represen	es applicable to this fic rules and procedu ty Manager and in for procedures through	s ures
	11	Proced	lures to be in typewrit	ten format.	
	12	Repre requi	copy of Lockout Procesentative, in accordan rements of clause 1.6 ncement of work.	ce with submittal	1
1.9 CONFORMANCE .	1	proje	that lockout procedur ct on site, are string nd compliance by all w	ently followed. Enfor	
	2	mecha	all persons working or nical and other equipme quirements of this sec	nt fed by an energy sou	
	3	regula specia Non-Ca Repre	re to perform lockouts atory requirements or fied herein may result ompliance Notification sentative's discretion plinary measures impose 28.	follow procedures in the issuance of a at Departmental with possible	
1.10 DOCUMENTS ON SITE .	1		ockout Procedures on si ng by workers.	te in common location	for
	2	Depar	copies of Request for I tmental Representative issued to workers durin project duration.	and lockout permits	or
	3	Repre	equest, make such data a sentative or to author sentative for inspecti	ized safety	ntal

DFO Special Procedures on Section 01 35 25
Lower Terra Nova Lockout Requirements Page 6 of 6
Infrastructure Upgrades
PROJECT NO. F6879-179013

PART 2 - PRODUCTS

2.1 NOT USED

PART 3 - EXECUTION

3.1 NOT USED

Section 01 35 29 DFO HEALTH AND SAFETY Lower Terra Nova Page 1 of 10 Infrastructure Upgrades Project No: F6879-179013 REQUIREMENTS 1.1 RELATED WORK .1 Section 01 35 24 - Special Procedures on Fire Safety Requirements. 1.2 DEFINITIONS .1 COSH: Canada Occupational Health and Safety Regulations made under Part II of the Canada Labour Code. Competent Person: means a person who is: .1 Qualified by virtue of personalknowledge, training and experience to perform assigned work in a manner that will ensure the health and safety of persons in the workplace, and; .2 Knowledgeable about the provisions of occupational health and safety statutes and regulations that apply to the Work and; .3 Knowledgeable about potential or actual danger to health or safety associated with the Work. .3 Medical Aid Injury: any minor injury for which medical treatment was provided and the cost of which is covered by Workers' Compensation Board of the province in which the injury was incurred. PPE: personal protective equipment. . 4 .5 Work Site: where used in this section shall mean areas, located at the premises where Work is undertaken, used by Contractor to perform all of the activities associated with the performance of the Work. Make submittals in accordance with Section 1.3 SUBMITTALS . 1 01 33 00. Submit site-specific Health and Safety Plan prior to commencement of work. .1 Submit within (5) work days of notification of Bid and Acceptance Form. .2 Departmental Representative will review Health and Safety Plan and provide comments. .3 Revise the Plan as appropriate and resubmit within five (5) work days after receipt of comments. .4 Departmental Representative's review and comments made of the Plan shall not be construed as an endorsement, approval or implied warranty of any kind by Canada and does not reduce Contractor's overall responsibility for Occupational Health and Safety of the Work.

.5 Submit revisions and updates made to the Plan

during the course of Work.

DFO HEALTH AND SAFETY Section 01 35 29 Lower Terra Nova

Project No: F6879-179013 REQUIREMENTS

Infrastructure Upgrades

3 Submit name of designated Health & Safety Site Representative and support documentation specified in the Health and Safety Plan.

Page 2 of 10

- .4 Submit building permit, compliance certificates and other permits obtained.
- .5 Submit copy of Letter in Good Standing from Provincial Workers Compensation or other department of labour organization.
 - .1 Submit update of Letter in Good Standing whenever expiration date occurs during the period of work.
- .6 Submit copies of reports or directions issued by Federal, Provincial and Territorial health and safety inspectors.
- .7 Submit copies of incident reports.
- .8 Submit WHMIS MDS Material Safety Data Sheets, unless otherwise directed by the Departmental Representative.

1.4 COMPLIANCE REQUIREMENTS

- .1 Comply with the Occupational Health and Safety Act for the Province of Newfoundland and Labrador, and the Occupational Health and Safety Regulations made pursuant to the Act.
- .2 Comply with Canada Labour Code Part II, (entitled Occupational Health and Safety) and the Canada Occupational Health and Safety Regulations (COSH) as well as any other regulations made pursuant to the Act.
 - .1 The Canada Labour Code can be viewed at: www.http://laws.justice.gc.ca/en/L-2/
 - .2 COSH can be viewed at:
 www.http://laws.justice.gc.ca/eng/SOR-86304/ne.html.
 - .3 A copy may be obtained at: Canadian Government Publishing Public Works & Government Services Canada Ottawa, Ontario, K1A OS9 Tel: (819) 956-4800 (1-800-635-7943) Publication No. L31-85/2000 E or F).
- .3 Observe construction safety measures of:
 - .1 Part 8 of National Building Code.
 - .2 Municipal by-laws and ordinances.
- .4 In case of conflict or discrepancy between any specified requirements, the more stringent shall apply.

Section 01 35 29 DFO HEALTH AND SAFETY Lower Terra Nova Page 3 of 10 Infrastructure Upgrades Project No: F6879-179013 REQUIREMENTS . 5 Maintain Workers Compensation Coverage in good standing for duration of Contract. Provide proof through submission of Letter in Good Standing Medical Surveillance: Where prescribed by legislation or regulation, obtain and maintain worker medical surveillance documentation. 1.5 RESPONSIBILITY . 1 Be responsible for health and safety of persons on site, safety of property and for protection of persons and environment adjacent to the site to extent that they may be affected by conduct of Work. . 2 Comply with and enforce compliance by all workers, sub-contractors and other persons granted access to work site with safety requirements of Contract Documents, applicable Federal, Provincial, and local by-laws, regulations, and ordinances, and with site specific Health and Safety Plan. 1.6 SITE CONTROL Control the Work and entry points to Work Site. . 1 AND ACCESS Approve and grant access only to workers and authorized persons. Immediately stop and remove non-authorized persons. .1 Departmental Representative will provide names of those persons authorized by Departmental Representative to enter onto Work Site and will ensure that such authorized persons have the required knowledge and training on Health and Safety pertinent to their reason for being at the site, however, Contractor remains responsible for the health and safety of authorized persons while at the Work Site. Isolate Work Site from other areas of the premises by use of appropriate means. .1 Erect fences, hoarding, barricades and temporary lighting as required to effectively delineate the Work Site, stop non-authorized entry, and to protect pedestrians and vehicular traffic around and adjacent to the Work and create a safe environment. .2 Post signage at entry points and other strategic locations indicating restricted access and conditions for access. .3 Use professionally made signs with bilingual message in the 2 official languages or international known graphic symbols.

Provide safety orientation session to persons

safety rules to be observed while on site.

granted access to Work Site. Advise of hazards and

DFO Lower Terra Nova Infrastructure Upgrades	Ι	HEALTH AND SAFETY	Section 01 35 29 Page 4 of 10
Project No: F6879-179013	R.	EQUIREMENTS	
	. 4	Ensure persons granted site acces	
		require access to conduct tests of inspections.	
	.5	Secure Work Site against entry when unoccupied and to protect persons Provide security guard where adequated and the achieved by other means	s against harm. quate protection
	.6	Given the remote location of the Contractor shall provide or plan site access and communication in emergency.	for a method of
1.7 PROTECTION	.1	Give precedence to safety and he protection of environment over considerations for Work.	
	. 2	Should unforeseen or peculiar saf or condition become evident duri Work, immediately take measures situation and prevent damage or Departmental Representative verk writing.	ng performance of to rectify harm. Advise
1.8 FILING OF NOTICE	.1	File Notice of Project with pertiperovincial health and safety authobeginning of Work. 1 Departmental Representative was locating address in needed.	norities prior to
1.9 PERMITS	.1	Post permits, licenses and compl specified in section 01 10 10, a	
	. 2	Where a particular permit or concannot be obtained, notify Depar Representative in writing and obproceed before carrying out appl work.	rtmental otain approval to
1.10 HAZARD ASSESSMENTS	.1	Perform site specific health and assessment of the Work and its s	
	. 2	Carryout initial assessment price of Work with further assessments progress of work, including when subcontractors arrive on site.	s as needed during

DFO	HEALTH AND SAFETY	Section 01 35 2
Lower Terra Nova Infrastructure Upgrades Project No: F6879-179013	REQUIREMENTS	Page 5 of 10
	.3 Record results and address in Safety Plan.	Health and
	.4 Keep documentation on site for the Work.	entire duration of
1.11 PROJECT/SITE CONDITIONS	 The following are potential hand safety hazards at site for involve contact with: 1 Isolated site location. 2 Wet and slippery condition. 3 Inclement weather condition. 	r which work may
	.4 Working during the winter.5 Heavy lifting..6 Falls..7 Drowning..8 Working at heights.	
	.9 Cutting tools and other tools..10 Working in close proximic contractors.	
	.11 Flooding and high water .12 Rapid flowing water13 River falls and steep dr .14 Sharp objects.	
	.2 Above items shall not be cons complete and inclusive of pot safety hazards encountered du	ential health, and
	.3 Include above items into hazar	d assessment process.
1.12 MEETINGS	.1 Contractor to hold pre-constr safety meeting prior to comme Ensure attendance of: .1 Superintendent of Work2 Contractor's designated Hea	ncement of Work.
	Representative3 Subcontractor's Health and Representative4 Health and Safety Site Coor	Safety Site
	.2 Conduct regularly scheduled to safety meetings during the Wor Occupational Health and Safet	k in conformance with
	.3 Keep documents on site.	
1.13 HEALTH AND SAFETY PLAN	.1 Prior to commencement of Work written Health and Safety Pla work. Implement, maintain, an entire duration of Work and u	n specific to the d enforce Plan for

Lower Terra Nova

Project No: F6879-179013

Infrastructure Upgrades Page 6 of 10

REQUIREMENTS

demobilization from site.

- .2 Health and Safety Plan shall include the following components:
 - .1 List of health risks and safety hazards identified by hazard assessment.
 - .2 Control measures used to mitigate risks and hazards identified.
 - .3 On-site Contingency and Emergency Response Plan as specified below.
 - .4 On-site Communication Plan as specified below.
 - .5 Name of Contractor's designated Health & Safety Site Representative and information showing proof of his/her competence and reporting relationship in Contractor's company.
 - .6 Names, competence and reporting relationship of other supervisory personnel used in the Work for occupational health and safety purposes.
- .3 On-site Contingency and Emergency Response Plan shall include:
 - .1 Operational procedures, evacuation measures and communication process to be implemented in the event of an emergency.
 - .2 Evacuation Plan: site and floor plan layouts showing escape routes, marshaling areas. Details on alarm notification methods, fire drills, location of firefighting equipment and other related data.
 - .3 Name, duties and responsibilities of persons designated as ${\tt Emergency\ Warden(s)}$ and deputies.
 - .4 Emergency Contacts: name and telephone number of officials from:
 - .1 General Contractor and subcontractors.
 - .2 Pertinent Federal and Provincial Departments and Authorities having jurisdiction.
 - .3 Local emergency resource organizations.
 - .5 Harmonize Plan with Facility's Emergency Response and Evacuation Plan. Departmental Representative will provide pertinent data including name of PWGSC and Facility Management contact.
- .4 On-site Communication Plan:
 - .1 Procedures for sharing of work related safety information to workers and subcontractors, including emergency and evacuation measures.
 - .2 List of critical work activities to be communicated with Facility Manager which have a risk of endangering health & safety of Facility users.
- .5 Address all activities of the Work including those of subcontractors.

DFO HEALTH AND SAFETY Section 01 35 29
Lower Terra Nova

Infrastructure Upgrades Page 7 of 10 Project No: F6879-179013 REQUIREMENTS

.6 Review Health and Safety Plan regularly during the Work. Update as conditions warrant to address emerging risks and hazards, such as whenever new trade or subcontractor arrive at Work Site.

- .7 Departmental Representative will respond in writing, where deficiencies or concerns are noted and may request re-submission of the Plan with correction of deficiencies or concerns.
- .8 Post copy of the Plan, and updates, prominently on Work Site.

1.14 SAFETY SUPERVISION

- .1 Employ Health & Safety Site Representative responsible for daily supervision of Health and Safety of the Work.
- .2 Health & Safety Site Representative may be the Superintendent of the Work or other person designated by Contractor and shall be assigned the responsibility and authority to:
 - .1 Implement, monitor and enforce daily compliance with health and safety requirements of the Work
 - .2 Monitor and enforce Contractor's site-specific Health and Safety Plan.
 - .3 Conduct site safety orientation session to persons granted access to Work Site.
 - .4 Ensure that persons allowed site access are knowledgeable and trained in health and safety pertinent to their activities at the site or are escorted by a competent person while on the Work Site
 - .5 Stop the Work as deemed necessary for reasons of health and safety.
- .3 Health & Safety Site Representative must:
 - .1 Be qualified and competent person in occupational health and safety.
 - .2 Have site-related working experience specific to activities of the Work.
 - .3 Be on Work Site at all times during execution of the Work.
 - .4 All supervisory personnel assigned to the Work shall also be competent persons.
 - .5 Inspections:
 - .1 Conduct regularly scheduled safety inspections of the Work on a minimum daily basis. Record deficiencies and remedial action taken.
 - .2 Conduct Formal Inspections on a minimum monthly basis. Use standardized safety inspection forms. Distribute to

DFO HEALTH AND SAFETY Section 01 35 29 Lower Terra Nova

Infrastructure Upgrades Page 8 of 10 Project No: F6879-179013 REQUIREMENTS

subcontractors.

- .3 Follow-up and ensure corrective measures are taken.
- .6 Keep inspection reports and supervision related documentation on site.
- .7 Cooperate with Facility's Occupational Health & Safety representative should one be designated by the Departmental Representative.

1.15 TRAINING

- .1 Use only skilled workers on Work Site who are effectively trained in occupational health and safety procedures and practices pertinent to their assigned task.
- .2 Maintain employee records and evidence of training received. Make data available to Departmental Representative upon request.
- .3 When unforeseen or peculiar safety-related hazard, or condition occur during performance of Work, follow procedures in place for Employee's Right to Refuse Work in accordance with Acts and Regulations of Province having jurisdiction and advise Departmental Representative verbally and in writing.
- .4 All workers dealing with hazardous materials are required to provide evidence of training, in accordance with Provincial regulations.

1.16 MINIMUM SITE SAFETY RULES

- 1 Notwithstanding requirement to abide by federal and provincial health and safety regulations; ensure the following minimum safety rules are obeyed by persons granted access to Work Site:
 - .1 Wear appropriate PPE pertinent to the Work or assigned task; minimum being hard hat, safety footwear, safety glasses safety vest and hearing protection.
 - .2 Immediately report unsafe condition at site, near-miss accident, injury and damage.
 - .3 Maintain site and storage areas in a tidy condition free of hazards causing injury.
 - .4 Obey warning signs and safety tags.
- .2 Brief persons of disciplinary protocols to be taken for non-compliance. Post rules on site.

1.17 CORRECTION OF NON-COMPLIANCE

- .1 Immediately address health and safety noncompliance issues identified by authority having jurisdiction or by Departmental Representative.
- .2 Provide Departmental Representative with written

DFO		HEALTH AND SAFETY	Section 01 35 2
Lower Terra Nova Infrastructure Upgrades Project No: F6879-179013		EQUIREMENTS	Page 9 of 10
		report of action taken to correhealth and safety issues ident: Departmental Representative will compliance of health and safety	ified. L stop Work if non-
1.18 INCIDENT REPORTING	.1	corrected in a timely manner. Investigate and report the following the following the corrected in a timely manner.	
		Departmental Representative: .1 Incidents requiring notificat Department of Occupational Safe Workers Compensation Board or t Agency2 Medical aid injuries3 Property damage in excess of .4 Interruptions to facility op an operational lost to a fec excess of \$5,000.	ety and Health, to other regulatory \$10,000.00. erations resulting in
	.2	Submit report in writing.	
1.19 HAZARDOUS PRODUCTS	.1	Comply with requirements of Won Materials Information System Wh	
	.2	<pre>Keep MSDS data sheets for all pr site1 Post on site2 Submit copy to Departmental F</pre>	
1.20 BLASTING	.1	Blasting or other use of explosion site (without prior receipt permission and instructions from Representative).	of written
1.21 POWDER ACTUATED DEVICES	.1	Use powder actuated fastening de receipt of written permission fastening Representatives.	
1.22 CONFINED SPACES	.1	Abide by occupational health and regarding work in confined space	
1.23 SITE RECORDS		Maintain on Work Site copy of sa documentation and reports stipped in compliance with Acts and Regauthorities having jurisdiction documents specified herein.	lated to be produced gulations of
	.2	Upon request, make available to	

Representative or authorized Safety Officer for

DFO HEALTH AND SAFETY Section 01 35 29
Lower Terra Nova
Infrastructure Upgrades Page 10 of 10
Project No: F6879-179013 REQUIREMENTS

inspection.

1.24 POSTING OF DOCUMENTS

- .1 Ensure applicable items, articles, notices and orders are posted in conspicuous location on Work Site in accordance with Acts and Regulations of Province having jurisdiction.
- .2 Post other documents as specified herein, including:
 - .1 Site specific Health and Safety Plan.
 - .2 WHMIS data sheets.

1.25 DIVING OPERATIONS

- .1 All diving work to comply fully with the requirements of the latest editions of CSA Standard Z275.2 "Occupational Safety Code for Diving Operations", CSA Z275.4, "Competency Standards for Diving Operations", and CSA Z180.1, "Compressed Breathing Air and Systems".
- .2 Dive personnel must meet the minimum competency requirements of the latest edition of CSA Z275.4 and all divers must possess a valid Category I Diving Certificate, or an unrestricted surface supply certificate.
- .3 Diving in free-swim mode is not permitted at the work site.
- .4 Divers must have a current (less than one year) validated medical examination certificate from a licensed diving physician in Newfoundland and Labrador, who is knowledgeable and competent in diving and hyperbaric medicine, for all dives.

DFO Lower Terra Nova Infrastructure Upgrades Project No. F6879-179013		Environmental Procedures	Section 01 35 43 Page 1 of 7
PART 1 - GENERAL			
1.1 RELATED WORK	. 1	Section 01 74 21 - Construc Management and Disposal.	tion/Demolition Waste
1.2 DEFINITIONS	.1	Hazardous Material: Product, s that is used for its original purp dangerous goods or a material t impact to the environment or ac of persons, animals or plant li the environment.	pose; and that is either that may cause adverse dversely affect health
1.3 SUBMITTALS	. 1	Submittals: in accordance wit Submittal Procedures.	ch Section 01 33 00 -
	. 2	Prior to commencing construction of materials to site, submit Entlement of Plan for review and approximate Environmental Environmental Environmental Comprehensive overview environmental issues which mus construction.	vironmental Protection val by Departmental Protection Plan is to of known or potential
	. 3	Address topics at level of det environmental issue and require	
	. 4	Environmental protection plan: .1 Names of persons respondherence to Environmental Prot. 2 Names and qualifications of for manifesting hazardous wastest. 3 Names and qualifications of for training site personnel4 Descriptions of environmental program.	nsible for ensuring tection Plan. of persons responsible to be removed from site.
	. 5	Erosion and sediment control planand location of erosion and se	

regulations.

.6 Drawings showing locations of proposed temporary excavations or embankments for haul roads, stream crossings, material storage areas, structures, sanitary facilities, and stockpiles of excess or spoil materials including methods to control runoff and to contain materials on site.

provided including monitoring and reporting requirements to assure that control measures are in compliance with erosion and sediment control plan, Federal, Provincial, and Municipal laws and

DFO		Environmental Procedures	Section 01 35 43
Lower Terra Nova Infrastructure Upgrades Project No. F6879-179013			Page 2 of 7
	.7	Spill Control Plan: inc instructions, and reports to b unforeseen spill of regulated su	
	.8	Non-Hazardous solid waste dispomethods and locations for soincluding clearing debris.	sal plan identifying lid waste disposal
	.9	Air pollution control plan deta assure that dust, debris, materia become air borne and travel off	ls, and trash, do not
	.10	Contaminant prevention plan potentially hazardous substances identifies intended actions to of such materials into air, wadetails provisions for compliprovincial, and Municipal laws storage and handling of these materials	prevent introduction ter, or ground; and ance with Federal, and regulations for
	.11	Wastewater management plan that i procedures for management and/or waters which are directly deriv activities, such as concrete cu water, dewatering of ground water hydrostatic test water, and water lines.	r discharge of waste ed from construction ring water, clean-up, disinfection water,
1.4 FIRES	.1	Fires and burning of rubbish on	site not permitted.
1.5 DISPOSAL OF WASTES AND HAZARDOUS MATERIALS	.1	Do not bury rubbish and waste Dispose at approved landfill si Section 01 74 21.	
	.2	Do not dispose of hazardous waste such as mineral spirits, paint into waterways, storm or sanit landfill sites.	thinner, oil or fuel
	.3	Store, handle and dispose of haz hazardous waste in accordance with and provincial laws, regulations,	th applicable federal
	. 4	Dispose of construction waste mat	erials and demolition

banned from landfills.

.5

debris, resulting from work, at approved landfill sites only. Carry out such disposal in strict accordance with provincial and municipal rules and regulations. Separate out and prevent improper disposal of items

Establish methods and undertake construction practices

DFO		Environmental Procedures	Section 01 35 43
Lower Terra Nova Infrastructure Upgrades Project No. F6879-179013			Page 3 of 7
		construction waste materials, product packaging and delivery crecycling abilities of various disposal of debris at landfill	demolition debris and ontainers into various materials and avoid site(s) in a "mixed trms specializing in exist, transport such
	.6	Communicate with landfill commencement of work, to det construction, demolition and materials have been banned from dand at transfer stations.	d renovation waste
1.6 DRAINAGE	.1	Provide temporary drainage and to keep excavations and site fr	
	. 2	Do not pump water containing sus waterways, sewer or drainage sy	
	.3	Control disposal or runoff suspended materials or other haccordance with governing requirements.	narmful substances in
	. 4	Pumped water must meet applicable and municipal standards before to a surface water body. If exceedences are noted, the Depart has the right to issue stop put the Contractor. Contractor wifor any delays associated with romeet guidelines.	it can be discharged regulatory guidelines tmental Representative mping instructions to ll not be compensated
	.5	Provide control devices such sediment traps and settling pond and prevent erosion of adjacengood order for duration of work	ds to control drainage t lands. Maintain in
1.7 PERMITS	1	All guidelines and instructions be strictly adhered to.	stated on permits must

DFO		Environmental Procedures Section 01 35 43
Lower Terra Nova		
Infrastructure Upgrades		Page 4 of 7
Project No. F6879-179013		
1.8 WORK ADJACENT TO WATERWAYS	.1	Do not operate construction equipment in waterways, unless approved in writing by the Departmental Representative.
	. 2	Do not use waterway beds for borrow material.
	.3	Do not dump excavated fill, waste material or debris in waterways.
	.4	At borrow sites, design and construct temporary crossings to minimize erosion to waterways in strict conformance with provincial and federal environmental regulations.
	.5	Do not skid logs or construction materials across waterways.
	.6	Avoid indicated spawning beds when constructing temporary crossings of waterways.
	.7	Do not blast within 100 m of spawning beds.
	.8	Equipment working in and adjacent to water way shall be equipped with biodegradable hydraulic oils specifically intended for environmentally sensitive areas. Contractor shall submit MSDS and Technical Data sheets on hydraulic oil to be used for approval by the Departmental Representative.
1.9 REFUELING	.1	Refueling of equipment to be performed in locations as directed by Departmental Representative.
	.2	Do not refuel equipment within 100 metres of any watercourse or storm water catch basin unless protection against spills is in place and location is approved by Departmental Representative.
	.3	Use petroleum containers approved for products with no spill fill spouts for dispensing fuels. The sure pour nozzle to have self closing valve, prevent any flow of fuel until the nozzle is inserted into the receiving container. On removal from the receiving container the slide valve closes to eliminate any fuel spill. Nozzle to be equipped with its own automatic vent eliminating the need for the user to open or close air inlets on the pouring container.
		Nozzle to support the weight of the pouring container. Nozzles to automatically stop the flow when the receiving container becomes full. The nozzle to be such that it reduces evaporative losses of volatile organic compounds during the fuel transfer.

.5

All spills of hydrocarbon based products such as

Environmental Procedures	Section 01 35 43
	Page 5 of 7
gasoline, kerosene, naphtha, lubricating oils, enginoils, greases and de-icing fluids or antifreeze no matter how large or small to be reported to Department.	
Representative.	
Oil changes or equipment reparament permitted.	airs in the field are not
Portland cement concrete or HM	MAC surfaces when approved
Contractor to have drip pans sized for amounts of product to be recovered and customized to fit under pieces of equipment to perform routine maintenance to equipment while maintaining equipment on property. Drip Pans to be used whenever leaving equipment on site or parking overnight when not in use.	
locations away from watercou Departmental Representative. poor mechanical repair to be	rses and as approved by Equipment with leaks or removed from site when
kit consisting of the follow equipment: .1 a spaded shovel; .2 a stable broom; .3 a broad nosed shovel; .4 a container(s) suitabl sufficient size to contain pused with equipment; .5 Absorbents; .6 rags; .7 metal container for so a Booms when working new will traverse the width of the and .9 Spill control kit to b by Wing Environment Office puspill control kits to be available and at all areas where being performed and at all tithe Contract10 Contractor employees to	te, compatible to and of petroleum products being viled rags; at to a watercourse that watercourse by two times; e inspected and approved rior to Work commencing. Allable to Contractor Work of the Contract is times during the course of to be trained in the use
	gasoline, kerosene, naphtha, oils, greases and de-icing f matter how large or small to be Representative. Oil changes or equipment representative. Refueling to be performed on Portland cement concrete or HW by the Departmental Represendirected. Contractor to have drip pans product to be recovered and pieces of equipment to perform equipment while maintaining Drip Pans to be used whenever or parking overnight when not perform the locations away from watercomperatemental Representative. Poor mechanical repair to be so ordered by Departmental Representative. 1 Contractor to have at the work it consisting of the follow equipment: 1 a spaded shovel; 2 a stable broom; 3 a broad nosed shovel; 4 a container(s) suitable sufficient size to contain pused with equipment; 5 Absorbents; 6 rags; 7 metal container for so as Booms when working new will traverse the width of the and 9 Spill control kits to be ave employees at all areas where being performed and at all tithe Contract.

DFO Lower Terra Nova Infrastructure Upgrades Project No. F6879-179013		Environmental Procedures	Section 01 35 43 Page 6 of 7
1.11 SPILLS	.1	Disposal of spilled materials to site/property and at approved lot to be disposed of.	
	.2	When parking of equipment on site to be secured from entry, inspection ground protected from leaks.	
	.3	Contractor to protect all wells, catch basins, drywells, drains and watercourses from contamination event of a spill.	
	. 4	All equipment to be used for the to be inspected by the Department leaks. Equipment not in good reremoved/repaired when directed Representative.	tal Representative for epair to be
	.5	Spills in excess of 74 litres to b to Departmental Representative and Labrador Department of Envi Conservation.	and the Newfoundland
	.6	For spills occurring the Contra remove as much or all of the conta by the spill from Work of the Co	aminated soils created
	.7	Contaminated soils/materials to containers compatible to the co	
	.8	Any remaining clean-up to be perf to Canada. Clean-ups to be to t Representative's satisfaction.	
1.12 POLLUTION CONTROL	.1	Maintain temporary erosion ar features installed under this c	
	. 2	Control emissions from equipmer authorities emission requiremen	
	.3	Prevent sandblasting and other from contaminating air beyond providing temporary enclosures.	application area, by
		Cover or wet down dry materials a blowing dust and debris. Prov temporary roads and around enti	ride dust control for

.5 Maintain inventory of hazardous materials and hazardous

.6 Have emergency spill response equipment and rapid clean-up kit, appropriate to work, at site. Locate

waste stored on site. List items by product name, quantity and date when storage began.

DFO	E	Environmental Procedures Section 01 35 43
Lower Terra Nova		
Infrastructure Upgrades		Page 7 of 7
Project No. F6879-179013		
		adjacent to work and where hazardous materials are
		stored. Provide personal protective equipment as
		required for clean-up.
	. 7	Report, to Federal and Provincial Department of the

- Environment, spills of petroleum and other hazardous materials as well as accidents having potential of polluting the environment. Also notify Departmental Representative and submit a written spill report to Departmental Representative within 24 hours of occurrence.
- .8 Provide a floating debris containment boom whenever any of the Contractors methods of work allow for the potential of floating debris.
- .1 Should nests of migratory birds in wetlands be encountered during work, immediately notify Departmental Representative for directives to be followed.
 - .1 Do not disturb nest site and neighbouring vegetation until nesting is completed.
 - .2 Minimize work immediately adjacent to such areas until nesting is completed.
 - .3 Protect these areas by following recommendations of Canadian Wildlife Service.

PART 2 - PRODUCTS

2.1 NOT USED

PART 3 - EXECUTION

DFO Lower Terra Nova		Testing & Quality Control	Section 01 45 00
Infrastructure Upgrades			Page 1 of 4
Project No. F6879-179013			
PART 1 - GENERAL			
1.1 SECTION .1	1	Inspection and testing, enforcement requirements.	administrative and
	. 2	Tests and mix designs.	
	. 3	Mock-ups.	
	. 4	Mill tests.	
	. 5	Equipment and system adjust ar	d balance.
1.2 RELATED SECTIONS	.1	Section 01 33 00 - Submittal F	rocedures.
	. 2	Section 01 78 00 - Closeout Su	ıbmittals.
1.3 INSPECTION	.1	Facilitate Departmental Representations of Work is preparations to allow access it is in progress.	being fabricated at cruction site, make
	.2	Give timely notice requesting designated for special test approvals by Departmental Rinspection authorities having	sts, inspections or Representative or by
	.3	If Contractor covers or permit designated for special test approvals before such is made particular inspections or test satisfactorily completed and Departmental Representative proceed. Pay costs to uncoversely.	sts, inspections or e, uncover Work until s have been fully and until such time as
	.4	In accordance with the Departmental Representative may to be examined if Work is su accordance with Contract Docum	spected to be not in
1.4 INDEPENDENT . INSPECTION AGENCIES	. 1	Departmental Representative wi service of Independent Ins Agencies for purpose of ins portions of Work except for the part of Contractor's responsib	pection and Testing specting and testing following which remain

DFO	Togting (Ouglity Control	Section 01 45 00
Lower Terra Nova Infrastructure Upgrades	Testing & Quality Control	Page 2 of 4
Project No. F6879-179013		1490 2 01 1
	.1 Inspection and testing ordinances, rules, regulations authorities2 Inspection and testing personance3 Mill tests and certificate .4 Tests as specified with designated to be carried out by supervision of Departmental Re.5 Additional tests specified	formed exclusively for es of compliance. In various sections Contractor under the presentative.
	reveal work not in accord	lance with contract all pay costs for ons as Departmental
	Inspection and testing complete does not relax responsibility accordance with Contract Docum	to perform Work in
1.5 ACCESS TO WORK .	1 Furnish labour and facility to work being inspected and teste	
	2 Cooperate to facilitate such in	spections and tests.
	3 Make good work disturbed by ins	spections and tests.
1.6 PROCEDURES .1	advance of when work is ready fo	or tests, in order for to make attendance sting Agency. When
. 2	to be tested. Deliver in re	quired quantities to sonable promptness and
. 3	Provide labour and facilities samples on site. Provide suffic Testing Agency's exclusive use toure test samples.	ient space on site for

DFO Lower Terra Nova Infrastructure Upgrades Project No. F6879-179013		Testing & Quality Control	Section 01 45 00 Page 3 of 4
1.7 REJECTED WORK		Remove and replace defective Wor poor workmanship, use of defective and whether incorporated in Work of identified by Departmental Repre- to conform to Contract Documents	e or damaged products or not, which has been esentative as failing
	.2	Make good damages to existing or work of other Contracts, result replacement of defective work.	
1.8 TESTING BY CONTRACTOR	.1	Provide all necessary instrumqualified personnel to perform Contractor's responsibilities he the Contract Documents.	tests designated as
	.2	At completion of tests, turn over fully documented test reports Representative. Additionally, of sufficient quantities to enable of test reports to be placed in eatmanuals specified in Section 01	ts to Departmental btain other copies in one (1) complete set ch of the maintenance
	.3	Submit mill test certificates an as specified in various sections	
	. 4	Furnish test results and mix des various sections.	igns as specified in
1.9 MOCK-UPS			fically requested in in each mock-up all sentative of final
	.2	Construct in locations accepta Representative.	ble to Departmental

- .3 Prepare mock-ups for Departmental Representative's review with reasonable promptness and in an orderly sequence, so as not to cause any delay in Work.
- .4 Failure to prepare mock-ups in ample time is not considered sufficient reason for an extension of Contract Time and no claim for extension by reason of such default will be allowed.
- .5 If requested, Departmental Representative will assist in preparing a schedule fixing dates for preparation.
- .6 Remove mock-up at conclusion of Work or when directed

DFO	Testing & Quality Control	Section 01 45 00
Lower Terra Nova		
Infrastructure Upgrades		Page 4 of 4
Project No. F6879-179013		
	bu Departmental Benrogentatius u	nlegg approval ig given

by Departmental Representative unless approval is given to remain as part of Work.

PART 2 - PRODUCTS

2.1 NOT USED

PART 3 - EXECUTION

DFO	Temporary Facilities	Section 01 50 00
Lower Terra Nova Infrastructure Upgrades Project No. F6879-179013		Page 1 of 2
PART 1 - GENERAL		
1.1 CONTRACTOR'S . SITE OFFICE	<u> </u>	ffice as directed by
1.2 SANITARY FACILITITES	Provide sanitary facilities for with governing regulations a	
	Post notices and take such pro- local health authorities. Ke sanitary condition.	
1.3 POWER	Arrange, pay for and maintain to supply in accordance with go ordinances.	
1.4 SCAFFOLDING .	Design, construct and maintai secure and safe manner CAN/CSA-S269.2-M87 (R2003).	in scaffolding in rigid, in accordance with
	Erect scaffolding independent no longer required.	t of walls. Remove when
1.5 CONSTRUCTION SIGNS AND NOTICES	1 Contractor or sub-contractor a are not permitted on site.	advertisement signboards
	2 Only notices of safety or ins on site.	structions are permitted
	3 Safety and Instruction Signs .1 Signs and notices for safe be in both official languages conform to CAN/CSA-Z321-96 (ety and instruction shall . Graphic symbols shall
	4 Maintenance and Disposal of S .1 Maintain approved signs condition for duration of pro site on completion of project by Departmental Representati	s and notices in good oject and dispose of off t or earlier if directed
1.6 REMOVAL OF TEMPORARY . FACILITIES	Remove temporary facilities : by Departmental Representativ	

DFO	Temporary Facilities	Section 01 50 00
Lower Terra Nova		
Infrastructure Upgrades		Page 2 of 2
Project No. F6879-179013		

PART 2 - PRODUCTS

2.1 NOT USED

PART 3 - EXECUTION

DFO	7	Temporary Barriers	Section 01 56 00
Lower Terra Nova			D 1 5 1
Infrastructure Upgrades Project No. F6879-179013		& Enclosures	Page 1 of 1
Project No. F00/9-1/9013		& Eliciosules	
PART 1 - GENERAL			
1.1 SECTION	.1	Barriers.	
INCLUDES	. 2	Traffic Controls.	
1.2 INSTALLATION AND REMOVAL	.1	Provide temporary controls in or expeditiously.	rder to execute work
	.2	Remove from site all such work a	fter use.
1.3 HOARDING	.1	Erect temporary site enclosure snow fence wired to rolled steel spaced at 2.4 m centres. Providgate. Maintain fence in good re	"T" bar fence posts le one lockable truck
1.4 GUARD RAILS AND BARRICARDS	.1	Provide secure, rigid guard rails open excavations, steep cliffs, protect against falls.	
	. 2	Provide as required by governing	authorities.
1.5 PUBLIC TRAFFIC FLOW	.1	Provide and maintain competent straffic signals, barricades and lanterns as required to perform public.	flares, lights, or
1.6 PROTECTION FOR OFF-SITE	E.1	Protect surrounding private and damage during performance of wor	

Be responsible for damage incurred.

.2

DFO	Common Product Requirements	Section 01 61 00
Lower Terra Nova		
Infrastructure Upgrades		Page 1 of 4
Project No. F6879-179013		

PART 1 - GENERAL

1.1 GENERAL

- .1 Use new material and equipment unless otherwise specified.
- .2 Within seven (7) days of written request by Departmental Representative, submit following information for any materials and products proposed for supply:
 - .1 name and address of manufacturer;
 - .2 trade name, model and catalogue number;
 - .3 performance, descriptive and test data;
 - .4 manufacturer's installation or application
 instructions;
 - .5 evidence of arrangements to procure.
 - .6 evidence of manufacturer delivery problems or unforseen delays.
- .3 Provide material and equipment of specified design and quality, performing to published ratings and for which replacement parts are readily available.
- .4 Use products of one manufacturer for equipment or material of same type or classification unless otherwise specified.
- .5 Permanent labels, trademarks and nameplates on products are not acceptable in prominent locations, except where required for operating instructions, or when located in mechanical or electrical rooms.

1.2 PRODUCT QUALITY & REFERENCED STANDARDS

- .1 Contractor shall be solely responsible for submitting relevant technical data and independent test reports to confirm whether a product or system proposed for use meets contract requirements and specified standards.
- .2 Final decision as to whether a product or system meets contract requirements rests solely with the Departmental Representative in accordance with the General Conditions.

1.3 ACCEPTABLE MATERIALS .1 AND ALTERNATIVES

Acceptable Materials: When materials specified include trade names or trade marks or manufacturer's or supplier's name as part of the material description, select and only use one of the names listed for incorporation into the Work.

DFO	C	Common Product Requirements	Section 01 61 00
Lower Terra Nova			
Infrastructure Upgrades			Page 2 of 4
Project No. F6879-179013			
	. 2	Alternative Materials: Submismaterials to trade names or specified must be done during following procedures indicated in Bidders.	the bidding period
	.3	Substitutions: After acceptance of a specified material will be a to the Work in accordance with tof the Contract.	dealt with as a change
1.4 MANUFACTURER'S INSTRUCTIONS	.1	Unless otherwise specified, complatest printed instructions installation methods to be used. or enclosure provided with prodinstructions directly from manuscripts.	for materials and Do not rely on labels ucts. Obtain written
	. 2		specifications and that Departmental
1.5 AVAILABILITY	.1	Immediately notify Departmenta writing of unforseen or unanticipy problems by manufacturer. documentation as per clause 1.1	ated material delivery Provide support
1.6 WORKMANSHIP	.1	Ensure quality of work is of higher by workers experienced and skille for which they are employed.	
	. 2	Remove unsuitable or incompetent stipulated in General Conditions	
	.3	Ensure cooperation or workers Maintain efficient and continuou at all times.	
	. 4	Coordinate work between trades	and sub-contractors.

accessories.

.5 Coordinate placement of openings, sleeves and

DFO	Common Product Requirements Section 01 61 00
Lower Terra Nova	
Infrastructure Upgrades	Page 3 of 4
Project No. F6879-179013	Durani da mata da farata da mara da ma
1.7 FASTENINGS - GENERAL.1	Provide metal fastenings and accessories in same texture, colour and finish as base metal in which they occur. Prevent electrolytic action between dissimilar metals. Use non-corrosive fasteners, anchors and spacers for securing exterior work and in humid areas.
.2	Space anchors within limits of load bearing or shear capacity and ensure that they provide positive permanent anchorage. Wood or organic material plugs not acceptable.
. 3	Keep exposed fastenings to minimum, space evenly and lay out neatly.
. 4	Fastenings which cause spalling or cracking of material to which anchorage is made, are not acceptable.
.5	Do not use explosive actuated fastening devices unless approved by Departmental Representative. See Section 01 35 29 on Health and Safety in this regard.
1.8 FASTENINGS1 EQUIPMENT	Use fastenings of standard commercial sizes and patterns with material and finish suitable for service.
. 2	Use heavy hexagon heads, semi-finished unless otherwise specified.
.3	Bolts may not project more than one (1) diameter beyond nuts.
. 4	Use plain type washers on equipment, sheet metal and soft gasket lock type washers where vibrations occur and, use resilient washers with stainless steel.
1.9 STORAGE, HANDING AND 1 PROTECTION	Deliver, handle and store materials in manner to prevent deterioration and soiling and in accordance with manufacturer's instructions when applicable.
. 2	Store packaged or bundled materials in original and undamaged condition with manufacturer's seal and labels intact. Do not remove from packaging or bundling until

- .2 Store packaged or bundled materials in original and undamaged condition with manufacturer's seal and labels intact. Do not remove from packaging or bundling until required in Work. Provide additional cover where manufacturer's packaging is insufficient to provide adequate protection.
- .3 Store products subject to damage from weather in weatherproof enclosures.
- .4 Store cementitious products clear of earth or concrete floors, and away from walls.
- .5 Keep sand, when used for grout or mortar materials,

DFO Lower Terra Nova Infrastructure Upgrades	(Common Product Requirements	Section 01 61 00 Page 4 of 4
Project No. F6879-179013			
		clean and dry. Store sand on woode with waterproof tarpaulins durin	
	.б	Store sheet materials and lumber or and keep clear of ground. Slope	
	.7	Store and mix paints in heated Remove oily rags and other combust daily. Take every precaution a spontaneous combustion.	ible debris from site
	. 8	Immediately remove damaged or resite.	jected materials from
	.9	Touch-up damaged factory fire Departmental Representative's touch-up materials to match original over name plates.	satisfaction. Use
1.10 CONSTRUCTION EQUIPMENT AND PLANT	.1	On request, prove to the satisfact Representative that the construption of the satisfacture of the satisfa	action equipment and re, transport, place and production rates replace or provide
	.2	Maintain construction equipment operating order. Prevent oil at leaks. Should any contaminant let the water, take immediate and appropriation, clean-up and dispose it responsible manner.	nd other contaminant ak onto ground or into propriate measures to

PART 2 - PRODUCTS

2.1 NOT USED

PART 3 - EXECUTION

DFO Lower Terra Nova Infrastructure Upgrades	С	Page 1 of 2
Project No. F6879-179013		
PART 1 - GENERAL		
1.1 SECTION INCLUDES	.1	Progressive cleaning.
	. 2	Final cleaning.
1.2 PRECEDENCE	.1	For Federal Government projects, Division 1 Sections take precedence over technical specification sections in other Divisions of this Project Manual.
1.3 RELATED SECTION	.1	Section 01 77 00 - Closeout Procedures.
1.4 PROJECT CLEANLINESS	.1	Maintain Work in tidy condition, free from accumulation of waste products and debris, including that caused by Owner or other Contractors.
	.2	Remove waste materials from site at regularly scheduled times or dispose of as directed by Departmental Representative. Do not burn waste materials on site.
	.3	Make arrangements with and obtain permits from authorities having jurisdiction for disposal of waste and debris.
	. 4	Provide on-site containers for collection of waste materials and debris.
	.5	Provide and use clearly marked separate bins for recycling.
	.6	Remove waste material and debris from site and deposit in waste container at end of each working day.
	.7	Store volatile waste in covered metal containers, and remove from premises at end of each working day.
	.8	Dispose of waste materials, and debris off site at approved facilities.
1.5 FINAL CLEANING	.1	When Work is Substantially Performed, remove surplus products, tools, construction machinery and equipment not required for performance of remaining Work.
	.2	Remove waste products and debris other than that caused by others, and leave Work clean and suitable for occupancy.

DFO	C.	leaning	Section 01 74 11
Lower Terra Nova			
Infrastructure Upgrades			Page 2 of 2
Project No. F6879-179013			
	.3	Prior to final review, remove surpose construction machinery and equip	
	. 4	Remove waste products and debris of by Owner or other Contractors.	ther than that caused
	.5	Remove waste materials from site a times or dispose of as directed Representative. Do not burn wast	by Departmental
	.6	Make arrangements with and obtain authorities having jurisdiction and debris.	
	.7	Broom clean and wash exterior was surfaces; rake clean other surfa	-
	.8	Remove dirt and other disfigurat surfaces.	ion from exterior
	.9	Sweep and wash clean paved areas	; .
PART 2 - PRODUCTS			
2.1 NOT USED	.1	Not Used.	
PART 3 - EXECUTION			

3.1 NOT USED .1 Not Used.

DFO		Construction/Demolition	Section 01 74 21
Lower Terra Nova Infrastructure Upgrades Project No. F6879-179013		Waste Management & Disposal	Page 1 of 5
PART 1 - GENERAL			
THE TODALITY			
1.1 RELATED SECTIONS	.1	Section 01 35 43 - Environmental	l Procedures.
	.2	Section 02 41 16 - Demolition ar	nd Removal.
1.2 WASTE MANAGEMENT PLAN	.1	Prior to commencement of work, pre Workplan.	pare waste Management
	. 2	Workplan to include: .1 Waste audit2 Waste reduction practices3 Material source separation practices4 Procedures for sending recy facilities5 Procedures for sending nones waste to approved waste probability site6 Training and supervising management at site. Workplan to incorporate waste man specified herein and in other	clables to recycling salvageable items and occessing facility or workforce on waste
	.4	Specifications. Develop Workplan in collab subcontractors to ensure all was and opportunities are addressed.	
	.5	Submit copy of Workplan to Department for review and approval. 1 Make revisions to Plan as dir Representative.	_
	.6	Implement and manage all aspects Workplan for duration of work.	of Waste Management
	.7	Revise Plan as work progres opportunities for diversion of w	ses addressing new aste from landfill.
1.3 WASTE AUDIT	.1	At project start-up, conduct was .1 Site conditions identifyi non-salvageable items and of demolition and removal work .2 Projected waste resulting from material leftover after	ng salvageable and waste resulting from . rom product packaging
	.2	Develop written list. Record ty quantity of various salvageab	

DFO	Construction/Demolition	Section 01 74 21
Lower Terra Nova Infrastructure Upgrades		Page 2 of 5
Project No. F6879-179013	Waste Management & Disposal	
	anticipated, reasons for to operational factors which cont	waste generation and cribute to waste.
1.4 WASTE REDUCTION	1 Based on waste audit, develop w	aste reduction program.
	2 Structure program to prioriti reduction as first priority, f recycling effort, then disposa	followed by salvage and
	3 Identify materials and equipme .1 Protected and turned Representative when indic .2 Salvaged for resale by Co .3 Sent to recycling facilit .4 Sent to waste processing/ recycling effort5 Disposed of in approved 1	over to Departmental sated. Intractor. y. landfill site for their
	4 Reduce construction waste dur Undertake practices which wi optimize full use of new mater .1 Use of a central cutting access to off-cuts; .2 Use of off-cuts for blocking .3 Use of effective and facilities on site for selective or partially cut to allow for easy incorporations possible avoiding unnecessible	Il minimize waste and rials on site, such as: area to allow for easy gand bridging elsewhere. strategically placed storage and staging of materials (such as gypsum iles, insulation, etc.) ation into work whenever
	.5 Develop other strategies and innovative procedures t reduce waste such as minimizing the extent of packagir used for delivery of materials to site, etc.	
1.5 MATERIAL SOURCE SEPARATION PROCESS	Develop and implement materials at commencement of work as pa waste management at site.	
	 2 Provide on-site facilities to canticipated quantities of reurecyclable materials. .1 Use suitable containers for of items based on intende 2 Locate to facilitate deposit 	sable, salvageable and or individual collection d purpose.

and use.

Locate to facilitate deposit but without hindering daily operations of existing building tenants. Clearly mark containers and stockpiles as to purpose

DFO Construction/Demolition Section 01 74 21 Lower Terra Nova Infrastructure Upgrades Page 3 of 5 Project No. F6879-179013 Waste Management & Disposal Perform demolition and removal of existing structure components and equipment following a systematic deconstruction process. Separate materials and equipment at source, carefully dismantling, labelling and stockpiling alike items for the following purposes: Reinstallation into the work where indicated. Salvaging reusable items not needed in project . 2 which Contractor may sell to other parties. Sale of such items not permitted on site. Sending as many items as possible to locally available recycling facility. Segregating remaining waste and debris into various individual waste categories for disposal in a "non-mixed state" as recommended by waste processing/landfill sites. Isolate product packaging and delivery containers from general waste stream. Send to recycling facility or return to supplier/manufacturer. Send leftover material resulting from installation work . 5 for recycling whenever possible. .6 Establish methods whereby hazardous and toxic waste materials, and their containers, encountered or used in the course of work are properly isolated, stored on site and disposed of in accordance with applicable laws and regulations from authorities jurisdiction. Isolate and store existing materials and equipment identified for re-incorporation into the Work. Protect against damage. Provide adequate training to workforce, through meetings 1.6 WORKER TRAINING AND . 1 and demonstrations, to emphasize purpose and worker SUPERVISION responsibilities in carrying out the Waste Management Plan. Waste Management Coordinator: designate full-time person on site, experienced in waste management and having knowledge of the purpose and content of Waste Management Plan to: Oversee and supervise waste management during work. .1

Provide instructions and directions to all workers and subcontractors on waste reduction, source

Post a copy of Plan in a prominent location on site

separation and disposal practices.

for review by workers.

DFO		(Construction/Demolition	Section 01 74 21
	r Terra Nova			
	astructure Upgrades			Page 4 of 5
	ect No. F6879-179013		Waste Management & Disposal	
1.7 CERTIFICATION OF MATERIAL DIVERSION		.1	Submit to Departmental Represe certified weigh bills from author sites and sale receipts from recycle confirming receipt of building may of waste diverted from landfill.	ized waste processing ling/reuse facilities
		.2	Submit data at pre-determined podetermined by Departmental Repre	
		.3	Compare actual quantities diverte projections made during waste au	
1.8	DISPOSAL REQUIREMENT	.1	Burying or burning of rubbish an prohibited.	d waste materials is
		.2	Disposal of waste, volatile materi oil, paint, paint thinner or unused into waterways, storm, or sanitary	preservative material
		.3	Do not dispose of preservative incineration.	treated wood through
		. 4	Do not dispose of preservative tr materials destined for recycling	
		.5	Dispose of treated wood, end pie sawdust at a sanitary landfill.	ces, wood scraps and
		.6	Dispose of waste only at approve facility or landfill sites approve jurisdiction.	
		.7	Contact the authority having just commencement of work, to deter demolition and construction wasted banned from disposal in landfi stations. Take appropriate action materials at site of work and disposal with provincial and municipal results.	emine what, if any, and and at transfer to isolate such banned at instrict accordance
		.8	Transport waste intended for lacondition, following rules and Landfill Operator in support of the recycle and reduce amount of sollandfill.	recommendations of meir effort to divert,
		.9	Collect, bundle and transport s	alvaged materials to

be recycled in separated categories and condition as directed by recycling facility. Ship materials only

.10 Sale of salvaged items by Contractor to other parties

to approved recycling facilities.

not permitted on site.

DFO	Construction/Demolition	Section 01 74 21
Lower Terra Nova	·	
Infrastructure Upgrades		Page 5 of 5
Project No. F6879-179013	Waste Management & Disposal	

PART 2 - PRODUCTS

2.1 NOT USED

PART 3 - EXECUTION

DFO		Closeout Procedures	Section 01 77 00	
Lower Terra Nova Infrastructure Upgrades Project No. F6879-179013			Page 1 of 2	
PART 1 - GENERAL				
1.1 SECTION .	. 1	Administrative procedures pr final inspections of Work.	eceding preliminary and	
1.2 PRECEDENCE .	. 1	For Federal Government projectake precedence over technica in other Divisions of this P	al specification sections	
1.3 RELATED . SECTIONS	. 1	Section 01 78 00 - Closeout	Submittals.	
-	. 2	Section 01 74 11 - Cleaning.		
1.4 INSPECTION AND DECLARATION	.1	Contractor's Inspection: Con Subcontractors shall conduct identify deficiencies and de required to conform to Contr. 1 Notify Departmental Re of satisfactory completion of and that corrections have be .2 Request Departmental R Inspection.	an inspection of Work, fects, and repair as act Documents. presentative in writing Contractor's Inspection en made.	
	. 2	Departmental Representative' Departmental Representative perform inspection of Work to or deficiencies. Contractor accordingly.	and Contractor will identify obvious defects	
	. 3	have been performed: .1 Work has been complete compliance with Contract Doc .2 Defects have been corr have been completed3 Certificates required Department of Labour and Env submitted4 Operation of systems have Departmental Representative'	d and inspected for uments. ected and deficiencies by Newfoundland ironment have been ave been demonstrated to	
	. 4	Off-Grid Power Supply System off-grid power supply system certified technician, approv Representative, it must be in by such a technician, to the	n is not installed by a red by the Departmental spected and commissioned	

completion.

by such a technician, to the approval of the Departmental Representative and prior to project

DFO Lower Terra Nova	Cl	oseout Procedures	Section 01 77 00
Infrastructure Upgrades Project No. F6879-179013			Page 2 of 2
	. 5	Final Inspection: when items noted request final inspection of World Representative, and Contractor. incomplete by Departmental Representation shall complete outstarequest re-inspection.	k by Departmental If Work is deemed esentative the
PART 2 - PRODUCTS			
2.1 NOT USED	.1	Not Used.	
PART 3 - EXECUTION			
3.1 NOT USED	. 1	Not Used.	

DFO		Closeout Submittals	Section 01 78 00
Lower Terra Nova Infrastructure Upgrades Project No. F6879-179013			Page 1 of 5
PART 1 - GENERAL			
1.1 SECTION INCLUDES	.1	As-built, samples, and specific	cations.
	.2	Equipment and systems.	
	.3	Product data, materials and fir information.	nishes, and related
	. 4	Operation and maintenance data.	
	.5	Spare parts, special tools and m	aintenance materials.
	.6	Warranties and bonds.	
	.7	Final site survey.	
1.2 PRECEDENCE	.1	For Federal Government projects take precedence over technical sin other Divisions of this Proj	pecification sections
	.1	Section 01 33 00 - Submittal Pr	cocedure.
SECTIONS	. 2	Section 01 45 00 - Testing & Qu	ality Control.
	.3	Section 01 77 00 - Closeout Pro	ocedures.
1.4 SUBMISSION	.1	Prepare instructions and data a experienced in maintenance and oproducts.	
	.2	Copy will be returned after fir Departmental Representative's	
	.3	Revise content of documents as r submittal.	equired prior to final
	. 4	Two weeks prior to Substantial Pessubmit to the Departmental Represopies of operating and maintenary	esentative, four final
	.5	Ensure spare parts, maintenance tools provided are new, undamage of same quality and manufacture in Work.	ged or defective, and
	.6	If requested, furnish evidence quality of products provided.	as to type, source and

DFO		Closeout Submittals	Section 01 78 00
Lower Terra Nova		Closeout Submitetais	Section of 70 00
Infrastructure Upgrades			Page 2 of 5
Project No. F6879-179013	.7	Defective products will be rej	ected, regardless of
	• /	previous inspections. Replace pr	-
	.8	Pay costs of transportation.	
1.5 FORMAT	.1	Organize data in the form of an	instructional manual.
	.2	Binders: vinyl, hard covered, 3 219 x 279 mm with spine and fac	
	.3	When multiple binders are used related consistent groupings. each binder on spine.	
	.4	Cover: Identify each binder with 'Project Record Documents'; lis identify subject matter of con-	t title of project and
	.5	Arrange content by systems, und sequence of Table of Contents.	er Section numbers and
	.6	Provide tabbed fly leaf for each system, with typed description component parts of equipment.	
	.7	Text: Manufacturer's printed data.	ata, or typewritten
	.8	Drawings: provide with reinforc Bind in with text; fold larger day pages.	
	.9	Provide 1:1 scaled CAD files in diskettes or CD.	n dxf or dwg format on
1.6 CONTENTS - EACH VOLUME	.1	Table of Contents: provide title .1 date of submission; name .2 addresses, and telephone and Contractor with name of res3 schedule of products and content of volume.	s, numbers of Consultant sponsible parties;
	.2	For each product or system: .1 list names, addresses and subcontractors and suppliers, if of supplies and replacement page.	including local source
	.3	Product Data: mark each sheet specific products and component applicable to installation; definition.	t parts, and data

. 4

Drawings: supplement product data to illustrate

DFO	Closeout Submittals	Section 01 78 00
Lower Terra Nova Infrastructure Upgrades Project No. F6879-179013		Page 3 of 5
	relations of component parts to show control and flow di	
	Typewritten Text: as required data. Provide logical sequence procedure, incorporating maspecified in Section 01 45	ce of instructions for each nufacturer's instructions
1.7 AS-BUILTS AND . SAMPLES .	<pre>1 Maintain at the site for Degrate one record copy of: .1 Contract Drawings. .2 Specifications. .3 Addenda. .4 Change Orders and other.</pre>	partmental Representative
	Contract5 Reviewed shop drawing samples6 Field test records7 Inspection certificat .8 Manufacturer's certif	es.
	Store record documents and apart from documents used f files, racks, and secure st	for construction. Provide
	3 Label record documents and Section number listings in Project Manual. Label each in neat, large, printed let	List of Contents of this document "PROJECT RECORD"
	Maintain record documents i condition. Do not use record purposes.	
,	5 Keep record documents and s inspection by Departmental	=
1.8 RECORDING . ACTUAL SITE CONDITIONS	Record information on set of by Departmental Representat	
	Provide felt tip marking pe colours for each major syst information.	
	Record information concurre progress. Do not conceal Wo information is recorded.	
	underground utilities and a to permanent surface improv	ruction, including: and vertical locations of appurtenances, referenced

.2 Measured locations of internal utilities and

DEO		
DFO Lower Terra Nova	Closeout Submittals	Section 01 78 00
Infrastructure Upgrades		Page 4 of 5
Project No. F6879-179013		_ ~ 5 - 5 - 5
	appurtenances, referenced to seatures of construction.	visible and accessible
	.3 Field changes of dimens.4 Changes made by change of	orders.
	.5 Details not on original.6 References to related shmodifications.	
. (Specifications: legibly mark ear construction, including:	e, and catalogue number alled, particularly items.
. (Other Documents: maintain manu certifications, inspection cer records, required by individual sections.	tifications, field test
1.9 FINAL SURVEY	Submit final site survey certicelevations and locations of conformance, or non-conformance Documents.	ompleted work are in
1.10 WARRANTIES AND BONDS	Separate each warranty or bond keyed to Table of Contents lis	
	List subcontractor, supplier, name, address, and telephone principal.	
.:	Obtain warranties and bonds, essubcontractors, suppliers, and ten days after completion of work.	d manufacturers, within
. 4	Except for items put into use Representative's permission, I of time of warranty until the Performance is determined.	leave date of beginning
	Verify that documents are in pr information, and are notarized	
. (Co-execute submittals when red	quired.
	Retain warranties and bonds ur submittal.	atil time specified for

DFO	(Closeout Submittals	Section 01 78 00
Lower Terra Nova Infrastructure Upgrades Project No. F6879-179013			Page 5 of 5
1.11 MATERIALS AND FINISHES	.1	Building Products, Applied Mate include produce data, with cata composition, and colour and tex Provide information for re-orde manufactured products.	logue number, size, ture designations.
PART 2 - PRODUCTS			
2.1 NOT USED	.1	Not Used.	
PART 3 - EXECUTION			
3.1 NOT USED	.1	Not Used.	

DFO	Demolition a	and Removal	Section 02 41 16
Lower Terra Nova			
Infrastructure Upgrades			Page 1 of 1
Project No. F6879-179013	}		

PART 1 - GENERAL

- 1.1 <u>Description</u> .1 This section specifies requirements for demolishing and removing wholly or in part various items designated to be removed or partially removed.
- 1.2 <u>Protection</u>
 .1 Protect existing objects designated to remain. In event of damage, immediately replace or make repairs to approval of, and at no additional cost to, Departmental Representative.

PART 2 - PRODUCTS

N/A

PART 3 - EXECUTION

- 3.1 Execution .1 Inspect site and verify with Departmental Representative full scope of removal, as shown on the drawings.
- 3.2 Removal .1 Remove in their entirety all materials and objects specified for removal.
 - .2 Do not disturb items designated to remain in place, if any such items exist.
- 3.3 Disposal
 of Material

 The Departmental Representative will have the first right of refusal (at no cost) to all demolished/removed materials (including all off-grid power system components) except those designated for reuse. If the Owner does not want any of the materials, such materials will become the property of the contractor to be removed from the site and disposed of to satisfaction of Departmental Representative and in accordance with all applicable permits.
- 3.4 Restoration .1 Upon completion of work, remove debris, trim surfaces and leave work site in clean condition.
 - .2 Reinstate areas and existing works outside areas of demolition to conditions that existed prior to commencement of work.

DFO			Concrete Formwork	Section 03 10 00
	r Terra Nova		Concrete Formwork	Section 03 10 00
	astructure Upgra			Page 1 of 2
Proj	ect No. F6879-1	79013	and Accessories	
PART	1 - GENERAL			
1.1	<u>Description</u>	.1	This section specifies requirements installation of concrete f	
1.2	Reference Standards	.1	Do concrete formwork to C indicated otherwise.	SA A23.1, except where
1.3	Shop Drawings	.1	Submit shop drawings.	
		.2	Clearly indicate meth construction, materials, ties, shores, liners and embedded parts. Comply wifor falsework drawings.	arrangement of joints, location of temporary
PART	2 - PRODUCTS			
2.1	<u>Materials</u>	.1	Formwork lumber: plywood materials to CSA A23.1.	l and wood formwork
		.2	accompanied with cer or other proof of c shall be appropriate	CSA S269.1 or grade marks, or be rtificates, test reports conformity. Materials e for use in a fresh water t to the aquatic habitat.
		.3	Form release agent: chemagents containing compoundime present in concrete to soaps, preventing set of fiwith form. Materials shall in a fresh water source with habitat.	ds that react with free provide water insoluble lm of concrete in contact ll be appropriate for use
		. 4	Form ties: removable or some or adjustable length, free larger than 25 mm dia in	of devices leaving holes
		.5	Premoulded joint fillers: .1 Bituminous impregna D1751.	ted fibreboard: to ASTM
		.6		

PART 3 - EXECUTION

3.1 <u>Formwork</u>

.1 Verify lines and levels before proceeding with formwork and ensure dimensions agree with drawings.

DFO			Concrete Formwork Se	ction 03 10 00
	r Terra Nova astructure Upgrad	des		Page 2 of 2
	ect No. F6879-179		and Accessories	1490 2 01 2
		.2	Construct forms to produce finish conforming to the shape, dimension elevations shown on drawings with required by CSA A23.1.	s, locations and
		.3	Construct falsework to CSA S269.1	
		. 4	Align form joints and make waterti joints to minimum.	ght. Keep form
		.5	Expansion and control joints as s Sections 03 30 00.	pecified in
		.6	Unless otherwise directed by the Representative, leave formwork in p of seven (7) days when work is compand three (3) days when work is compait moisture curing.	lace for minimum pleted in-water
		.7	All exposed formwork to be stripped cured.	d after concrete
		.8	Reuse of formwork subject to requA23.1 Clause 11.9.	irements of CSA
3.2	Joint Fillers	.1	Locate and form expansion joints Install joint filler.	as indicated.
		.2	Use 13 mm thick joint filler to s slabs-on-grade and extend joint fi of slab to within 25 mm of finish unless indicated otherwise.	ller from bottom
3.3	Workmanship	.1	Place concrete in accordance with Section 03 30 00.	CAN3-A23.1-M90,
		.2	Ensure reinforcement and inserts a during concrete placement.	re not disturbed
		.3	Obtain Departmental Representative proposed method for protection of placing and curing in adverse weat placing of concrete.	concrete during
3.4	<u>Inserts</u>	.1	Set sleeves, ties and other insert required.	s in concrete as
		.2	All sharp and protruding ties and removed to the face of the concret non-abrasive surface.	
3.5	Defective Concrete	.1	Remove defective concrete, blemis embedded debris and repair as dir Departmental Representative, and a Owner.	ected by

DFO			Concrete Reinforcement Section 03 20 00
Infr	r Terra Nova astructure Upgra ect No. F6879-17		Page 1 of 2
PART	1 - GENERAL		
1.1	Description	.1	This section specifies requirements for supplying and placing reinforcing steel for concrete work.
1.2	Reference Standards	.1	Do concrete reinforcement work to CSA A23.1.
1.3	Source <u>Sampling</u>	.1	Provide Departmental Representative with certified copy of mill test of steel supplied, showing physical and chemical analysis, minimum four (4) weeks prior to commencing work.
1.4	Shop Drawings	.1	Submit shop drawings and bar list of rebar.
1.5	Delivery and Storage	.1	To CSA A23.1
PART	2 - PRODUCTS		
2.1	<u>Materials</u>	.1	Reinforcing Steel - to CSA G30.12 billet steel, deformed bars having yield stress of 400 Mpa.
		.2	Wire Ties - to CSA G30.3, plain, cold drawn annealed steel wire.
		.3	Supports - to CSA A23.1.
2.2	<u>Fabrication</u>	.1	Ship bundles of bar reinforcement, clearly identified in accordance with bar list to be supplied upon request.
PART	3 - EXECUTION		
3.1	Field Bending	.1	Do not field bend reinforcement except where indicated or authorized by Departmental Representative.
		.2	When authorized, bend without heat, applying a slow and steady pressure.
3.2	Placing	.1	Accurately place the reinforcing steel as indicated on the drawings and hold firmly during placing, compacting and setting of the concrete.

DFO Lower Terra Nova Infrastructure Upgrades Project No. F6879-179013			Concrete Reinforcement Section 03 20 00 Page 2 of 2
		.2	Use approved type chairs to locate the reinforcing at the proper grade.
		.3	Tie reinforcement where spacing in each direction is: .1 Less than 300 mm: - tie at alternate intersections2 300 mm or more: - tie at each intersection.
3.3	Cleaning	.1	Clean reinforcing before placing concrete to CSA A23.1.
3.4	Inspection	.1	Do not place concrete until Departmental Representative has inspected and approved reinforcement work in place.

Lower Terra Nova Infrastructure Upgrades Project No. F6879-179013

Page 1 of 8

PART 1 - GENERAL

- 1.1 <u>Description</u> .1 This section specifies requirements for supplying, placing, finishing, protecting and curing concrete.
- 1.2 Reference .1 Do structural concrete work to CSA-A23.1 standards and CSA A23.3.
- 1.3 Submittals .1 Qualifications of personnel performing the work.
 - .2 Mix designs including compressive test data used to establish proportions. Material certificates for materials, including cements, aggregates and admixtures.
- 1.4 Source Sampling
- .1 At least two (2) weeks prior to commencing work inform Departmental Representative of proposed source of following material to be supplied and forward samples to testing laboratory to be designated by the Departmental Representative.
 - .1 Coarse and fine aggregate
 - .2 Portland cement
 - .3 Admixtures
 - .4 Joint filler
 - .5 Joint sealant
 - .6 Curing compound
 - .7 Blended hydraulic cement.8 Supplementary cementing materials
- .2 Provide certification that mix proportions selected will produce concrete of quality, yield and strength as specified in concrete mixes and will comply with CAN/CSA-A23.1.
- .3 Provide certification that plant, equipment, and materials to be used in concrete comply with requirements of CAN/CSA-A23.1.
- 1.5 Storage of Materials
- .1 Store materials to prevent contamination or deterioration.
- .2 Provide adequate storage facilities for materials to ensure a continuous supply of these materials during batching operations.
- .3 Store cement in weathertight facility.
- .4 Stockpile aggregates in accordance with good standard practice.
- 1.6 Quality
 Assurance
- .1 Minimum two (2) weeks prior to starting concrete work, submit proposed quality control procedures to Departmental Representative for the

DFO		Cast-In-Place	Contrete	Section	03	30	00
_	_						

Lower Terra Nova Infrastructure Upgrades Project No. F6879-179013

Page 2 of 8

following items:

- .1 Cold weather concrete;
- .2 Curing;
- .3 Finishes;
- .4 Formwork removal;
- .5 Joints.

1.7 Waste Management & Disposal

- .1 Use trigger operated spray nozzles for water hoses.
- .2 Designate a cleaning area for tools to limit water use and runoff.
- .3 Carefully coordinate the specified concrete work with weather conditions.
- .4 Ensure emptied containers are sealed and stored safely for disposal away from children.
- .5 Prevent plasticizers, water-reducing agents and air-entraining agents from entering water supplies or streams. Using appropriate safety precautions, collect liquid or solidify liquid with an inert, non-combustible material and remove for disposal. Dispose of all waste in accordance with applicable local, provincial and national regulations.
- .6 Choose least harmful appropriate cleaning method which will perform adequately.

PART 2 - PRODUCTS

2.1 Materials

- .1 Cement to CAN/CSA-A3001, Type GUb, Portland Cement (blended).
- .2 Supplementary cementing materials: to CAN/CSA-A3001.
- .3 Cementitious hydraulic slag: to CAN/CSA-A3001.
- .4 Water: to CAN/CSA-A23.1.
- .5 Aggregates: to CAN/CSA-A23.1. Coarse aggregates to be normal density.
- .6 Air entraining admixture: to ASTM C260.
- .7 Chemical admixtures: to ASTM C494/C494M.

 Departmental Representative to approve accelerating or set retarding admixtures during cold and hot weather placing.
- .8 Concrete retarders: to ASTM C494M. Do not allow moisture of any kind to come in contact with the retarder film.
- .9 Curing compound: curing compounds are not to be used.

- .10 Pre-moulded joint fillers:
 - .1 Sponge rubber: to ASTM D1752, Type 1, flexible grade.
 - .2 Joint sealer: to CGSB 19-GP-24M and CSA A23.1, chemical curing, multi-component, Class 'B', Type 1 for horizontal joints.
- .11 Bonding Agent
 - .1 Bonding agent to be weld-crete or approved equal.
- .12 Water Stops
 - .1 Flexile butyl rubber and swellable clay waterproofing compound that swells upon contact with water to form a compression seal.
 - .1 Swellstop Waterstop by Greenstreak or approved equal.

2.2 Concrete Mixes

- .1 Concrete shall be mixed and proportioned in accordance to CSA A23.1, Clause 4.3.
- .2 Concrete shall be proportioned to comply with Alternative 1, Table 2 in CSA A23.1 and following requirements:
 - .1 Cement: Type GUb, Portland Cement (blended).
 - .2 Minimum compressive strength of all concrete to be 35 MPa at 28 days.
 - .3 Class "F1" exposure.
 - .4 Nominal size of course aggregate 20 mm.
 - .5 Slump range at point of discharge 50 mm to 100 mm.
 - .6 Air Content 5 8 percent.
 - .7 Density of air-dry concrete will be in range of 2240 to 2400 kg/m³.
 - .8 Minimum cement content: 385 kg/m³.
 - .9 Maximum w/c ratio : 0.40
 - .10 High range water reducing agents (superplasticizers) may be used at the Contractor's request, if so indicated when the mix design is submitted. The Contractor must demonstrate competence and experience in their use and specific approval must be obtained. The Contractor shall state his method of concrete placement when submitting his concrete mix design.
 - .11 If superplasticizers are used, the maximum concrete slump in a superplasticized condtion shall be limited to 230 mm. The mix design shall state the design slump before and after the addition of superplasticizers along with the appropriate tolerances. Note that the slump in the above may not be applicable when using superplasticizers.

- .3 When the Contractor wishes to purchase concrete from a ready mix concrete supplier, submit a letter from the supplier certifying the following:
 - .1 That his plant and equipment is certified and all materials to be used in the concrete comply with the requirements of CSA Standard CSA A23.1.
 - .2 That the mix proportions selected will produce concrete of the specified quality and yield. Indicate mix proportions and sources of all materials.
 - .3 That the strengths will comply with the strengths specified herein.
- .4 When the Contractor wishes to mix concrete on site, he shall identify the source of aggregates and submit samples of fine and coarse aggregates to a testing laboratory for testing and trial mixes in order to determine a suitable mix design. The testing laboratory, at Contractor's cost, will test the trial mix for slump, air content, density and strength. The results of these tests will be submitted to the Departmental Representative to be reviewed for compliance with the specification. This review must be completed before permission to place concrete is given.
 - .1 The sand, gravel, water and air entraining agent should be mixed prior to the addition of cement and water reducer.
- .5 Weigh aggregates, cement, water and admixture when batching. No alternative methods of measuring will be permitted.
- .6 Do not use calcium chloride.

PART 3 - EXECUTION

3.1 General

- .1 Comply with additional requirements of CSA A23.1, Clause 15, for concrete exposed to seawater environments.
- .2 Place concrete in hot weather to CSA A23.1.
- .3 Place concrete in cold weather to CSA A23.1.
- .4 Keep concrete surfaces moist continually during protection stage.
- .5 Place, consolidate, finish, cure and protect concrete to CSA A23.1.
- .6 Do not commence placing concrete until Departmental Representative has inspected and approved forms, foundations, reinforcing steel, joints, conveying, spreading, consolidation and finishing equipment and curing and protective methods.

3.2 Scheduling and Work Metholology

- .1 Prior to commencing any work, obtain all requirements and approvals of fish habitat and related regulatory authorities for carrying out the work.
- .2 Develop a detailed work schedule and methodology for all excavation and construction work and submit to Departmental Representative and applicable regulatory authorities for review and approval. Contractor's schedule and methodology shall address all restrictions placed on work by regulatory authorities and indicate how the work plan will address such issues.
- All work must be carried out in the dry, unless otherwise approved by the Departmental Representative. Where berms are required to accomplish this, the design of such berms is to be carried out by a professional Engineer licensed to practice in Newfoundland. Drawings of the berm design, stamped by the Engineer, are to be submitted to and approved by the Departmental Representative before any work starts.

3.3 Preparation

- .1 Prior to installing rock/concrete anchors or concrete formwork, remove all loose and fractured rock/concrete to sound competent material, to satisfaction of Departmental Representative. This will provide a clean and competent rock/concrete surface for dowelling and concrete placement. Roughen rock/concrete surface to approval of Departmental Representative, prior to placement of bonding agent and fresh concrete.
- .2 Hardened concrete which shall receive new concrete shall be roughened to a full amplitude of no less than 5 mm, and have bonding agent applied prior to placement.
- .3 Over excavation for rock removal will not be accepted. Additional work to correct over excavation, to the approval of the Departmental Representative, will be at the contractors expense.
- .4 Obtain Departmental Representative's approval before placing concrete. Provide 24 hours notice prior to placing concrete.
- .5 Pumping of concrete is permitted only after approval of equipment and mix.
- .6 Ensure reinforcement and inserts are not disturbed during concrete placement.
- .7 Prior to placing of concrete obtain Departmental Representative's approval of proposed method for protection of concrete during placing and curing in adverse weather.

DFO	т Потто Могго	C	ast-in-Place Contrete Section 03 30 00
Infr	r Terra Nova astructure Upgra ect No. F6879-17		Page 6 of 8
110)	CCC NO. 1 00 / 9 1 /	J013	
		.8	Maintain accurate records of poured concrete items to indicate date, location of pour, quality, air temperature and test samples taken.
		.9	Do not place load upon new concrete until authorized by Departmental Representative.
		.10	Apply approved bonding agent on all concrete to rock interfaces and all concrete to concrete interfaces prior to pouring fresh concrete.
3.4	Formwork	.1	Install and strip formwork to CSA A23.1 and Section 03 10 00.
3.5	Inserts	.1	Position and secure anchor bolts/pre-engineered, C.I.P. anchors (by Simpson Strong-tie, or approved equal) in formwork to maintain line and grades.
3.6	Placing Concrete	.1	Place and consolidate concrete to CSA - A23.1.
		.2	Do not place concrete on or against frozen material.
		.3	Place concrete continuously from joint to joint. Unless otherwise specified, consolidate concrete with high speed internal vibrators.
		. 4	Place concrete in a uniform heading, normal to the centreline. Limit rate of placing to that which can be finished before beginning of initial set.
		.5	If proposed by the Contractor, alternate placement methods to those described herein (which yield, the desired results), can be reviewed by the Departmental Representative with necessary submittals from the Contractor.
3.7	Bonding Agent	.1	Apply bonding agent to all concrete/rock interfaces and hardened concrete to fresh concrete interfaces, in accordance with manufacturer's instruction prior to pouring concrete. Bonding agent to be weldcrete or approved equal. Rock surfaces to be roughened to approval of the Departmental Representative before placement of fresh concrete. Hardened concrete surfaces to be roughened to a full amplitude of at least 5 mm prior to placement of fresh concrete.
3.8	Strike Off and Consolidation	.1	Internal poker vibrators shall be used to consolidate the concrete during placing.
		.2	Strikeoff and consolidation must be completed before excess water bleeds to the surface.

Ensure that the concrete conforms to the elevations

and slopes as shown on the drawings.

.3

Cast-In-Place Contrete

Section 03 30 00

DFO

DFO	Cast-In-Place Contrete	Section 03 30 00
Lower Terra Nova		
Infrastructure Upgrades		Page 7 of 8
Project No. F6879-179013	3	

- 3.9 <u>Finishing</u> .1 Refer to Section 03 35 00: Concrete Finish.
- 3.10 Protection .1 Cure to CSA-A23.1. and Curing
 - .2 Concrete shall be cured by protecting it against loss of moisture, rapid temperature change and mechanical injury for at least seven days after placement. After finishing operations have been completed, the entire surface of the newly placed

the Departmental Representative.

The Contractor shall have the equipment needed for adequate curing at hand and ready to install before actual concrete placement begins.

concrete shall be covered by whatever curing medium is applicable to local conditions and approved by

- .3 When air temperature is at or below 5°C or when there is a probability of its falling to that limit within 24 hours of placing (as forecast by the nearest official meteorological office) cold weather protection as per CSA A23.1 will be provided and the following:
 - Housing Protect concrete by a windproof shelter of canvas or other material to allow free circulation of inside air around fresh touch formwork and provide sufficient space for removal of formwork for finishing. Supply approved heating equipment capable of keeping inside air at a constant temperature sufficiently height to maintain concrete at following curing temperatures.
 - .2 For initial three (3) days at a temperature of not less than 15 degrees C nor more than 27 degrees C at surface.
 - .3 Maintain concrete at 10 degrees C for an extra four (4) days plus the initial three (3) days.
 - .4 In addition to the protective housing, the concrete must be cured as outlined in Clause 3.10.2 above.

- 3.11 Testing
- .1 Contractor will appoint a concrete testing company approved by the Departmental Representative to test all work under this section of specification as per CSA A23.1.
- .2 Cost of comprehensive strength tests shall be paid for by the Contractor.
- .3 Testing company shall issue reports to Departmental Representative on quality of test cylinders.
- .4 Contractor shall notify Departmental Representative at least seven (7) days prior to start of placing concrete. He shall provide for testing purposes an adequate quantity of approved test cylinders.

- .5 At least one (1) set of three (3) cylinders each shall be taken from 25 m³ or fraction thereof of each day's pour, whichever is less. One (1) cylinder shall be tested at seven (7) days and other two (2) tested at twenty-eight (28) days.
- .6 Cylinders will be crated and delivered to the testing laboratory within forty-eight (48) hours after casting in accordance with CSA A23.1. Contractor will pay for crating and delivery of cylinders to the laboratory.
- .7 If strength tests of test cylinder for any portion of the work falls below the specified compressive strength at 28 days, the Departmental Representative reserves the right to determine the acceptability of the concrete by performing additional field testing as outlined in CSA-A23.1.
- .8 If concrete does not conform to drawings or specifications, the Contractor will take measures as directed to correct the deficiency. All costs of correctional measures will be at the expense of the Contractor.
- .9 Inspection or testing enforced by the Departmental Representative will not replace Contractor quality control or relieve him of his contractual responsibility.

3.12 Placement Tolerance

.1 All concrete work shall be within \pm 12 mm of the dimensions and elevations indicated on the drawings. Failure to meet this condition may result in rejection of the work and replacement at the Contractor's expense.

PART 1 - GENERAL

1.1 Reference Standards

.1 Do concrete finishing to CSA-A23.1 unless specified otherwise.

PART 2 - PRODUCTS

2.1 Not Used

PART 3 - EXECUTION

3.1 Concrete Finish

- .1 Finish concrete in accordance with CAN3-A23.1-M90.
- .2 Rub exposed sharp edges of concrete with carborundum to produce 3 mm radius edges unless otherwise detailed.
- .3 All concrete surfaces, unless specified otherwise, that will be visible on completion of the work shall conform to surface finish Class 2. The surface shall be uniform in colour and texture when viewed from a distance of 15 m.
- .4 Class 2 Rubbed Finish
 - .1 Immediately following the removal of forms, all fins and irregular projections shall be removed from all interior and exterior surfaces except from those which are not to be exposed. On all surfaces, the cavitied produced by form ties and all other holes, honeycombs, spots, broken corners or edges and other defects shall be cut back to sound concrete and thoroughly cleaned. No feather edging is permissible.
 - After having been kept saturated . 2 with water for a period of not less than three hours, the cavities shall be carefully pointed and trued with a 40 mPa non-shrink grout. The patches shall be placed and cured as specified by the manufacturer. The resulting surfaces shall be true and uniform. After removal of forms, the rubbing of concrete shall be started as soon as its condition will permit. However, before starting this work the concrete shall be kept thoroughly saturated with water for a minimum period of three hours but sufficient time shall have elapsed before the wetting down to allow the grout used in the pointing of rod holes and defects to thoroughly set. Surfaces to be finished shall be rubbed with a medium coarse carborundum stone, using a small amount of mortar on its face. The mortar shall be composed of extra cement and fine and mixed in proportions such as to match

existing concrete verified by a patch test. Rubbing shall be continued until all form marks, projections and irregularities have been removed, all voids filled, and a uniform surface has been obtained. The paste produced by this rubbing shall be left in place at this item. After all concrete above the surface being treated has been cast, the final finish shall be obtained by rubbing with a fine carborundum stone and water. This rubbing shall be continuous until the entire surface is of a smooth texture and uniform colour. After the final rubbing is completed and the surface has dried, it shall be rubbed with burlap to remove loose powder and shall be left free from all unsound patches, paste, powder, and objectionable marks.

- .3 Steel trowel concrete surfaces by means of hand trowel. Do not leave any hard, smooth, polished or burnished surface area.
- .4 Do not bring water and fines to the surface by over trowelling.
- .5 After slight interval necessary for concrete to further harden, repeat the trowelling operation.
- .6 The surface shall be true and accurate within a tolerance acceptable to the Departmental Representative. Refer to Section 03 30 00, for acceptable concrete placement tolerances.

DFO Lower Terra Nova Infrastructure Upgrades PROJECT NO. F6879-179013	F	Rough Carpentry	Section 06 10 00 Page 1 of 5 August 2017
PART 1 - GENERAL			
1.1 RELATED SECTIONS	.1	Section 01 74 21 - Construct Management and Disposal.	ion/Demolition
1.2 REFERENCES	.1	Canadian General Standards B .1 CAN/CGSB-51-32, Sheathi Breather Type.	
	.2	Canadian Standards Association of CSA B111, Wire Nails, Sp. 2 CAN/CSA-G064, Hot Dip Gastragularly Shaped Articles. 3 CSA 0112 Series, CSA Standhesives. 4 CSA 0121, Douglas Fir Pl. 5 CAN/CSSA-0141, Softwood 6 CSA 0151, Canadian Softwood 7 CAN/CSA-0325.0, Construction	pikes and Staples. Alvanizing of Andards for Wood Lywood. Lumber. Wood Plywood.
	.3	National Lumber Grades Autho .1 Standard Grading Rules fo	-
1.3 QUALITY ASSURANCE	.1	Lumber identification: by g agency certified by Canadian Accreditation Board.	rade stamp of an Lumber Standards
	.2	Plywood, particleboard, OSB composite panels in accordance standards.	
1.4 SUBMITTALS	.1	Submit proof of compatibilit Copper Quaternary (ACQ) presand fasteners to be utilized	sure treated lumber

PART 2 - PRODUCTS

2.1 FRAMING AND LUMBER .1 Lumber: unless specified otherwise, softwood, No. 1 or No. 2 grade, S4S, moisture content 19%

DFO	R	ough Carpentry	Section 06 10 00
Lower Terra Nova			Page 2 of 5
Infrastructure Upgrades PROJECT NO. F6879-179013			August 2017
		(S-dry) or less in accordance standards: .1 CAN/CSA-0-1412 NLGA Standard Grading Ru	e with following
	.2	Framing and board lumber: in NBC.	n accordance with
	.3	Furring, blocking, nailing strands, fascia backing and sleed of the strands of th	eepers: or better grade. lard" light framing
	. 4	Pressure treated material to Quaternary (ACQ).	be Alkaline Copper
2.2 PANEL MATERIALS	.1	Plywood, OSB and wood based to CAN/CSA-0325.0.	composite panels:
	.2	Douglas fir plywood (DFP): to construction.	CSA 0121, standard
	.3	Canadian softwood plywood (Castandard construction.	SP): to CSA 0151,
2.3 ACCESSORIES	.1	General purpose adhesive: to	o CSA 0112 Series.
	.2	Nails, spikes and staples:	to CSA B111.
	.3	Bolts: to ASTM A307 Grade, and washers. Diameter as indurating.	
	. 4	Proprietary fasteners: toggle shields and lag bolts, screws inorganic fibre plugs, explos fastening devices, recommended manufacturer.	s and lead or sive actuated

2.4 FASTENER FINISHES .1 Galvanizing: to ASTM A153/A153M , use galvanized

fasteners for exterior work.

DFO	Rough Carpentry	Section 06 10 00
Lower Terra Nova		Page 3 of 5
Infrastructure Upgrades		
PROJECT NO. F6879-179013		August 2017

2.5 WOOD PRESERVATIVE

.1 Surface-applied wood preservative: clear or copper napthenate or 5% pentachlorophenol solution, water repellent preservative.

2.6 PRE-ENGINEERED GALVANIZED METAL CONNECTORS

.1 Use metal connectors, hangers, caps, bases, hold-downs and plates for all wood to wood and wood to concrete connections as indicated on the drawings.

.2 Steel:

.1 Sheet: ASTM A36, ASTM A653, ASTM A1011 2. Fasteners: ASTM A307, ASTM F1554, ASTM F1667, SAE C1022 (SDS Screws).

.3 Finishes:

- .1 Hot-dipped galvanized or electro-plated galvanized: G90, G185 (ZMAX or HDG).
- .4 Install in strict accordance with the manufacturers specifications.
- .5 Standard of acceptance: Manufactured products by Simpson Strong-Tie Co., Inc. or approved equal. See drawings for specific connector details.

2.7 BOARDWALK/PATIO AND .1 HANDRAILING MATERIALS

Timber Materials:

- .1 Use timber graded and stamped in accordance with applicable grading rules and standards of associations or agencies approved to grade lumber by Canadian Lumber Standards Administration Board of CSA.
- .2 Species: Spruce/Pine/Fir (S-P-F) (CCA or ACA Treated).
- .3 Grade: No. 1/No. 2.
- .4 Grading Authority: NLGA
- .5 Preservative Treatment: Treated material to be Alkaline Copper Quaternary (ACQ), to CSA 080. Timbers will be treated in the lengths required. Unnecessary field

DFO	R	ough Carpentry	Section 06 10 00
Lower Terra Nova			Page 4 of 5
Infrastructure Upgrades PROJECT NO. F6879-179013			7 2017
PROJECT NO. F68/9-1/9013		cutting will not be per	August 2017
		cutting will not be per	.mrtted.
	.2	Footing Materials: Provide new as depicted on the drawings, .1 140 mm x 140 mm timber p .2 Precast concrete footing 140 mm post, by Shaw Bri approved equal.	c/w the following: cost; , 4-way deck block for
PART 3 - EXECUTION			
3.1 PREPARATION	.1	Treat cut surfaces of plant tr wood preservative, before ins	
	.2	Apply preservative by dipping completely saturate and maint surface for minimum 3 minute one minute soak on plywood.	tain wet film on
	.3	Re-treat surfaces exposed by or boring with liberal brush preservative before installat	application of
	. 4	All material to be treated un noted otherwise on the drawing Departmental Representative.	
3.2 INSTALLATION	.1	Comply with requirements of N	IBC latest edition.
	.2	Install members true to line, elevations, square and plumb	
	.3	Construct continuous members longest practical length.	from pieces of
	. 4	Install spanning members with	n "crown-edge" up.
	.5	Select exposed framing for ap lumber and panel material so t other defacing marks are conce by sanding where materials an	hat grade-marks and aled or are removed
	.6	Install rough bucks, nailers a openings as required to provide and other work.	

.7 Use dust collectors and high quality respirator masks when cutting or sanding wood panels.

DFO Lower Terra Nova Infrastructure Upgrades	Rough Carpentry		Section 06 10 00 Page 5 of 5
PROJECT NO. F6879-179013			August 2017
	.8	Construct new boardwalks to for topography. Install steps/st	_
	.9	New section from Accommodation Equipment Shed, including New Patio Deck #3, and New Timber to contain no steps or stairs. as required in this area, in (maximum slope = 1:12).	Patio Deck #2, New Boardwalk #3, is Ramp the boardwalk
	.10	Contractor may construction of prefabricated sections and transcriptions to site for installations to site for installations.	ansport completed
3.3 ERECTION	.1	Frame, anchor, fasten, tie an provide necessary strength an	
	.2	Countersink bolts where neces clearance for other work.	sary to provide
	.3	Use nailing disks for soft sh recommended by sheathing manu	_

DFO Building Structures Section 13 34 23.01 Lower Terra Nova

Infrastructure Upgrades
Project No. F6879-179013

and Equipment

PAGE 1 OF 7

PART 1 - GENERAL

1.1 DESCRIPTION

- .1 This section covers the construction of the New Equipment Shed and Renovations to the Existing Accommodations Building, including all associated building equipment (propane heater, solar controls, propane water heater, solar batteries, etc.), as detailed on the drawings and outlined in the specifications.
- .2 Contractor will coordinate work with other trades responsible for related work. Examine all drawings, details and specifications to coordinate work with the work of other trades. No claim for any extra work will be entertained for delays occasioned by such activities.

PART 2 - PRODUCTS

2.1 MATERIALS

- .1 Materials specified herein shall be of the best quality available for the use intended.

 Materials deemed by the Departmental Representative as being unsuitable shall be rejected and replaced by acceptable material.
- .2 Materials shall conform to the requirements and details indicated on the drawings and to the latest standards of the following regulatory agencies:
 - .1 Canadian Government Specification Board;
 - .2 Canadian Standards Association;
 - .3 Canadian Lumbermen's Association Standard Grading Rules;
 - .4 Plywood Manufacturer's Association of British Columbia;
 - .5 British Columbia Lumber Manufacturer's Association;
 - .6 National Building Code of Canada.

.3 New Equipment Shed:

- .3 Dimension Lumber: to CSA 0141-05 and species group to CSA 086-01 as listed and to National Grades Authority Standard Grading Rules 1970 Grade category as follows:
 - .1 Structural light framing: species Group D, No. 1 grade.
 - .2 See Section 06 10 00 Rough Carpentry.
- .4 Plywood shall be as follows:
 - .1 Plywood shall be good one side (GIS),
 waterproof, Douglas Fir Plywood,
 conforming to CSA Standard 0121-08.
 - .2 See Section 06 10 00 Rough Carpentry.

Project No. F6879-179013

and Equipment

PAGE 2 OF 7

- .5 Rigid Vinyl Siding prefinished:
 - .1 Rigid vinyl: extruded polyvinylchloride to CAN/CGSB-41.24-95. Style and colour to be selected by the Departmental Representative.
 - .2 Accessories: internal corners, external corners, cap strip, drip cap, undersill trim, starter strip and window/door trim of extruded plastic, same material and colour as siding, with nailing strip pre-punched.
 - .3 Exterior wall sheathing membrane: to CAN/CGSB-51.32 spunbonded olefin type as indicated.
 - .4 Fasteners: nails to CSA B111, screws to ANSI B18.6.4 aluminum purpose made.
 - .5 Galvanized steel sheet: commercial grade to ASTM A652M with Z275 zinc coating.
 - .6 Aluminum sheet: mill finish plain utility sheet, 0.80 mm thick.
 - .7 Include gable end roof vent, both sides.
- .6 Nails, spikes, and staples to CSA Bill-1974 (R2003); galvanized for exterior work, interior highly humid areas and for treated lumber; plain finished elsewhere. Use spiral thread nails except where specified otherwise.

.7 Paint:

- .1 Exterior Door: factory paint, colour as selected by Departmental Representative, prior to ordering.
- .2 Interior walls and ceiling: quality grade alkyd primer and finish paint, as approved by the Departmental Representative. Egg shell finish and colour selected by Owner.
- .3 Interior plywood floor: quality grade primer and finish paint for wooden floor surfaces with non-slip additive as approved by the Departmental Representative. Colour selected by Owner.
- .8 Metal Roofing:
 - .1 Metal Roofing shall be SuperVic by Vicwest, or approved equal. Colour to be selected by the Departmental Representative, prior to ordering.
 - .2 Provide all trim and accessories required, including but not limited to;
 - .1 Ridge Cap
 - .2 Gable Trim
 - .3 Eave Trim
 - .4 Sidewall/Endwall Flashing
 - .5 Foam Closures/Sealers
 - .6 Metal Building Tape
 - .7 Timber Strapping
 - .8 Fasteners and Hardware
 - .3 Install new metal roofing, as recommended

Project No. F6879-179013

and Equipment

PAGE 3 OF 7

by the manufacturer.

- .9 Door and Hardware: Insulated Hollow Metal Door, pressed steel frames 1 ½ pair stainless steel hinges with non-removable pins, 1 only deadbolt and stainless steel passage set, 1 only aluminum door closure cush operation, 1 set weatherstripping W14, 1 only aluminum threshold weatherstripped and suitable for an in-swing door.
- .10 Insulation:
 - .1 As noted on drawings.
- .11 Aluminum Thread Plate: to CSA HA.4.
- .12 Shop-Fabricated Wood Trusses
 - .1 Design Requirements:
 - .1 Design trusses, bracings, and bridging in accordance with CAN/CSA-086.1 for loads indicated and minimum uniform and minimum concentrated loadings stipulated in NBC commentary.
 - .2 Limit live load deflection to 1/360th of span where plaster gypsum board ceilings are hung directly from trusses.
 - .3 Limit live load deflection to 1/240th of span unless otherwise specified or indicated.
 - .4 Provide camber for trusses as indicated.
 - .2 Submittals:
 - .1 Each shop drawings submission shall bear signature and stamp of professional Engineer registered or licensed in Province of Newfoundland and Labrador, Canada.
 - .3 Materials:
 - .1 Lumber: Spruce (S-P-F) species, No. 1 grade, softwood, S4S, with maximum moisture content of 19% at time of fabrication and to following standards:
 - .1 CAN/CSA-0141.
 - .2 NLGA (National Lumber Grading Association), Standard Grading Rules for Canadian Lumber.
 - .3 See Section 06 10 00 Rough Carpentry.
 - .2 Fastenings: to CAN/CSA-086.1.
 - .4 Fabrication:
 - .1 Fabricate wood trusses in accordance with reviewed shop drawings.
 - .2 Provide for design camber and roof slopes when positioning truss members.

Project No. F6879-179013

DFO

and Equipment

PAGE 4 OF 7

- .3 Connect members using metal connector plates.
- .13 Foundation: Provide new foundation, as depicted on the drawings, c/w the following:
 - .1 Treated timber knee wall, including: 38 x 140 double top plate, 38 x 140 bottom plate, 38 x 140 studs, 38 x 140 blocking, and levelling timbers as shown on the drawings;
 - .2 Treated timber footing including: 140 x 140×600 treated bearing timbers, 38×140 strapping pieces, 8 mil polyethylene vapour barrier, granular base levelling material, 12.7 mm galvanized bolts, and any required fasteners, all as shown on the drawings;
 - .3 Knee wall to timber beam fastening hardware, including: 12.7 mm Ø galvanized lag screws, 16 mm thick treated plywood gusset plates, and any required fasteners and/or blocking timbers, all as shown on the drawings;
 - .4 Treated timber cross bracing, including: 38 x 89 cross bracing, blocking timbers, and any required fasteners, as shown on the drawings.
 - .5 All timbers to be treated.

Accommodations Building Renovations:

- Foundation (Timber Beam Support): Provide new foundation, as depicted on the drawings, c/w the following:
 - .1 Treated timber knee wall, including: 38 x 140 double top plate, 38 x 140 bottom plate, $38 \times 140 \text{ studs}$, $38 \times 140 \text{ blocking}$ and levelling timbers, as shown on the drawings;
 - .2 Treated timber footing, including: 140 x 140 x 600 treated bearing timbers, 38 x140 strapping pieces, 8 mil polyethylene vapour barrier, granular base levelling material, 12.7 mm galvanized bolts, and any required fasteners and/or blocking timbers, all as shown on the drawings;
 - .3 Knee wall to timber beam fastening hardware, including: 12.7 mm Ø galvanized lag screws, 16 mm thick treated plywood gusset plates, and any required fasteners, all as shown on the drawings;
 - .4 Treated timber cross bracing, including: 38 x 89 cross bracing, blocking timbers, and any required fasteners, as shown on the drawings.
 - .5 All timbers to be treated.
- .2 Foundation (Steel Beam Support): Provide new foundation, as depicted on the drawings, c/w the following:
 - .1 Treated timber knee wall, including: 38

and Equipment

PAGE 5 OF 7

- x 140 double top plate, 38 x 140 bottom plate, 38 x 140 studs, 38 x 140 blocking and levelling timbers, as shown on the drawings;
- .2 Treated timber footing, including: 140 x 140 x 600 treated bearing timbers, 38 x 140 strapping pieces, 8 mil polyethylene vapour barrier, granular base levelling material, 12.7 mm Ø galvanized bolts, and any required fasteners and/or blocking timbers, all as shown on the drawings;
- .3 Knee wall to steel beam fastening hardware, including: 38 x 140 treated timber blocking (if required), 12.7 mm galvanized bolts, and any required fasteners, as shown on the drawings;
- .4 Treated timber cross bracing, including: 38 x 89 cross bracing, blocking timbers, and any required fasteners, as shown on the drawings.
- .5 All timbers to be treated.

.3 Metal Roofing:

- .1 Metal Roofing shall be SuperVic by Vicwest, or approved equal. Colour to be selected by the Departmental Representative, prior to ordering.
- .2 Provide all trim and accessories required, including but not limited to;
 - .1 Ridge Cap
 - .2 Gable Trim
 - .3 Eave Trim
 - .4 Sidewall/Endwall Flashing
 - .5 Foam Closures/Sealers
 - .6 Metal Building Tape
 - .7 Timber Strapping
 - .8 Fasteners and Hardware
- .3 Install new metal roofing, as recommended by the manufacturer.
- .4 Touch-up Paint (walls and ceiling):
 - .1 Quality grade alkyd primer and finish paint as approved by the Departmental Representative. Finish and colour to match adjacent surfaces.

.5 Building Equipment (off-grid power supply):

- .1 Propane Space Heater: Provide one (1) gas space heater, DV25 model by Empire Heating Systems, or approved equal.
- .2 Solar Controls: Provide one (1) 60 amp solar charge controller/regulator c/w digital display and proper overload protections, Outback FM-60 or, or approved equal.
- .3 Propane Water Heater: Provide one (1) on-demand gas hot water heater, ProTankless GWH 260 PN model by Bosch, or approved equal.
- .4 Solar Batteries: Batteries to be supplied by Canada. See Section 01 16 10 Material Supplied by Canada. Contractor to provide insulated battery enclosure box, to the

DFO
Lower Terra Nova
Infrastructure Upgrades
Project No. F6879-179013

Building Structures

Section 13 34 23.01

and Equipment

PAGE 6 OF 7

- approval of the Departmental Representative. Do not stack new batteries within new enclosure. Batteries to be installed in a single row-only.
- .5 Inverter Power Board Assembly: Provide one (1) Inverter power board assembly, c/w all AC/DC wiring, overload protection safety disconnect, and remote monitor display, Magnum PBMS-2812, or approved equal.
- .6 All connecting wires (indoor and outdoor), fittings, conduit, mounting equipment, and any other items required to completely install and operate the off-grid power supply and propane heaters, are to be included.
- .7 All off-grid power supply components to be supplied by a single supplier, to ensure compatability.

PART 3 - EXECUTION

3.1 WORKMANSHIP

- .1 Rough and finished carpentry shall be executed by mechanics skilled in the trade. All work shall be neatly and accurately erected, scribed and fitted to produce closed joints and connections. Only expert workmanship will be accepted and work which, in the opinion of the Departmental Representative, is not of first class quality, will be rejected and replaced at no cost to Canada.
- .2 Install rough blocking securely to pre-set anchor bolts. Blocking shall be of the proper size to accurately align to adjoining surfaces to receive can't boards, frames and other items detailed on the drawings and to be installed under this section.
- .3 Finish carpentry to receive paint or varnish, as noted on the drawings, finished shall be neatly erected, joined, sanded and have all nail heads set and puttied, ready for finishing.

3.2 <u>INSTALLATION</u>

- .1 Install new siding and attachments sequentially to manufacturer's instructions.
- .2 Install exterior corners, fillers and closures trips with carefully formed and profiled work using concealed fasteners.
- .3 Maintain joints in exterior sheets, true to line, tight fitting.
- .4 Caulk and seal in accordance with paragraphs 4.6.2 and 4.6.3 of CGSB 93-GP-5M with sealant.
- .5 Provide all components including drip and cap flashings, screws and fasteners as required to

and Equipment

PAGE 7 OF 7

complete installation.

- .6 Apply paint material to CGSB 85-GP series standards and in accordance with materials manufacturer's recommendations. Apply one primer and two finish coats to intersurfaces as recommended by the paint manufacturer.
- .7 Install metal roof and eave flashings in accordance with manufacturer's recommendations.
- .8 Install pressed steel door frame plumb, square, level and at correct elevation. Insulate exterior frames with batt insulation. Secure anchors and connections to adjacent construction.
- .9 Install insulated metal doors and hardware in accordance with manufacturer's instructions.
- .10 All building equipment included in the off-grid power supply, including Propane Heater, Solar Controls, Inverter, Propane Water Heater, and Solar Batteries should be installed by a certified technician, familiar with off-grid electrical systems and approved by the Departmental Representative. If the system is not installed by such a technician, it must be inspected and commissioned by a such a technician, to the approval of the Departmental Representative and prior to project completion.
- .11 Install all components to any applicable manufacturers'/supplier's recommendations.

DFO	Tree	and	Shrub	Preservation	Section 32 01 91
Lower Terra Nova					
Infrasturcture Upgrades				Page 1 of 2	
Project No. F6879-179013					

PART 1 - GENERAL

- 1.1 <u>CLEARING</u>

 .1 Do not clear any areas, or remove any trees beyond the minimum limits required to accommodate the work. Obtain approval of Departmental Representative for any clearing required.
 - .2 In areas of clearing, reinstatement to be carried out following completion of work to leave it in a clean and natural state, free of any dead or cut organic debris.
- 1.2 <u>SCHEDULING</u> .1 Obtain approval from Departmental Representative of schedule indicating commencement of work.

PART 2 - EXECUTION

- 2.1 IDENTIFICATION .1 Identify plants and limits of root

 AND PROTECTION systems to be preserved to satisfaction of Departmental Representative.
 - .2 Protect plant and root systems from damage, compaction and contamination resulting from construction to satisfaction of Departmental Representative.
 - .3 Ensure no pruning is done inside drip line.

2.2 ROOT CURTAIN SYSTEM

- .1 Identify limits to required construction excavation to satisfaction of Departmental Representative.
- .2 Prune exposed roots cleanly at side of trench nearest plants to be preserved. Pruned ends to point obliquely downwards.
- .3 Protect root curtain from damage during construction operations.
- .4 Water plants and root curtain sufficiently during construction to maintain optimum soil moisture condition until backfill operations are complete.
- .5 Protect root curtain before and during backfill operations.

DFO	Tree ar	d Shrub	Preservation	Section 32 01 91
Lower Terra Nova				
Infrasturcture Upgrades			Page 2 of 2	
Project No. F6879-179013				

2.3	LOWERING GRADE AROUND EXISTING TREE	.1	Commence work in accordance with schedule approved by Departmental Representative.
		.2	Cut slope not less than 500 mm from tree trunk to new grade level.
		.3	Excavate to depths as indicated. Protect from damage root zone which is to remain.
		. 4	When severing roots at excavation level, cut roots with sharp tools.
		.5	Cultivate excavated surface manually to 15 mm depth.
			Place soil mixture over area of excavation to finished grade level. Compact to 85% Standard Proctor Density.
		. 7	Water entire root zone to optimum soil moisture level.
		.8	Install surface cover of hydroseed in accordance with Section 32 92 21.
2.4	PRUNING	.1	Prune crown to compensate for root loss while maintaining general form and character of plant.
2.5	ANTI-DESSICANT	.1	Apply anti-dessicant to foliage where applicable and as directed by Departmental Representative.

DFO Aggregate Base Courses Section 32 11 23
Lower Terra Nova
Infrastructure Upgrades
PROJECT NO. F6879-179013 PAGE 1 OF 2

PART 1 - GENERAL

- 1.1 <u>RELATED SECTIONS</u> .1 Section 01 74 21 Construction/ Demolition Waste Management and Disposal.
- 1.2 <u>REFERENCES</u> .1 American Society for Testing and Materials
 - .1 ASTM C117-95, Standard Test Methods for Material Finer Than 0.075 mm Sieve in Mineral Aggregates by Washing.
 - .2 ASTM C131-96, Standard Test Method for Resistance to Degradation of Small-Size Coarse Aggregate by Abrasion and Impact in the Los Angeles Machine.
 - .3 ASTM C136-96a, Standard Test Method for Sieve Analysis of Fine and Coarse Aggregates.
 - .4 ASTM D698-00a, Standard Test Methods for Laboratory Compaction Characteristics of Soil Using Standard Effort $(12,400ft-lbf/ft^3)$ $(600kN-m/m^3)$.
 - .5 ASTM D1557-00, Test Method for Laboratory Compaction Characteristics of Soil Using Modified Effort $(56,000ft-lbf/ft^3)$ $(2,700kN-m/m^3)$.
 - .6 ASTM D1883-99, Standard Test Method for CBR (California Bearing Ratio) of Laboratory Compacted Soils.
 - .7 ASTM D4318-00, Standard Test Methods for Liquid Limit, Plastic Limit and Plasticity Index of Soils.
 - .2 Canadian General Standards Board (CGSB)
 .1 CAN/CGSB-8.1-88, Sieves, Testing,
 Woven Wire, Inch Series.
 .2 CAN/CGSB-8.2-M88, Sieves, Testing,
 Woven Wire, Metric.
- - .2 Divert unused granular material from landfill to local facility as approved by Departmental Representative.

PART 2 - PRODUCTS

2.1 MATERIALS
.1 Granular base: material in accordance with Section 31 05 17 - Aggregate Materials and following requirements:

.1 Crushed stone or gravel.

agregate	Base	Courses	Section	32	11	23

Lower Terra Nova Infrastructure Upgrades PROJECT NO. F6879-179013

DFO

PAGE 2 OF 2

.2 Gradations to be within limits specified when tested to ASTM C136 and ASTM C117. Sieve sizes to CAN/CGSB-8.1 and CAN/CGSB-8.2.

.1 Gradation Method to:

Sieve Designation	% Passing		
19 mm	100		
9.5 mm	55-100		
4.75 mm	35-60		
1.20 mm	17-35		
0.300 mm	39648		
0.075 mm	39514		

- .2 Liquid limit: to ASTM D4318, maximum 25.
- .3 Plasticity index: to ASTM D4318, maximum 6.
- .4 Los Angeles degradation: to ASTM C131. Max. % loss by weight: 45.
- Crushed particles: at least 60% of particles by mass within each of following sieve designation ranges to have at least 1 freshly fractured face. Material to be divided into ranges using methods of ASTM C136.

Passing Retained on 19.0 mm to 4.75 mm

PART 3 - EXECUTION

3.1 SEQUENCE OF OPERATION .1 Placing

- .1 Place granular base upon existing, undisturbed ground to level area under new footings and to ensure footings are fully bearing.
- .2 Ensure no frozen material is placed.
- .3 Do not place material on snow or ice.

3.2 SITE TOLERANCES .1 Finished base surface to be within plus or

minus 10 mm of established grade and cross section but not uniformly high or low.

3.3 PROTECTION .1 Maintain finished base in condition conforming to this Section until succeeding

material is applied or until acceptance by Departmental Representative.

DFO			Dewatering	Section 35 00 00
Lower Terra Nova Infrastructure Upgrades Project No. F6879-179013			Page 1 of 2	
PART	1 - GENERAL			
1.1	DESCRIPTION	.1	The work covered under to supply and installation of necessary for the follow .1 Dewatering of the .2 Maintaining this condition during c	fall labour and materials ing: area of construction. area in a developed
		.2	The contractor shall submin Departmental Representa approval prior to constactivities.	ative for review and
		.3	All work on the diversion in the dry.	wall must be carried out
1.2	CODES AND STANDARDS	.1	Carry out all work in ac applicable Federal, Provi and Regulations. In eac application, the Code, By-Law, or specification requirements applies.	ncial and Municipal Codes ch and every instance of Regulation, Statute,
1.3	PERMITS AND FEES	.1	Obtain and pay all permi related to the work contathe specifications.	
1.4	TEMPORARY BERMS	.1	All work must be carried berms are required to acc of such berms is to be carr Departmental Representat in Newfoundland and Labrac design to be stamped by the to the Departmental Repre commences.	complish this, the design ried out by a professional ive licensed to practice dor. Drawings of the berm the Engineer and submitted
PART	2 - PRODUCTS			
	N/A			
PART	3 - EXECUTION			
3.1	DEWATERING	.1	Contractor to determine particular site to achieve of construction. This ma	ve dewatering of the area

- of construction. This may involve such things as:
 - Utilization of sandbags
 - Bypass pumping
 - Construction of settling pond if siltation is a problem
- .2 Any pumps and appurtenances used in dewatering are to be thoroughly cleaned and disinfected prior to use.
- .3 Dispose of water in a manner not detrimental to

DFO	Dewatering	Section 35 00 00
Lower Terra Nova		
Infrastructure Upgrades		Page 2 of 2
Project No. F6879-179013		

public health, environment, public or private property, or any portion of work completed or under construction. Comply with all requirements of the Department of Environment and Conservation and other regulatory agencies having jurisdiction regarding disposal of water.

.4 The Contractor will be responsible to maintain, dewater devices/structures for the duration of time they are required.

Appendix A

Contractor's Copy of the Regulatory Approvals

Appendix B

Photos













<u>July, 2016:</u>




















































August, 2017:





August, 2017:



