



# TENDER AMENDMENT

## RETURN BIDS TO:

Parks Canada Agency  
635 – 8 Avenue S.W., Suite 1300  
Calgary, AB T2P 3M3  
Bid Fax: (403) 292-4475

The referenced document is hereby amended: unless otherwise indicated, all other terms and conditions of the contract remain the same.

## Issuing Office:

Parks Canada Agency  
635 – 8 Avenue S.W., Suite 1300  
Calgary, AB T2P 3M3

# MODIFICATION D'APPEL D'OFFRES

## RETOURNER LES SOUMISSIONS À :

Agence Parcs Canada  
635 – 8 Avenue S.O., pièce 1300,  
Calgary, AB T2P 3M3  
N° de télécopieur pour soumissions : (403) 292-4475

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

## Bureau de distribution :

Agence Parcs Canada  
635 – 8 Avenue S.O., pièce 1300  
Calgary (AB) T2P 3M3

<b>Title:</b> (2) Pit Privies Construction – East Gate NHS & Mount Agassiz – Riding Mountain National Park		
<b>Solicitation No. / N° de l'invitation :</b> 5P420-17-5396/A	<b>Amendment No. / N° de modification de l'invitation :</b> 001	<b>Date:</b> November 28, 2017  <b>Date :</b> 28 novembre 2017
<b>GETS Reference No. / N° de référence de SEAG :</b> PW-17-00801785		
<b>Solicitation Closes / L'invitation prend fin :</b>		
<b>At:</b> 02:00 PM	<b>On:</b> <b>December 19, 2017</b>	<b>Time Zone:</b> Mountain Standard Time (MST)
<b>À :</b> 14h00	<b>Le :</b> <b>19 décembre 2017</b>	<b>Fuseau horaire :</b> Heure normale des Rocheuses (HNR)
<b>Address Inquiries to / Adresser toute demande de renseignements à :</b> Danny Ahn		
<b>Telephone No. / N° de téléphone :</b> (403) 292-5451	<b>Fax No. / N° de télécopieur :</b> 1-866-246-6893	<b>Email Address / Courriel :</b> Danny.ahn@pc.gc.ca
<b>TO BE COMPLETED BY THE BIDDER (type or print) À ÊTRE COMPLÉTER PAR LE SOUMISSIONNAIRE (taper ou écrire en caractères d'imprimerie)</b>		
<b>Vendor/Firm Name – Nom du fournisseur/de l'entrepreneur</b>		
<b>Address - Adresse</b>		
<b>Name of person authorized to sign on behalf of the Vendor/Firm Nom de la personne autorisée à signer au nom du fournisseur/de l'entrepreneur</b>		
<b>Title - Titre</b>		
<b>Signature</b>		<b>Date</b>

## **Amendment 01**

This amendment is being raised to answer questions, extend the closing date, and publish site visit attendance sheet. All such revisions will become part of the Work and the effects shall be included in the Tender Price. All work shall be performed in accordance with the Contract Documents.

### **A) Bid Closing Date**

The closing date for tender 5P420-17-5396/A titled (2) Pit Privies Construction – East Gate NHS & Mount Agassiz – Riding Mountain National Park is extended from December 14, 2017 until **December 19, 2017 at 2:00PM Mountain Standard Time (MST).**

### **B) Site visit Attendees**

Please see attached photo below Ref-3

### **C) Questions & Answers**

- Q1** Is there a Parks supplied water supply that a contractor can use?  
**A1** No, using a municipal water source from within the RM of McCreary is suggested.
- Q2** Is there a designated waste disposal site for Construction materials (wood, styrofoam etc.)?  
**A2** No, the contractor will be free to dispose of these materials at a site of their choosing.
- Q3** Are there additional specifications for the holding tank access panel and related hardware?  
**A3** No. The dimensions of the hatch are shown in the drawings. Related hardware will be approved by way of shop drawing submittal after the contract is awarded.
- Q4** What is the "Metal Transom Panel"?  
**A4** There is an error in the drawings. Within Detail 1 on sheet S102; a line separating the doors from the above transom panels is missing giving the impression that the doors extend further up than they are supposed to. A revised drawing has been produced. (Attached).
- Q5** Have these privies been constructed previously, and if so, are there any pictures available?  
**A5** Yes, they have been, however the design was slightly different. (Notable changes include the location of the doors, size of the structure and detailing on the precast panels). Pictures are available, however the drawings and specifications in the bid package are to supersede the photos. (See attached photos below Ref-1 & Ref-2)
- Q6** Who is responsible for Compaction and Material Testing?  
**A6** Refer to Section 31 23 33 of the Specifications document.
- Q7** What is known about the underlying sub-grade conditions?  
**A7** Large signs were recently installed in the area and during the excavation for the posts, 6-10" of topsoil with an underlying 5 - 6' of predominantly gravel (shale) with some silt was observed.
- Q8** What are the underlying ground water conditions?  
**A8** The area is well drained. During the above sign installation, no ground water was observed.
- Q9** What is to be done with any unused excavated material?  
**A9** All excavated material that is deemed excess is to be hauled off site to a disposal facility of the contractor's choosing.
- Q10** Will there be a staging/lay down area provided?  
**A10** Yes, both sites have adequate space for this to be provided.

- Q11** On the lower portion of the panels there is a recess for wood cladding to be attached to the panel. On the upper portion the pattern is cast integral with the panel. Is there a specific liner code for the upper portion or does the precaster have some discretion in the pattern chosen?
- A11** There is no specification for the architectural finish on the exterior of the walls at this point. Parks Canada's intent is that the finish would be a wood grain effect. The precaster contracted to do this work will have some discretion in the samples they present to the project authority for final selection of pattern.
- Q12** Section 3/S102 show the integral pattern full height, Section 1/S103 shows it broke into the lower and upper portion with the two patterns. Which section is correct?
- A12** Detail 3 on sheet S102 is correct.
- Q13** Could ASI Group Canada Products be considered for approval as an equal or alternate for the proposed job, under Section 10 28 10 for Toilet & Bath Accessories?
- A13** ASI Group Canada Products have been approved as an equal or alternate product for products/services related outlined in Section 10 28 10 for Toilet & Bath Accessories.

Ref-1



Ref-2



Ref-3



### SITE VISIT ATTENDANCE SHEET

Solicitation No: 5P420-17-5396/A		Project: Pit Privies Construction East Gate and Mount Agassiz		Date & Time: Nov 16 at 10:30am
Contracting Office or Project Manager: 635 - 8 Avenue S.W., Suite 1300 Calgary, AB T2P 3M3				Location: East Gate NHS
Date	Vendor / Firm Name	Representative's Name	Telephone No.	Signature
2019-11-16	DG Konkin Construction	Brett Konkin	204 724-6350	Brett Konkin
"	"	Tamara Jones	204 725-0191	Tamara Jones

**All other terms and conditions remain the same.**