



Materiel and Procurement Services
200 Kent Street, Station 9W088
Ottawa, Ontario
K1A 0E6

November 28, 2017

Subject: Invitation to Tender: FP802-170233
Title: Lower Terra Nova river infrastructure upgrades
Work site location: Terra Nova River, Newfoundland and Labrador

Department of Fisheries and Oceans

Bid Closing Date: Tuesday, December 5, 2017
Time: 2:00 pm Eastern Standard Time (EST)
RFP File No: FP802-170233

ADDENDUM: No. 2

Further to the above mentioned Invitation to Tender documentation previously posted on the Government Electronic Tendering Site (GETS), BuyandSell.gc.ca, Addendum (#2) is hereby issued.

****PLEASE NOTE THE FOLLOWING CHANGES TO THIS SOLICITATION****

1. Please delete :

Bid closing date: Wednesday, November 29, 2017

Please insert:

Bid closing date: Tuesday, December 5, 2017



2. **Please insert:**

The document entitled “*Amendment to specifications and drawings*”.

THE FOLLOWING QUESTIONS WAS SUBMITTED BY A POTENTIAL BIDDER TO THE CONTRACTING AUTHORITY IN RELATION TO THE SUBJECT ITT:

Q01: There is no mention of solar panels within the Upgrades. That is, there is no quantity or specification for this item, nor is there any placement of same in the drawings of the equipment shed or site plan. Please confirm the panels in the drawings are intended to be re-used?

A01: As per Note 5 - Sheet C1, existing solar panels are to be relocated to new equipment shed. Existing solar panels are to be installed on the roof of the new shed, and incorporated into the new off-grid power supply system.

Q02: There is no detail on if the power system will connect to an AC distribution panel and/or a backup generator. If it is intended to be connected to these, we would require more detail.

A02: No back-up generator. Minimum 4 circuit, 60 Amp, AC distribution panel (load centre) will be required in the accommodations building.

Q03: The model of Bosch propane water heater specified has been discontinued, please advise an alternate.

A03: Bosch ProTankless GWH 330 will also be accepted, however the Contractor must ensure adequate venting is supplied, to the manufacturer’s specifications (This model has a 4” flue as opposed to the 5” existing). This item is confirmed as available from suppliers in NL. Other manufacturers may also carry an equivalent product. Approved equals will be considered during construction, as long as they are comparable to the products noted above, and are compatible for the required use.

Q04: If DFO is providing 50 hrs of helicopter time for moving materials to and from site. What size helicopter and what is its sling load capabilities to be used during these 50 hours? These will be needed to calculate how many trips in and out we will require.

A04: 2000lb lift capacity



All other Terms and Conditions for this requirement remain unchanged.

Tenderers are to acknowledge this Addendum by signing in the space provided below and enclosing a copy of this document with their tender submission.

Regards

Julie Michelle Tremblay
Senior Contracting Officer
Material and Procurement Services
Julie.Michelle.Tremblay@dfo-mpo.gc.ca
Téléphone | Telephone 613-998-1614
Télécopieur | Facsimile 613-991-4545
200 Kent Street
Ottawa, ON K1A 0E6
Fisheries and Oceans Canada
Government of Canada

RECEIPT ACKNOWLEDGED

Name of Company _____

Signature _____