




BRENKMAN & COMPANY LTD.
PERMIT NUMBER P11225
The Association of Professional Engineers, Geologists and Geophysicists of Alberta



1 ROOF PLAN
M2.2 1:150

KEY NOTES	
1	INSTALL NEW CONDENSING UNITS ON ROOF USING EXISTING CURBS. CONTRACTOR IS RESPONSIBLE FOR ANY MODIFICATIONS TO THE CURBS/SUPPORT. RUN NEW REFRIGERATION LINES BACK TO AIR HANDLER COOLING COILS AND CONNECT.

GENERAL NOTES	
1	CONTRACTOR IS RESPONSIBLE FOR ALL PERMITS.
2	CONTRACTOR TO ENSURE ALL WORK COMPLIES WITH AUTHORITY HAVING JURISDICTION.
3	E-RTU1 GAS DEMAND: 1.42 M ³ /HR
4	CONTRACTOR TO VERIFY EXISTING UNITS POWER REQUIREMENT PRIOR TO ORDER OF NEW UNITS AND TO ENSURE NEW UNITS DO MATCH VOLTAGE AND PHASE AND DO NOT EXCEED EXISTING AMP DRAW REQUIREMENTS. CONTRACTOR TO RECONNECT ALL NEW UNITS TO EXISTING ELECTRICAL AND TO REPAIR/REPLACE DAMAGED CONDUIT, WIRING, JUNCTION BOXES AND OTHER ELECTRICAL DAMAGED DURING DEMOLITION AND INSTALL OF NEW EQUIPMENT WITH SAME THAN ORIGINAL.

#	Description/Description	Date/Date
2	ISSUED FOR TENDER	16/09/07
1	ISSUED FOR 90% REVIEW	16/05/30
0	ISSUED FOR 60% REVIEW	15/10/10

PUBLIC WORKS AND GOVERNMENT SERVICES CANADA

Project title/Titre du projet
**Pê Sâkâstêw Centre
Maskwacis, Alberta**

**Pê Sâkâstêw Centre
REPLACEMENT OF
ROOFTOP UNITS BOILERS**

Approved by/Approuvé par
GBB

Designed by/Concept par
HFB

Drawn by/Dessiné par
HFB

PWGSC Project Manager/Administrateur de Projets TFSGC
STEVE PHYPERS

PWGSC, Architectural and Engineering Resources Manager/
Ressources Architectural et de Directeur d'ingénierie, TFSGC

Client/client
PWGSC

Drawing title/Titre du dessin
**BUILDING E - CONDENSING UNITS
CONSTRUCTION PLAN**

Project No./No. du projet R.077183.00	Sheet/Feuille M2.3 OF 16	Revision no./ La Révision no. 2
---	---------------------------------------	--