




BRENKMAN & Company LTD.
PERMIT NUMBER P11225
The Association of Professional Engineers,
Geologists and Geophysicists of Alberta



KEY NOTES

1 DEMOLISH AND DISPOSE OFF CONDENSING UNITS ON ROOF. DEMOLISH REFRIGERATION LINES BACK TO AIR HANDLER COOLING COILS. RETAIN EXISTING ROOF SUPPORT/CURB FOR RE-USE.

GENERAL NOTES

1 CONTRACTOR IS RESPONSIBLE FOR ALL PERMITS.

2 CONTRACTOR TO ENSURE ALL WORK COMPLIES WITH AUTHORITY HAVING JURISDICTION.

3 E-RTU1 GAS DEMAND: 1.42 M³/HR

4 CONTRACTOR TO RETAIN ELECTRICAL FOR RECONNECTION.

1 ROOF PLAN
M2.2 1:150

#	Description/Description	Date/Date
2	ISSUED FOR TENDER	16/09/07
1	ISSUED FOR 95% REVIEW	16/05/30
0	ISSUED FOR 60% REVIEW	15/10/10

PUBLIC WORKS AND GOVERNMENT SERVICES CANADA

Project title/Titre du projet
**Pê Sâkâstêw Centre
Maskwacis, Alberta**

**Pê Sâkâstêw Centre
REPLACEMENT OF
ROOFTOP UNITS BOILERS**

Approved by/Approuvé par
GBB

Designed by/Concept par
HFB

Drawn by/Dessiné par
HFB

PWGSC Project Manager/Administrateur de Projets IPSCG
STEVE PHYPERS

PWGSC Architectural and Engineering Resources Manager/
Ressources Architectural et de Directeur d'Ingénierie, IPSCG

Client/client
PWGSC

Drawing title/Titre du dessin
**BUILDING E - CONDENSING UNITS
DEMOLITION PLAN**

Project No./No. du projet	Sheet/Feuille	Revision no./La Révision no.
R.077183.00	M2.2 OF 16	2

