



RETURN BIDS TO:

RETOURNER LES SOUMISSIONS À:

Public Works and Government Services / Travaux
publics et services gouvernementaux
Kingston Procurement
Des Acquisitions Kingston
86 Clarence Street, 2nd floor
Kingston
Ontario
K7L 1X3
Bid Fax: (613) 545-8067

**SOLICITATION AMENDMENT
MODIFICATION DE L'INVITATION**

The referenced document is hereby revised; unless otherwise
indicated, all other terms and conditions of the Solicitation
remain the same.

Ce document est par la présente révisé; sauf indication contraire,
les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution
Public Works and Government Services / Travaux
publics et services gouvernementaux
Kingston Procurement
Des Acquisitions Kingston
86 Clarence Street, 2nd floor
Kingston
Ontario
K7L 1X3

Title - Sujet Solar Roller Blinds	
Solicitation No. - N° de l'invitation W0114-18PS46/A	Amendment No. - N° modif. 002
Client Reference No. - N° de référence du client W0114-18PS46	Date 2017-12-13
GETS Reference No. - N° de référence de SEAG PW-\$KIN-508-7333	
File No. - N° de dossier KIN-7-48144 (508)	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2017-12-20	
Time Zone Fuseau horaire Eastern Standard Time EST	
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Weaver, Tammy	Buyer Id - Id de l'acheteur kin508
Telephone No. - N° de téléphone (613) 484-1809 ()	FAX No. - N° de FAX (613) 545-8067
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction:	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

Bidders in attendance of Mandatory Site Visit

JMC

The Shutter Professionals
Tradeworks Interiors Canada Corp
Floormaster
BOS Window Coverings Ltd.
Grand and Toy
The Deltic Group Inc
Waterfield Design
Buyer's Gallery Blinds Corp

Q1. Would it be possible to temporarily place a disposal bin at each pair of buildings for the discarded blinds?

R1. Yes, the temporarily placement of supplier's arranged disposal bins can be dropped at each location. The placement of the bins would need to be pre-arranged with the client and the cost associated would be paid by the supplier.

Q2. Are existing valences to be removed along with the blinds?

R2. Yes, the requirement is for the removal and disposal of four hundred and eighty-four (484) currently installed old window coverings, valance and hardware.

Q3. Removing the existing blinds and valences may leave holes and other possible cosmetic damage to the window frame and/or casing around the windows where the mounting brackets were fitted. Will the base look after any rehabilitation (filling in the holes and painting) that may be required?

R3. It is requested that the removal of the currently old window coverings, valance and hardware is done with care and respect to government property so as to ensure that minimal repairs and painting are required. Suppliers must ensure that proper tools (drills/screwdrivers) are used to remove the currently installed vertical blinds, valance and hardware to limit any damage. Any filing of holes and painting required after the installation will be done by the maintenance section on base.

Q4. Will rooms be occupied during the installation? How will access to empty/locked rooms be arranged? Will access to multiple rooms at a time be possible?

R4. Access to all rooms will be arranged and monitored by the onsite DND representative at the time of the installation. Access to multiple rooms will be possible.

Q5. Could you please confirm the quantity and rough measurements for buildings VB-06 and VB-07 as there was a discrepancy during the site visit?

R5. Total blinds required for building VB06 is Qty 198. Total blinds required for building VB07 is Qty 202. See amendment002basis_of_payment for further details.

Q 6. On the sheet "Annex "B" Basis of Payment" along with the site plan you handed out building MB-54 and building MB-55 states a total of 82 shades in each building (a total of 564 shades for all 4 buildings). On the document titled "Annex "B" Basis of Payment" amendment001basis_of_paymentenglish.xlsx it states there are only 42 shades in each of the above buildings (a total of 484 shades for all 4 buildings). Could you please clarify which it is, 82 or 42?

R6. The site plan that was handed out on the site visit had the incorrect quantities for Bldg MB-54 and MB-55 the correct quantity for Bldg MB-54 and MB-55 is 42/building as listed on amendment002basis_of_payment.

Q7. Please confirm that we can deliver the shades before the installation date and store on site in a locked room before the installation date.

R7. The client has confirmed that the shades can be delivered, stored on site in a locked room prior to the actual installation date. It must be noted that the control of the keys to the storage room would remain in the hands of DND representative.

Q8. There was a room with no number in VB-07 on the second floor that might have been room 254 or 258? Is this to be included in the quotation? If so how many are there in the 2 buildings?

Total blinds required for building VB-07 is Qty 202, the breakdown is listed in amendment002basis_of_payment.

Q9. Are the roller shades to be open roll or with a cassette. If a cassette is required which style?

R9. The roller shades are to come with an open roll at the top of the shade where the material is visible.

Q10. Is a fabric that is 70% PVC and 30% polyester used commercially acceptable?

R 10. No, the specifications listed in Annex "A", 2.0 Requirement, 2.1 Requirements must be met to maintain the same standard/colour of solar sunscreen roller blinds installed in CFB Kingston, Base Accommodation to maintain a consistence within each building.

Q11. There are a few companies located out of the city. Is it possible for accommodations to be provided on the base?

R11. Accommodations can be provided on the base but the cost associated would have to be paid by the supplier.

Q12. Is there any chance we can work either later than 3 or possibly on weekends if planned in advance?

R12. As the building involve house students currently on course any additional timings would interrupt their schedule study time.

Annex A 2.3 Constraints 2. Can be amended to read as follows:

“The installation, removal and disposal can only be done between 7:30 a.m. until 4:00 p.m. (EDT, ON) Monday through Friday excluding statutory holidays.”

Q13. Would you consider a slightly different bottom bar that is coordinated and performs as well or better than what you currently have on your windows?

R13. No, the specifications listed in Annex “A”, 2.0 Requirement, 2.1 Requirements must be met to maintain the same standard/colour of solar sunscreen roller blinds installed in CFB Kingston, Base Accommodation to maintain a consistence within each building.

Q14. Would you like us to supply an actual blind with our quote?

R14. No, as per the bid solicitation section 4.1.1 Technical Evaluation

“1. The Bidder must provide with their proposal the necessary documentation and colour swatch to support and demonstrate compliance with the Mandatory Technical Criteria outlined in Annex “A” attached.

Q15. Can multiple rooms be opened at one time so more than one worker can be doing the job at one time? Example: one wing of a floor so work can be completed efficiently.

R15. Yes.

Q16. Will Tie down chain retainers be needed for this project?

R16. No, the specifications listed in Annex “A”, 2.0 Requirement, 2.1 Requirements list what the requirement are.

Q17. In building VB 06, the window jamb depth is smaller than the other building, so brackets installed inside, would make the shade sit out a bit farther.

Would you still like the shades installed inside between the jambs, or outside mounted to the frame?

Q17. The preferred installation method is that the blinds are mounted on the side and head jamb at the top of the window frame but some corner rooms require a combination of mounting on the inside of the jamb and outside frame.

Q18. In the specs- Annex A – 2.1 e) Finish- “Zenith”. Can you clarify what component the finish of? and what is the terminology “zenith”?

R18. This question was previously asked and replied too. Please see amendment 001.

https://buyandsell.gc.ca/cds/public/2017/11/09/98c9741d1ce73235a2c822d0ca96d7b1/A/BES.PROD.PW_KIN.B508.E7333.EBSU001.PDF