



RETURN BIDS TO:

RETOURNER LES SOUMISSIONS À:

Bid Receiving Public Works and Government
Services Canada/Réception des soumissions Travaux
publics et Services gouvernementaux Canada
800 Burrard Street, Room 219
800, rue Burrard, pièce 219
Vancouver
British Columbia
V6Z 0B9
Bid Fax: (604) 775-9381

**SOLICITATION AMENDMENT
MODIFICATION DE L'INVITATION**

The referenced document is hereby revised; unless otherwise
indicated, all other terms and conditions of the Solicitation
remain the same.

Ce document est par la présente révisé; sauf indication contraire,
les modalités de l'invitation demeurent les mêmes.

Comments - Commentaires

Vendor/Firm Name and Address
Raison sociale et adresse du
fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution
Public Works and Government Services Canada - Pacific
Region
800 Burrard Street, Room 219
800, rue Burrard, pièce 219
Vancouver
British C
V6Z 0B9

Title - Sujet Health Care Expansion	
Solicitation No. - N° de l'invitation EZ899-181607/A	Amendment No. - N° modif. 006
Client Reference No. - N° de référence du client	Date 2017-12-18
GETS Reference No. - N° de référence de SEAG PW-\$PWY-025-8228	
File No. - N° de dossier PWY-7-40258 (025)	CCC No./N° CCC - FMS No./N° VME
Solicitation Closes - L'invitation prend fin at - à 02:00 PM on - le 2017-12-22	Time Zone Fuseau horaire Pacific Standard Time PST
F.O.B. - F.A.B. Plant-Usine: <input type="checkbox"/> Destination: <input checked="" type="checkbox"/> Other-Autre: <input type="checkbox"/>	
Address Enquiries to: - Adresser toutes questions à: Fung, Donna(PWY)	Buyer Id - Id de l'acheteur pwy025
Telephone No. - N° de téléphone (604) 671-9689 ()	FAX No. - N° de FAX (604) 775-6633
Destination - of Goods, Services, and Construction: Destination - des biens, services et construction: CSC - Mountain Institution - Agassiz, BC	

Instructions: See Herein

Instructions: Voir aux présentes

Delivery Required - Livraison exigée	Delivery Offered - Livraison proposée
Vendor/Firm Name and Address Raison sociale et adresse du fournisseur/de l'entrepreneur	
Telephone No. - N° de téléphone Facsimile No. - N° de télécopieur	
Name and title of person authorized to sign on behalf of Vendor/Firm (type or print) Nom et titre de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur (taper ou écrire en caractères d'imprimerie)	
Signature	Date

Solicitation No. - N° de l'invitation
EZ899-181607/A
Client Ref. No. - N° de réf. du client

Amd. No. - N° de la modif.
006
File No. - N° du dossier
PWY-7-70258

Buyer ID - Id de l'acheteur
PWY025
Project No.- No. du projet
R.077724.001

This Amendment No. 005 is raised to incorporate:

- 1) Addendum #03, and
- 2) the BidCentral Online Bidding for Subcontractors (BOBS) Pre-Bid Interpretation No. 2.

Please see the attached Addendum #03.

Please see the attached Pre-Bid Interpretation No. 2.

ALL OTHER TERMS AND CONDITIONS REMAIN UNCHANGED.

The following changes in the tender documents are effective immediately. This addendum will form part of the contract documents.

DRAWINGS

.1 G002 WALL TYPES

- a) **[Revise]** WL1 and WL2 revise lead lining thickness to be 1.6 mm Min.

SPECIFICATIONS

.1 13 49 00 RADIATION PROTECTION

- a.) **[Revise]** 2.1.1.1.1 revise 0.8 mm to 1.6 mm minimum lead thickness.
b.) **[Revise]** 2.1.1.1.3 strike out "Refer to Nuclear Medical Shielding Summary."

QUESTIONS AND ANSWERS:

1. Question: We are facing difficulty in getting the total price for medical equipment's supply and Install. My suggestion is to include all the medical equipment in the cash allowance.

Answer: All medical equipment relocation, provision, and installation as per the tender documents shall be included in the contract, including the specified x-ray machine.
2. Question: Drawing G002 wall assembly WL1 & WL2 state the lead lining thickness is to be 0.8mm thickness minimum. In the specification section 13 49 00 part 2.1.1.1.3 it states three different thickness's and to refer to Nuclear Medicine Shielding Summary. I have tried to find this report but I do not see it anywhere in your specification document, nor can I find it online. Can you please clarify what thickness of lead lining is required for this project?
3. Answer: All walls are to have a minimum of 1.6mm of lead thickness or equivalent. 13 49 00 1.5 (.3) "Design of work of this Section to be determined by the Contractor's physicist." The contractor's physicist will provide a shielding report based on the contractor's submitted X-ray machine.
4. Question: In the specification section 2.1.1.5 it states two different lead equivalences' (1.6mm or 2.4mm). Please clarify what lead equivalence the glass must achieve?

Answer: All Glass is to have a minimum of 1.6mm of lead thickness equivalent. 13 49 00 1.5 (.3) "Design of work of this Section to be determined by the Contractor's physicist." The contractor's physicist will provide a shielding report based on the contractor's submitted X-ray machine.
5. Question: I have contacted Cook Medical directly to see if they still manufacture the Cook TFA-4 lead apron, they have indicated to me they do not. Can you please provide an alternative make/model? One of our suppliers has suggested "Shielding International"

as a quality manufacturer. Would their product Economy Coat Apron (Model E) meet your requirements?

Answer: Shielding International Flex Back Model FB would be an acceptable equivalent or GE Healthcare Mavig Model 650 (GE cat #E3053xx), Lengths should correspond to the respective sizes specified.

6. Question: In the specification section 13 49 00 part 2.1.1.7, it shows a specification for a "Radiation Shielding Glass/Acryclic X-Ray Barrier." This unit is not listed under new or existing equipment in the equipment schedule in spec section 12 51 00 or 12 52 00. Please clarify if we are to supply this?

Answer: Provide One (1) barrier per specificalton13 49 00 2.1.1.7.

7. Question: The GE rep has indicated that a physicist may need to be hired to ensure the lead shielding is working properly. Section 12 50 00 does not state any physicist requirement though. Can you please confirm if one will need to be hired, and if so, who will cover his fees?

Answer: Specification 13 49 00 1.5 (2) Requires the contractor to employ a registered X-ray Physicist for shielding testing and inspection. The contractor is responsible for all costs of this Physicist.

8. Question: Please confirm if the existing WL2 wall in the X-Ray room is a 92mm steel stud wall assembly?

Answer: The existing assemblies related to this room are typically composed of 92mm steel studs, but they may vary where chases, furring or other deviations were necessary in construction.



British
Columbia
Construction
Association

British Columbia Construction Association
BidCentral Online Bidding for Subcontractors
401 – 655 Tyee Road Victoria, BC V9A 6X5
P: (250) 475-1077 F: (250) 475-1078
E: warrenp@bccassn.com
W: www.bccassn.com or www.bidcentral.ca

PRE-BID INTERPRETATION No. 2

Date: December 18, 2017
To: All Plan Holders
Project: Health Care Expansion, Mountain Institution
Agassiz, BC

BC Bid Calling Authority: Public Services and Procurement Canada

As allowed under Rule 1. F. Pre-Bid Interpretations, we are hereby issuing the following clarification to all plan holders. Unless defined herein the Standard Exclusions will apply; *General Contractors are responsible to include all work that may be excluded from a BidCentral Online Bidding for Subcontractor's (BOBS) Bid as they deem necessary.* This document does not imply a requirement to include work not specified:

1. Mechanical

01. Clarification: The Appendix A Standard Exclusion for 'weeping tile and/or footing drains' applies whether this work is inside or outside the building. General Contractors shall include for this work as they deem necessary.
02. For the purposes of this project the 'outside site services piping' (as defined in Rule Clarification 3.0) as shown on the Civil Drawings is excluded from this Bid. Also excluded from this Bid is the storm drainage system shown outside the building on Drawing P-3. General Contractors shall include for this work as they deem necessary. The storm drainage system under the building shown on P-3 is included in this Bid.

END

BidCentral Online Bidding for Subcontractors per;

Warren E. Perks, Administrator

<p>All Plan Holders should insure that copies of this Pre-Bid Interpretation are forwarded to all those to whom they have issued copies of the project documents.</p>
--