

1.1 GENERAL

- .1 Security system scope of work is limited to removal and reinstallation of existing devices and small control panel as indicated on electrical plans and detail on drawing E-04. The existing system is owner-installed.

END OF SECTION

- .3 To assist the Contractor in preparing his bid, prior to closing of tenders, the System Manufacturer shall indicate the number of hours the Contractor is to provide as necessary to complete the inspection.
- .4 The Contractor shall advise the Departmental Representative in writing when the electrical work on the project is ready for Substantial Performance inspection. Prior to that date, request the System Manufacturer to perform a final verification of the system.
- .5 The Fire Alarm System manufacturer shall make an inspection and final verification of the fire alarm equipment install under this contract. The verification shall be comprised of an examination and subsequent verification of all equipment in accordance with Standard for Verification of Fire Alarm Systems CAN/ULC-S537-04.
- .6 All costs for verifications, reverifications and corrections both from the System Manufacturer and the Contractor shall be included in the Tender. Allow sufficient verifications and reverifications to complete the Work. No additional costs for verifications or reverifications will be considered beyond the scope of the base contract.
- .7 The final system verification report shall be submitted prior to Substantial Performance of the project.

END OF SECTION