



Royal Canadian Mounted Police
Gendarmerie royale du Canada

RETURN BIDS TO :

RETOURNER LES SOUMISSIONS :

Bid Receiving Unit / Grope de la réception des soumissions

Procurement & Contracting Services / Services d'acquisitions et des marchés.

VISITOR'S CENTRE
Royal Canadian Mounted Police
73 Leikin Drive, Ottawa, Ontario

Telephone No.

no de téléphone: (613) 843-3798

AMENDMENT TO THE INVITATION TO TENDER

Royal Canadian Mounted Police

We hereby offer to sell to Her Majesty the Queen in right of Canada, in accordance with the terms and conditions set out herein, referred to herein or attached hereto, the goods, services and construction listed herein and on any attached sheets at the price(s) set out therefore.

MODIFICATION À L'APPEL D'OFFRES

Gendarmerie royale du Canada

Nous offrons par la présente de vendre à Sa Majesté I Reine du chef du Canada, aux conditions énoncées ou incluses par référence dans la présente et aux annexes ci-jointes, les biens, services et construction énumérés ici sur toute feuille ci-annexée, au(x) prix indiqué(s).

Comments – Commentaries

Vendor/Firm Name and Address

Raison sociale et adresse du fournisseur/de l'entrepreneur

Telephone No. – No de téléphone:

()

Facsimile No. – No de télécopieur:

()

Title-Sujet Construction – Site Clearing and Parking Lot Construction		
Solicitation No. – No. de l'invitation 201805065	Amend. – Modif. No. : 6	Date Jan. 16th, 2018 / 16 janvier, 2018
Client Reference No. - No. de Référence du Client 201805065		
GETS Reference No. – No de Référence du SEAG PW-17-00809889		
Solicitation Closes – L'invitation prend fin at – à 2:00 P.M. EST on – January 18th, 2018., 18 janvier, 2018		
F.O.B. - F.A.B. Destination		
Address Enquiries to: - Adresser toute questions à : Jordan McKenna		
Telephone No. - No de téléphone 613-843-5518	Fax: 613-825-0082	
Destination of Goods - Destinations des biens: See Herein		
Instructions : See Herein / Voir aux présentes		
Delivery Required – Livraison exigée: See Herein		
Name and Title of person authorized to sign on behalf of Vendor/Firm. Nom et titre de la personne autorisée à signer au nom du fournisseur/de l'entrepreneur		

Amendment No. 6

Construction – Site Clearing and Parking Lot Construction
SOLICITATION NO. : 201805065

Date: January 16th, 2018

Amendment #6 is being issued in order to amend the tender, and respond to Questions PART 2 as follows:

Questions and Answer Part 3

- Q1) Drawing E1 detail 7/E1, could someone look into this detail as visually with the rock I do not think this will be done , also the depth of the footing is 2440mm but at the bottom right it states the footing is 600 x 600 x 600mm, could it be clarified please.
- A1) Detail 7/E1 indicates that it will be the responsibility of the contractor to provide sealed engineered shop drawings, as such detail 7/E1 shows general intent only. The expectation is that a variation of this detail will be implemented based on the design the contractors engineer provides.
- Q2) Would it be possible for you to ask if the attached shielding for the LED fixtures would be acceptable? These are a physical shield, instead of a back light control via the optics.
- A2) Bid as per spec
- Q3) Is there a pole mounted ground operated switch required for the 27KV pole feeding the new transformer? Or just fused cut outs?
- A3) Provide ground operated switch for the 27kV feed to the new transformer c/w fused cutouts.
- Q4) The location of the camera's and code blue station are we just to provide the box and outlet with the devices to be installed by others in the future?
- A4) Box and outlet to be provided as specified, pole to be prepared for mounting of devices. Stations and cameras will be installed under separate contract.
- Q5) What's the size of the poles for the parking lot fixtures?
- A5) Bid as per contract documents. Refer to pole height indicated at each individual pole below circuit number.

Q6) The conduits feeding the future light bases indicate to cap but also indicate to supply wiring. Are we to cap these conduits with no wiring or supply boxes at the bases to pull conductors to?

A6) Wiring to be installed as indicated on drawings. Provide junction box at future pole locations to house and make safe wiring as indicated on drawings.

Q7) Addendum #4 – Question #13 + Electrical Drawing E3 – Detail #2
Please confirm the service kiosk is only to house Electrical Panels 'LP-01', 'BP-01', and 'BP-02'. The separate Communication Enclosure and 75 kVA Transformer will be mounted at the back of the service kiosk (exposed) as shown on Detail #2. If not, please clarify exactly what is required.

A7) Bid as per documents, detail 2 on E3.

Q8) Would you be able to provide the overall dimensions required for the Nema 3 enclosure?

A8) No, scale from the drawings

Q9) The spec says that you would like square aluminum tapered poles. My electrical sub is telling their suppliers Valmont and Novapole have both informed them that this does not exist but they can do straight square poles. Can you please confirm if this is an acceptable style of pole.

A9) Confirmed

Q10) Would PVC SDR35 pipe be acceptable in place of HDPE storm sewer pipes?

A10) Bid as per tender documents.

Q11) What size diameter are the Curb inlet Catch Basins Leaders to be?

A11) Curb inlet catch basin leaders are to be 200mm diameter.

Q12) Does the tree clearing and grubbing need to be complete on all three project sites by March 31st 2018 or just the site #1 where the new parking lot is made? This will affect a lot in regards to pricing because of man power requirements and site requirements.

A12) Yes, clearing and grubbing of all sites is to be complete before March 31, 2018

Q13) The specifications makes reference to have a competent safety coordinator present

at all times when work is taking place, does this person have to be separate from the site super intendant or can this be a dual role?

A13) Require a separate safety coordinator based on the assumption of the quantity of personnel on site at one time.

Q14) If the answer to question one is YES, do we need to provide a site office on each of the three site simultaneously complete with the security officers requirements?

A14) Only one site trailer is required.

Q15) Is there a list of qualified contractors to perform the electrical services and duct bank work as required in the specification?

A15) There are no prequalified contractors. Bid as per tender documents.

Q16) Likewise to question no.4 is there a list of qualified contractors to perform the tree removal portion of work as required in the spec?

A16) There are no prequalified contractors. Bid as per tender documents

Q17) The specification makes reference to 120v single phase power being available on site, is this available on all three sites?

A17) 120v power is only available on Site 1.

Q18) Do the new parking lot light standard bases need to be precast or are they cast in place?

A18) Bid as per contract documents. Refer to detail 7/E1 and requirement for contractor to provide sealed engineered shop drawing. Bid as per contract documents. Refer to detail 7/E1 and requirement for contractor to provide sealed engineered shop drawing.

Q19) Can the topographic survey dated August 29th, 2016 that is referenced in specification be made available to us there are discrepancies in the topographic elevations shown on the borehole log and the civil drawings?

A19) Bid as per contract documents. Supplemental information will not be provided.

Q20) I want to talk about the trees and how it a problem getting pricing for their removal. we have gone to the tree removal contractors in Ottawa and they are telling us without a tree quantity or seeing the site they cannot price the work.

A20) Please bid to the best of your ability per current tender documents. A comprehensive tree quantity is not available at this time. It will not be exact, but it is suggested to utilize a tool such as google maps in order to possibly gather additional data.

Q21) What permits are we responsible to carry for in our bid, as it is unclear in the specification.

A21) Environment Canada Species at Risk permit is in place. All other permits with the exceptions of City of Ottawa building permit are required

ALL OTHER TERMS AND CONDITIONS REMAIN THE SAME.

END