

PART 1 - GENERAL

1.1 REFERENCE STANDARDS

- .1 American Society of Heating, Refrigerating and Air-Conditioning Engineers, Inc. (ASHRAE)
- .2 National Fire Protection Association (NFPA)
 - .1 NFPA 90A (Latest Edition), Standard for the Installation of Air-Conditioning and Ventilating Systems.
 - .2 NFPA 90B (Latest Edition), Standard for Installation of Warm Air Heating and Air-Conditioning Systems.
- .3 Sheet Metal and Air-Conditioning Contractors' National Association (SMACNA)
 - .1 SMACNA HVAC Duct Construction Standards - Metal and Flexible, (Latest Edition).
 - .2 SMACNA IAQ Guideline for Occupied Buildings under Construction, (Latest Edition).
- .4 Underwriters' Laboratories (UL)
 - .1 UL 181 (Latest Edition), Standard for Factory-Made Air Ducts and Air Connectors.
- .5 Underwriters' Laboratories of Canada (ULC)
 - .1 CAN/ULC-S110 (Latest Edition), Standard Methods of Tests for Air Ducts.

1.2 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's instructions, printed product literature and data sheets for flexible ducts and include product characteristics, performance criteria, physical size, finish and limitations.
 - .2 Indicate:
 - .1 Thermal properties.
 - .2 Friction loss.
 - .3 Acoustical loss.
 - .4 Leakage.
 - .5 Fire rating.
- .3 Test and Evaluation Reports:
 - .1 Catalogue or published ratings to be those obtained from tests carried out by manufacturer or independent testing agency signifying adherence to codes and standards.

1.3 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements and with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
 - .1 Store materials off ground indoors in dry location and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Store and protect flexible ducts from nicks, scratches, and blemishes.
 - .3 Replace defective or damaged materials with new.

PART 2- PRODUCTS

2.1 GENERAL

- .1 Factory fabricated to CAN/ULC-S110.
- .2 Pressure drop coefficients listed below are based on relative sheet metal duct pressure drop coefficient of 1.00.
- .3 Flame spread rating not to exceed 25. Smoke developed rating not to exceed 50.

2.2 METALLIC - INSULATED

- .1 Type 2: spiral wound flexible aluminum with factory applied, 37 mm thick flexible glass fibre thermal insulation with vapour barrier and vinyl reinforced mylar/neoprene laminate, aluminum jacket, as indicated.
- .2 Performance:
 - .1 Factory tested to 2.5 kPa without leakage.
 - .2 Maximum relative pressure drop coefficient: 3.
 - .3 RSI Value, minimum 0.74.

2.3 NON-METALLIC - UNINSULATED

- .1 Type 3: non-collapsible, coated mineral base fabric, aluminum foil mylar type, mechanically bonded to, and helically supported by, external steel wire, as indicated.
- .2 Performance:
 - .1 Factory tested to 2.5 kPa without leakage.
 - .2 Maximum relative pressure drop coefficient: 3.

2.4 NON-METALLIC - INSULATED

- .1 Type 4: non-collapsible, coated mineral base fabric, aluminum foil/mylar type mechanically bonded to, and helically supported by, external steel wire with factory applied, 37 mm thick flexible mineral fibre thermal insulation with vapour barrier and vinyl reinforced mylar/neoprene laminate jacket.
- .2 Performance:
 - .1 Factory tested to 2.5 kPa without leakage.
 - .2 Maximum relative pressure drop coefficient: 3.
 - .3 RSI minimum: 0.7.

PART 3 - EXECUTION

3.1 EXAMINATION

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for flexible ducts installation in accordance with manufacturer's written instructions.
 - .1 Visually inspect substrate in presence of Departmental Representative.
 - .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.
 - .3 Proceed with installation only after unacceptable conditions have been remedied [and after receipt of written approval to proceed from Departmental Representative.

3.2 DUCT INSTALLATION

- .1 Install in accordance with: CAN/ULC-S110, UL 181, NFPA 90A, and NFPA 90B.

3.3 CLEANING

- .1 Progress Cleaning: clean in accordance with Section 01 74 11 - Cleaning.
 - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 - Cleaning.

END OF SECTION