

PART 1 - GENERAL

1.1 DEFINITIONS

- .1 Hazardous Material: Product, substance, or organism that is used for its original purpose, and that is either dangerous goods or a material that may cause adverse impact to the environment or adversely affect health of persons, animals, or plant life when released into the environment.

1.2 WASTE MANAGEMENT

- .1 Incorporate environmental and sustainable practises in managing waste resulting from work.
- .2 Divert as much waste as possible from landfill.
- .3 Coordinate work of subtrades and subcontractors to ensure all possible waste reduction and recycling opportunities are taken. Follow waste management requirements specified in trade sections of the Specifications.
- .4 Reduce waste during installation of new materials. Undertake practices which will optimize full use of materials and minimize waste.
- .5 Develop innovative procedures to reduce quantity of waste generated by construction such as by delivering materials to site with minimal packaging etc...
- .6 Provide on-site facilities to collect, handle and store anticipated quantities of reusable, salvageable and recyclable materials.
- .7 During demolition and removal work separate materials and equipment at source, carefully dismantling, labelling and stockpiling alike items for the following purposes:
 - .1 Reinstallation into the work where indicated.
 - .2 Salvaging reusable items not needed in project which Contractor may sell to other parties.
 - .3 Sending as many items as possible to locally available recycling facility.
 - .4 Segregating remaining waste and debris into various individual waste categories for disposal in a "non-mixed state" as recommended by waste processing/landfill sites.
- .8 Isolate product packaging and delivery containers from general waste stream. Send to recycling facility or return to supplier/manufacturer.
- .9 Send leftover material resulting from installation work for recycling whenever possible.
- .10 Establish methods whereby hazardous and toxic materials, and their containers used on site are properly handled, stored and disposed in accordance with applicable federal, provincial and municipal laws and regulations.

1.3 DISPOSAL REQUIREMENTS

- .1 Burying or burning of rubbish and waste materials is prohibited.
- .2 Disposal of volatile materials, mineral spirits, oil, paint, and other hazardous materials into waterways, storm, or sanitary sewers is prohibited.
- .3 Dispose of waste only at approved waste processing facility or landfill sites approved by authority having jurisdiction.
- .4 Contact the authority having jurisdiction prior to commencement of work, to determine what, if any, demolition and construction waste materials have been banned from disposal in landfills and at transfer stations. Take appropriate action to isolate such banned materials at site of work and dispose in strict accordance with provincial and municipal regulations.
- .5 Transport and dispose of waste intended for waste processing plant or landfill facility in separated condition and to Operator's rules and recommendations in support of their effort to recycle, reduce and divert certain waste stream from general landfill.
- .6 Collect, bundle and transport salvaged materials to be recycled in separated categories and condition as directed by recycling facility. Ship materials only to approved recycling facilities.
- .7 Sale of salvaged items by Contractor to other parties not permitted on site.

PART 2 - PRODUCTS

2.1 NOT USED

- .1 Not Used.

PART 3 - EXECUTION

3.1 NOT USED

- .1 Not Used.

END OF SECTION