




DOOR SCHEDULE

DOOR No.	DIMENSIONS			DOOR					FRAME					Fire Rating	REMARKS
	W	H	Th.	Elev.	Type	Fin.	Hdwe.	Misc.	Elev.	Type	Jamb	Fin.	Misc.		
X01	915	2134	45	1	AL	PF	X01		1	AL	A	PF			
X02	2-915	2134	45	2	HMI	P	X02		2	PS	A	P			
103	915	2134	45	3	WD	PF	H01		1	PS	B	P		20 min.	
104	915	2134	45	3	WD	PF	H02		1	PS	B	P		20 min.	
105	915	2134	45	4	WD	PF	H10		1	PS	B	P		20 min.	
106	915	2134	45	3	WD	PF	H04		1	PS	B	P		20 min.	
106a	2-460	2134	45	5	WD	PF	H08		3	PS	B	P			
107	915	2134	45	3	WD	PF	H05		1	PS	B	P			
108	915	2134	45	3	WD	PF	H05		1	PS	B	P			
109	915	2134	45	3	WD	PF	H04		1	PS	B	P		20 min.	
109a	2-460	2134	45	5	WD	PF	H08		3	PS	B	P			
110	915	2134	45	3	WD	PF	H04		1	PS	B	P		20 min.	
110a	2-460	2134	45	5	WD	PF	H08		3	PS	B	P			
111	915	2134	45	3	WD	PF	H04		1	PS	B	P		20 min.	
111a	2-460	2134	45	5	WD	PF	H08		3	PS	B	P			
112	915	2134	45	3	WD	PF	H05		1	PS	B	P			
113	915	2134	45	3	WD	PF	H04		1	PS	B	P		20 min.	
113a	2-460	2134	45	5	WD	PF	H08		3	PS	B	P			
114	915	2134	45	3	WD	PF	H04		1	PS	B	P		20 min.	
115	915	2134	45	3	WD	PF	H05		1	PS	B	P			
116	915	2134	45	4	WD	PF	H10		1	PS	B	P		20 min.	
118	915	2134	45	3	WD	PF	H03		1	PS	B	P		20 min.	
118a	2-460	2134	45	5	WD	PF	H08		3	PS	B	P			
119a	915	2134	45	4	WD	PF	H10		1	PS	B	P		20 min.	
119b	915	2134	45	4	WD	PF	H10		1	PS	B	P		20 min.	
121	915	2134	45	3	WD	PF	H02		1	PS	B	P			
125	915	2134	45	3	WD	PF	H06		1	PS	B	P			
129a	915	2134	45	3	WD	PF	H02		1	PS	B	P			
129b	2-915	2134	45	2	WD	PF	H07		2	PS	B	P			
130	915	2134	45	3	WD	PF	H02		1	PS	B	P			
137	915	2134	45	4	WD	PF	H10		1	PS	B	P		20 min.	
139	915	2134	45	3	WD	PF	H06		1	PS	B	P			
140	915	2134	45	3	WD	PF	H06		1	PS	B	P			
X101	-	-	-	-	-	-	H02		-	-	-	-			NEW HARDWARE ON EXISTING DOOR
X117	-	-	-	-	-	-	H01		-	-	-	-			NEW HARDWARE ON EXISTING DOOR
X133	-	-	-	-	-	-	H01		-	-	-	-			NEW HARDWARE ON EXISTING DOOR

DOOR & FRAME ELEVATIONS



DOOR SCHEDULE

2
A7

ROOM FINISH SCHEDULE

ROOM NAME	ROOM No.	FLOOR		BASE		WALLS								CEILING			REMARKS
		MAT.	FIN.	MAT.	FIN.	NORTH		SOUTH		EAST		WEST		MAT.	FIN.	HGT.	
EXIST. VESTIBULE	101	EX	-	R	-	EX	P	EX	P	GB	P	GB/EX	P	GB	P	-	SEE NOTE: 1, 5
FOYER	102	LIN	-	R	-	GB	P	EX	P	GB	P	GB	P	GB	P		SEE NOTE: 5
JANITOR	103	PT1	-	PT1	-	GB	P	GB	P	GB	P	GB	P	GB	P		SEE NOTE: 5
CGSAR MUD ROOM	104	PT1/PT2	-	PT1/PT2	-	FRP	-	FRP	-	FRP	-	FRP/CT1	-	FRP	-		SEE NOTE: 4
CORRIDOR	105a	VPF	-	R	-	GB/EX	P	GB	P	GB	P	-	-	GB	P		SEE NOTE: 5
CORRIDOR	105b	VPF	-	R	-	GB	P	-	-	GB/EX	P	GB	P	GB	P		SEE NOTE: 5
CABIN	106	VPF	-	R	-	GB	P	EX	P	GB	P	GB	P	GB	P		SEE NOTE: 5
SHOWER	107	PT1	-	PT1	-	EX	P	CT1	-	CT1	-	CT1	-	GB	P	-	SEE NOTE: 5
EXIST. WASHROOM	108	EX	-	EX	-	CT1	-	EX	-	EX	-	EX	-	GB	P	-	SEE NOTE: 2, 3, 5
CABIN	109	VPF	-	R	-	GB	P	EX	P	GB	P	GB	P	GB	P		SEE NOTE: 5
CABIN	110	VPF	-	R	-	GB	P	EX	P	GB	P	GB	P	GB	P		SEE NOTE: 5
C/O CABIN	111	VPF	-	R	-	GB	P	EX	P	GB	P	EX	P	GB	P		SEE NOTE: 5
SHOWER	112	PT1	-	PT1	-	CT1	-	CT1	-	CT1	-	CT1	-	GB	P	-	SEE NOTE: 5
C/E CABIN	113	VPF	-	R	-	GB	P	GB	P	GB	P	EX	P	GB	P		SEE NOTE: 5
LAUNDRY	114	EX	-	R	-	GB/EX	P	GB	P	GB	P	EX	P	GB	P		SEE NOTE: 1, 5
WASHROOM	115	PT1	-	PT1	-	CT1	-	CT1	-	CT1	-	CT1	-	GB	P		SEE NOTE: 5
FOYER	116	LIN	-	R	-	GB	P	GB	P	GB	P	GB/EX	P	GB	P		SEE NOTE: 5
EXIST. VESTIBULE	117	EX	-	EX	-	GB	P	GB	P	EX	P	EX	P	GB	P	-	SEE NOTE: 1, 5
FITNESS	118	EX	-	EX	-	EX	P	GB/EX	P	GB	P	EX	P	ACT/EX	-/P		
CLEAN WORKSHOP	119	LIN	-	R	-	EX	P	GB/EX	P	EX	P	GB	P	ACT	-		
E&I STORAGE	120	EX	-	EX	-	EX	P	GB	P	EX	P	GB	P	EX	P	-	SEE NOTE: 1
E&I	121	LIN	-	R	-	EX	P	GB	P	GB/EX	P	EX	P	ACT	-		
EXIST. MECH.	122	EX	-	EX	-	EX	P	EX	P	EX	P	EX	P	EX	P	-	
EXIST. ELECTRICAL	123	EX	-	EX	-	EX	P	EX	P	EX	P	EX	P	EX	P	-	
EXISTING UPS	124	EX	-	EX	-	EX	P	EX	P	EX	P	EX	P	EX	P	-	
TRAINING ROOM	125	LIN	-	R	-	GB	P	GB	P	EX	P	GB	P	ACT	-		
STORAGE	126	LIN	-	R	-	GB/EX	P	GB/EX	P	GB/EX	P	EX	P	ACT/EX	-/P		
EXIST. WASHROOM	127	EX	-	EX	-	EX	-	EX	-	EX	-	EX	-	EX	P	-	SEE NOTE: 2
ADMIN STAFF	128	EX	-	EX	-	EX	P	EX	P	EX	P	EX	P	EX	P	-	
MOCK-UP SPACE	129	LIN	-	R	-	EX	P	GB	P	GB	P	GB	P	ACT/EX	-/P		
DIRTY WORKSHOP	130	LIN	-	R	-	EX	P	GB	P	EX	P	GB	P	ACT/EX	-/P		
EXISTING DINING	131	LIN	-	R	-	EX	P	EX	P	GB/EX	P	EX	P	ACT/EX	-/P		
EXISTING KITCHEN	132	LIN	-	R	-	EX	P	EX	P	EX	P	GB/EX	P	EX	P	-	
FOYER	133	LIN	-	R	-	EX	P	GB/EX	P	EX	P	EX	P	GB/EX	P		
CGSAR CREW LIVING QUARTERS	134	VPF	-	R	-	GB	P	EX	P	EX	P	GB	P	ACT/EX	-/P		
CHART ROOM	135	LIN	-	R	-	EX	P	EX	P	EX	P	EX	P	EX	P	-	
EXIST. WASHROOM	136	EX	-	EX	-	EX	-	EX	-	EX	-	EX	-	EX	P	-	SEE NOTE: 2
CGSAR OPERATIONS	137	LIN	-	R	-	GB/EX	P	EX	P	GB	P	EX	P	ACT/EX	-/P		
STORAGE	138	LIN	-	R	-	GB/EX	P	GB/EX	P	GB/EX	P	GB/EX	P	ACT	-		
C/O OFFICE	139	LIN	-	R	-	GB	P	EX	P	EX	P	GB	P	ACT/EX	-/P		
ENGINEER OFFICE	140	LIN	-	R	-	EX	P	GB	P	EX	P	GB	P	ACT/EX	-/P		

ROOM FINISH SCHEDULE NOTES:


- EXISTING FLOORING TO REMAIN, NEW RUBBER BASE
- EXISTING WALL TILE TO REMAIN
- NEW CERAMIC WALL TILE AT NORTH WALL
- PT2 & CT1 AT CURBED DRAIN AREA
- 45min RATED CEILING ASSEMBLY

SCHEDULE LEGEND:

- | | |
|--------------------------------|---------------------------|
| ACT ACOUSTIC CEILING TILE | P PAINT |
| AL ALUMINUM | PF PREFINISHED |
| CT1 CERAMIC WALL TILE | PS PRESSED STEEL |
| EX EXISTING MATERIAL OR FINISH | PT1 PORCELAIN TILE |
| FRP FIBERGLAS REINFORCED PANEL | PT2 PORCELAIN MOSAIC TILE |
| GB GYPSUM BOARD | R RUBBER |
| HMI HOLLOW METAL INSULATED | VPF VINYL PLANK FLOORING |
| LIN LINOLEUM | WD WOOD DOOR |

ROOM FINISH SCHEDULE

1
A7



C01	Issued for Tender	DEC 21 2017
revisions		date
project		projet

SAR STATION
REFURBISHMENT
ST. ANTHONY

LIFEBOAT STATION

drawing dessin

SCHEDULES

designed NS	conçu
date 2017-10-27	
drawn TP	dessiné
date 2017-10-27	
approved MK	approuvé
date 2017-10-27	
Tender D.B.	Soumission
PWGSC Project Manager	Administrateur de projets TPSGC
project number	no. du projet
R.089934.001	
drawing no.	no. du dessin
A7	