

PART 1 - GENERAL

1.1 SUMMARY

- .1 Section Includes:
 - .1 Use of mechanical systems during construction.

1.2 USE OF SYSTEMS

- .1 Use of new heating and/or ventilating systems for supplying temporary heat or ventilation] is permitted only under following conditions:
 - .1 Entire system is complete, pressure tested, cleaned, flushed out.
 - .2 Specified water treatment system has been commissioned, water treatment is being continuously monitored.
 - .3 Building has been closed in, areas to be heated/ventilated are clean and will not thereafter be subjected to dust-producing processes.
 - .4 There is no possibility of damage.
 - .5 Supply ventilation systems are protected by 60 % filters, inspected daily, changed every week or more frequently as required.
 - .6 Return systems have approved filters over openings, inlets, outlets.
 - .7 Systems will be:
 - .1 Operated as per manufacturer's recommendations and instructions.
 - .2 Operated by Contractor.
 - .3 Monitored continuously by Contractor.
 - .8 Warranties and guarantees are not relaxed.
 - .9 Regular preventive and other manufacturers recommended maintenance routines are performed by Contractor at own expense and under supervision of Departmental Representative.
 - .10 Refurbish entire system before static completion; clean internally and externally, restore to "as- new" condition, replace filters in air systems.
- .2 Filters specified in this Section are over and above those specified in other Sections of this project.
- .3 Exhaust systems are not included in approvals for temporary heating ventilation.

PART 2 - PRODUCTS

2.1 NOT USED

- .1 Not Used.

PART 3 - EXECUTION

3.1 NOT USED

.1 Not Used.

END OF SECTION