

DRAWING NOTES:

- 1 PLUMBING VENT STACK LOCATION.
- 2 3/4 NPS CONDENSATE DRAIN FROM HEAT RECOVERY UNIT. ROUTE TO NEAREST DRAIN IN MECHANICAL ROOM.
- 3 INDOOR EVAPORATOR UNIT C/W CONDENSATE PUMP. (TYPICAL).
- 4 NEW TYPE B FIRE EXTINGUISHER. SEE SPEC FOR DESCRIPTION (TYPICAL).
- 5 NEW TYPE K FIRE EXTINGUISHER IN KITCHEN. SEE SPEC FOR DESCRIPTION. (TYPICAL).

CONSTRUCTION NOTES

1. THESE DRAWINGS REASONABLY REPRESENT EXISTING CONDITIONS. ACTUAL CONDITIONS MAY DEVIATE FROM THAT SHOWN/IDENTIFIED ON THE DRAWINGS. THE CONTRACTOR SHALL VERIFY ACTUAL CONDITIONS, CHECK ALL DIMENSIONS, AND VERIFY MATERIALS REQUIRED TO COMPLETE THIS WORK. CONTRACTOR SHALL INFORM THE DEPARTMENTAL REPRESENTATIVE OF ANY DISCREPANCIES PRIOR TO COMMENCING WORK.
2. REMOVE FROM SITE DEMOLISHED MATERIALS, DEBRIS, AND RUBBISH. DISPOSE DEMOLISHED MATERIALS AS PER THE REQUIREMENTS OF THE AUTHORITY HAVING JURISDICTION.
3. COMPLETE ALL WORK IN ACCORDANCE WITH THE NATIONAL BUILDING CODE OF CANADA (LATEST EDITION).
4. CONTRACTOR IS RESPONSIBLE FOR ALL DEMOLITION & REINSTATEMENT NECESSARY FOR THE INSTALLATION OF THE NEW WORK WHETHER SHOWN HERE OR NOT.
5. BUILDING WILL NOT BE OPERATIONAL DURING DEMOLITION AND CONSTRUCTION OF INTERIOR FIT-UP PORTION OF WORK. AS OF MAY 30, 2018, BUILDING WILL BE OCCUPIED. ALL EXTERIOR WORK TO BE COMPLETED WHILE BUILDING IS OPERATIONAL. CONTRACTOR TO TAKE NECESSARY STEPS TO ENSURE SAFETY OF BUILDING PERSONNEL AND THE PUBLIC DURING CONSTRUCTION WHILE BUILDING IS OPERATIONAL.
6. THE CONTRACTOR IS RESPONSIBLE FOR TEMPORARY REMOVAL/RELOCATION OF MECHANICAL SYSTEMS WHICH INTERFERE WITH COMPLETING THE REPAIR WORK INDICATED ON THE DRAWINGS. MECHANICAL SYSTEMS TO BE REINSTATED ONCE REPAIR WORK IS COMPLETE. ALL WORK MUST BE COMPLETED IN ACCORDANCE WITH ALL APPLICABLE BUILDING CODES, BY LICENSED TRADES PEOPLE.
7. ALL ITEMS WILL BE COORDINATED WITH STRUCTURAL, ARCHITECTURAL, ELECTRICAL AND CIVIL DURING CONSTRUCTION STAGE.
8. ANY MECHANICAL EQUIPMENT ON ROOF STRUCTURE SUCH AS BUT NOT LIMITED TO A/C UNITS AND EXHAUST FANS, HOODS, SHALL BE REMOVED AND REINSTALLED AND MADE WATER TIGHT. FOR ALL SUCH EQUIPMENT LOCATION REFER TO ARCHITECTURAL ROOF PLAN.
9. EXISTING DUCTS AND A/C UNITS LOCATED IN ATTIC SPACE TO BE REMOVED PRIOR TO THE INSTALLATION OF NEW. ATTIC IS LIMITED IN SPACE FOR MANEUVERING AND REMOVAL OF EXISTING MECHANICAL EQUIPMENT.

PLUMBING LEGEND


- NEW DOMESTIC COLD WATER PIPING
--- NEW DOMESTIC HOT WATER PIPING
--- V NEW VENT PIPING
--- NEW SANITARY PIPING
--- CD NEW CONDENSATE DRAIN PIPING
--- EV- NEW EVAPORATOR UNIT
--- CU- NEW CONDENSER UNIT
--- A,B,C NEW FIRE EXTINGUISHER AND TYPE

DETAIL NUMBERING SYSTEM

- A --- DETAIL NUMBER.
B C --- LOCATION DRAWING NO.
--- DETAIL DRAWING NO.
- A --- DETAIL NUMBER.
C --- LOCATION DRAWING NO.

EQUIPMENT TAGS

- WC - # WATER CLOSET
L - # LAVATORY
LT - # LAUNDRY TUB
BT - # BATH TUB
MS - # MOP SINK
SH - # SHOWER



PLUMBING FLOOR PLAN

SCALE : 1:100
0m 1m 2m 3m 4m 5m 6m 7m 8m 9m 10m



PROVINCE OF NEWFOUNDLAND
PERMIT HOLDER
CLASS "A"
This Permit Allows
SNC-LAVALIN Inc.
To practice Professional Engineering
in Newfoundland and Labrador.
Permit No. as issued by PEONL N0458
which is valid for the year 2017.
ENGINEER IN RESPONSIBLE CHARGE
D.M. Morris

C01	ISSUED FOR TENDER	12/21 2017
revisions		date
project		projet

SAR STATION
REFURBISHMENT
ST. ANTHONY
LIFEBOAT STATION

drawing dessin

PLUMBING
FLOOR PLAN

designed D.M.	conçu
date 2017-11-17	
drawn D.B.	dessiné
date 2017-11-17	
approved MK	approuvé MK.
date 2017-11-17	
Tender D.B.	Soumission
PWSC Project Manager	Administrateur de projets TPSCG
project number	no. du projet
R.089934.001	
drawing no.	no. du dessin
M3	