



**RETURN BIDS TO:**

**RETOURNER LES SOUMISSIONS À:**

**Parks Canada Agency**  
1869 Upper Water Street, Suite AH 201  
Halifax, Nova Scotia B3J 1S9

**Agence Parcs Canada**  
1869 rue Upper Water, Pièce AH201  
Halifax (Nouvelle-Écosse) B3J 1S9

**SOLICITATION AMENDMENT**

**MODIFICATION DE L'INVITATION**

The referenced document is hereby revised; unless otherwise indicated, all other terms and conditions of the Solicitation remain the same.

Ce document est par la présente révisé; sauf indication contraire, les modalités de l'invitation demeurent les mêmes.

**Comments - Commentaries**

Vendor/Firm Name and Address  
Raison sociale et adresse du fournisseur/de l'entrepreneur

Issuing Office - Bureau de distribution

**Parks Canada Agency**  
1869 Upper Water Street, Suite AH 201  
Halifax, Nova Scotia B3J 1S9

**Agence Parcs Canada**  
1869 rue Upper Water, Pièce AH201  
Halifax (Nouvelle-Écosse) B3J 1S9

<b>Title-Sujet</b> Fundy National Park Headquarters Water Distribution System		
<b>Solicitation No. - No. de l'invitation</b> 5P201-17-5184/A		<b>Amendment No./N° de modification de l'invitation</b> 003
<b>Client Ref. No. - No. de réf du client.</b> 1318		<b>Date:</b> February 6, 2018
<b>GETS Reference No. - No de reference de SEAG</b> PW-18-00813133		
<b>Solicitation Closes:</b>		
<b>at - à</b> 02:00 PM	<b>on - le</b> February 8, 2018	<b>Time Zone - Fuseau horaire</b> AST - HNA
<b>F.O.B. - F.A.B.</b>		
<b>Plant-Usine:</b> <input type="checkbox"/> <b>Destination:</b> <input checked="" type="checkbox"/> <b>Other-Autre:</b> <input type="checkbox"/>		
<b>Address Inquiries to: - Adresser toute demande de renseignements à :</b>		
Tanya Allen – tanya.allen@pc.gc.ca		
<b>Telephone No. - No de téléphone</b>		<b>Fax No. - No de FAX:</b>
(902) 426-7543		(902) 426-1775
<b>Destination of Goods, Services, and Construction:</b> <b>Destinations des biens, services et construction:</b>		
See Herein – Voir ici		

**TO BE COMPLETED BY THE BIDDER (type or print)**  
**À ÊTRE COMPLÉTER PAR LE SOUMISSIONNAIRE (taper ou écrire en caractères d'imprimerie)**

<b>Vendor/Firm Name - Nom du fournisseur/de l'entrepreneur</b>	
<b>Address - Adresse</b>	
<b>Name of person authorized to sign on behalf of the Vendor/Firm</b> <b>Nom de la personne autorisée à signer au nom du fournisseur/ de l'entrepreneur</b>	
<b>Titale - Titre</b>	
<b>Telephone No. - N° de téléphone:</b> _____	
<b>Facsimile No. - N° de télécopieur:</b> _____	
<b>Signature</b>	<b>Date</b>

## AMENDMENT 003

### 1.0 Questions

**Q1 a) Could you clarify what is required for “insulated backflow preventer covering bag” and “2691mm inside closure”.**

**b) Is the cover provided by the park?**

A1 a) The insulated bag is intended to be placed over the whole backflow preventer unit as a means of insulating and protecting the unit. It is to be provided by the contractor

b) The 2691mm inside closure is simply stating that there is to be a closure that allows for 2691mm clear space inside the enclosure (an inside measurement of the box).

**Q2 Where the work is to be completed in two phases (spring 2018, and Fall/Winter 2018-2019), are there certain items that should be done in either phase?**

A2 No, there is no required work sequence for this job.

**Q3 Given that the temporary water could freeze if laid on the ground, could a water shut down be possible rather than using temporary water?**

A3 No, the temporary water system described on C4 is intended to supply water to the rest of system while the pipe is installed from the compound to the treatment plant. It would not be possible to keep the old pipe in service while installing the new pipe as it is intended that the new pipe be installed in the old trench. Installing in a new trench would possibly require a substantial amount of rock excavation. Temporary water will need to be installed to avoid freezing.

**Q4 Hydroseed payable through powerline area, quantities in bid form only seem to cover areas where grubbing is shown?**

A4 As per section 33 11 16 section 3.15.1, surface is to be restored to original condition. The hydroseed is included in the bid for to cover locations where the finished area is different than the original condition.

**Q5 Will an inspector be on site full time?**

A5 At this point it is unsure what hours the inspector will be on site, they will be present when any connections are being made or tests done.

**Q6 Is there rock present on the site?**

A6 Yes, some rock is to be expected on site when digging in new trenches.

**Q7 What permits are required?**

A7 It is ultimately up to the contractor to ensure they have the required permits for the job, but at the very least an Environmental Protection Plan in accordance with Section 01 35 43 as stated in Section 31 25 00 of the specs.

**Q8 Section 21 07 20 talks about “Thermal Insulation for Piping” Is there actually Thermal Insulated Pipe on this job?**

A8 Yes, after reviewing the drawings sheet C7 shows a detail of the “Fundy Highlands – Backflow Preventer Assembly” and where the pipes come up from the ground there are two sections of insulated pipe roughly 0.7m in length.

**Q9 Please provide detail for manhole restraining strap referred to on drawing C7.**

Solicitation No. - N° de l'invitation  
5P201-17-5184/A

Amd. No. - N° de la modif.  
003

Buyer - l'acheteur  
Tanya Allen

Client Ref. No. - N° de réf. du client

File Name - Nom du dossier  
Fundy National Park Headquarters Water Distribution System

---

A9 See detail titled 'strap detail'

---

**ALL OTHER TERMS AND CONDITONS REMAIN THE SAME.**

---