

ADDENDUM No. 2

The following changes to the tender documents are effective immediately and will form part of the contract documents:

1. GENERAL

1.1	The Bidding Documents are amended as noted in this Addendum, which consists of one (1) page plus the following attachments: 1. Drawing #A1.9 – Interior Manual Gates 2. Specification Section 01 11 00 – Summary of Work
1.2	This Addendum is issued prior to bid closing to incorporate revisions noted herein. Include in the Bid price all such revisions which will become part of the Work. Perform all such Work in accordance with the Contract Documents.
1.3	All affected drawings, schedules and panel changes shall be reflected in final as-built and manual submissions.

2. ANSWERS TO BIDDERS' QUESTIONS

2.1	<p><u>Question #1:</u> 32 31 13, Part 2.1.7.3 states that swing gates are to be supplied with latch and latch catch with provision for padlock that can be operated from either side of the gate. Drawing A1.9 Gate Legend note 3 (from CSC TCD) states that vehicle swing gates are to be supplied with foot, mid height, and top locking detention grade cremone bolts or engineered mechanism and locked with padlocks. Which instruction is to be followed? If the CSC Technical Criteria is to be followed, does the engineered mechanism require an engineer's stamp? How many padlocks are to be used if this lock type is required? The drawings on A1.9 do not show a header for a top locking point.</p> <p><u>Answer to Question #1:</u> See revisions to Section 32 31 13 – Chain Link Fences and Drawing #A1.9 below.</p>
-----	----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

3. SPECIFICATIONS

3.1	Section 01 11 00 – Summary of Work: See attached revised section with changes to Article 1.5 – Work Sequence.
3.2	Section 32 31 13 - Chain Link Fences and Gates: 1) Revise sub-paragraph 2.1.7.4 to read 'Furnish vehicle swing gates with three galvanized malleable iron hinges and a three-point locking heavy-duty cremone bolt as indicated. 2) New paragraph 2.1.12 to read 'Furnish manual bi-parting vehicle sliding gates with a three-point locking heavy-duty cremone bolt as indicated.'

4. DRAWINGS

4.1	Drawing #1.9 - Interior Manual Gate Type Elevations: 1) See attached revised drawing complete with new vehicle gate cremone bolts and revised drawing title.
-----	-----------------------------------------------------------------------------------------------------------------------------------------------------------------

END OF ADDENDUM NO. 2

Part 1 General

1.1 WORK COVERED BY CONTRACT DOCUMENTS

- .1 Work of this Contract comprises of Gate and Fence Repair and Replacement at the Saskatchewan Penitentiary in Prince Albert, Saskatchewan; and further identified as Project No. R.058018.001.

1.2 CONTRACT METHOD

- .1 Construct Work under single stipulated price contract.

1.3 WORK OF THIS CONTRACT AND EXISTING SERVICES

- .1 Ensure that the work of this contract including the provision of new fence post piles and sally port gate grade beam foundations does not accidentally interfere with existing underground services.
- .2 Establish location and extent of service lines in area of work before starting Work. Notify Departmental Representative of findings.
- .3 Where unknown services are encountered, immediately advise Departmental Representative and confirm findings in writing.
- .4 Record locations of maintained, re-routed and abandoned service lines.
- .5 Protect, relocate or maintain existing active services. When inactive services are encountered, cap off in manner approved by authorities having jurisdiction.

1.4 USER OCCUPANCY

- .1 User will occupy premises during entire construction period for execution of normal operations.
- .2 Co-operate with User in scheduling operations to minimize conflict and to facilitate User Occupancy.

1.5 WORK SEQUENCE

- .1 Construct Work in stages to accommodate User's continued use of premises during construction.
- .2 Co-ordinate Progress Schedule and co-ordinate with User Occupancy during construction.
- .3 Maintain fire access/control.
- .4 Required stages:
 - .1 Refer to Drawing #A0.1 – Site Demolition Plan.

1.6 CONTRACTOR USE OF PREMISES

- .1 Limit use of premises for Work, for storage and for access, to allow:
 - .1 User occupancy.

- .2 Co-ordinate use of premises under direction of Departmental Representative.
- .3 Obtain and pay for use of additional storage or work areas needed for operations under this Contract.
- .4 Remove or alter existing work to prevent injury or damage to portions of existing work which remain.
- .5 Repair or replace portions of existing work which have been altered during construction operations to match existing or adjoining work, as directed by Departmental Representative.
- .6 At completion of operations condition of existing work: equal to or better than that which existed before new work started.

1.7 EXISTING SERVICES - TEMPORARY MEASURES

- .1 Notify, Departmental Representative and utility companies of intended interruption of services and obtain required permission.
- .2 Where Work involves breaking into or connecting to existing services, give Departmental Representative 48 hours notice for necessary interruption of mechanical or electrical service throughout course of work. Minimize duration of interruptions. Carry out work at times as directed by governing authorities with minimum disturbance to pedestrian and vehicular traffic.
- .3 Provide alternative routes for pedestrian and vehicular traffic.
- .4 Submit schedule to and obtain approval from Departmental Representative for any shut-down or closure of active service or facility including power and communications services. Adhere to approved schedule and provide notice to affected parties.
- .5 Provide temporary services when directed by Departmental Representative to maintain critical building and tenant systems.
- .6 Provide adequate bridging over trenches which cross sidewalks or roads to permit normal traffic.
- .7 Construct barriers in accordance with Section 01 56 00 - Temporary Barriers and Enclosures.

1.8 ALTERATIONS, ADDITIONS OR REPAIRS TO EXISTING BUILDING

- .1 Execute work with least possible interference or disturbance to building operations, occupants, public and normal use of premises. Arrange with Departmental Representative to facilitate execution of work.

1.9 DOCUMENTS REQUIRED

- .1 Maintain at job site, one copy each document as follows:
 - .1 Contract Drawings.
 - .2 Specifications.
 - .3 Addenda.
 - .4 Reviewed Shop Drawings.
 - .5 List of Outstanding Shop Drawings.

- .6 Change Orders.
- .7 Other Modifications to Contract.
- .8 Field Test Reports.
- .9 Copy of Approved Work Schedule.
- .10 Health and Safety Plan and Other Safety Related Documents.
- .11 Other documents as specified.

Part 2 Products

2.1 NOT USED

- .1 Not used.

Part 3 Execution

3.1 NOT USED

- .1 Not used.

END OF SECTION